

## CONTENTS

### CITY OF WOODBURN ORDINANCE COMPILATION

#### 1. GOVERNMENT AND ADMINISTRATION

[Evidentiary Rules of Procedure](#)  
[Cable Television Advisory Board](#)  
[Nomination Procedures](#)  
[Civil Infractions](#)  
[City Council Bylaws](#)  
[Jurisdiction Over Public Rights-of-Way](#)  
[Museum Committee](#)  
[Library Board](#)  
[Recreation & Park Board](#)  
[Ward Boundaries](#)  
[Management of Public Right-of-Way Relating to Telecommunications](#)  
[Emergency Management Ordinance](#)  
[Measure 37 Claim Process](#)  
[Public Contracting Rules](#)  
[Municipal Judges Pro-Tem](#)  
[Master Fee Schedule](#)

#### 2. LOCAL IMPROVEMENTS

[Public Right-of-Way Construction Permit Fees](#)  
[Sidewalk Construction and Repair](#)  
[Public Improvement Procedure](#)  
[Reimbursement District Process](#)  
[Street and Park Trees](#)

#### 3. UTILITIES

[Water Regulation and Rates](#)  
[Sewer and Water Regulations](#)  
[System Development Charges for Water, Sewer and Parks and Recreation](#)  
[Traffic Impact Fees and System Development Charges for Storm Water](#)  
[Drainage](#)  
[Methodology for Park and Recreation System Development Charges](#)

[Municipal Sewer and Water Service to Properties located outside City Boundaries](#)

[Process for the Forced Conversion of Electric and Communication Facilities](#)

[Transportation System Development Charges](#)

4. **SANITATION**

[Sewage Disposal](#)

[Sewer Connection Fees](#)

[Industrial Waste Cost Recovery](#)

[Waste Discharge Regulations](#)

[Sewer Capacity Fees](#)

[Wastewater Discharge Fees \(Sewer Charges\)](#)

[Sewer Use Ordinance](#)

[Cross Connection Control and Backflow Prevention](#)

5. **OFFENSES**

[Peddlers](#)

[Municipal Violations](#)

[Gambling](#)

[Offenses \(Adoption of Oregon Criminal Code\)](#)

[Prostitution \(Procurement\)](#)

[Prostitution \(Solicitation\)](#)

[Park Regulations](#)

[Juvenile Curfew](#)

[Chronic Nuisance Property](#)

[Inventory Search by Woodburn Police Department](#)

[Noise Regulation](#)

[Nuisances](#)

[Library Rules of Conduct](#)

[Graffiti Property](#)

[Animal Control](#)

6. **TRAFFIC**

[Abandoned Vehicles Hearings Officer](#)

[Truck Routes](#)

[On-Street Parking](#)

[Golf Carts](#)

[Prohibited Parking in Portion of Downtown](#)

[Traffic](#)

[Police Training Assessment in Traffic Violation Cases](#)  
[Taxicabs](#)

8. **BUSINESS**

[Cable Television Regulations](#)  
[Public Dances](#)  
[Alarms](#)  
[Film Permit Process](#)  
[Business Registration](#)  
[Permitting of Newsracks](#)  
[Local Incentives for Businesses within Enterprise Zone](#)

9. **BUILDING**

[House Numbering](#)  
[Seasonal Decorations](#)  
[Moving of Buildings](#)  
[Technical and Environmental Services Charge](#)  
[Mobile Home Inspection and Permits](#)  
[Building Nuisances](#)  
[Flood Plain Management](#)  
[Specialty Codes, Building Official Duties](#)  
[Habitable Rental Housing](#)

10. **WOODBURN DEVELOPMENT ORDINANCE (WDO)**

[Organization And Structure](#)

[-Structure](#)  
[-Definitions](#)  
[-Zoning Map](#)  
[-Nonconforming Uses and Development Standards](#)  
[-Planning Commission](#)

[Land Use Zoning](#)

[-General Provisions](#)  
[-Single Family Residential \(RS\)](#)  
[-Retirement Community Single Family Residential \(R1S\)](#)  
[-Medium Density Residential \(RM\)](#)  
[-Commercial Office \(CO\)](#)  
[-Commercial General \(CG\)](#)  
[-Downtown Development and Conservation \(DDC\)](#)  
[-Nodal Neighborhood Commercial \(NNC\)](#)  
[-Industrial Park \(IP\)](#)  
[-Light Industrial \(IL\)](#)

- [-Public and Semi-Public \(P/SP\)](#)
- [-Neighborhood Conservation Overlay District \(NCOD\)](#)
- [-Riparian Corridor and Wetland Overlay District \(RCWOD\)](#)
- [-Southwest Industrial Reserve \(SWIR\)](#)
- [-Nodal Overlay Districts](#)
- [-Interchange Management Area \(IMA\) Overlay District](#)

#### **Specified Use Standards**

- [-Accessory Uses and Structures: Residential Zones and Residential Uses](#)
- [-Accessory Uses and Structures: Non-Residential Zones and Uses](#)
- [-Special Use Standards](#)
- [-Specific Conditional Uses](#)

#### **Development Guidelines And Standards**

- [-Street Standards](#)
- [-Utilities and Easements](#)
- [-Setback, Open Space and Lot Standards, Generally](#)
- [-Access](#)
- [-Off Street Parking and Loading](#)
- [-Landscaping Standards](#)
- [-Architectural Design Guidelines and Standards](#)
- [-Partition and Subdivision Standards](#)
- [-Planned Unit Development Standards](#)
- [-Signs](#)

#### **Administration And Procedures**

- [-Decision Making Procedures](#)
- [-Review, Interpretation and Enforcement](#)

#### **Applications Requirements**

- [-Type I Application Requirements](#)
- [-Type II Application Requirements](#)
- [-Type III Application Requirements](#)
- [-Type IV Application Requirements](#)

#### **Appendices**

##### **List of Figures**

##### **Tree Guidelines**

##### **Use Classifications in the WDO**

## **11. FRANCHISES AND TAXES**

[Pacific Northwest Bell Telephone Co. \(Pay Phone\)](#)

[Cable Television Rate Schedule](#)

[Gas Tax](#)

[Hotel/Motel Tax](#)

[Portland General Electric Company Franchise](#)

[Privilege Tax \(PGE\)](#)

[Cable Television Basic Service Rates and Charges](#)  
[Privilege Tax \(NW Natural Gas\)](#)  
[Pacific NW Bell Telephone Co. Franchise](#)  
[Cable TV Franchise Transfer to NW Television](#)  
[Telecommunications Franchise - Datavision](#)  
[Transfer Cable TV Franchise to Willamette Broadband](#)  
[Woodburn Ambulance Service Franchise](#)  
[Northwest Natural Gas Company Franchise](#)  
[United Disposal Garbage Franchise](#)  
[Lightspeed Networks, Inc.](#)

## ORDINANCE NO. 1582

**AN ORDINANCE PRESCRIBING PROCEDURES FOR EVIDENTIARY HEARINGS; AND DECLARING AN EMERGENCY.****THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:**

**Section 1.** In all evidentiary hearings before the common council and planning commission, the following procedures for the conduct of the hearings are prescribed:

(1) All interested persons in attendance shall be heard on the matter for hearing, and this fact shall be communicated to those in attendance.

(2) A summary of the application or other matter for hearing shall be given by the presiding officer or someone appointed by him or her.

(3) The staff report, if any, shall be made.

(4) Questions, if any, by the hearing body of the staff.

(5) Testimony shall be received in the following order:

- (a) Applicant.
- (b) Proponents.
- (c) Opponents.
- (d) Rebuttal by proponents.
- (e) Others.

(6) Close public hearing. However, the common council or planning commission may continue the hearing and the taking of evidence to another meeting, the time, date and place of which shall be announced before adjournment.

(7) Question, if any, by the hearing body.

(8) Discussion by the hearing body.

(9) A decision shall be made by the hearing body; except, however, that further discussion and/or decision by the hearing body may be postponed to another meeting, the time, date and place of which shall be announced before adjournment.

(10) All persons who speak at such a hearing shall identify themselves by name, address and interest in the matter. Attorneys or others shall be allowed to speak on behalf of proponents or opponents.

(11) Written briefs by any interested party, their attorney or other agent will be accepted if filed with the secretary or clerk of the hearing body.

(12) The record made at any prior hearing shall be accepted, considered and used by the hearing body, but such record need not set forth evidence verbatim. [Subsection 12 as amended by Ordinance No. 1609, passed June 5, 1978.]

**Section 2.** [Emergency clause.]

*Passed by the Council November 8, 1977, and approved by the Mayor November 10, 1977.*

---

ORDINANCE NO. 1816**AN ORDINANCE CREATING A CABLE TELEVISION ADVISORY BOARD, DEFINING ITS DUTIES AND RESPONSIBILITIES.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose.** The Woodburn Cable Television Advisory Board is hereby created to advise and make recommendations to the City Administrator and when appropriate, the Mayor and City Council, on matters pertaining to the operation of the Cable Television System in the City of Woodburn.

**Section 2. Board Membership.** The Board shall consist of seven (7) members, appointed by the Mayor with the approval of the City Council, and from resident voters of the City. Members shall serve without pay. Terms of office shall be three years from the date of appointment. Appointments shall be made annually upon the expiration or other determination of the members term of office. Terms of office shall begin the first year, with three members who will serve for the period of one year, two who shall serve for the period of two years and two who shall serve for the period of three years from the date of their appointment. Each member of the Board serves at the pleasure of the Mayor and City Council and may be removed prior to expiration of their terms without cause of hearing. Members may be removed by the Mayor, with the consent of the City Council. In addition to the appointed members, the Mayor and the City Administrator or his designee will serve as ex-officio members.

**Section 3. Meetings.** The Board shall meet at such times as the Board may determine are appropriate and necessary. All Board meetings shall be conducted in accordance with the bylaws of the organization, the provisions of this ordinance and with law.

**Section 4. Officers.** The Cable Television Advisory Board shall, at its first annual meeting, elect a chairman, secretary and such other officers as the Board may deem appropriate. Officers shall have such duties and authority as the Board shall establish, consistent with its bylaws, other provisions of this ordinance and with law.

**Section 5. Board Responsibilities.** The Cable Television Advisory Board shall work directly with the Cable Franchise holder and have the responsibility for advising and making recommendations to the City Administrator or the designated staff liaison, and when appropriate, to the Mayor and Council, on matters pertaining to the use of community access channels; to foster awareness of the community access channels; to act as intermediary for the community with respect to all issues, concerns and needs of the community regarding cable television; and to perform as a respondent to all grievances brought before the committee.



**Section 6. Rules and Regulations.** The Cable Television Advisory Board shall advise and recommend to the Cable Franchise holder, and when appropriate the City Administrator and the Mayor and Council, reasonable rules and regulations governing the use and control of community access cable television channels in the City of Woodburn.

**Section 7. Internal Administration Policies and Procedures.** The Cable Television Advisory Board shall operate in conformance with all City administrative procedures.

**Section 8. Annual Reports.** The Cable Television Advisory Board shall make a full and complete report to the City Council and make such other reports as may be required by the Mayor and Council.

*Passed by the Council May 9, 1983, and approved by the Mayor May 10, 1983.*

---

ORDINANCE NO. 1867**AN ORDINANCE ESTABLISHING NOMINATION PROCEDURES FOR THE OFFICES OF MAYOR AND CITY COUNCILOR AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Eligibility.** Any person who is eligible pursuant to Section 12 of the Woodburn City Charter may be nominated for an elective City position.

**Section 2. Nomination Procedure.** Nomination shall be by petition specifying the position sought and signed by the requisite number of electors as that term is defined by Section 2 of the Oregon Constitution. Such petition shall be signed by not fewer than twenty (20) electors. No elector shall sign more than one such petition for the same office. If an elector signs more than one petition for the same office the signature of the elector shall be valid only on the first petition filed. The signatures of a nomination petition need not all be appended to one paper. However, an affidavit of the circulator of the petition shall be attached to each separate paper of the petition indicating the number of signers of the paper and stating that each signature appended thereto was made in his presence and is the genuine signature of the person whose name it purports to be. The signer's place of residence, identified by its street and number or other sufficient description shall accompany each signature.

**Section 3. Filing.** All nomination papers shall be assembled and filed with the City Recorder as one instrument not earlier than 250 nor later than 70 days before the election.

**Section 4. Duty of the City Recorder.** The City Recorder shall make a record of the exact time at which each petition is filed and shall take and preserve the name and address of the person who filed the petition. Each petition shall be accompanied by the acceptance of the nominee which shall be endorsed upon the petition and signed by the nominee. If the petition is not signed by the required number of qualified electors, or does not contain the endorsed acceptance of the nominee, the Recorder shall notify the nominee and the person who filed the petition within five (5) days after the filing. If the petition is insufficient in any other particular, the Recorder shall return it immediately to the person who filed it, certifying in writing wherein the petition was insufficient. Such deficient petition may be amended and filed again as a new petition, or a different petition for the same candidate may be filed within the regular time for filing nomination petitions. Upon determination that the petition is in all respects sufficient, the Recorder shall cause the nominee's name to be printed on the ballots. The nomination petition for a successful candidate at an election shall [be] preserved in the office of the Recorder until the term of office for which the candidate is elected expires.

Section 5. [Emergency clause.]

*Passed by the Council April 23, 1984, and approved by the Mayor April 24, 1984.*

## ORDINANCE NO. 1998

AN ORDINANCE ESTABLISHING A STREAMLINED CIVIL INFRACTION PROCEDURE TO ENFORCE CITY ORDINANCE VIOLATIONS; PROVIDING A SCHEDULE OF FORFEITURES FOR THE VIOLATION OF SAID ORDINANCES; REPEALING ORDINANCE 1610; AND DECLARING AN EMERGENCY.

[Where as clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Definitions.** For the purpose of this ordinance the following mean:

(A) Civil Infraction - Commission of an act or omission to act in a manner prescribed by this ordinance or other city ordinance constituting breach or infringement of a section of a city ordinance or of this ordinance constitutes a civil infraction and shall be handled in accordance with the procedures established by this ordinance. Civil infraction does not include violations of other city ordinances where a criminal penalty is provided. When an infraction is of a continuing nature, except where specifically provided otherwise, a separate infraction will be deemed to occur on each calendar day the infraction continues to exist, and a separate citation may be filed for each such infraction.

(B) Enforcement Officer - The City Administrator or any designee appointed by the Administrator to enforce this ordinance.

(C) Forfeiture; Forfeiture Schedule - The only penalty to be imposed for an infraction is a monetary penalty called a forfeiture. The forfeiture to be assessed for a specific infraction will be determined pursuant to specific provisions within the ordinance defining the infraction, or the forfeiture schedule found in Section 5 of this ordinance. The procedure prescribed by this ordinance shall be exclusive procedure for imposing a forfeiture; however, this section shall not be read to prohibit in any way any alternative remedies set out in ordinances or state statute or state law which are intended to abate or alleviate ordinance violations, nor shall the city be prohibited from recovering, in a manner prescribed by law, any expense incurred by it in abating or removing ordinance violations pursuant to any ordinance.

(D) Person - Any natural person or persons, firm, partnership, association or corporation.

(E) Responsible Party - The person responsible for curing or remedying an infraction and includes:

(1) The owner of the property or the owner's manager or agent or other person in control of the property on behalf of the owner;

(2) The person occupying the property including bailee, leasee, tenant or other person having possession;

(3) The person who is alleged to have committed or authorized the commission of the infraction.

**Section 2. Infraction Procedure.**

(A) Issuance of uniform citation and complaint;

(1) When a violation of a city ordinance occurs a uniform infraction citation and complaint signed by the enforcement officer may be filed with the municipal court charging the responsible party with the civil infraction and setting a date for the responsible party to appear before the municipal court to answer said complaint.

(2) The enforcement officer shall prescribe the form of the uniform infraction citation and complaint, but it shall consist of at least three pages. Additional pages may be inserted for administrative purposes by those charged with the enforcement of the ordinances. The required pages are:

- (a) the complaint;
- (b) the city department record; and
- (c) the summons.

(3) Each of the three pages shall contain the following information:

- (a) the name of the court and the court's file number;
- (b) the name of the person cited;
- (c) the infraction with which the person is charged;
- (d) the date, time and place the infraction occurred, or if the infraction is of a continuing nature, the date, time and place the infraction was observed by the enforcement officer, or the citizen signing the complaint;
- (e) the date on which the citation was issued;
- (f) the scheduled forfeiture for the alleged infraction;
- (g) the time and place at which the person cited is to appear in court to answer the complaint.

(4) The complaint shall contain a form of certification that the person signing the complaint states that the person has reasonable ground to believe, and does believe that the person cited committed the infraction.

(5) The summons shall also contain notice to the person cited that a civil complaint will be filed in the municipal court of the city.

(B) Summons. Service of the uniform citation and complaint shall be made by personal service upon the responsible party. If personal service cannot be made then service of the uniform infraction citation and complaint shall be in accordance with the Oregon Rules of Civil Procedure.

(C) Answer

(1) A person who receives a summons and complaint alleging an infraction shall answer such complaint by personally appearing to answer at the time and place specified therein; except an answer may be made by mail or personal delivery if received by the city within ten days of the date of the receipt of the summons as provided in subsection 2 and 3 below.

(2) If the person alleged to have committed an infraction admits the infraction, the person may complete the appropriate answer on the back of each summons and forward the summons to the municipal court. Cash, check or money order in the amount of the forfeiture for the infraction alleged as shown on the back of the summons shall be submitted with the answer. Upon receipt of the forfeiture, an appropriate order shall be entered in the municipal court records.

(3) If the person alleged to have committed the infraction denies part or all of the infraction, the person may request a hearing by completing the appropriate answer on the back of the summons and forwarding the summons, together with security for court fees. Upon receipt, the answer shall be entered and a hearing date established by the municipal court. The municipal court shall notify the person alleged to have committed the infraction by return mail of the date of the hearing. The security deposit may be waived in whole or in part at the discretion of the municipal court for good cause shown and upon written application of the person alleged to have committed the infraction setting forth the reason for requesting the waiver and certifying that the person alleged to have committed the infraction will attend the hearing when scheduled.

(D) Hearing.

(1) Every hearing to determine whether an infraction has been committed shall be held before the municipal court without a jury.

(2) The defendant may be represented by legal counsel, but legal counsel shall not be provided at public expense.

(3) The defendant shall have the right to present evidence and witnesses in the defendant's favor, to cross-examine witnesses who testify against the defendant and to submit rebuttal evidence.

(4) If the defendant alleged to have committed the infraction desires that witnesses be ordered to appear by subpoena, the defendant must so request in writing from the court.

(5) The complainant shall have the burden of proving the alleged ordinance infraction by a preponderance of the evidence.

(6) After due consideration of the evidence and arguments presented at the hearing, the court shall determine whether the infraction as alleged in the complaint was committed. When the infraction has not been proven, an order dismissing the complaint shall be entered in the municipal court records. A copy of the order shall be delivered to the person named in the order personally or by mail. When the court finds that the infraction was committed, and upon written request by a party to the hearing, the order shall include a brief statement of the necessary findings of fact to establish the infraction alleged.

(7) Upon a finding that an infraction has occurred, the court shall assess a forfeiture pursuant to the schedule established in accordance with this ordinance, plus court costs and witness fees. The municipal court judge is authorized to set reasonable court costs including security for court fees by court order.

(8) Any written documents, correspondence or physical evidence associated with the matter shall be retained by the municipal court until disposed of by order of the municipal court

(9) The determination of the municipal court shall be final. Review of the court's determination shall be to the circuit court by writ of review pursuant to ORS Chapter 34.

### **Section 3.    Enforcement.**

(A) If a cited person fails to answer the summons or appear at a scheduled hearing as provided herein, a default judgment shall be entered for the schedule forfeiture applicable to the charged infraction. In addition, when a person fails to appear for a hearing, the security posted, or an amount equal to the security waived, shall be ordered forfeited. Nothing in this subsection shall be construed to limit in any way the contempt powers of the municipal judge granted by the charter of state law, and the judge may exercise those powers as the judge considers necessary and advisable in conjunction with any matter arising under the procedures set forth in this ordinance.

(B) Any forfeiture assessed is to be paid no later than ten days after the receipt of the final order declaring that forfeiture. Such period may be extended upon order of the municipal judge.

(C) Delinquent forfeitures and those brought to default judgment which were assessed for infractions may in addition to any other method be collected or enforced pursuant to ORS 30.310 or 30.315.

### **Section 4.    Lien Filing and Docketing.**

(A) When a judgment is given in municipal court in favor of the city for the sum of \$10.00 or more, exclusive costs or disbursements, the enforcement officer may, at any time thereafter while the judgment is enforceable, file with the City Recorder a

certified transcript of all those entries made in the docket of the municipal court with respect to the action in which the judgment was entered.

(B) Thereupon, the City Recorder shall enter the judgment of the municipal court on the city lien docket.

(C) From the time of the entry of the municipal court judgment in the city lien docket, the judgement shall be a lien upon the real property of the person against whom judgment was entered in the municipal court. Except as provided in subsection D, entry of the municipal court judgment in the city lien docket shall not thereby extend the lien of the judgment more than ten years from the original entry of the judgment in the municipal court.

(D) Whenever a judgment of the municipal court which has been entered pursuant to this section is renewed by the municipal court the lien established by subsection C of this section is automatically extended ten years from the date of the renewal order.

(E) The City Recorder may file the transcript of the judgment with the county clerk for entry in the judgment docket of the circuit court.

#### **Section 5. Schedule of Forfeitures.**

##### **Schedule of Forfeitures.**

(A) Infractions as classified for the purpose of determining forfeitures in the following categories:

- (1) Class 1 civil infractions.
- (2) Class 2 civil infractions.
- (3) Class 3 civil infractions.
- (4) Class 4 civil infractions.
- (5) Class 5 civil infractions.

(B) As assessment of a forfeiture for an infraction shall be an assessment to pay an amount not exceeding:

- (1) \$750.00 for a class 1 civil infraction.
- (2) \$500.00 for a class 2 civil infraction.
- (3) \$250.00 for a class 3 civil infraction.
- (4) \$125.00 for a class 4 civil infraction.
- (5) \$100.00 for a class 5 civil infraction.



(C) Infraction of specific Woodburn ordinances are classified as follows:

<u>Ordinance No.</u>	<u>Class</u>
583.....	4
1015.....	4
1084.....	1
1187.....	4
1358.....	2
1638 Section 21/Vicious Dogs .....	2
Remainder of Ordinance .....	5
1641.....	2
1790.....	1
1795.....	1
1866.....	2
1908.....	3
1917.....	1
1925.....	2
1957.....	5
1965.....	3
1988.....	5
1999.....	1
2399.....	2
2057.....	2
2060.....	1, 4
2084.....	4
2122.....	2
2173.....	1
2225.....	2
2262.....	5
2285.....	4
2293.....	1
2312.....	1
2313.....	1
2336.....	1

(D) Where an ordinance of the City of Woodburn provides that an ordinance violation may be processed in accordance with the Civil Infraction Ordinance, but does not classify the civil infraction, this unclassified civil infraction shall constitute a Class I civil infraction under this ordinance.

Ordinances enacted after the effective date of this ordinance which require a forfeiture provision for their enforcement shall incorporate the infraction procedure set out herein and classify violations thereof in accordance with Section 5 of Ordinance 1998.

[Section 5 as amended by Ordinance No. 2362, passed May 24, 2004.]

**Section 6.     Severability.** The provisions of this ordinance are severable. If a portion of this ordinance is for any reason held by a court of competent jurisdiction to be invalid, such decision shall not affect the validity of the remaining portions of this ordinance.

**Section 7.     Non-Exclusive Remedy.** The procedures and remedies contained in this ordinance shall not be read to prohibit in any way any alternative remedies set out in ordinances or state statutes intended to alleviate ordinance violations.

**Section 8.     Repeal and Saving Clause.**

(A)     Ordinance 1610, as amended, is hereby repealed.

(B)     After the effective date of this ordinance, any reference to Ordinance 1610 contained in the ordinances or resolutions of the City of Woodburn shall be construed by any court to be a reference to the provisions of this ordinance.

(C)     Notwithstanding subsection A of this section, Ordinance 1610 shall remain valid and in force for the purpose of allowing the prosecution and punishment of a person who violated Ordinance 1610 prior to the effective date of this ordinance.

**Section 9.     [Emergency clause.]**

***Passed by the Council May 23, 1988, and approved by the Mayor May 23, 1988.***

**ORDINANCE NO. 2182****AN ORDINANCE ADOPTING BYLAWS GOVERNING PROCEEDINGS OF THE CITY COUNCIL, REPEALING ORDINANCE NO. 1971, AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose.** The purpose of this ordinance is to prescribe rules to govern all meetings and proceedings of the Council, consistent with all provisions contained in the Woodburn City Charter and Oregon state law. The intent of this ordinance is to supplement the Woodburn City Charter to allow implementation of any substantive charter requirements. In this respect, provisions of the Woodburn City Charter and Oregon state law override and supersede any conflicting provisions of this ordinance. If any section or subsection of this ordinance is determined by a court to be invalid or unenforceable, then such section or subsection shall be severed from this ordinance and the remainder of this ordinance shall remain in full force and effect.

**Section 2. Ordinances and Resolutions.**

A. Proposed Ordinances and Resolutions (Council Bills) may be introduced by any member of the Council.

B. An Ordinance shall receive two readings prior to final passage.

C. Readings of an Ordinance may be by title only unless a Councilor requests that the Ordinance be read in full.

D. A Resolution shall receive one reading prior to final passage and this reading shall be by title only unless a Councilor requests a full reading.

E. Procedure.

(1) A Councilor presents a proposed Ordinance or Resolution (Council Bill). (No motion is necessary since no vote is required for introduction of a bill, e.g. "Mr./Madam Mayor, I introduce Council Bill \_\_\_\_\_.")

(2) The Mayor asks that the Council Bill be read in full/or by title only if there is no objection from the Council.

(3) The Council Bill is read as requested.

(4) If the Council Bill is a proposed Resolution, the Mayor asks if there is any discussion. After discussion and motions, if any, the Mayor shall call for a vote on the Resolution. Upon the request of any Councilor, the ayes and nays shall be taken and entered in the record.

(5) If the Council Bill is a proposed Ordinance, the Mayor asks that the Council Bill be read a second time by title only if there are no objections from a Councilor.

(6) The Council Bill (proposed Ordinance) is read as requested.

(7) The Mayor then asks if there is any discussion on the Council Bill (proposed Ordinance). After discussion and motions, if any, the Mayor shall call for a vote and the ayes and nays shall be taken and entered in the record.

F. A Resolution shall be declared passed by affirmative vote of a majority of the Councilors present at the meeting.

G. An Ordinance may be enacted in a single meeting by unanimous consent of the Councilors present. If not approved by unanimous consent of the Councilors present, the Ordinance shall be read and voted upon on a different day at another meeting, and enacted if a majority of the Councilors present at that meeting vote affirmatively.

H. All Resolutions and Ordinances passed or enacted by the Council are subject to veto of the Mayor as provided in Chapter V, Section 20, of the Woodburn City Charter.

I. Except in extreme emergencies, copies of Council Bills shall be provided the Mayor and members of the Council at least 48 hours prior to any session at which they could be introduced.

### **Section 3. Meetings.**

A. A majority of the incumbent members of the Council constitutes a quorum.

B. The Council shall hold a regular meeting at least once each month in the city at a time and place it designates.

C. The Council may hold a special meeting at the call of the Mayor or at the request of three Councilors in accordance with Chapter IV, Section 13 of the Woodburn City Charter.

### **Section 4. City Officers.**

A. Mayor

(1) The Mayor shall preside over all Council meetings at which he/she is present in accordance with the Woodburn City Charter.

(2) Consistent with the Woodburn City Charter all appointments by the mayor are subject to Council confirmation.

(3) The Mayor shall make a good faith effort to confer with the Council about who he/she will appoint to a committee so that any comments, objections, etc. Of individual councilors may be considered by the Mayor prior to the appointment. Both the Mayor and Council shall make every possible effort to avoid embarrassment to appointees.

(4) In the event that the Council does not confirm any appointment made by the Mayor and submitted to the Council for consideration, the Mayor shall within 10 days make a new appointment and submit it to the Council.

B. The Council President shall be elected by the Council and shall serve in accordance with the Woodburn City Charter.

#### **Section 5. Agenda.**

A. Matters to be considered by the Council shall be placed on an agenda to be prepared by the Mayor and the City Administrator. Any Councilor desiring to have a matter considered by the Council shall advise the Mayor or City Administrator to place it on the agenda.

B. In addition to the written agenda, any Councilor may bring items to the attention of the Council during a meeting, in accordance with the provisions of this ordinance, the Woodburn City Charter and state law.

C. At the discretion of the presiding officer and in accordance with state law, any visitor may speak on any matter of city business. The presiding officer may establish time limits on such comments by visitors to insure that all persons desiring to be heard shall have the opportunity to speak.

#### **Section 6. Public Hearings.**

A. Consistent with the provisions of state law, the following procedure shall be used at all public hearings:

(1) Public hearing opened

(2) Declarations:

(a) The presiding officer will ask if any member of the Council has a conflict of interest in the matter.

(b) The presiding officer will ask if any member of the Council has had any EX-PARTE contact he wishes to disclose.

(c) The presiding officer will ask if anyone from the audience wishes to challenge any member of the council from acting on the matter.

(3) Staff report

(4) Testimony by applicant

- (5) Testimony by proponents
- (6) Testimony by opponents
- (7) Rebuttal by applicant
- (8) Hearing is closed
- (9) COUNCIL Discussion

(10) Final decision (or motion to direct staff to draft ordinance for CONSIDERATION at next Council meeting if land use decision is involved)

B. Any questions by the Mayor and Council addressed to individuals giving public testimony must be asked to these individuals prior to the close of the public hearing.

**Section 7. Roberts Rules of Order.**

A. Roberts Rules of Order, Newly Revised, shall be used as the guideline for conduct of Council meetings, except in those cases where specific provisions contrary to Robert Rules are provided herein.

B. The Chair will not condone any inappropriate conduct in a meeting. Meetings will be conducted in an orderly and dignified manner.

C. If in the chair's judgment any person is not in accordance with these rules, that person will be asked to leave.

**Section 8. Miscellaneous Rules of Procedure.**

A. In all matters to be heard by the Council, the City Administrator or member of his staff shall be given the first opportunity to speak thereon. Proponents of the matter before the Council shall be afforded the next opportunity to speak thereon. Opponents of the matter before the Council shall be afforded the opportunity to speak thereon after proponents have completed their presentations. Councilors have the privilege of asking questions at any time. After all presentations are complete, the Council may discuss the matter and take action as desired.

B. Official "public hearings" shall be conducted as prescribed by law and/or current regulations governing said hearings. All persons attending official "public hearings" will be given reasonable time to present their arguments, but such persons are requested to avoid repetitious and irrelevant statements.

C. Visitors desiring to speak will formally address the chair, and visitors will identify themselves by their name, address, and whether they represent a person, group or organization.

D. If at all possible, all regular and special Council meetings shall be tape recorded. Council members, staff and visitors shall use the microphones provided for that purpose. The visitors microphone shall not be removed from its stand without permission of the presiding officer.

**Section 9. Suspension of the Rules.** In accordance with the Woodburn City Charter, the rules contained in this Ordinance may be suspended by the concurrence of a majority of the Council present at a Council meeting.

**Section 10. Repeal of Ordinance 1971.** Ordinance 1971 is hereby repealed

*Passed by the Council October 28, 1996, approved by the Mayor  
October 29, 1996.*

## ORDINANCE NO. 2225

AN ORDINANCE ASSERTING JURISDICTION AND EXERCISING AUTHORITY OVER PUBLIC RIGHTS-OF-WAY; REQUIRING PERMISSION TO USE SAID RIGHTS-OF-WAY; REGULATING THE USE OF SAID RIGHTS-OF-WAY; REPEALING ORDINANCE NO. 2185 AND DECLARING AN EMERGENCY.

[Whereas clauses.]

**Section 1. Definitions.** For the purpose of this ordinance, the following mean:

City: The City of Woodburn, Oregon.

Person: Individual, corporation, association, firm, partnership, joint stock company, and similar entities.

Public rights-of-way: Include, but are not limited to, streets, roads, highways, bridges, alleys, sidewalks, trails, paths, public easements and all other public ways or areas, including subsurface and air space over these areas.

Within the city: Territory over which the city now has or acquires jurisdiction for the exercise of its powers.

**Section 2. Jurisdiction.** The city of Woodburn has jurisdiction and exercises regulatory control over all public rights-of-way within the city under the authority of the city charter and state law.

**Section 3. Scope of Regulatory Control.** The city has jurisdiction and exercises regulatory control over each public right-of-way whether the city has a fee, easement, or other legal interest in the right-of-way. The city has jurisdiction and regulatory control over each right-of-way whether the legal interest in the right-of-way was obtained by grant, dedication, prescription, reservation, condemnation, annexation, foreclosure or other means.

**Section 4. City Permission Requirement.** No person may occupy or encroach on a public right-of-way without the permission of the city. The city grants permission to use rights-of-way by franchises, licenses and permits.

**Section 5. Obstructions Prohibited.** No person shall obstruct, cause to be obstructed, assist in obstructing or interfere with a public right-of-way by depositing or storing personal property or other material on the right-of-way or by any other manner obstructing or interfering with the right-of-way without first obtaining city permission. This section shall not apply to the delivery of merchandise, equipment, or services provided the delivery is accomplished with a reasonable time.

**Section 6. Deposit of Materials Prohibited.** No person shall deposit garbage, earth, debris, or rubbish of any kind on a public right-of-way without first obtaining city permission.



**Section 7. Obligations of the City.** The exercise of jurisdiction and regulatory control over a public right-of-way by the city is not official acceptance of the right-of-way, and does not obligate the city to maintain or repair any part of the right-of-way.

**Section 8. Penalty.** Violation of this ordinance constitutes a class 2 civil infraction and may be dealt with according to the procedures established by Ordinance 1998.

**Section 9. Non-Exclusive Remedy.** The penalty described in this ordinance shall not be the exclusive remedy of the city for the violation of the ordinance. The procedures and remedies contained in this ordinance shall not be read to prohibit in any way any alternative remedies set out in ordinances or state statutes intended to alleviate ordinance violations.

**Section 10. Repeal.** Ordinance No. 2185 is hereby repealed.

**Section 11. Severability.** Invalidity of a section or part of a section of this ordinance shall not affect the validity of the remaining sections or part of sections.

**Section 12.** [Emergency clause.]

*Passed by the Council and approved by the Mayor August 10, 1998.*

## ORDINANCE NO. 2254

**AN ORDINANCE CREATING A MUSEUM COMMITTEE AND DEFINING ITS DUTIES AND RESPONSIBILITIES AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose.** The Woodburn Museum Committee is hereby created to advise and make recommendations to the City Administrator and Mayor and City Council, on matters related to the management of the museum.

**Section 2. Membership.** The Committee shall consist of seven (7) members, appointed by the Mayor with the approval of the City Council, and shall be responsible to the Mayor and City Council. Six (6) members shall be appointed from resident voters of the greater Woodburn area. The seventh member shall be appointed from the student body of Woodburn High School and need not be a resident voter. Members shall possess a background and interest in historic collections, historic preservation and local and/or natural history. Members shall serve without pay. Terms of office, excepting that of the member appointed from the student body of Woodburn High School, shall be four (4) years from the date of appointment and staggered so three positions will expire every two years. The term of office for the member appointed from the Woodburn High School shall be two (2) years from the date of appointment, which shall be in August. All other appointments shall be made annually, in December, upon the expiration or other determination of the members' term of office. Each member of the Committee serves at the pleasure of the Mayor and City Council and may be removed prior to expiration of their terms without cause or hearing. Members may be removed by the Mayor, with the consent of the City Council. In addition to the appointed members, the Mayor and City Administrator will serve as ex-officio members.

**Section 3. Meetings.** The Committee shall meet quarterly, or at such times as the Committee may deem necessary and appropriate. All Committee meetings shall be conducted in accordance with the bylaws of the organization, the provisions of this ordinance and with law.

**Section 4. Officers.** The Museum Committee shall, at its first meeting, elect a chairman and such other officers as the Committee may deem appropriate. Officers shall have such duties and authority as the Committee shall establish, consistent with its bylaws, other provisions of this ordinance and with law.

**Section 5. Committee Responsibilities.** The Museum Committee shall be responsible for advising and making recommendations to the City Administrator, and when appropriate, to the Mayor and Council, on all matters pertaining to the planning, acquisition, development and management of the Museum.

**Section 6. Budget.** The Museum Committee shall participate in the preparation of the annual budget and shall recommend to the Budget Officer a budget for the expenditure of all funds produced by tax or other means for the development, promotion and management of the Museum in the City of Woodburn.

**Section 7. Rules and Regulations.** The Museum Committee shall advise the City Administrator regarding preparation and adoption of reasonable rules and regulations governing the use of and proper conduct in the Museum in the City of Woodburn.

**Section 8. Supervision of Curator.** The City Administrator shall have the responsibility for the hiring, termination, discipline and any other personnel actions affecting the Museum Curator, or other paid museum personnel.

**Section 9. Internal Administrative Policies and Procedures.** The City Administrator shall be the fiscal and internal administrative agent for the Museum. The museum shall operate in conformance with City administrative procedures including those pertaining to the following:

- (1) Personnel, including recruitment, selection, classification and pay for department staff;
- (2) Personnel matters, including discipline and grievances;
- (3) Receipt, disbursement and accounting for monies;
- (4) Maintenance of general books, cost accounting records, and other financial documents;
- (5) Purchasing;
- (6) Budget administration; and
- (7) Operation and maintenance of equipment and buildings.

**Section 10. Assistance to the Committee.** The Curator, shall assist the Committee in the performance of its duties, and shall prepare reports as requested by the Committee.

**Section 11. Annual Reports.** The Museum Committee shall make a full and complete annual report to the City Council and make such other reports as may be required by the Mayor and Council. The Curator shall be responsible for the preparing the report with Committee input.

**Section 12. [Emergency clause.]**

*Passed by the Council and approved by the Mayor January 11, 2000.*

## ORDINANCE NO. 2265

AN ORDINANCE CREATING A LIBRARY BOARD, DEFINING ITS DUTIES AND RESPONSIBILITIES, AND REPEALING ORDINANCE NO. 1797 AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Purpose.** The Woodburn Public Library Board is hereby created to advise and make recommendations to the Community Services Director and the Mayor and City Council, on all matters related to the management of the library and rules and regulations governing the use of the library.

[Section 1 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 2. Board Membership.** The Board shall consist of seven (7) members, appointed by the Mayor with the approval of the City Council, and shall be responsible to the Mayor and City Council. Six (6) members shall be appointed from resident voters of the City or of the urban growth boundary. The seventh member shall be appointed from the student body of Woodburn High School and need not be a resident voter. Members shall possess a background and interest in library science and programs, library management and operations, or literacy. Members shall serve without pay. Terms of office, excepting that of the member appointed from the student body from Woodburn High School, shall be four (4) years from the date of appointment and staggered so three positions will expire every two years. The term of office for the member appointed from Woodburn High School shall be one (1) year from the date of appointment, which shall be in August. All other appointments shall be made annually, in December, or upon the expiration or other termination of the member's term of office. Each member of the Committee serves at the pleasure of the Mayor and City Council and may be removed prior to expiration of their terms without cause or hearing. Members may be removed by the Mayor pursuant to City resolution. In addition to the appointed members, the Mayor or the Mayor's representative and the Director will serve as ex-officio members.

[Section 2 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 3. Meetings.** The Board shall meet at such times as the Board may determine are appropriate and necessary. All Board meetings shall be conducted in accordance with the bylaws of the organization, the provisions of this ordinance and with law.

**Section 4. Officers.** The Library Board shall, at its first meeting, elect a chairman and such other officers as the Board may deem appropriate. Officers shall have such duties and authority as the Board shall establish, consistent with its bylaws, other provisions of this ordinance and with law.

**Section 5. Board Responsibilities.** The Library Board shall have the responsibility for advising and making recommendations to the Community Services Director and to the Mayor and Council, on all matters pertaining to the planning, acquisition, development and management of the library.

[Section 5 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 6. Budget.** The Library Board shall participate in the preparation of the annual budget and shall recommend to the Budget Officer a budget for the expenditure of all funds produced by tax or other means for the development, promotion and management of the library in the City of Woodburn.

**Section 7. Rules and Regulations.** The Library Board shall recommend to the Mayor and City Council reasonable rules and regulations governing the use of and proper conduct in the library in the City of Woodburn.

**Section 8. Supervision of Director.** The City Administrator shall have the responsibility for the hiring, termination, discipline and any other personnel actions affecting the Community Services Director. The Board shall act in an advisory capacity in the selection, discipline, or termination of the Director.

[Section 8 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 9. Internal Administrative Policies and Procedures.** The City Administrator shall be the fiscal and internal administrative agent for the library and the department shall operate in conformance with City administrative procedures including those pertaining to the following:

- (1) Personnel, including recruitment, selection, classification and pay for department staff;
- (2) Personnel matters, including discipline and grievances;
- (3) Receipt, disbursement and accounting for monies;
- (4) Maintenance of general books, cost accounting records, and other financial documents;
- (5) Purchasing;
- (6) Budget administration; and
- (7) Operation and maintenance of equipment and buildings.

**Section 10. Assistance to the Board.** The Director shall assist the Board in the performance of its duties, and shall prepare reports as requested by the Board.

**Section 11. Annual Reports.** The Library Board shall make a full and complete annual report to the City Council and make such other reports as may be required by the Mayor and Council. The Community Services Director shall be responsible for the preparation of the report with Board input.

[Section 11 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 12. Repeal.** Ordinance No. 1797 is hereby repealed.

**Section 13.** [Emergency clause.]

*Passed by the Council June 12, 2000 and approved by the Mayor June 13, 2000.*

## ORDINANCE NO. 2270

## AN ORDINANCE CREATING A RECREATION AND PARK BOARD, DEFINING ITS DUTIES AND RESPONSIBILITIES, REPEALING ORDINANCE 1796 AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Purpose.** The Woodburn Recreation and Park Board is hereby created to advise and make recommendations to the Community Services Director, and when appropriate, the Mayor and City Council, on all matters related to the development and management of parks, recreation facilities and a program of leisure and recreational services in the City of Woodburn, and to formulate and adopt rules and regulations governing the use of those facilities.

[Section 1 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 2. Board Membership.** The Board shall consist of seven (7) members, appointed by the Mayor with the approval of the City Council, and shall be responsible to the Mayor and City Council. Six (6) members shall be appointed from resident voters of the City or of the urban growth boundary. The seventh member shall be appointed from the student body of Woodburn High School and need not be a resident voter. Members shall possess a background and interest in library science and programs, library management and operations, or literacy. Members shall serve without pay. Terms of office, excepting that of the member appointed from the student body from Woodburn High School, shall be four (4) years from the date of appointment and staggered so three positions will expire every two years. The term of office for the member appointed from Woodburn High School shall be one (1) year from the date of appointment, which shall be in August. All other appointments shall be made annually, in December, or upon the expiration or other termination of the member's term of office. Each member of the Committee serves at the pleasure of the Mayor and City Council and may be removed prior to expiration of their terms without cause or hearing. Members may be removed by the Mayor pursuant to City resolution. In addition to the appointed members, the Mayor or the Mayor's representative and the Director will serve as ex-officio members.

[Section 2 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 3. Meetings.** The Board shall meet at such times as the Board may determine are appropriate and necessary. All Board meetings shall be conducted in accordance with the bylaws of the organization, the provisions of this ordinance and with law.

**Section 4. Officers.** The Recreation and Park Board shall, at its first annual meeting, elect a chairman, secretary and such other officers as the Board may deem appropriate. Officers shall have such duties and authority as the Board shall establish, consistent with its bylaws, other provisions of this ordinance and with law.

**Section 5. Board Responsibilities.** The Recreation and Park Board shall have the responsibility for advising and making recommendations to the Community Services Director, and when appropriate, to the Mayor and Council, on all matters pertaining to the planning, acquisition, development and management of leisure services operated or owned by the City near or adjacent thereto.

[Section 5 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 6. Budget.** The Recreation and Park Board shall participate in the preparation of the annual budget and shall recommend to the budget officer a budget for the expenditure of all funds produced by tax or other means for the development, promotion and management of parks, recreation facilities and leisure services in the City of Woodburn.

**Section 7. Rules and Regulations.** The Recreation and Park Board shall recommend to the Mayor and City Council reasonable rules and regulations governing the use and proper conduct of parks, recreation facilities and leisure services in the City of Woodburn.

**Section 8. Supervision of Director.** The City Administrator shall have the responsibility for the hiring, termination, discipline and any other personnel actions affecting the Community Services Director. The Board shall act in an advisory capacity in the selection, discipline, or termination of the Director.

[Section 8 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 9. Internal Administrative Policies and Procedures.** The City Administrator shall be the fiscal and internal administrative agent for the Recreation and Park Department and the department shall operate in conformance with city administrative procedures including those pertaining to the following: (1) Personnel, including recruitment, selection, classification and pay for department staff; (2) Personnel matters, including discipline and grievances; (3) Receipt, disbursement, and accounting for monies; (4) Maintenance of general books, cost accounting records, and other financial documents; (5) Purchasing; (6) Budget administration; and (7) Operation and maintenance of equipment and buildings.

**Section 10. Assistance to the Board.** The Director shall assist the Board in the performance of its duties, and shall prepare reports as requested by the Board.

**Section 11. Annual Reports.** The Recreation and Park Board shall make a full and complete report to the City Council and make such other reports as may be required by the Mayor and Council. The Community Services Director shall be responsible for the preparation of the report with Board input.

[Section 11 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 12. Repeal.** Ordinance No. 1796 is hereby repealed.

**Section 13.** [Emergency clause.]



*Passed by the Council June 26, 2000 and approved by the Mayor June 28, 2000.*

**ORDINANCE NO. 2304****AN ORDINANCE RELATING TO REAPPORTIONMENT OF WARD BOUNDARIES, REPEALING ORDINANCE 2075, AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**The City of Woodburn Ordains as Follows:**

**Section 1.** That the City Of Woodburn is hereby divided into six wards, which shall be designated as Wards I, II, III, IV, V, and VI.

**Section 2.** That the boundaries of the six wards created by section 1 above shall be as indicated on a map known as "Ward Map of 2001", a copy of which is attached hereto and, by this reference, incorporated herein.


**Section 3.** That two (2) copies of said ward map are on file in the office of the City Recorder, and said map of boundaries indicated thereon are hereby adopted until such time as they shall be amended or abolished by ordinance or Charter.

**Section 4.** That Ordinance 2075 is repealed.

**Section 5.** That a copy of this ordinance and the attached Ward Map of 2001 be sent to the elections department of Marion County.

**Section 6.** [Emergency clause.]

*Passed by the Council November 13, 2001 and approved by the Mayor*



---

ORDINANCE NO. 2284**AN ORDINANCE RELATING TO TELECOMMUNICATIONS WITHIN THE CITY; PROVIDING FOR THE MANAGEMENT OF PUBLIC RIGHTS OF WAY; AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose.** The purpose and intent of this Ordinance are to:

- (1) Comply with the 1996 Telecommunications Act as it applies to local governments, telecommunications carriers and the services those carriers offer;
- (2) Promote competition on a competitively neutral basis in the provision of telecommunications services;
- (3) Encourage the provision of advanced and competitive telecommunications services on the widest possible basis to the City's businesses and residents;
- (4) Permit and manage reasonable access to the City's public rights-of-way for telecommunications purposes on a competitively neutral basis and conserve the limited physical capacity of those public rights of way held in trust by the City;
- (5) Assure that the City's current and ongoing costs of granting and regulating private access to and the use of the public rights of way are fully compensated by the persons seeking such access and causing such costs;
- (6) Secure fair and reasonable compensation to the City and its residents for permitting private use of the public right of way;
- (7) Assure that all telecommunications carriers providing facilities or services within the City, or passing through the City, register and comply with the ordinances, rules and regulations of the City;
- (8) Assure that the City can continue to fairly and responsibly protect the public health, safety and welfare of its citizens;
- (9) Enable the City to discharge its public trust consistent with the rapidly evolving federal and state regulatory policies, industry competition and technological development.

**Section 2. Definitions.** As used in this Ordinance, the following definitions apply. Words not defined shall be given the meaning set forth in the Communications Policy Act of 1934, as amended, the Cable Communications Policy Act of 1984, the Cable Television Consumer Protection and Competition Act of 1992, and the Telecommunications Act of 1996. If not defined there, the words shall be given their common and ordinary meaning.

- (1) "Aboveground Facilities" See Overhead Facilities.

- (2) "Affiliated Interest" has the same meaning as ORS 759.010.
- (3) "Cable Act" means the Cable Communications Policy Act of 1984, 47 U.S.C. § 521, et seq., as now and hereafter amended.
- (4) "Cable service" is defined consistent with federal laws and means the one-way transmission to subscribers of video programming, or other programming service; and subscriber interaction, if any, which is required for the selection or use of such video programming or other programming service.
- (5) "City" means the City of Woodburn, an Oregon municipal corporation, and individuals authorized to act on the City's behalf.
- (6) "City Administrator" means the City Administrator of the City of Woodburn.
- (7) "City Engineer" means the City Engineer of the City of Woodburn.
- (8) "City property" includes all real property owned by the City, other than public rights of way and utility easements as defined in this ordinance, and all property held in a proprietary capacity by the City that are not subject to right of way franchising under this Ordinance.
- (9) "Control" or "controlling interest" means actual working control in whatever manner exercised.
- (10) "Conduit" means any structure or portion of a structure containing one or more ducts, conduits, manholes, handholes, bolts, or other facilities used for telegraph, telephone, cable television, electrical, or communications conductors, or cable right of way, owned or controlled, in whole or in part, by one or more public utilities.
- (11) "Construction" means an activity in the public rights of way resulting in physical change, including excavation or placement of structures, but excluding routine maintenance or repair of existing facilities.
- (12) "Days" means calendar days unless otherwise specified.
- (13) "Duct" means a single enclosed raceway for conductors or cable.
- (14) "Emergency" has the meaning provided for in ORS 401.025.
- (15) "Federal Communications Commission" or "FCC" means the federal administrative agency, or its lawful successor, authorized to regulate and oversee telecommunications carriers, services and providers on a national level.

(16) "Franchise" means an agreement between the City and a grantee which grants a privilege to use public right of way and utility easements within the City for a dedicated purpose and for specific compensation.

(17) "Grantee" means the person to which a franchise is granted by the City.

(18) "Oregon Public Utilities Commission" or "OPUC" means the statutorily-created state agency in the State of Oregon responsible for licensing, regulation and administration of certain telecommunications carriers as set forth in Oregon Law, or its lawful successor.

(19) "Overhead" or "Aboveground Facilities" means utility poles, utility facilities and telecommunications facilities on or above the surface of the ground, including the underground supports and foundations for such facilities.

(20) "Person" means an individual, corporation, company, association, joint stock company or association, firm, partnership, or limited liability company.

(21) "Private telecommunications network" means a system, including the construction, maintenance or operation of the system, for the provision of a service or portion of a service that is owned or operated exclusively by a person for his or her use and not for resale, directly or indirectly. "Private telecommunications network" includes services provided by the State of Oregon pursuant to ORS 190.240 and 283.140.

(22) "Public rights of way" means a strip of land reserved for public uses such as roadways and sewer and water lines and includes, but is not limited to, streets, roads, highways, bridges, alleys, sidewalks, trails, paths, public easements, and all other public ways or areas, including the subsurface under and air space over these areas. This definition applies only to the extent of the City's right, title, interest or authority to grant a franchise to occupy and use such areas for telecommunications facilities. "Public rights of way" also includes utility easements as defined below.

(23) "Telecommunications" means the transmission between and among points specified by the user, of information of the user's choosing, without change in the form or content of the information as sent and received.

(24) "Telecommunications Act" means the Communications Policy Act of 1934, as amended by subsequent enactments including the Telecommunications Act of 1996 (47 U.S.C. 151 et seq.) and as hereafter amended.

(25) Telecommunications carrier means a provider of telecommunications services and includes every person that directly or indirectly owns, controls, operates or manages telecommunications facilities within the City.

(25) "Telecommunications facilities" means the plant and equipment, other than customer premises equipment, used by a telecommunications carrier.

(26) "Telecommunications service" means two-way switched access and transport of voice communications but does not include: a) services provided by radio common carrier; b) one-way transmission of television signals; c) surveying; d) private telecommunications networks; or e) communications of the customer which take place on the customer side of on-premises equipment.

(27) "Telecommunications system" see "Telecommunications facilities" above.

(28) "Telecommunications utility" has the same meaning as ORS 759.005(1).

(29) "Underground facilities" means utility and telecommunications facilities located under the surface of the ground, excluding the underground foundations or supports for "Overhead facilities."

(30) "Usable space" means all the space on a pole, except the portion below ground level, the 20 feet of safety clearance space above ground level, and the safety clearance space between communications and power circuits. There is a rebuttable presumption that six feet of a pole is buried below ground level.

(31) "Utility easement" means an easement granted to or owned by the City and acquired, established, dedicated or devoted for public utility purposes.

(32) "Utility facilities" means the plant, equipment and property, including but not limited to the poles, pipes, mains, conduits, ducts, cable, wires, plant and equipment located under, on, or above the surface of the ground within the public right of way of the City and used or to be used for the purpose of providing utility or telecommunications services.

### **Section 3. Jurisdiction and Management of the Public Rights of Way**

(1) The City has jurisdiction and exercises regulatory management over all public rights of way within the City under authority of the City charter and state law.

(2) Public rights of way include, but are not limited to, streets, roads, highways, bridges, alleys, sidewalks, trails, paths, public easements and all other public ways or areas, including the subsurface under and air space over these areas.

(3) The City has jurisdiction and exercises regulatory management over each public right of way whether the City has a fee, easement, or other legal interest in the right of way. The City has jurisdiction and regulatory management of each right of way whether the legal interest in the right of way was obtained by grant, dedication, prescription, reservation, condemnation, annexation, foreclosure or other means.

(4) No person may occupy or encroach on a public right of way without the permission of the City. The City grants permission to use rights of way by franchises and permits.

(5) The exercise of jurisdiction and regulatory management of a public right of way by the City is not official acceptance of the right of way, and does not obligate the City to maintain or repair any part of the right of way.

(6) The City retains the right and privilege to cut or move any telecommunications facilities located within the public rights of way of the City, as the City may determine to be necessary, appropriate or useful in response to a public health or safety emergency.

#### **Section 4. Regulatory Fees and Compensation Not a Tax.**

(1) The fees and costs provided for in this Ordinance, and any compensation charged and paid for use of the public rights of way provided for in this Ordinance, are separate from, and in addition to all federal, state, local, and City charges as may be levied, imposed, or due from a telecommunications carrier, its customers or subscribers, or on account of the lease, sale, delivery, or transmission of telecommunications services.

(2) The City has determined that any fee provided for by this Ordinance is not subject to the property tax limitations of Article XI, Sections 11 and 11b of the Oregon Constitution. These fees are not imposed on property or property owners, and these fees are not new or increased fees.

(3) The fees and costs provided for in this Ordinance are subject to applicable federal and state laws.

#### **Section 5. Purpose of Registration.** The purpose of registration is:

(1) To assure that all telecommunications carriers who have facilities or provide services within the City comply with the ordinances, rules and regulations of the City.

(2) To provide the City with accurate and current information concerning the telecommunications carriers who offer to provide telecommunications services within the City, or that own or operate telecommunications facilities within the City.

(3) To assist the City in the enforcement of this Ordinance and the collection of any city franchise fees or charges that may be due the City.

#### **Section 6. Registration Required.**

(1) Except as provided in Section 7 of this ordinance, all telecommunications carriers having telecommunications facilities within the corporate limits of the City, and all telecommunications carriers that offer or provide telecommunications service to customer premises within the City, shall register with the City. The appropriate application and license from the Oregon Public Utility Commission (PUC) or the Federal Communications Commission (FCC) qualify as necessary registration information. Applicants also have the option of providing the following information:



(a) The identity and legal status of the registrant, including the name, address, and telephone number of the duly authorized officer, agent, or employee responsible for the accuracy of the registration information.

(b) The name, address, and telephone number for the duly authorized officer, agent, or employee to be contacted in case of an emergency.

(c) A description of the registrant's existing or proposed telecommunications facilities within the City, a description of the telecommunications facilities that the registrant intends to construct, and a description of the telecommunications service that the registrant intends to offer or provide to persons, firms, businesses, or institutions within the City.

(d) Information sufficient to determine whether the transmission, origination or receipt of the telecommunications services provided, or to be provided, by the registrant constitutes an occupation or privilege subject to any business license requirements. A copy of the business license or the license number must be provided.

(2) Each application for registration as a telecommunications carrier shall be accompanied by a nonrefundable registration fee in an amount to be determined by resolution of the City Council

**Section 7. Exceptions to Registration.** The following telecommunications carriers are excepted from registration:

(1) Telecommunications facilities that are owned and operated exclusively for its own use by the State or a political subdivision of this State.

(2) A private telecommunications network, provided that such network does not occupy any public rights of way of the City.

**Section 8. Construction Standards.**

(1) No person shall commence or continue with the construction, installation or operation of telecommunications facilities within a public right of way except as provided in this Ordinance, and with all other applicable codes, ordinances, rules, and regulations.

(2) Telecommunications facilities shall be constructed, installed, operated and maintained in accordance with all applicable federal, state and local codes, rules and regulations including the National Electrical Code and the National Electrical Safety Code.

**Section 9. Construction Permits.** No person shall construct or install any telecommunications facilities within a public right of way without first obtaining a construction permit, and paying the construction permit fee established in this Ordinance. No permit shall be issued for the construction or installation of telecommunications facilities within a public right of way unless:

(1) The telecommunications carrier has first filed a registration statement with the City pursuant to this Ordinance; and if applicable,

(2) The telecommunications carrier has first applied for and received a franchise pursuant to this Ordinance.

#### **Section 10. Permit Applications.**

(1) Applications for permits to construct telecommunications facilities shall be submitted upon forms to be provided by the City and shall be accompanied by drawings, plans and specifications in sufficient detail to demonstrate:

(a) That the facilities will be constructed in accordance with all applicable codes, rules and regulations.

(b) That the facilities will be constructed in accordance with the franchise agreement.

(c) The location and route of all facilities to be installed aboveground or on existing utility poles.

(d) The location and route of all new facilities on or in the public rights of way to be located under the surface of the ground, including the line and grade proposed for the burial at all points along the route that are within the public rights of way. Applicant's existing facilities shall be differentiated on the plans from new construction.

(e) The location of all of applicant's existing underground utilities, conduits, ducts, pipes, mains and installations which are within the public rights of way along the underground route proposed by the applicant. A cross section shall be provided showing new or existing facilities in relation to the street, curb, sidewalk or right of way.

(f) The construction methods to be employed for protection of existing structures, fixtures, and facilities within or adjacent to the public rights of way, and description of any improvements that applicant proposes to temporarily or permanently remove or relocate.

(g) Details of work area restoration including but limited to paving, compaction, landscaping.

(2) All permit applications shall be accompanied by the verification of a registered professional engineer, or other qualified and duly authorized representative of the applicant, that the drawings, plans and specifications submitted with the application comply with applicable technical codes, rules and regulations.

(3) All permit applications shall be accompanied by a written construction schedule, which shall include a deadline for completion of construction. The construction schedule is subject to approval by the City Engineer.

(4) City will review application and may make requests for elevation and horizontal location to eliminate planned existing conflicts with other underground lines.

**Section 11. Construction Permit Fee.** Unless otherwise provided in a franchise agreement, prior to issuance of a construction permit, the applicant shall pay a permit fee in an amount to be determined by resolution of the City Council. Such fees shall be designed to defray the costs of city administration of the requirements of this ordinance.

**Section 12. Issuance of Permit.** If satisfied that the applications, plans and documents submitted comply with all requirements of this Ordinance and the franchise agreement, the City Engineer shall issue a permit authorizing construction of the facilities, subject to such further conditions, restrictions or regulations affecting the time, place and manner of performing the work as they may deem necessary or appropriate.

**Section 13. Notice of Construction.** Except in the case of an emergency, the permittee shall notify the Engineering and Building Department not less than two working days in advance of any excavation or construction in the public rights of way.

**Section 14. Compliance with Permit.** All construction practices and activities shall be in accordance with the permit and approved final plans and specifications for the facilities. The Engineering and Building Department and its representatives shall be provided access to the work site and such further information as they may require to ensure compliance with such requirements.

**Section 15. Noncomplying Work.** Subject to the notice requirements in Section 13, all work that does not comply with the permit, the approved or corrected plans and specifications for the work, or the requirements of this Ordinance, shall be removed at the sole expense of the permittee. The City is authorized to stop work in order to assure compliance with this Ordinance.

**Section 16. Completion of Construction.** The permittee shall comply with any time lines and special construction activity conditions placed on the construction permit and promptly complete all construction activities so as to minimize disruption of the city rights of way and other public and private property. All construction work within city rights of way, including restoration, must be completed within 120 days of the date of issuance of the construction permit unless an extension or an alternate schedule has been approved by the City Engineer.

**Section 17. As-Built Drawings.** If requested by the City for a necessary public purpose, as determined by the City, the permittee shall furnish the City with up to two complete sets of plans drawn to scale and certified to the City as accurately depicting

the location of all telecommunications facilities constructed pursuant to the permit. These plans shall be submitted to the City Engineer or designee within 60 days after completion of construction, in a format mutually acceptable to the permittee and the City.

#### **Section 18. Restoration of Public Rights of Way and City Property.**

(1) When a permittee, or any person acting on its behalf, does any work in or affecting a public right of way or City property, it shall, at its own expense, promptly remove any obstructions and restore the ways or property to good order and condition unless otherwise directed by the City and as determined by the City Engineer or designee.

(2) If weather or other conditions do not permit the complete restoration required by this Section, the permittee shall temporarily restore the affected rights of way or property at the permittee's sole expense. The permittee shall promptly undertake and complete the required permanent restoration when the weather or other conditions no longer prevent such permanent restoration. Any corresponding modification to the construction schedule may be subject to approval by the City.

(3) If the permittee fails to restore rights of way or property to good order and condition, the City shall give the permittee written notice and provide the permittee a reasonable period of time not exceeding 30 days to restore the rights of way or property. If, after said notice, the permittee fails to restore the rights of way or property to as good a condition as existed before the work was undertaken, the City shall cause such restoration to be made at the expense of the permittee.

(4) A permittee or other person acting in its behalf shall use suitable barricades, flags, flagging attendants, lights, flares and other measures as required for the safety of all members of the general public and to prevent injury or damage to any person, vehicle or property by reason of such work in or affecting such rights of way or property.

**Section 19. Performance and Completion Bond.** Unless otherwise provided in a franchise agreement, a performance bond or other form of surety acceptable to the City equal to at least 100% of the estimated cost of constructing permittee's telecommunications facilities within the public rights of way of the City, shall be provided before construction is commenced.

(1) The surety shall remain in force until 60 days after substantial completion of the work, as determined in writing by the City Engineer, including restoration of public rights of way and other property affected by the construction.

(2) The surety shall guarantee, to the satisfaction of the City:

(a) Timely completion of construction;

(b) Construction in compliance with applicable plans, permits, technical codes and standards;

(c) Proper location of the facilities as specified by the City;

(d) Restoration of the public rights of way and other property affected by the construction; and

(e) Timely payment and satisfaction of all claims, demands or liens for labor, material, or services provided in connection with the work.

(f) Maintenance for one year of trench areas, pavement, landscaping, and areas disrupted by the construction.

**Section 20. Location of Facilities.** All facilities located within the public right of way shall be constructed, installed and located in accordance with the following terms and conditions, unless otherwise specified in a franchise agreement:

(1) Whenever all existing electric utilities, cable facilities or telecommunications facilities are located underground within a public right of way of the City, a grantee with permission to occupy the same public right of way must also locate its telecommunications facilities underground.

(2) Whenever all new or existing electric utilities, cable facilities or telecommunications facilities are located or relocated underground within a public right of way of the City, a grantee that currently occupies the same public right of way shall relocate its facilities underground concurrently with the other affected utilities to minimize disruption of the public right of way, absent extraordinary circumstances or undue hardship as determined by the City and consistent with applicable state and federal law.

**Section 21. Interference with Public Rights of Way.** No grantee may locate or maintain its telecommunications facilities so as to unreasonably interfere with the use of the public rights of way by the City, by the general public or by other persons authorized to use or be present in or upon the public rights of way. All use of public rights of way shall be consistent with City codes, ordinances and regulations.

**Section 22. Relocation or Removal of Facilities.** Except in the case of an emergency, within 90 days following written notice from the City, a grantee shall, at no expense to Grantor, temporarily or permanently remove, relocate, change or alter the position of any telecommunications facilities within the public rights of way whenever the City has determined that such removal, relocation, change or alteration is reasonably necessary for:

(1) The construction, repair, maintenance or installation of any city or other public improvement in or upon the public rights of way.

(2) The operations of the City or other governmental entity in or upon the public rights of way.

(3) The public interest.

**Section 23. Removal of Unauthorized Facilities.** Within 30 days following written notice from the City, any grantee, telecommunications carrier, or other person that owns, controls or maintains an unauthorized telecommunications system, facility, or related appurtenances within the public rights of way of the City shall, at its own expense, remove such facilities and appurtenances from the public rights of way of the City. Both parties are required to participate in good faith negotiations on such issues. A telecommunications system or facility is unauthorized and subject to removal in the following circumstances:

(1) One year after the expiration or termination of the grantee's telecommunications franchise.

(2) Upon abandonment of a facility within the public rights of way of the City. A facility will be considered abandoned when it is deactivated, out of service, or not used for its intended and authorized purpose for a period of 90 days or longer. A facility will not be considered abandoned if it is temporarily out of service during performance of repairs or if the facility is being replaced. The City shall make a reasonable attempt to contact the telecommunications carrier before concluding that a facility is abandoned. A facility may be abandoned in place and not removed if there is no apparent risk to the public safety, health, or welfare.

(3) If the system or facility was constructed or installed without the appropriate prior authority at the time of installation.

(4) If the system or facility was constructed or installed at a location not permitted by the grantee's telecommunications franchise or other legally sufficient permit.

**Section 24. Coordination of Construction Activities.** All grantees are required to make a good faith effort to cooperate with the City.

(1) By January 1 of each year, grantees shall provide the City with a schedule of their known proposed construction activities in, around or that may affect the public rights of way.

(2) If requested by the City, each grantee shall meet with the City annually or as determined by the City, to schedule and coordinate construction in the public rights of way. At that time, City will provide available information on plans for local, state, and/or federal construction projects.

(3) All construction locations, activities and schedules shall be coordinated, as ordered by the City Engineer or designee, to minimize public inconvenience, disruption or damages.

**Section 25. Telecommunications Franchise.** A telecommunications franchise shall be required of any telecommunications carrier who desires to occupy public rights of way of the City.

**Section 26. Application.** Any person that desires a telecommunications franchise must register as a telecommunications carrier and shall file an application with the City which includes the following information:

- (1) The identity of the applicant.
- (2) A description of the telecommunications services that are to be offered or provided by the applicant over its telecommunications facilities.
- (3) Engineering plans, specifications, and a network map in a form customarily used by the applicant of the facilities located or to be located within the public rights of way in the City, including the location and route requested for applicant's proposed telecommunications facilities.
- (4) The area or areas of the City the applicant desires to serve and a preliminary construction schedule for build-out to the entire franchise area.
- (5) Information to establish that the applicant has obtained all other governmental approvals and permits to construct and operate the facilities and to offer or provide the telecommunications services proposed.
- (6) An accurate map showing the location of any existing telecommunications facilities in the City that applicant intends to use or lease.

**Section 27. Application and Review Fee.**

- (1) Subject to applicable state law, applicant shall reimburse the City for such reasonable costs as the City incurs in entering into the franchise agreement.
- (2) An application and review fee of \$2,000 shall be deposited with the City as part of the application filed pursuant to Section 26 above. Expenses exceeding the deposit will be billed to the applicant or the unused portion of the deposit will be returned to the applicant following the determination granting or denying the franchise.

**Section 28. Determination by the City.** The City Council shall issue a written determination granting or denying the application in whole or in part. If the application is denied, the written determination shall include the reasons for denial.

**Section 29. Rights Granted.** No franchise granted pursuant to this Ordinance shall convey any right, title or interest in the public rights of way, but shall be deemed a grant to use and occupy the public rights of way for the limited purposes and term, and upon the conditions stated in the franchise agreement.

**Section 30. Term of Grant.** Unless otherwise specified in a franchise agreement, a telecommunications franchise shall be for a term of five years.

**Section 31. Franchise Territory.** Unless otherwise specified in a franchise agreement, a telecommunications franchise shall be limited to a specific geographic area of the City to be served by the franchise grantee, and the public rights of way necessary to serve such areas, and may include the entire city.

**Section 32. Franchise Fee.** Each franchise granted by the City is subject to the City's right, which is expressly reserved, to fix a fair and reasonable compensation to be paid for the privileges granted. Nothing in this Ordinance shall prohibit the City and a grantee from agreeing to the compensation to be paid. The compensation shall be subject to the specific payment terms and conditions contained in the franchise agreement and applicable state and federal laws.

**Section 33. Amendment of Grant.** Conditions for amending a franchise:

(1) A new application and grant shall be required of any telecommunications carrier that desires to extend or locate its telecommunications facilities in public rights of way of the City that are not included in a franchise previously granted under this Ordinance.

(2) If ordered by the City to locate or relocate its telecommunications facilities in public rights of way not included in a previously granted franchise, the City shall grant an amendment without further application.

(3) A new application and grant shall be required of any telecommunications carrier that desires to provide a service which was not included in a franchise previously granted under this Ordinance.

**Section 34. Renewal Applications.** A grantee that desires to renew its franchise under this Ordinance shall file an application with the City for renewal of its franchise, not less than 180 days before expiration of the current agreement, which shall include the following information:

(1) The information required under Section 26 of this Ordinance.

(2) Any information required pursuant to the franchise agreement between the City and the grantee.

**Section 35. Renewal Determinations.** Within 90 days after receiving a complete renewal application under Section 34, the City shall issue a written determination granting or denying the renewal application in whole or in part, applying the following standards. If the renewal application is denied, the written determination shall include the reasons for non-renewal.

(1) The financial and technical ability of the applicant.

(2) The legal ability of the applicant.



(3) The continuing capacity of the public rights of way to accommodate the applicant's existing and proposed facilities.

(4) The applicant's compliance with the requirements of this Ordinance and the franchise agreement.

(5) Applicable federal, state and local telecommunications laws, rules and policies.

(6) Such other factors as may demonstrate that the continued grant to use the public rights of way will serve the community interest.

**Section 36. Obligation to Cure As a Condition of Renewal.** No franchise shall be renewed until all ongoing violations or defaults in the grantee's performance of the agreement, or of this Ordinance, have been cured, or a plan detailing the corrective action to be taken by the grantee has been approved by the City Council.

**Section 37. Assignments or Transfers of System or Franchise.** Ownership or control of a majority interest in a telecommunications system or franchise may not, directly or indirectly, be transferred, assigned or disposed of by sale, lease, merger, consolidation or other act of the grantee, by operation of law or otherwise, without the prior consent of the City, which consent shall not be unreasonably withheld or delayed, and then only on such reasonable conditions as may be prescribed in such consent.

(1) Grantee and the proposed assignee or transferee of the franchise or system shall agree, in writing, to assume and abide by all of the provisions of the franchise.

(2) No transfer shall be approved unless the assignee or transferee has the legal, technical, financial and other requisite qualifications to own, hold and operate the telecommunications system pursuant to this Ordinance.

(3) Unless otherwise provided in a franchise agreement, the grantee shall reimburse the City for all direct and indirect fees, costs, and expenses reasonably incurred by the City in considering a request to transfer or assign a telecommunications franchise.

(4) A transfer or assignment of a telecommunications franchise, system or integral part of a system without prior approval of the City Council under this Section or under a franchise agreement shall be void and is cause for revocation of the franchise.

**Section 38. Revocation or Termination of Franchise.** A franchise to use or occupy public rights of way of the City may be revoked for the following reasons:

(1) Construction or operation in the City or in the public rights of way of the City without a construction permit.

(2) Construction or operation at an unauthorized location.

(3) Failure to comply with Section 37 of this Ordinance with respect to sale, transfer or assignment of a telecommunications system or franchise.

(4) Misrepresentation by or on behalf of a grantee in any application to the City.

(5) Abandonment of telecommunications facilities in the public rights of way. As used in this ordinance, "abandonment" refers to facilities remaining in the right of way following the expiration of the franchise, or not otherwise used to provide services, for a period of one year.

(6) Failure to relocate or remove facilities as required in this Ordinance.

(7) Failure to pay taxes, compensation, fees or costs when and as due the City under this ordinance.

(8) Insolvency or bankruptcy of the grantee.

(9) Violation of material provisions of this Ordinance.

(10) Violation of the material terms of a franchise agreement.

**Section 39. Notice and Duty to Cure.** If the City believes that grounds exist for revocation of a franchise, the City shall give the grantee written notice of the apparent violation or noncompliance, providing a short and concise statement of the nature and general facts of the violation or noncompliance, and providing the grantee a reasonable period of time, not exceeding 30 days, to furnish evidence that:

(1) Corrective action has been, or is being actively and expeditiously pursued, to remedy the violation or noncompliance;

(2) Rebuts the alleged violation or noncompliance; and/or

(3) It would be in the public interest to impose some penalty or sanction less than revocation.

**Section 40. Public Hearing.** If a grantee fails to provide evidence reasonably satisfactory to the City as provided in Section 39, the City Administrator may refer the apparent violation or non-compliance to the City Council. The City Council shall provide the grantee with notice and a reasonable opportunity to be heard concerning the matter.

**Section 41. Standards for Revocation or Lesser Sanctions.** If persuaded that the grantee has violated or failed to comply with material provisions of this Ordinance, or of a franchise agreement, the City Council shall determine whether to revoke the

franchise, or to establish some lesser sanction and cure, considering the nature, circumstances, extent, and gravity of the violation as reflected by one or more of the following factors. Whether:

- (1) The misconduct was egregious.
- (2) Substantial harm resulted.
- (3) The violation was intentional.
- (4) There is a history of prior violations of the same or other requirements.
- (5) There is a history of overall compliance.
- (6) The violation was voluntarily disclosed, admitted or cured.

**Section 42. Other City Costs.** All grantees shall, within 30 days after written demand, reimburse the City for all reasonable direct and indirect costs and expenses incurred by the City in connection with any modification, amendment, renewal or transfer of the franchise or any franchise agreement consistent with applicable state and federal laws.

**Section 43. Facilities.** Upon request, each grantee shall provide the City with an accurate map or maps certifying the location of all telecommunications facilities within the public rights of way. Grantees shall provide updated maps to the City semi-annually.

**Section 44. Damage to Grantee's Facilities.** Unless directly and proximately caused by negligent, careless, wrongful, willful, intentional or malicious acts by the City, and consistent with Oregon law, the City shall not be liable for any damage to or loss of any telecommunications facility within the public rights of way of the City as a result of or in connection with any public works, public improvements, construction, excavation, grading, filling, or work of any kind in the public rights of way by or on behalf of the City, or for any consequential losses resulting directly or indirectly from such acts.

**Section 45. Duty to Provide Information.** Except in emergencies, within 60 days of a written request from the City, each grantee shall furnish the City with the following:

- (1) Information sufficient to demonstrate that grantee has complied with all requirements of this Ordinance.
- (2) All books, records, maps, and other documents, maintained by the grantee with respect to its facilities within the public rights of way shall be made available for inspection by the City at reasonable times and intervals.

**Section 46. Service to the City.** If the City contracts for the use of telecommunication facilities, telecommunication services, installation, or maintenance from the grantee, the grantee shall charge the City the grantee's most favorable rate

offered at the time of the request charged to similar users within Oregon for a similar volume of service, subject to any of grantee's tariffs or price lists on file with the OPUC. With the City's permission, the grantee may deduct the applicable charges from fee payments. Other terms and conditions of such services may be specified in a separate agreement between the City and grantee.

**Section 47. Compensation for City Property.** If any right is granted, by lease, franchise or other manner, to use and occupy city property for the installation of telecommunications facilities, the compensation to be paid for such right and use shall be fixed by the City.

**Section 48. Cable Franchise.** Telecommunication carriers providing cable service shall be subject to the requirements for cable franchises.

**Section 49. Leased Capacity.** A grantee has the right, without prior City approval, to offer or provide capacity or bandwidth to its customers; however, the grantee shall notify the City that such lease or agreement has been granted to a customer or lessee.

**Section 50. Grantee Insurance.** Unless otherwise provided in a franchise agreement, each grantee shall, as a condition of the grant, secure and maintain the following liability insurance policies insuring both the grantee and the City, and its elected and appointed officers, officials, agents and employees as coinsured:

- (1) Comprehensive general liability insurance with limits not less than
  - (a) \$3,000,000 for bodily injury or death to each person;
  - (b) \$3,000,000 for property damage resulting from any one accident;and,
  - (c) \$3,000,000 for all other types of liability.
- (2) Automobile liability for owned, non-owned and hired vehicles with a limit of \$1,000,000 for each person and \$3,000,000 for each accident.
- (3) Worker's compensation within statutory limits and employer's liability insurance with limits of not less than \$1,000,000.
- (4) Comprehensive form premises-operations, explosions and collapse hazard, underground hazard and products completed hazard with limits of not less than \$3,000,000.
- (5) The grantee shall maintain liability insurance policies required by this Section throughout the term of the telecommunications franchise, and such other period of time during which the grantee is operating without a franchise, or is engaged in the removal of its telecommunications facilities. Each such insurance policy shall contain the following endorsement:

"It is hereby understood and agreed that this policy may not be canceled nor the intention not to renew be stated until 90 days after receipt by the City, by registered mail, of a written notice addressed to the Woodburn City Attorney of such intent to cancel or not to renew."

(6) Within 60 days after receipt by the City of said notice, and in no event later than 30 days prior to cancellation, the grantee shall obtain and furnish evidence to the City that the grantee meets the requirements of this Section.

(7) As an alternative to the insurance requirements listed above, a grantee may provide evidence of self-insurance subject to review and acceptance by the City.

(8) Grantees shall either provide insurance coverage as described above for their contractors and subcontractors or require that the contractors and subcontractors provide evidence of such insurance coverage before beginning work in the public rights of way

**Section 51. General Indemnification.** To the extent permitted by law, each franchise agreement shall include grantee's express undertaking to defend, indemnify and hold the City and its officers, employees, agents and representatives harmless from and against any and all damages, losses and expenses, including reasonable attorney's fees and costs of suit or defense, arising out of, resulting from or alleged to arise out of or result from the negligent, careless or wrongful acts, omissions, failures to act or misconduct of the grantee or its affiliates, officers, employees, agents, contractors or subcontractors in the construction, operation, maintenance, repair or removal of its telecommunications facilities, and in providing or offering telecommunications services over the facilities or network, whether such acts or omissions are authorized, allowed or prohibited by this Ordinance or by a franchise agreement made or entered into pursuant to this Ordinance.

**Section 52. Performance Surety.** Before a franchise granted pursuant to this Ordinance is effective, and as necessary thereafter, the grantee shall provide a performance bond, in form and substance acceptable to the City, as security for the full and complete performance of a franchise granted under this Ordinance, including any costs, expenses, damages or loss the City pays or incurs because of any failure attributable to the grantee to comply with the codes, ordinances, rules, regulations or permits of the City. This obligation is in addition to the performance surety required by Section 19 of this Ordinance for construction of facilities.

**Section 53. Governing Law.** A franchise granted under this Ordinance is subject to the Constitution and laws of the United States, the State of Oregon and the ordinances and Charter of the City.

**Section 54. Written Agreement.** No franchise shall be granted under this ordinance unless the agreement is in writing.

**Section 55. Nonexclusive Grant.** No franchise granted under this Ordinance shall confer any exclusive right, privilege, license or franchise to occupy or use the public rights of way of the City for delivery of telecommunications services or any other purposes.

**Section 56. Severability and Preemption.** If any article, section, subsection, sentence, clause, phrase, term, provision, condition, covenant or portion of this Ordinance is for any reason held to be invalid or unenforceable by a court of competent jurisdiction, or superseded by state or federal legislation, rules, regulations or decision, the remainder of the Ordinance shall not be affected but shall be deemed as a separate, distinct and independent provision, and such holding shall not affect the validity of the remaining portions. Each remaining section, subsection, sentence, clause, phrase, provision, condition, covenant and portion of this Ordinance shall be valid and enforceable to the fullest extent permitted by law. If federal or state laws, rules or regulations preempt a provision or limit the enforceability of a provision of this Ordinance, then the provision shall be read to be preempted only to the extent required by law. If such federal or state law, rule, or regulation is subsequently repealed, rescinded, amended or otherwise changed so that the provision that had been preempted is no longer preempted, such provision shall return to full force and effect, and shall be binding, without the requirement of further action on the part of the City.

**Section 57. Penalty.** In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class I Civil Infraction which shall be processed according to the procedures contained in the Woodburn Civil Infraction Ordinance. Each violation of this Ordinance constitutes a separate Civil Infraction, and each day that a violation of this Ordinance is committed or permitted to continue shall constitute a separate Civil Infraction.

**Section 58. Other Remedies.** Nothing in this Ordinance shall be construed as limiting any judicial remedies that the City may have, at law or in equity, for enforcement of this Ordinance.

**Section 59. Captions.** The captions to sections throughout this Ordinance are intended solely to facilitate reading and reference to the sections. Such captions shall not affect the meaning or interpretation of this Ordinance and constitute no part of the law.

**Section 60. Compliance with Laws.** A grantee under this Ordinance shall comply with all federal and state laws and regulations, including regulations of its administrative agencies, as well as all ordinances, resolutions, rules and regulations of the City adopted or established during the entire term of a franchise granted under this Ordinance, that are relevant and relate to the construction, maintenance and operation of a telecommunications system.

**Section 61. Consent.** Wherever the consent of either the City or of the grantee is specifically required by this Ordinance or in a franchise granted, such consent will not be unreasonably withheld.

**Section 62. Application to Existing Ordinance and Agreements.** To the extent that this Ordinance is not in conflict with and can be implemented with existing ordinance and franchise agreements, this Ordinance shall apply to all existing ordinance and franchise agreements for use of the public right of way for telecommunications.

**Section 63. Confidentiality.** The City shall preserve the confidentiality of information as requested by a grantee, to the extent permitted by the Oregon Public Records Law.

**Section 64.** [Emergency clause.]

*Passed by the Council April 12, 2001, and approved by the Mayor April 13, 2001.*

## ORDINANCE NO. 2315

AN ORDINANCE ADOPTING PROCEDURES TO PREPARE FOR AND CARRY OUT ACTIVITIES TO PREVENT, MINIMIZE, RESPOND TO OR RECOVER FROM EMERGENCIES; PROVIDING A PROCESS FOR THE DECLARATION OF A STATE OF EMERGENCY; GRANTING THE AUTHORITY TO ORDER MANDATORY EVACUATIONS; PRESCRIBING A PENALTY; AND DECLARING AN EMERGENCY.

[Whereas clauses.]

THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Title.** This ordinance shall be known as the Emergency Management Ordinance of the City of Woodburn.

**Section 2. Purpose.** The purpose of this ordinance is to provide procedures to minimize injuries to persons and property and to prepare for, respond to, and recover from any emergency within the incorporated area of the City of Woodburn. This ordinance is implemented by the City of Woodburn Emergency Management Plan. The authority to enact this ordinance is granted by the Woodburn Charter and ORS Chapter 401.

**Section 3. Definition of Emergency.** "Emergency" is defined pursuant to ORS 401.025(4) as "any man-made or natural event or circumstance causing or threatening loss of life, injury to person or property, human suffering or financial loss, and includes, but is not limited to, fire, explosion, flood, severe weather, drought, earthquake, volcanic activity, spills or releases of oil or hazardous material as defined in ORS 466.605, contamination, utility or transportation emergencies, disease, blight, infestation, crisis influx of migrants unmanageable by the county, civil disturbance, riot, sabotage and war."

**Section 4. Emergency Management Agency.** Pursuant to ORS 401.305, an "Emergency Management Agency" for the City of Woodburn is hereby established as specified in the City of Woodburn Emergency Management Plan which is incorporated herein by reference. The functions of the Emergency Management Agency include, but are not limited to, program development, fiscal management, coordination with government and nongovernmental agencies and organizations, public information, personnel training and development and implementation of exercises to test the system.

**Section 5. Emergency Management Plan.** The procedures to prepare for and carry out any activity to prevent, minimize, respond to or recover from emergencies within the City of Woodburn are set out in the City of Woodburn Emergency Management Plan which is incorporated herein by reference.

**Section 6. Emergency Program Manager.** The City Administrator shall appoint an Emergency Program Manager who shall be responsible for the organization, administration, and operation of the agency and coordination of emergency activities



with county, state, and other governments and private organizations, subject to the direction and control of the City Council and City Administrator.

**Section 7. Declaration of State of Emergency.** The authority to declare a state of emergency is delegated to the City Administrator. If the City Administrator is unable to act due to absence or incapacity, the Emergency Program Manager is delegated authority. If in the judgment of the Incident Commander, time does not permit access to the others authorized, the Incident Commander may declare a state of emergency. The City Council shall convene as soon as practical to ratify the state of emergency declaration. The declaration must include a description of the situation, existing conditions, and must delineate the geographic boundaries involved.

**Section 8. Conditions Required to Declare a State of Emergency.** A state of emergency may be declared whenever an event or circumstance exists within the City of Woodburn that meets the definition of an emergency and requires a response under the City of Woodburn Emergency Management Plan.

**Section 9. Authority to Order Mandatory Evacuations.** After a state of emergency has been declared, the City Administrator or Incident Commander may order mandatory evacuations of residents and other individuals pursuant to the City of Woodburn Emergency Management Plan if necessary for public safety or the efficient conduct of activities that minimize or mitigate the effects of the emergency.

**Section 10. Penalty.**

A. Any person, firm, corporation, association or entity who violates any emergency measure taken under the authority of this ordinance shall be subject, upon conviction, to a fine of not more than \$500 per offense.

B. Each day of violation shall be deemed a separate offense for purposes of imposition of penalty.

C. The penalty provisions contained in this ordinance are in addition to and not in lieu of any other procedures and remedies provided to the city by law, including equitable relief and damages.

**Section 11. Severability.** If any section, subsection, sentence, clause, phrase or portion of this ordinance is, for any reason, held invalid or unconstitutional by a court of competent jurisdiction, such portion shall be deemed a separate, distinct and independent provision, and such holding shall not affect the validity of the remaining portions of this ordinance.

**Section 12.** [Emergency clause.]

***Passed by the Council May 13, 2002 and approved by the Mayor  
May 14, 2002.***

**THE FULL TEXT OF THE EMERGENCY MANAGEMENT PLAN IS ON FILE FOR REFERENCE IN THE OFFICE OF THE CITY RECORDER.**

## ORDINANCE NO. 2378

**AN ORDINANCE REGARDING MEASURE 37 CLAIMS; ESTABLISHING A PROCESS FOR THE CITY TO EVALUATE SAID CLAIMS SO THAT THE CITY CAN DECIDE SAID CLAIMS ON A RATIONAL BASIS; AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**Section 1. Findings.** The City makes the following findings:

A. On November 2, 2004, the voters of the State of Oregon approved Measure 37. The measure amends ORS Chapter 197 to require, under certain circumstances, payment of compensation to owners of real property if government land use regulations reduce fair market property value; and

B. Measure 37 provides that to receive compensation, an owner of real property must make a "written claim for compensation" to the government entity enacting a new land use regulation or enforcing an existing a land use regulation that allegedly restricts the use of their property and has the effect of reducing its fair market value; and

C. Measure 37 authorizes the City to adopt necessary claims procedures; and

D. Measure 37 requires payment of just compensation for any reduction in fair market value of real property, or in the alternative allows cities to modify, remove or not apply the land use regulation allegedly reducing a property's fair market value; and

E. The City has a duty to safeguard public funds and not pay public funds to private parties without a legal justification and a rational basis; and

F. Measure 37 imposes a new duty on the City to review claims for compensation and make decisions on those claims. A determination to waive or modify a land use regulation, or compensate a property owner must be based on substantial factual information and analysis. Necessary information must be provided by a real property owner when making a written claim for compensation; and

G. Measure 37 states that if a public entity enacts or enforces a new land use regulation or enforces a land use regulation enacted prior to the effective date of the measure that restricts the use of private real property or any interest therein and has the effect of reducing the fair market value of the property, or any interest therein, then the owner of the property shall be paid just compensation; and

H. Except for certain new land use regulations, the City finds it is necessary and required that the City make a Measure 37 determination as to whether a land use regulation should be enforced prior to a claim accruing under Measure 37; and

I. The City finds that it is necessary for Measure 37 claimants to provide factual and analytical information regarding their claims so that the City can evaluate the claims and have a rational basis to decide the claims.

**Section 2. Accrual of Claims.** Except in cases where the enactment of a new land use regulation by the City is shown by Claimant to restrict the use of private real property and have the effect of reducing the fair market value of the property, no enforcement of a land use regulation under Measure 37 shall be deemed to have occurred and no claim under Measure 37 shall have accrued until the City is provided necessary information under this Ordinance to evaluate and decide the Measure 37 claim presented by Claimant on a rational basis.

**Section 3. Definitions.** As used in this Ordinance, the following words and phrases mean:

**City Administrator.** The City Administrator of the City of Woodburn, or the City Administrator's designee.

**Claim.** A claim filed under Measure 37.

**Claimant.** The owner of property making a claim under Measure 37 and this Ordinance, or their designee, so long as written authorization is provided to the City by the property owner for the designee to represent the owner in making the claim.

**Exempt Land Use Regulation.** A land use regulation that:

1. Restricts or prohibits activities commonly and historically recognized as public nuisances under common law;
2. Restricts or prohibits activities for the protection of public health and safety, such as fire and building codes, health and sanitation regulations, solid or hazardous waste regulations, pollution control regulations, wetlands and floodplain regulations, grading and fill regulations, landslide hazard regulations, and street regulations, wireless communication facility siting regulations, tree preservation regulations, sign regulations, setback and fencing regulations and natural resource regulations to the extent they are determined necessary for public health and safety;
3. Is required in order to comply with federal law;
4. Restricts or prohibits the use of property for the purpose of selling pornography or performing nude dancing;
5. Was enacted prior to the date of acquisition of the property by the owner or a family member of the owner who owned the subject property prior to acquisition or inheritance by the owner, whichever occurred first; or

**Family Member.** Includes the wife, husband, son, daughter, mother, father, brother, brother-in-law, sister, sister-in-law, son-in-law, daughter-in-law, mother-in-law, father-in-law, aunt, uncle, niece, nephew, stepparent, stepchild, grandparent, or grandchild of the owner of the property, an estate of any of the foregoing family members, or a legal entity owned by any one or combination of these family members or the owner of the property.

**Land Use Regulation.** Includes:

1. Any statute regulating the use of land or any interest therein;
2. Administrative rules and goals of the Land Conservation and Development Commission;
3. Local government comprehensive plans, zoning ordinances, land division ordinances, and transportation ordinances; and
4. Statutes and administrative rules regulating farming and forest practices as applicable to lands in the City.

A land use regulation does not include any City system development charge or any other City development fee or charge.

**Owner.** The present Owner of the property, or any interest therein.

**Section 4. Claim Filing Procedures.**

A. A person seeking to file a claim under this Ordinance must be the present owner of the property that is the subject of the claim at the time the claim is submitted. The claim shall be filed with the City Administrator's office, or another department of the City if so designated by the City Administrator.

B. A claim shall include a completed claim form, which will be provided by the City, together with the following additional information:

1. The name(s), address(es) and telephone number(s) of all owners, and anyone with any interest in the property, including lien holders, trustees, renters, lessees or easement holders, and a description of the ownership interest of each;
2. The address, tax lot, and legal description of the real property that is the subject of the claim, together with a title report issued by a title company no more than 30 days prior to the submission of the claim that reflects the ownership interest in the property, or other documentation reflecting sole ownership of the property by Claimant, and the date the property was acquired by the present Owner. Where it is necessary for the City to evaluate the claim, all "chain of title" information shall be included;

3. The land use regulation that Claimant alleges restricts the use of the real property and allegedly causes a reduction in the fair market value of the property;

4. Claimant shall specify the remedy sought. Claimant may specify alternative remedies. If Claimant is seeking "just compensation," the amount of the claim, based on the alleged reduction in value of the real property shall be supported by an appraisal by an appraiser licensed by the State of Oregon establishing the reduction in the fair market value of the property as of the date of the claim;

5. Copies of any leases or Covenants, Conditions and Restrictions (CCR's) applicable to the property, if any, that impose restrictions on the use of the property, or which would affect its valuation;

6. Identification of the particular use that is proposed for the property and proof that the requested use was allowed as proposed at the time the owner or family member acquired the property;

7. Where the claim is based on family descent, proof that the former owner(s) was a family member of the present owner.

8. A list of names of property owners, certified by either a title company or the Marion County Assessor, or all current owners of record of all properties that lie within 500 feet of the perimeter boundary of the real property subject to the claim;

9. Signatures of all owners or those claiming ownership in the property over which the claim is being made; and

10. A deposit for costs in the amount of \$500, and which will be administered, billed and collected as provided for in this Ordinance.

**Section 5. Voluntary Claim Conference.** Before submitting a claim, or at any time after a claim is submitted, Claimant may request a claim conference with the City Administrator or designee. The City Administrator or designee is not authorized to settle any claim at a Claim Conference, but may use the conference to fully discuss the claim with Claimant and may include information on this discussion in the City Administrator's report to the City Council.

**Section 6. Burden of Proof.** Claimant has the burden of presenting sufficient evidence under this Ordinance so that the City can rationally apply Measure 37 to the claim.

**Section 7. Claim Review Process.**

A. The City Administrator shall assess any claim and make a recommendation to the City Council on the disposition of the claim.

B. The City Administrator shall mail notice of the claim to Claimant and to all owners of record of the property, and to all owners of property within five hundred (500) feet of the property that is subject of the notice, as listed on the most recent property tax assessment roll where such property is located.

C. The City Administrator's notice shall:

1. State the basis of the claim, the amount of the compensation sought and the regulation that causes the compensation to be alleged to be due.

2. Identify the property by the street address or other easily understood geographical reference;

3. State that persons notified may provide written comments on the claim, and provide the date written comments are due or, if a hearing has been scheduled, the date, time and location of the hearing;

4. Identify the City representative and telephone number to contact to obtain additional information; and

5. State that a copy of the claim and the supporting documents is available for inspection at no cost, and that copies will be provided at reasonable cost.

D. The City Administrator shall schedule a public hearing, in the City Administrator's discretion, after having an opportunity to review the Claim.

E. If a hearing is conducted:

1. Claimant and all interested parties may present and submit documents and evidence.

2. Any staff report used at the hearing shall be available prior to the hearing.

3. The City, at its discretion, may reopen a record to admit new evidence or testimony.

4. The failure of a person entitled to notice to receive notice as provided in this section shall not invalidate such proceedings. The notice provisions of this section shall not restrict the giving of notice by other means.

F. The City Administrator shall make a recommendation on the claim to the City Council applying the standards of Measure 37 and based on all of the information received pursuant to this Ordinance.

G. The City Administrator may, in the City Administrator's discretion, retain the services of an appraiser to appraise the property and evaluate the claim to assist in determining the validity of the Claim.

H. In deciding a Claim, the City Council will consider the standards of Measure 37 and the information presented by Claimant pursuant to this Ordinance; the benefit(s) accruing to the public arising as a result of application of the regulation; and the burden to the public in paying compensation to Claimant, taking into consideration the available financial resources of the City. The City Council may take, but is not limited to taking, any one or more of the following actions on a claim, as appropriate:

1. Deny the claim based on, but not limited to, any one or more of the following findings:

(a) The land use regulation does not restrict the use of the private real property;

(b) The fair market value of the property is not reduced by the enactment, enforcement or application of the land use regulation;

(c) The claim was not timely filed;

(d) Claimant failed to provide the necessary information under this Ordinance;

(e) Claimant is not the property owner, or the property was not owned by a family member if that is required for compensation, or was not the property Owner at the time the land use regulation was enacted, enforced or applied;

(f) The land use regulation is an exempt land use regulation;

(g) The land use regulation in question is not an enactment of the City;

(h) The City has not taken action to enact, enforce or apply the land use regulation to the property;

(i) The owner is not entitled to compensation under Measure 37, for a reason other than those provided herein.

2. Award compensation, either in the amount requested, or in some other amount supported by the evidence in the record. Payment of any compensation is subject to the availability and appropriation of funds for that purpose.

3. Modify the regulation.

4. Remove the regulation.

5. Not apply the regulation.

6. Acquire the affected property through negotiation or eminent domain.

7. Take such other actions as the City Council deems appropriate consistent with Measure 37.

I. If the City Council removes or modifies the challenged land use regulation, it may, at its discretion, put back into effect with respect to the subject property, all of the land use regulations in effect at the time Claimant acquired the property.

J. The City Council shall have the right to condition any grant of waiver or modification of land use regulations for any purpose, which protects the health, safety and welfare of the public. Any condition so imposed must be clear and concise and related directly to the claim and the use being proposed therein. Failure to comply with any condition of approval is grounds for revocation of the approval of the claim, grounds for recovering any compensation paid and grounds for revocation of any other action taken under Measure 37 and this Ordinance. All conditions, time limits or other restrictions imposed with approval of a claim will bind all subsequent owners of the property.

K. A decision by the City Council to remove or modify a land use regulation shall result in the proposed use allowed by the waiver or modification being thereafter considered a non-conforming use under Oregon Revised Statutes, Oregon Administrative Rules, and the Woodburn Development Ordinance. Upon grant of waiver or modification, Claimant shall cause notice thereof by way of a "License" form provided by the City, to be recorded in the deed records of the subject property so that all future owners thereof are put on notice of the non-conforming use status of the development on the property.

L. Any waiver or modification of land use regulation granted pursuant to this Ordinance under the authority of Measure 37 is personal and shall not be transferred to any third party.

#### **Section 8. Deposit and Final Bill.**

A. Claimant shall be required to deposit with the City the sum of \$500 as costs for the processing of the claim. The City shall maintain a record of its claim processing costs, including the costs of obtaining information required herein which Claimant does not provide to the City.

B. If a claim is found to be valid by the City or a Circuit Court, then the City shall refund the amount of the deposit to Claimant.

C. If a claim is finally determined to be invalid, then the City Administrator shall send Claimant a final bill showing the total costs incurred by the City in reviewing and acting on the claim, showing credit for the deposits posted, and either refund or bill the balance as dictated by the deposit ledger.



D. If the property owner owes an amount to the City and does not pay the amount due within 30 days after the final bill is sent, then the City shall pursue collection, including filing a lien on the property. The City shall be entitled to costs of collection, including attorney fees, costs and disbursements incurred in collection.

**Section 9. Appellate Rights.** Any decision under this Ordinance is not a land use decision, and none of the formalities required of land use decisions by statute, rule or local ordinance are necessary. Appeal of any final decision of the City made hereunder shall not be to the Oregon Land Use Board of Appeals, but to Marion County Circuit Court on Writ of Review pursuant to ORS 34.010 to 34.102.

**Section 10. Record Keeping.** The City shall keep a central record of all Claims made hereunder and the disposition thereof. Specific notation shall be made on the comprehensive plan and zone maps of the existence and extent of any waiver or modification granted under this Ordinance.

**Section 11. Private Cause of Action.** If the City's approval of a claim by removing or modifying a land use regulation causes a reduction in value of other property located in the vicinity of the property, the owner(s) of the other property shall have a cause of action in Circuit Court to recover from Claimant the amount of the reduction. This section shall not be construed to create a cause of action against the City of Woodburn.

**Section 12. Attorney Fees.** If an owner commences an action to collect compensation and the City prevails, the City is entitled to all fees and costs it incurred, as well as any sum that a court, including an appellate court, deems reasonable as attorney fees.

**Section 13. Severability.** If any phrase, clause, or other part or parts of this Section 1.950 is found to be invalid by a court of competent jurisdiction, the remaining phrases, clauses and other part or parts shall remain in full force and effect.

**Section 14.** [Emergency clause.]

***Passed by the Council November 29, 2004 and approved by the Mayor  
December 1, 2004.***

## ORDINANCE NO. 2381

**AN ORDINANCE ADOPTING RULES FOR PUBLIC CONTRACTING; ESTABLISHING CERTAIN CONTRACT CLASS EXEMPTIONS; PROVIDING PROCEDURES FOR PERSONAL SERVICE CONTRACTS; AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1. Definitions.**

A. "Formal competitive selection procedures" means procedures for public contracting as required by ORS 279B.050(1) (competitive sealed bids or competitive sealed proposals for goods and services), or ORS 279C.335(1) (competitive bids for public improvements) or, for personal service contracts, the same formal procedures required for the selection of goods and services pursuant to ORS 279B.060 (competitive sealed proposals).

B. "Formal competitive selection process" means the process of using formal competitive selection procedures for the procurement of goods and services or for public improvements contracts.

C. "Personal service contracts" include contracts for services that require specialized technical, artistic, creative, professional or communication skills or talent, unique and specialized knowledge, or the exercise of discretionary judgment skills, and for which the service depends on attributes that are unique to the service provider, other than contracts for an architect, engineer, land surveyor or provider of related services as defined in ORS 279C.100.

**Section 2. Local Contract Review Board.** The City Council of the City of Woodburn is designated as the Local Contract Review Board under the Oregon Public Contracting Code. The Local Contract Review Board may delegate its powers and responsibilities consistent with the Oregon Public Contracting Code, the Model Rules, and the Woodburn City Charter and ordinances.

**Section 3. Contracting Agency.** The City Administrator or his/her designee is designated as the City's "Contracting Agency" for purposes of contracting powers and duties assigned to the City of Woodburn as a "Contracting Agency."

**Section 4. Model Rules.** Except as modified herein, or by subsequent ordinance or resolution, the Model Rules, Divisions 46, 47, 48 and 49, adopted by the Attorney General under ORS 279A, 279B, and 279C, as they now exist, and as they may be amended in the future, are hereby adopted as the City's public contracting rules. Words and phrases used by these rules that are defined in ORS subchapters 279A, 279B, and 279C and in the Model Rules, have the same meaning as defined in ORS subchapters 279A, 279B, and 279C and the Model Rules.

**Section 5. Public Contracting Authority.** Administrative staff and departments have contracting authority and responsibilities as follows:

A. The City Administrator is authorized to:

1. Enter into city contracts not to exceed \$75,000 without additional authorization of the Local Contract Review Board. Contracts exceeding \$75,000 for public improvements, identified in a Capital Improvement Plan, that have been approved by the City Council through the budgetary process, shall be deemed to be approved by the Local Contract Review Board.

2. Recommend that the Local Contract Review Board approve or disapprove contract awards in excess of \$75,000, or to change orders or amendments to contracts of more than \$75,000.

3. Adopt forms, computer software, procedures, and administrative policies for all City purchases consistent with the Woodburn City Charter and ordinances.

B. All contracting by departments shall conform to approved City purchasing procedures adopted by the City Administrator or the Local Contract Review Board.

C. Each department shall plan purchase requirements sufficiently in advance so that orders can be placed in economical quantities.

D. The City Administrator shall process requisition forms and negotiate purchases on the most favorable terms in accordance with adopted ordinances, state laws (including the Oregon Public Contracting Code), policies and procedures.

**Section 6. Formal Competitive Selection Procedures-Exemptions.** All public contracts shall be based upon formal competitive selection requirements of ORS 279B.050(1) or ORS 279C.335(1), except as expressly provided in this subsection, or by subsequent ordinance or resolution. The following classes of public contracts are hereby exempted from the formal competitive selection requirements of ORS 279B.050(1) and ORS 279C.335(1):

A. Any contract exempted by the State of Oregon Public Contracting Code or Model Rules;

B. Any contract expressly exempted from formal competitive selection procedures adopted by ordinance or resolution of the Local Contract Review Board pursuant to ORS 279B.085;

C. Purchases through federal programs pursuant to ORS 279A.180;

D. In the event of an emergency involving an immediate hazard to the public health, safety, or welfare, the City Administrator, Finance Director, Public Works Director, or Chief of Police may secure necessary goods and/or services without a formal competitive selection process, provided that the Local Contract Review Board, at a regularly scheduled meeting within 30 days of the procurement, is furnished with a full report of the circumstances and costs of the materials and/or services secured;

E. Contracts for goods or services, or a class of goods or services, which are available from only one source. To the extent reasonably practical, the City Administrator shall negotiate with the sole source to obtain contract terms advantageous to the City. Sole source contracts for goods or services, or classes of goods or services, which are available from only one source which exceed \$5,000, but do not exceed \$75,000, must be approved by the City Administrator. Sole source contracts for goods or services, or classes of goods or services, which are available from only one source which exceed \$75,000 must be approved by the Local Contract Review Board. The determination of a sole source must be based on written findings that may include:

1. That the efficient utilization of existing goods requires the acquisition of compatible goods or services;

2. That the goods or services required for the exchange of software or data with other public or private agencies are available from only one source;

3. That the goods or services are for use in a pilot or experimental project;

4. Other findings that support the conclusion that the goods or services are available from only one source; or

5. Sole source contracts for goods or services, or classes of goods or services, which are available from only one source which exceed \$5,000, but do not exceed \$75,000, must be approved by the City Administrator. Sole source contracts for goods or services, or classes of goods or services, which are available from only one source which exceed \$75,000 must be approved by the Local Contract Review Board;

F. Contracts for products, services or supplies if the value of the contract does not exceed \$5,000. Any procurement of goods or services not exceeding \$5,000 per item may be awarded in any manner deemed practical or convenient by the City Administrator, including by direct selection or award. A contract awarded under this section may be amended to exceed \$5,000 only upon approval of the City Administrator and in no case may exceed \$6,000. A procurement may not be artificially divided or fragmented so as to constitute a small procurement under this selection;

G. Contracts for the purchase of copyrighted materials where there is only one supplier available within a reasonable purchase area for such goods;

H. Contracts for the purchase of advertising, including that intended for the purpose of giving public or legal notice;

I. Contracts for the procurement of banking services;

J. Contracts for the purchase of services, equipment or supplies for maintenance, repair or conversion of existing equipment if required for efficient utilization of such equipment;

K. Contracts for the purpose of investment of public funds or the borrowing of funds;

L. Contracts for the purchase of goods or services where the rate or price for the goods or services being purchased is established by federal, state or local regulating authority;

M. Contracts not to exceed \$75,000 for the purchase of goods, materials, supplies and services. For contracts for the purchase of goods, materials, supplies and services that are more than \$5,000, but that do not exceed \$75,000, a minimum of three competitive written quotes shall be obtained. The City Administrator shall keep a written record of the source and amount of quotes received. If three quotes are not available, a lesser number will suffice, provided that a written record is made of the effort to obtain the quotes;

N. Contracts not to exceed \$75,000 for public improvements, including contracts for services of architects, engineers, land surveyors and related services, (other than contracts for a highway, bridge or other transportation projects), if the following conditions are met:

1. The contract is for a single project and is not a component of or related to any other project;

2. When the amount of the public improvement contract (other than contracts for a highway, bridge or other transportation projects) is more than \$5,000, but does not exceed \$75,000, a minimum of three competitive written quotes shall be obtained. The City Administrator shall keep a written record of the source and amount of quotes received. If three quotes are not available, a lesser number will suffice, provided that a written record is made of the effort to obtain the quotes;

3. The City Administrator shall award the contract to the prospective contractor whose quote will best serve the interests of the City, taking into account price and other applicable factors, such as experience, specific expertise, availability, project understanding, contractor capacity and contractor responsibility. If the contract is not awarded on basis of lowest price, the City Administrator shall make a written finding of the basis for the award;

O. Contracts for a highway, bridge or other transportation projects more than \$5,000, but not to exceed \$50,000, if the following conditions are complied with:

1. The contract is for a single project and is not a component of or related to any other project;

2. When the amount of the contract for a highway, bridge or other transportation projects is more than \$5,000, but does not exceed \$50,000, a minimum of three competitive written quotes shall be obtained. The City Administrator shall keep a written record of the source and amount of quotes received. If three quotes are not available, a lesser number will suffice, provided that a written record is made of the effort to obtain the quotes;

3. The City Administrator shall award the contract to the prospective contractor whose quote will best serve the interests of the City, taking into account price and other applicable factors, such as experience, specific expertise, availability, project understanding, contractor capacity and contractor responsibility. If the contract is not awarded on basis of lowest price, the City Administrator shall make a written finding of the basis for the award.

**Section 7. Notice of Public Contracts.** Notice of public improvement contracts or contracts for the purchase of goods or services may be published electronically where the City Administrator finds that such publication is likely to be cost effective as provided in ORS 279C.360.

**Section 8. Disposal of Surplus and Abandoned Property.** The City Administrator shall have the authority to dispose of surplus property and abandoned personal property not owned by the City by any means determined to be in the best interests of the City, including but not limited to, transfer to other departments, government agencies, non-profit organizations, sale, trade, auction, or destruction; provided however, that disposal of personal property having residual value of more than \$10,000 shall be subject to authorization by the Local Contract Review Board.

**Section 9. Personal Service Contracts.** Personal service contracts shall be used to retain the services of independent contractors (other than contracts for an architect, engineer, land surveyor or provider of related services as defined in ORS 279C.100). Nothing in this section shall apply to the employment of regular city employees.

**Section 10. Procedures for Personal Services Contracts.** Personal service contracts are subject to the rules established by this section:

A. Unless otherwise approved by the City Administrator, all personal service contracts shall require the contractor to defend, indemnify, and hold harmless the City, its officers, agents and employees against and from any and all claims or demands for damages of any kind arising out of or connected in any way with the contractor's performance thereunder and shall include a waiver of contractor's right to ORS 30.285 and ORS 30.287 indemnification and defense.

B. Unless otherwise approved by the City Administrator, personal service contracts shall contain a provision requiring the person or entity providing the service to obtain and maintain liability insurance coverage in at least the amount of the City's tort liability limits, naming the City as an additional named insured, during the life of the contract.

C. All personal service contracts shall contain all contract provisions mandated by state law. These provisions may be incorporated in the personal service contract by reference unless otherwise provided by law.

D. The formal competitive selection procedures described in this section may be waived by the City Administrator when an emergency exists that could not have been reasonably foreseen and requires prompt execution of a contract to remedy the situation that there is not sufficient time to permit utilization of the formal competitive selection procedures.

E. Personal service contract proposals may be modified or withdrawn at any time prior to the conclusion of discussions with an offeror.

F. For personal service contracts that are anticipated to cost \$5,000 or less, such contracts must be memorialized by a formal purchase order.

G. For personal service contracts that are anticipated to exceed \$5,000, but not exceed \$75,000, at least three competitive written quotes from prospective contractors who shall appear to have at least minimum qualifications for the proposed assignment, shall be solicited. Each solicited contractor shall be notified in reasonable detail of the proposed assignment. Any or all interested prospective contractors may be interviewed for the assignment by an appropriate City employee or by an interview committee.

H. For personal service contracts that are anticipated to cost in excess of \$75,000, the department head for the department that needs the services shall make the following determinations:

1. That the services to be acquired are personal services;
2. That a reasonable inquiry has been conducted as to the availability of City personnel to perform the services, and that the City does not have the personnel nor resources to perform the services required under the proposed contract; and
3. That the department has developed, and fully plans to implement, a written plan for utilizing such services, which will be included in the contractual statement of work.

I. All personal service contracts exceeding \$75,000 shall be based upon formal competitive selection procedures, except as expressly provided in this subsection, or by subsequent ordinance or resolution. For personal service contracts that are anticipated to cost in excess of \$75,000 per year, the department head for the department that needs the services shall follow the formal competitive selection procedures for formal competitive sealed proposals as found in the Model Rules, OAR 137-047-0260.

**Section 11. Personal Services Contracts – Exemptions from Formal Competitive Selection Procedures.** Contracts for personal services are exempt from formal competitive selection procedures if any of the following conditions exist:

- A. The contract amount is anticipated to be \$75,000 or less.
- B. Contract amendments, which in the aggregate change the original contract price or alters the work to be performed, may be made with the contractor if such change or alternation is less than twenty-percent (25%) of the initial contract, and are subject to the following conditions:
  - 1. The original contract imposes binding obligation on the parties covering the terms and conditions regarding changes in the work; or
  - 2. The amended contract does not substantially alter the scope or nature of the project.
- C. The City Administrator finds that there is only one person or entity within a reasonable area that can provide services of the type and quality required.
- D. The contract for services is subject to selection procedures established by the State or Federal government.
- E. The contract is for non-routine or non-repetitive type legal services provided by attorneys outside of the City Attorney's Office.

**Section 12. Personal Services Contracts-Screening Criteria.** The following criteria shall be considered in the evaluation and selection of a personal service contractor for personal service contracts:

- A. Specialized experience in the type of work to be performed.
- B. Capacity and capability to perform the work, including any specialized services within the time limitations for the work.
- C. Educational and professional record, including past record of performance on contracts with governmental agencies and private parties with respect to cost control, quality of work, ability to meet schedules, and contract administration, where applicable.



D. Availability to perform the assignment and familiarity with the area in which the specific work is located, including knowledge of designing or techniques peculiar to it, where applicable.

E. Cost of the services.

F. Any other factors relevant to the particular contract.

**Section 13. Personal Services Contracts-Selection Process.** The following rules shall be followed in selecting a contractor for personal services:

A. Personal service contracts less than \$5,000 may be awarded in any manner deemed practical including by direct selection or award by the City Administrator (or any person with purchasing authority). A personal service contract awarded under this section may be amended to exceed \$5,000 only upon approval of the City Administrator any in no case may exceed \$6,000. A personal service contract may not be artificially divided or fragmented.

B. For personal service contracts that exceed \$5,000, but do not exceed \$75,000, the department head for the department that needs the services shall award the contract to the offeror whose quote or proposal will best serve the interests of the City, taking into account the relevant criteria found in this ordinance. The Department Head shall make written findings justifying the basis for the award.

C. For personal service contracts that will cost \$75,000 or more, the City Administrator shall award the contract based upon the formal competitive selection processes found in the Model Rules. The City Administrator shall make written findings justifying the basis of the award.

D. The City official conducting the selection of a personal service contract shall negotiate a contract with the best qualified offeror for the required services at a compensation determined in writing to be fair and reasonable.

**Section 14.** [Emergency clause.]

***Passed by the Council February 28, 2005 and approved by the Mayor  
March 2, 2005.***

**ORDINANCE NO. 2428****AN ORDINANCE DELEGATING TO THE MUNICIPAL JUDGE THE AUTHORITY TO APPOINT MUNICIPAL JUDGES PRO TEM SUBJECT TO THE PROCESS PROVIDED IN THIS ORDINANCE.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** Consistent with the Charter and pursuant to this Ordinance, one or more Municipal Judges pro tem may be appointed to serve when the Municipal Judge is ill, disqualified or otherwise unavailable. Municipal Judges pro tem, when acting in that capacity, shall have all the duties and powers of the Municipal Judge.

**Section 2.** Municipal Judges pro tem shall be members in good standing of the Oregon State Bar.

**Section 3.** Municipal Judges pro tem may be appointed by the Municipal Judge, subject to the authority vested in the Council under the Charter to hire and terminate judges of the Municipal Court and the discretion of the Council to amend or repeal the procedures provided in this Ordinance. The Municipal Judge may terminate any appointment to the position of Municipal Judge pro tem, with or without cause. The Municipal Judge shall within 30 days advise the Council of all appointments, resignations and terminations of Municipal Judges pro tem. The Council retains its authority to disapprove or terminate the appointment on a Municipal Judge pro tem, with or without cause, but until the Council so acts, a Municipal Judge pro tem shall have the power to serve after taking the oath of office prescribed in Section 28 of the Charter.

**Section 4.** Assignment of a Municipal Judge pro tem to serve in particular matters or cases shall be made by the Municipal Judge. If the Municipal Judge does not make an assignment, it may be made administratively by the clerk of the Municipal Court in accordance with directions or procedures previously established by the Municipal Judge.

**Section 5.** The City Council may by resolution establish the rate of any compensation to be paid to Municipal Judges pro tem for services performed in that capacity.

**Section 6.** Any action, decision or judgment made or taken by a Municipal Judge pro tem prior to the effective date of this Ordinance is in all respects ratified and confirmed, and shall remain effective and binding, whether or not the Municipal Judge pro tem was appointed in accordance with the standards set forth in this Ordinance.

***Passed by the Council January 14, 2008 and approved by the Mayor  
January 16, 2008.***

## ORDINANCE NO. 2433

AN ORDINANCE REPEALING ORDINANCE 2368 (THE 2004-05 MASTER FEE SCHEDULE); ADOPTING THE 2007-08 REVISED SCHEDULE OF FEES AND CHARGES FOR CITY SERVICES; PROVIDING FOR THE ANNUAL REVIEW OF SAID FEE SCHEDULE; AND SETTING AN EFFECTIVE DATE.

[Whereas clauses.]

THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Repeal.** The 2004-05 Master Fee Schedule adopted on August 9, 2004 as Ordinance 2368 is hereby repealed. All fees and charges which are inconsistent with this Ordinance are hereby repealed.

**Section 2. Fee Schedule Adoption.** The City hereby adopts the 2007-08 Master Fee Schedule affixed hereto as Attachment "A" listing applicable fees and charges which shall be charged and collected for those services enumerated.

**Section 3. Separate Fee For Additional Process.** All fees set by this Ordinance are for each identified process; additional fees shall be required for each additional process or service that is requested or required. Where fees are indicated on a per unit of measurement basis, the fee is for each identified unit or portion thereof within the indicated ranges of such units.

**Section 4. Review.** It is the intention of the City Council to review the fees and charges adopted by this Ordinance on an annual basis based on the City's next annual budget and all the City's costs reasonably borne as established at the time and, if warranted, to revise such fees and charges based thereon.

***Passed by the Council March 10, 2008 and approved by the Mayor  
March 26, 2008.***

Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Development -- Planning</b>		
<b><i>Annexation</i></b>		
Annexation - more than 1.00 acre	\$3,418	
Annexation - less than or equal to 1.00 acre	\$2,659	
<b><i>Appeals</i></b>		
Appeal-Land Use Action to Council (Type III)	\$0	\$100 + 1/2 original application fee but not more than \$2,000.
Appeal-Land Use Action to Council (Type II)	\$250	limited by state statute (ORS 227.175(10)(b)).
<b><i>Comprehensive Plan Amendments</i></b>		
more than 1.00 acre	\$3,481	
less than or equal to 1.00 acre	\$3,133	
<b>Conditional Use</b>	\$3,591	
<b><i>Design Review</i></b>		
–under 1,000 sq. ft.	\$2,177	
–1,000-4,999 sq. ft.	\$3,624	
–5,000 to 24,99 sq. ft.	\$6,326	
–25,000 to 99,999 sq. ft.	\$7,269	
–100,000 to 199,999 sq. ft.	\$10,279	
–200,000 + sq. ft.	\$14,397	
Exception to Street ROW and Improve (Type III)	\$2,363	
Formal Interpretation of the WDO (5.104.03)	\$1,759	
Formal Pre-Application Conference	\$508	\$100 of application fee reduced if application subject to pre-application applied for within 90 days and Ordinances have not changed.
Interpretation of Uses	\$615	plus Measure 56 notice costs, if applicable
Interpretation of Zoning District Boundaries	\$1,578	plus Measure 56 notice costs, if applicable
<b><i>Manufactured Dwelling Park</i></b>		
–Preliminary Approval	\$3,137	
–Final Plan Approval	\$1,081	
<b><i>Partition</i></b>		
–Preliminary Approval	\$2,478	
–Final Plat Approval	\$1,238	
<b>Phasing Plan</b>	\$1,428	

Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Development--continued</b>		
<b><i>Planned Unit Development</i></b>		
–Preliminary Plan Approval	\$2,985	plus \$40 per lot
–Final Plat Approval	\$2,585	
Property Line Adjustments	\$599	
Resident Architectural Stds Substitution	\$358	
Repair Corridor/Wetlands Over Dist (RCWOD)	\$446	
<b><i>Sign Ordinance Compliance Permit</i></b>		
–Type I	\$85	
–Type II	\$385	
Spec Conditional Use for a Historically Significant Site	\$1,148	
<b><i>Subdivision</i></b>		
–Preliminary Approval	\$3,775	plus \$40 per lot
–Final Plat Approval	\$2,585	
Telecom Facility Specific Conditional Use	\$2,188	
Temp Outdoor Mkt and Spec Event Permit	\$157	
Significant Tree Removal Permit	\$145	
Variance	\$2,432	
Zone Map Amend	\$3,074	
Zoning Adjustment	\$1,042	
<b><i>New Fees</i></b>		
Access Permit to public ROW	\$29	
Addressing	\$145	for first lot, plus \$3 for each subsequent lot
Exception to Street standard (Type II)	\$1,197	New de-regulation, previously Type III at \$1,627
<b>Regulation, Product or Service</b>		
<b>Fee</b>		
<b>Notes (Add'l Fees, Equipment, Etc.)</b>		
<b>Community Development--continued</b>		
Expedited Land Use Review-Partition	\$4,680	(statutory) [ORS 197.360]
Expedited Land Use Review-Subdivision	\$6,708	statutory
Expedited Review	\$65	subject to staff availability and as allowed by law for use. In addition to application fees.
Renewal Authorization	\$75	
3rd and successive Final Re-Inspection	\$165	
3rd and successive Submittal Review	\$265	

Tree Credit	\$185	Per tree in lieu of significant tree replacement
Land Use Compatibility Statements		
Fence Permit		
Temporary Sign Permit		
Business Registration Review		
Modification of Condition	Original fee	\$100 plus 1/2 of original fee
Grading Permit		Coordinate with Public Works Department as primary review body.
Planning counter and phone inquiry service		
(As amended by Ordinance 2443 passed June 25, 2008)		
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services -- Aquatic Center</b>		
<b>Aquatic Center--Resident Fees</b>		
<b>Daily Admissions</b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$2.25	
–youth (13-18)	\$2.75	
–adult (19 and up)	\$3.25	
–honored citizens (55+and disabled)	\$2.75	
<b>Punch Cards</b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$40.50	(20 for price of 18)
–youth (13-18)	\$49.50	(20 for price of 18)
–adult (19-54)	\$58.50	(20 for price of 18)
–honored citizens (55+ and disabled)	\$49.50	(20 for price of 18)
<b>Memberships (3 months)</b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$55	
–youth (13-18)	\$65	
–adult (19 and up)	\$80	
–honored citizen (55+ and disabled)	\$65	
–household (2 adult, 2 youth)	\$152.50	*All members must live under the same roof. First member-100% of the highest fee. Second member-50% of the second highest fee. Third member-25% of the next highest fee. Adults are a minimum of 50% of the highest fee. 2 adult+2 youth=\$152.50
<b>Memberships (annual)</b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$200	

–youth (13-18)	\$250	
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services--continued</b>		
–adult (19 and up)	\$410	
–honored citizen (55+ and disabled)	\$451	
–household (2 adult, 2 youth)	\$675	*See household membership Note above. 2 adult+2 youth=\$575
<b>Pool Rentals--Resident Fees--continued</b>		
<b>–Birthday Party Package</b>	\$130	up to 25 swimmers, includes cake, tables & chairs
–1-50 swimmers/hour	\$80	
–51-100 swimmers/hour	\$100	
–101-150 swimmers/hour	\$120	
–151-200 swimmers/hour	\$140	
<b>Lessons, Training, Swim Instruction</b>		
–Group Swimming Lessons	\$32.50	ages 3-18, 8 lessons
–Adult Swimming Lessons	\$33	
–Private Swimming Lessons	\$80	
–Semi-Private Swimming Lessons	\$120	
–Lifeguard Training	\$125	texts and certification fee included
–Jr. Lifeguard Training	\$100	texts and certification fee included
–WSI	\$150	texts and certification fee included
<b>Aquatic Center--Non-Resident Fees</b>		
<b>Daily Admissions</b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$2.75	
–youth (13-18)	\$3.25	
–adult (19 and up)	\$3.75	
–honored citizens (55+ and disabled)	\$3.25	
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services--continued</b>		
<b>Punch Cards--Non-Resident Fees--continued</b>		
–infant (0-2 with paid adult)	\$0	
–child (0-3)	\$49.50	
–youth (4-18)	\$58.50	
–adult (19-54)	\$67.50	
–honored citizens (seniors and disabled)	\$58.50	

<b><i>Memberships (3 months)</i></b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$65	
–youth (13-18)	\$80	
–adult (19 and up)	\$93	
–honored citizen (55+ and disabled)	\$80	
–household (2 adult, 2 youth)	\$512	*See household membership Note above. 2 adult+2 youth=179.50
<b><i>Memberships (annual)</i></b>		
–infant (0-2 with paid adult)	\$0	
–child (3-12)	\$250	
–youth (13-18)	\$300	
–adult (19 and up)	\$350	
–honored citizen (55+ and disabled)	\$300	
–household (2 adult, 2 youth)	\$575	*See household membership Note above. 2 adult+2 youth= \$675
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services--continued</b>		
<b><i>Pool Rentals--Non-Resident fees--continued</i></b>		
– <b>Birthday Party Package</b>	\$155	up to 25 swimmers, includes cake, tables & chairs
–1-50 swimmers/hour	\$105	
–51-100 swimmers/hour	\$125	
–101-150 swimmers/hour	\$145	
–151-200 swimmers/hour	\$165	
<b><i>Lessons, Lifeguard Training, Swim Instruction</i></b>		
–Group Swimming Lessons	\$38	ages 3-18, 8 lessons
–Adult Swimming Lessons	\$54	
–Private Swimming Lessons	\$100	
–Semi-Private Swimming Lessons	\$150	
–Lifeguard Training	\$135	texts and certification fee included
–Jr. Lifeguard Training	\$110	texts and certification fee included
–WSI	\$160	texts and certification fee included



Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services--Parks</b>		
<b><i>Park and Athletic Field Rentals Private</i></b>		
Field Prep Soccer, Softball, Baseball	\$40	per game
Any Entire Park	\$300	
Athletic Field Lighting	\$15	per hour
Burlingham Park Picnic	\$25	
Centennial Park Ball Field	\$25	
Centennial Park Youth Soccer Field	\$25	
Centennial Park Adult Soccer Field	\$25	
Legion Park Picnic	\$35	
Legion Park Adult Soccer Field	\$25	
Settlemier Park Picnic	\$35	
Settlemier Park Ball Field	\$25	
Plaza	\$300	
Special Event Permit	\$6,600	As amended by Ordinance 2452 Passed on May 11, 2009
Special Event Permit Add'l Days	\$4,000	
<b><i>Park and Athletic Field Rentals Commercial</i></b>		
Any Entire Park	\$400	
Athletic Field Lighting	\$20	per hour
Burlingham Park Picnic	\$45	
Centennial Park Ball Field	\$35	
Centennial Park Youth Soccer Field	\$35	
Centennial Park Adult Soccer Field	\$35	
Legion Park Picnic	\$55	
Legion Park Adult Soccer Field	\$35	
Settlemier Park Picnic	\$55	
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services--Parks</b>		
Settlemier Park Ball Field	\$35	
Plaza	\$400	
Special Event Permit	\$6,600	
Special Event Permit Add'l Days	\$4,000	
<b><i>Recreation Programs</i></b>		
Adult Basketball	\$63	per game
Adult Drop-In Sports Class	\$3	
Adult Trips	n/a	varies, depending on distance of trip, this fee only covers transportation costs.

		Individuals are responsible for admission to events, etc.
After School Club	\$100	per term dependent upon agreement w/WSD
Senior Trips	n/a	varies, depending on distance of trip, this fee only covers transportation costs. Individuals are responsible for admission to events, etc.
Teen Programs	n/a	depended on grant funding
Youth Basketball	\$40	
Youth Soccer	\$40	
Youth T-Ball	\$40	
<b>Summer Day Camp</b>		
–per week	\$75	
–all 9 weeks	\$575	
<b>Walt's Run</b>		
–Individual	\$15	Sponsor support \$500 sponsorship
–Family (5 people max)	\$50	Sponsor support \$500 sponsorship
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Community Services--Library</b>		
Charge for Interlibrary Loan (ILLs)		
Fines for Overdue Library Materials	\$0.25	per day \$.25/day, max=replacement cost
Key Ring Cards, Replacement Cards	\$2	per card (established by CCRLS)
Lost Books and Materials	list price	
<b>Non-Resident Borrowing Card</b>		
--Inside CCRLS	\$60	
--Outside CCRLS	\$75	
Printing	\$0.05	per page
Color Printing	\$0.75	
Room Use Monitor Fee	\$40	charged per hour for room use after business hours in addition to room use fee, only for groups charging admission \$80
Use of Carnegie Room	\$16	per hour, during business hours, only for groups charging admission
Use of Multi-Purpose room	\$20	per hour, during business hours, only for groups charging admission \$16
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Finance</b>		
Copy Fees (documents including fax & e-mail)	\$0.05	fee charged per page side (plus a research fee of \$41/ hour, charged to the nearest 1/4 hour only for complex duplicative requests requiring over 1/4 hour research). additional charges may

		be added for postage and handling, if necessary.
Copy Fees (tapes)	\$3	fee charged per tape (plus a research fee of \$41/ hour, charged to the nearest 1/4 hour only for complex duplicative requests requiring over 1/4 hour research). additional charges may be added for postage and handling, if necessary.
Copy of the Budget	\$0	budget provided for free to public
<i>Liquor License</i>		
--new (all types)	\$244	plus noticing costs in the event of a denial
--change in ownership/location/privilege	\$75	plus noticing costs in the event of a denial
--renewal (all types)	\$136	plus noticing costs in the event of a denial
--temporary/special event liquor license	\$35	plus noticing costs in the event of a denial
Lien Filing	\$34	
Lien Search Fees	\$25	
NSF Check (Avoidance)	\$10	payment to avoid water shut-off (in addition to check fee)
NSF Check (1st and 2nd)	\$25	
NSF Check (3rd)	\$30	
Public Dance Permit	\$143	
<i>Solicitors' License</i>		
--new	\$102	
--renewal	\$45	
<b>Sound Amplification Permit</b>	<b>\$33</b>	
Regulation, Product or Service      Fee      Notes (Add'l Fees, Equipment, Etc.)		
<b>Police</b>		
Archived Records Retrieval	\$19	
Computer Records Scan	\$19	
Fingerprinting (for SD)	\$29	fee charged per person
Investigation for private parties	\$87	
<i>Nuisance Abatement</i>		
–first hour	\$159	
–each add'l hour or fraction	contractor costs	
Processing Compact Disk Prints	\$58	
Processing Photo Prints	\$14	
Tow Uninsured Vehicle	\$150	
Police/Traffic Accident Report	\$23	
<i>Vegetation Abatement</i>		
–first hour	\$120	
–each add'l hour or fraction	\$58	

thereof		
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Public Works</b>		
<b>Construction Permit for Work in the ROW</b>		
–under \$5,000	n/a	limited by statute, 5% of cost but not less than \$10
–\$5,000 - \$25,000	n/a	limited by statute, plus 4% over \$5,000
–\$25,000 - \$100,000	n/a	limited by statute, plus 3% over \$25,000
–over \$100,000	n/a	limited by statute, plus 2% over \$100,000
Weep Holes--First	\$67	
Weep Holes--Each Additional	\$34	
Sewer Tap	\$202	
<b>Water Service Installation Charges</b>		
–1" line and 5/8" meter	\$284	
–1" line and meter	\$284	
–1-1/2" line and meter	\$1,134	
–2" line and meter	\$1,134	
–3" and larger line and meter	n/a	costs based on actual cost of installation for labor and materials, plus 15% of said cost for administrative and overhead expense
<b>Utility Late Fees</b>		
Delinquent balance-first notice	\$10	
Delinquent balance-second notice	\$10	
Restore disconnected service	\$25	
Turn off/onn	\$35	for reasons other than non-payment (excludes emergency such as waterline or equipment breakage)
<b>Curb Cuts</b>	\$134	fee for two cuts
<b>Approaches</b>	\$2	fee charged per foot
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Public Works--continued</b>		
T & E	\$1	fee charged per \$1,000 valuation on building permit
Charge for Leak Adjustment Service	\$49	deducted from total credit of leak adjustment [Ordinance 1866]
Charge for Lock Removal/Meter Damage	n/a	charges are based on actual cost of replacement locks/meters cut or damaged by users, and labor cost for staff to replace items
B&W Copies--24" x 36" (full sheet)	\$12	
B & W Copies--18" x 24" (half sheet)	\$12	

24" x 36" (Aerials, Ward Maps, 1"=800' City Maps, Plotted)	\$25	
<b>Monthly Water Service Related Charges</b>		
Deposit Application for 5/8" lines (Resident) [Ord 1965]	\$75	
<b>Other Deposit Amount</b>		
-1"	\$90	
-1-1/2"	\$125	
-2"	\$150	
-3"	\$170	
-4"	\$275	
-6"	\$540	
-8"	\$600	
Bulk Water Rate	\$30	
<b>Meter Error (when customer requests the city to test the meter serving individual's premises [Ordinance 1866])</b>		
-5/8"-3/4"	\$35	
Regulation, Product or Service	Fee	Notes (Add'l Fees, Equipment, Etc.)
<b>Public Works--continued</b>		
<b>Meter Error--continued</b>		
-1"	\$71	
-1-1/2"	\$71	
-2"	\$106	
-3"	\$106	
-4"	\$142	
-6"	\$177	
-8"	\$213	
Outside City Surcharge for Water Charges [Ord 1965]	n/a	
Hardship Relief [Ordinance 1965]	n/a	
Hydrant Relocation	n/a	
Street Vacation Request	\$572	

## ORDINANCE NO. 1795

**AN ORDINANCE PROVIDING FOR CONSTRUCTION PERMIT FEES FOR WORK IN PUBLIC RIGHT-OF-WAY; AND PROVIDING FOR DISPOSITION OF PROCEEDS.****THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:**

**Section 1. Permits.** All street, water, sewer and storm drain service connections, installations, and alterations and franchisee installations and alterations, other than those activities exempted by Section 7 of this ordinance, in the City of Woodburn right-of-way shall require a permit from the City. The application shall be filed with the Public Works Department and at the time of issuance of the permit a fee shall be paid as outlined in Section 3 of this ordinance. No permit fee is required for those exempted by Section 4 or by Section 7 of this ordinance.

**Section 2. Engineering Plan.** Each type of construction project, such as water or sewer, will constitute a separate project. An engineering plan shall be required and reviewed by the City on all major construction projects before a permit can be issued. There shall be no charge for the engineering plan review and approval.

**Section 3. Fees.** The construction permit charge in the City of Woodburn shall be as follows:

<u>Cost</u>	<u>Fee</u>
Under \$5,000	5% of cost but not less than \$10
\$ 5,000 - \$25,000	\$ 250 + 4% over \$ 5,000
\$25,000 - \$100,000	\$1,000 + 3% over \$ 25,000
Over \$100,000	\$3,000 + 2% over \$100,000

**Section 4. Franchisee Exemption.** Franchisees will not be required to pay a permit fee, however, a percentage of the franchise fee shall be diverted to Public Works to cover the cost of permit, plan review and general inspection process.

**Section 5. Public Works Technical Fund.** Starting in the fiscal year 1983-84, and thereafter each succeeding year, the City Recorder shall transfer an amount equal to 4 percent (4%) of the franchise fee from telephone, electric, natural gas, and cable television to the Public Works Technical Fund, at the time of receipt. [Section 5 as amended by Ordinance No. 1805, passed January 10, 1983.]

**Section 6. Construction Permit Fees Fund** All payments received by the City under the provisions of Section 3 of this ordinance shall be deposited in, and credited to, the Construction Permit Fees Fund of the City of Woodburn, and used by the Public Works Department for engineering inspection and related activities.

**Section 7. Exemptions.** The City may not require a construction permit fee on:

- (1) Construction activity performed by City crews.
- (2) Certain construction activities not involving underground main extensions by a franchisee.
- (3) Wheelchair ramp construction.
- (4) Construction activities outside improved portions of street and/or activities covered by other City fees.

**Section 8. Materials and Methods.** Only City approved materials and methods will be used on a project during excavation and fill in the public right-of-way.

**Section 9. Inspections.** A minimum of 24 hours notice shall be provided to the City to inspect an approved construction project.

**Section 10. Interpretation and Enforcement.** Interpretation and enforcement of this ordinance shall be the responsibility of the City Engineer.

**Section 11. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 1 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 11 as amended by Ordinance 2008, passed October 24, 1988.]

***Passed by the Council November 4, 1982, and approved by the Mayor November 9, 1982.***

## ORDINANCE NO. 1917

## AN ORDINANCE REGULATING THE CONSTRUCTION, ALTERATION AND REPAIR OF SIDEWALKS.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.** Unless the context requires otherwise, the following mean:

- (1) Person. A natural person, firm, corporation or other legal entity.
- (2) Sidewalks. The part of the street right-of-way or an easement which contains a walking structure between the curb lines on the pavement or gravel edge of a roadway and the adjacent property lines, including the driveway approach.
- (3) Major construction. Work that requires new construction or alteration and repair of more than 50% of the existing or future sidewalk area.
- (4) Minor construction. Work that requires alteration or repair of less than 50% of the existing sidewalk area.

**Section 2. Duty to Repair Sidewalks.** The owner of land adjoining a city street shall maintain in good repair the adjacent sidewalk whenever it becomes damaged or deteriorated in any way.

**Section 3. Liability for Sidewalk Injuries.**

- (1) The owner of real property responsible for maintaining the adjacent sidewalk shall be liable to any person injured because of failure of the owner to maintain the sidewalk in good condition.
- (2) If the City is required to pay damages for an injury to persons or property caused by the failure of a person to perform the duty which this ordinance imposes, the person shall reimburse the City for the amount of damages thus paid and the attorney fees and costs of defending against the claim of damages. The City may maintain an action in a court of competent jurisdiction to enforce the provisions of this section.

**Section 4. Standards and Specifications.** Sidewalks shall be constructed, altered and repaired in accordance with City standards and specifications.

**Section 5. Submission of Plans.** No person shall construct, alter or repair a sidewalk within the City without first making application for a permit and submitting the plans for the proposed work. The application shall be made to the City Engineer's office, and all applicable standards and specifications established under Section 4 shall be met by the plans, and thereafter the City Engineer or designee may issue a permit for the proposed work. There will be no charge for the permit.



**Section 6. Supervision of Work.** The property owner or agent thereof, may perform construction, alteration or repair of sidewalks after obtaining a permit from the City Engineer's office. The City Engineer or designee may inspect any materials and construction details as in the Engineer's judgment may be necessary to insure compliance with the applicable standards and specifications.

**Section 7. Notice to Repair or Make Alterations.**

(1) When major construction is involved the Council shall, by motion, direct the City Engineer to issue a notice.

(2) When minor construction is involved and the repair or alteration is brought to the City Engineer's attention, the Engineer may issue a notice directly.

(3) The notice shall require the owner of the property adjacent to the sidewalk to complete the work within 60 days after service of notice. The notice shall also state that if the work is not completed by the owner within the 60-day time period, the City may complete it and assess the cost against the property adjacent to the sidewalk.

(4) The City Engineer shall cause a copy of the notice to be served upon the owner of the property adjacent to the sidewalk, or the notice may be served by registered or certified mail, return receipt requested. If after diligent search the owner is not discovered, the City Engineer shall cause a copy of the notice to be posted in a conspicuous place on the property, and such posting shall have the same effect as service of notice by mail or by personal service upon the owner of the property.

(5) The person serving the notice shall file with the Recorder a statement stating the time, place and manner of service of notice.

**Section 8. City May Alter or Repair Sidewalk.** If the sidewalk alteration or repair is not completed within 60 days after service of the notice, the City may complete it. Upon completion of the project, the City Engineer shall submit a report to the Council. The report shall contain an itemized statement of the cost of the work.

**Section 9. Assessment for Sidewalk Work Done by City.** Upon receipt of the report, the Council, by ordinance, shall assess the cost of the work against the property adjacent to the sidewalk. The assessment shall be a lien against the property and may be collected in the same manner as is provided for the collection of street improvement assessments.

**Section 10. Sidewalk Construction Requested by the Property Owner.** If a property owner petitions the Council for an order to build a sidewalk on the part of the street abutting his or her property, agrees to pay cash or to make application to pay the cost in installments as provided by the Bancroft Bonding Act (ORS 223.205 to 223.295), waives the right of service and publication of notice of construction, and consents to the assessment of the property upon which the sidewalk abuts, the Council

may order the construction of the requested sidewalk, if in its judgment the sidewalk should be built.

**Section 11. Penalty.** A violation of any section of this ordinance constitutes a class 1 civil infraction and shall be handled according to the procedures established by ordinance relating to civil infractions.

**Section 12. Severability.** Each portion of this ordinance constitutes a class 1 civil infraction and shall be handled according to the procedures established by ordinance relating to civil infractions.

**Section 13. Repeal.** Ordinance No. 778 (enacted February 3, 1942) is repealed.

***Passed by the Council July 8, 1985 and approved by the Mayor July 9, 1985.***

## ORDINANCE 2105

**AN ORDINANCE PROVIDING PROCEDURES FOR LOCAL IMPROVEMENTS AND SPECIAL ASSESSMENTS; REPEALING ORDINANCE 1879, AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1. Initiating Improvements.**

(1) When the Council considers it necessary to require that improvements to a street, sewer, water facility, sidewalk, parking, curbing, drain or other public improvement defined in ORS 223.387 be paid for in whole or in part by special assessment according to benefits conferred, the Council shall declare by resolution that it intends to make the improvement and direct the City Engineer to make a survey of the improvement and a written report.

(2) When owners of two-thirds of the property that will benefit specially by improvements defined in subsection (1) request by written petition that the Council initiate an improvement, the Council shall declare by resolution that it intends to make the improvement and direct the City Engineer to make a survey of the improvement and a written report.

**Section 2. Engineer's Report.** The Engineer's report may contain, but is not limited to, the following:

(1) A map or plat showing the general nature, location and extent of the proposed improvement and the land to be assessed for payment of the cost.

(2) Plans, preliminary sketches and estimates of work to be done. If the proposed project is to be carried out in cooperation with another governmental agency, the Engineer may adopt plans, specifications and estimates of that agency.

(3) An estimate of probable cost of the improvement, including legal, administrative and engineering cost.

(4) An estimate of unit cost of the improvement to the benefited properties, per square foot, per front foot, or another unit of cost.

(5) A recommendation concerning the method of assessment to be used to arrive at a fair apportionment of the whole or a portion of the cost of the improvement to the benefited properties.

(6) A description of each lot, parcel of land, or portion of land to be benefited, with names of the record owners and, when readily available, names of contract purchasers, as shown on books and records of the Marion County Tax Department. To describe each lot or parcel or land under provisions of this section, it shall be sufficient to use the tax account number assigned to the property by the tax department or shown on books and records of the Marion County Clerk.

(7) A recommendation regarding the rate of interest, but it shall be as the governing body may determine based on a certain percent per annum, to be paid on assessments bonded under the Bancroft Bonding Act and ORS Chapter 223.

**Section 3. Action on Engineer's Report.** After reviewing the Engineer's report, the Council may approve the report, modify the report and approve it as modified, require the Engineer to supply additional or different information for the improvement, or abandon the improvement.

**Section 4. Resolution and Notice of Hearing.** After the Council has approved the Engineer's report as submitted or modified, the Council shall declare by resolution that it intends to make the improvement and direct the Recorder to give notice of the Council's intention by two publications, one week apart, in a newspaper of general circulation in the city. The notice shall contain the following:

(1) That the Council will hold a public hearing on the proposed improvement on a specified date, which shall be not less than 10 days after the first publication of notice, at which objections and remonstrances to the improvement will be heard by the Council; and that action on any proposed public improvement, except a sidewalk or except an improvement unanimously declared by the Council to be needed at once because of an emergency, shall be suspended for six months upon written remonstrance thereto by the owners of a majority of the land to be specially assessed therefor.

(2) A description of the property to be benefited by the improvement, owners of the property as shown on the books and records of the Marion County Tax Department, as the Engineer's estimate of total cost of the improvement to be paid by special assessment to benefited properties.

For purposes of this subsection it shall be sufficient to describe the property to be benefited by a metes and bounds description or by the tax account number assigned to the property and used by the Marion County Tax Department or the subdivision lot and block number or the book and page designations shown on books and records of the Marion County Clerk.

**Section 5. Manner of Doing Work.** The Council may at its discretion provide that the construction work may be done in whole or in part by the City, by contract, by another governmental agency, or by a combination of the above.

**Section 6. Ordinance of Approval or Abandonment of Improvement.** The Council may by ordinance at the time of the hearing or within 90 days thereafter, order the improvement carried out in accordance with the resolution, modify the proposed improvement, or, if the project was initiated by Council motion and not by petition of property owners, abandon the improvement.

**Section 7. Call for Bids.** The City may advertise for bids for construction of all or any part of the improvement project on the basis of the Council-approved report and before the passage of the resolution, or after the passage of the resolution and before the public hearing on the proposed improvement, or at any time after the public hearing; provided however, that no contract shall be let until after the public hearing has been held to hear remonstrances and oral objection to the proposed improvement.

**Section 8. Method of Assessment and Alternative Methods of Financing.**

(1) The Council, in adopting a method of assessing the cost of the improvement, may:

(a) Use any just and reasonable method to determine the extent of any improvement district consistent with the benefits derived.

(b) Use any just and reasonable method of apportioning the sum to be assessed among the benefited properties.

(c) Authorize payment by the City of all or part of the cost of an improvement when in the opinion of the Council the topographical or physical conditions, unusual or excessive public travel, or other character of the work involved warrants only partial payment or no payment of the cost by the benefited property.

(2) Nothing contained in this section shall preclude the Council from using other means of financing improvements, including federal and state grant-in-aid, sewer charges or fees, revenue bonds, general obligation bonds, or other legal means of finance. If other means of financing are used, the Council may levy special assessments according to benefits derived to cover any remaining part of the cost.

**Section 9. Final Assessment Ordinance.**

(1) If the Council caused the public improvement to be made and the actual cost has been determined, upon completion of the project the Council shall determine whether the benefited property shall bear all or a portion of the cost. The Recorder or other person designated by the Council shall prepare the final assessment for each lot within the assessment district and file the assessments in the Records office.

(2) Notice of the proposed assessment shall be published and mailed or personally delivered to the owner of each lot proposed to be assessed at the address shown on the Marion County Tax Assessor's rolls. The notice shall state the amount of final assessment on the property and fix a date by which time any objections shall be filed with the Recorder and the date and time set for the public hearing at which the Council will hear objections. An objection shall state the grounds for the objection.

(3) At the hearing the Council shall consider the objections and may adopt, correct, modify or revise the assessment against each lot in the district according to special peculiar benefits accruing to it from the improvement.

**Section 10. Notice of Assessment.**

(1) Within 10 days after the ordinance levying assessments has been passed, the Recorder shall send a notice of assessment to the owner of the assessed property by registered or certified mail and public notice of the assessment twice in a newspaper of general circulation in the city. The first publication of notice shall be not later than 20 days after the date of assessment ordinance.

(2) The notice of assessment shall include the name of the property owner, a description of the assessed property, the amount of the assessment, and the date of the assessment ordinance and shall state that interest will begin to run on the assessment and the property will be subject to foreclosure unless the owner either makes application to pay the assessment in installments within 10 days after the date of the first publication of notice or pays the assessment in full within 30 days after the date of the assessment ordinance.

**Section 11. Lien Record and Foreclosure Proceedings.**

(1) After passage of the assessment ordinance, the Recorder shall enter into the docket of liens a statement of the amount assessed on each lot, parcel of land or portion of land, description of the improvement, names of property owners, and the date of the assessment ordinance. Upon entry in the lien docket, the amounts shall become liens and charges on the lots, parcels of land or portions of land that have been assessed for improvement.

(2) Assessment liens of the City shall be superior and prior to all other liens or encumbrances on property insofar as state law permits.

(3) The City may enter a bid on property being offered at a foreclosure sale. The City bid shall be prior to all bids except those made by persons who would be entitled under state law to redeem the property.

**Section 12. Errors in Assessment Calculations.** Claimed errors in the calculation of assessments shall be called to the attention of the Recorder, who shall determine whether there has been an error. If there has been an error, the Recorder shall recommend to the Council an amendment to the assessment ordinance to correct the error. On enactment of the amendment, the Recorder shall make the necessary correction in the docket of liens and send a correct notice of assessment by registered or certified mail.

**Section 13. Supplemental Assessments.** If a supplemental assessment is required pursuant to Section 18 of this ordinance, the Council may declare the insufficiency by motion and prepare a proposed supplemental assessment. The

Council shall set a time for hearing objections to the supplemental assessment and direct the City Recorder to publish one notice in a newspaper of general circulation in the city. After the hearing, the Council shall make a just and equitable supplemental assessment by ordinance, which shall be entered in the docket of liens as provided by Section 11. Notice of the supplemental assessment shall be published and mailed, and collection of the assessment shall be made in accordance with Sections 10 and 11.

**Section 14. Rebates.** If a rebate is required pursuant to Section 18 of this ordinance, the Council shall ascertain and declare the excess by ordinance. When declared, the excess amounts must be entered on the lien docket as a credit on the appropriate assessment. If an assessment has been paid, the person who paid it or that person's legal representative shall be entitled to payment of the rebate credit.

**Section 15. Remedies.**

(1) Subject to curative provisions of Section 17 and rights of the city to reassess as provided in Section 18, proceedings for writs of review and equitable relief may be filed not earlier than 30 days nor later than 60 days after filing written objection as provided by Section 9.

(2) A property owner who has filed a written objection with the Recorder before the public hearing may have the right to apply for a writ of review based on the Council's exercising its functions erroneously or arbitrarily or exceeding its jurisdiction to the injury of a substantial right of the owner, if the facts supporting the claim have been specifically set forth in the written objections.

(3) A property owner who has filed a written objection with the Recorder before the public hearing may begin an action for equitable relief based on a total lack of jurisdiction on the part of the city. If notice of the improvement was not sent to the owner and if the owner did not have actual knowledge of the proposed improvement before the hearing, the owner may file a written objection alleging lack of jurisdiction with the Recorder within 30 days after receiving notice or knowledge of the improvement.

(4) A provision of this section shall not be construed to lengthen the period of redemption or to affect the running of a statute of limitation. A proceeding on a writ of review or for equitable relief shall be abated if proceedings are begun and diligently pursued by the Council to remedy or cure alleged errors or defects.

**Section 16. Abandonment of Proceedings.** The Council may abandon proceedings for improvements made under Section 1 to 15 at any time before final completion of the improvements. If liens have been placed on property under this procedure, they shall be canceled, and payments made on assessments shall be refunded to the person who paid them or to that person's legal representatives.

**Section 17. Curative Provisions.**

- (1) An improvement assessment shall not be rendered invalid by reason of:
- (a) Failure of the Engineer's report to contain all information required by Section 2.
  - (b) Failure to have all information required in the improvement resolution, assessment ordinance, lien docket, or notices required to be published and mailed.
  - (c) Failure to list the name or mail notice to an owner of property as required by this ordinance.
  - (d) Any other error, mistake, delay, omission, irregularity or other act, jurisdictional or otherwise, in the proceedings or steps specified, unless it appears that the assessment is unfair or unjust in its effect on the person complaining.
- (2) The Council shall have authority to remedy and correct all matters by suitable action and proceedings.

**Section 18. Reassessment.** When an assessment, supplemental assessment, or reassessment for an improvement made by the city has been set aside, annulled, declared void, or its enforcement restrained by a court of this state or by a federal court having jurisdiction, or when the Council doubts the validity of the assessment, supplemental assessment, rebate, or any part of it, the Council may make a reassessment in the manner provided by state law.

**Section 19. Severability.** Each portion of this ordinance shall be deemed severable from any other portion. The unconstitutionality or invalidity of any portion of this ordinance shall not invalidate the remainder of this ordinance.

**Section 20. Repeal.** Ordinance No. 1879 is hereby repealed.

**Section 21.** [Emergency clause.]

*Passed by the Council March 22, 1993, approved by the Mayor March 23, 1993.*



## ORDINANCE NO. 2237

AN ORDINANCE ESTABLISHING A PROCESS FOR THE FORMATION OF A REIMBURSEMENT DISTRICT IN ORDER TO PROVIDE A MECHANISM WHEREBY THE PROPERTIES WHICH WILL BENEFIT BY THE CONSTRUCTION OF THE REQUIRED PUBLIC IMPROVEMENTS BY CRAIG REALTY GROUP, WOODBURN LLC, WILL SHARE IN THE COST OF THOSE IMPROVEMENTS; PROTECTING THE PUBLIC INTEREST; AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.** The following terms are defined as follows for the purposes of this Ordinance.

- A. "City" means the City of Woodburn, Oregon.
- B. "Developer" means a person who is required or chooses to finance some or all of the cost of a street, water or sewer improvement which is available to provide service to property, other than property owned by the person, and who applies to the City for reimbursement for the expense of the improvement.
- C. "Development Permit" means any final land use decision, limited land use decision, expedited land division decision, partition, subdivision, or driveway permit.
- D. "Person" means a natural person, the person's heirs, executors, administrators or assigns; a firm, partnership, corporation, association or legal entity, its or their successors or assigns; and any agent, employee or representative thereof.
- E. "Public Improvement" means any construction, reconstruction or upgrading of water, stormwater, sewer or street improvements
- F. "Public Works Director" means the Public Works Director of the City of Woodburn.
- G. "Reimbursement Agreement" means the agreement between the Developer and the City which is authorized by the City Council and executed by the City Administrator, providing for the installation of and payment for reimbursement district public improvements.
- H. "Reimbursement District" means the area which is determined by the City Council to derive a benefit from the construction of public improvements, financed in whole or in part by the Developer.
- I. "Reimbursement Fee" means the fee required to be paid by a resolution of the City Council and the reimbursement agreement. The City Council resolution and reimbursement agreement shall determine the boundaries of the reimbursement district

and shall determine the methodology for imposing a fee which considers the cost of reimbursing the Developer for financing the construction of the improvement within the reimbursement district.

**Section 2. Application to Establish a Reimbursement District.**

A. A person who is required to or chooses to finance some or all of the cost of a public improvement which will be available to provide service to property other than property owned by the person may by written application filed with the Public Works Director request that the City establish a reimbursement district. The public improvement must be of a size greater than that which would otherwise ordinarily be required in connection with an application for a building permit or development permit or must be available to provide service to property other than property owned by the Developer, so that the public will benefit by making the improvement.

B. The application shall be accompanied by an application fee, in the amount of \$1000, which the City Council has determined reasonable to cover the cost of the preparation of the Public Works Director's Report and notice pursuant to this ordinance.

C. The application shall include the following:

1. A written description of the location, type, size and cost of each public improvement which is to be eligible for reimbursement.

2. A map showing the boundaries of the proposed reimbursement district, the tax account number of each property, its size and boundaries.

3. A map showing the properties to be included in the proposed reimbursement district; the zoning district for the properties; the front footage and square footage of said properties, or similar data necessary for calculating the apportionment of the cost; the property or properties owned by the Developer; and the names and mailing addresses of owners of other properties to be included in the proposed reimbursement district.

4. The actual or estimated cost of the public improvements.

D. The application may be submitted to the City prior to the installation of the public improvement but not later than 180 days after completion and acceptance of the public improvements by the City.

**Section 3. Public Works Director's Report.** The Public Works Director shall review the application for the establishment of a reimbursement district and evaluate whether a district should be established. The Public Works Director may require the submission of other relevant information from the Developer in order to assist in the evaluation. The Public Works Director shall prepare a written report for the City Council that considers and makes a recommendation concerning each of the following factors:

A. Whether the Developer will finance, or has financed some or all of the cost of the public improvement, thereby making service available to property, other than that owned by the Developer.

B. The boundary and size of the reimbursement district.

C. The actual or estimated cost of the public improvement serving the area of the proposed reimbursement district and the portion of the cost for which the Developer should be reimbursed for each public improvement.

D. A methodology for spreading the cost among the properties within the reimbursement district and, where appropriate, defining a "unit" for applying the reimbursement fee to property which may, with City approval, be partitioned, subdivided, altered or modified at some future date.

E. The amount to be charged by the City for an administration fee for the reimbursement agreement. The administration fee shall be fixed by the City Council and will be included in the resolution approving and forming the reimbursement district. The administration fee is due and payable to the City at the time the agreement is signed.

F. Whether the public improvements will or have met City standards.

G. Whether it is fair and in the public interest to create a reimbursement district.

**Section 4. Amount to be Reimbursed.**

A. A reimbursement fee shall be computed by the City for all properties within the reimbursement district, excluding property owned by or dedicated to the City or the State of Oregon, which have the opportunity to use the public improvements, including the property of the Developer, for formation of a reimbursement district. The fee shall be calculated separately for each public improvement. The Developer for formation of the reimbursement district shall not be reimbursed for the portion of the reimbursement fee computed for its own property.

B. The cost to be reimbursed to the Developer shall be limited to the cost of construction engineering, construction, and off-site dedication of right of way. Construction engineering shall include surveying and inspection costs and shall not exceed 7.5% of eligible public improvement construction cost. Costs to be reimbursed for right of way shall be limited to the reasonable market value of land or easements purchased by the Developer from a third party in order to complete off-site improvements.

C. No reimbursement shall be allowed for the cost of design engineering, financing costs, permits or fees required for construction permits, land or easements dedicated by the Developer, the portion of costs which are eligible for systems development charge credits or any costs which cannot be clearly documented.

D. Reimbursement for legal expenses shall be allowed only to the extent that such expenses relate to the preparation and filing of an application for reimbursement.

E. Reimbursement for the amount of the application fee required by Section 2 on this ordinance.

**Section 5. Public Hearing.**

A. Within 45 days after the Public Works Director has completed the report required in Section 3, the City Council shall hold an informational public hearing in which any person shall be given the opportunity to comment on the proposed reimbursement district. Because formation of the reimbursement district does not result in an assessment against property or lien against property, the public hearing is for informational purposes only and is not subject to mandatory termination because of remonstrances. The City Council has the sole discretion after the public hearing to decide whether a resolution approving and forming the reimbursement district shall be adopted.

B. Not less than ten (10) days prior to any public hearing held pursuant to this Ordinance, the Developer and all owners of property within the proposed district shall be notified of the public hearing and the purpose thereof. Such notification shall be accomplished by either regular and certified mail or by personal service. Notice shall be deemed effective on the date that the letter of notification is mailed. Failure of the Developer or any affected property owner to be so notified shall not invalidate or otherwise affect any reimbursement district resolution or the City Council's action to approve the same.

C. If a reimbursement district is formed prior to construction of the improvement(s), a second public hearing, subject to the same notice requirements, shall be held after the improvement has been accepted by the City. At that time, the City Council at its discretion may modify the resolution to reflect the actual cost of the improvement(s).

**Section 6. City Council Action.**

A. After the public hearing held pursuant to Section 5(A), the City Council shall approve, reject or modify the recommendations contained in the Public Works Director's report. The City Council's decision shall be contained in a resolution. If a reimbursement district is established, the resolution shall include the Public Works Director's report as approved or modified, and specify that payment of the reimbursement fee, as designated for each parcel, is a precondition of receiving any city permits applicable to development of that parcel as provided for in Section 10.

B. The resolution shall establish an interest rate to be applied to the reimbursement fee as a return on the investment of the Developer. The interest rate shall be fixed and computed against the reimbursement fee as simple interest and will not compound.

C. The resolution shall instruct the City Administrator to enter into an agreement with the Developer pertaining to the reimbursement district improvements. If the agreement is entered into prior to construction, the agreement shall be contingent upon the improvements being accepted by the City. The agreement shall contain at least the following provisions:

1. The public improvement(s) shall meet all applicable City standards.
2. The total amount of potential reimbursement to the Developer shall be specified.
3. The total amount of potential reimbursement shall not exceed the actual cost of the public improvement(s).
4. The Developer shall guarantee the public improvement(s) for a period of twelve (12) months after the date of installation.
5. A clause in a form acceptable to the City Attorney stating that the Developer shall defend, indemnify and hold harmless the City from any and all losses, claims, damage, judgments or other costs or expense arising as a result of or related to the City's establishment of the reimbursement district, including any City costs, expenses and attorney fees related to collection of the reimbursement fee should the City Council decide to pursue collection of an unpaid reimbursement fee under Section 10(H).
6. A clause in a form acceptable to the City Attorney stating that the Developer agrees that the City, can not be held liable for any of the Developer's alleged damages, including all costs and attorney fees, under the agreement or as a result of any aspect of the formation of the reimbursement district, or the reimbursement district process, and that the Developer waives, and is estopped from bringing, any claim, of any kind, including a claim in inverse condemnation, because the Developer has benefited by the City's approval of its development and the required improvements.
7. Other provisions the City determines necessary and proper to carry out the provisions of this Ordinance.

A. If a reimbursement district is established by the City Council, the date, of the formation of the district shall be the date that the City Council adopts the resolution forming the district.

**Section 7. Notice of Adoption of Resolution.** The City shall notify all property owners within the district and the Developer of the adoption of a reimbursement district resolution. The notice shall include a copy of the resolution, the date it was adopted and a short explanation specifying the amount of the reimbursement fee and that the property owner is legally obligated to pay the fee pursuant to this ordinance.

**Section 8. Recording the Resolution.** The City Recorder shall cause notice of the formation and nature of the reimbursement district to be filed in the office of the Marion County Clerk so as to provide notice to potential purchasers of property within the district. Said recording shall not create a lien. Failure to make such recording shall not affect the legality of the resolution or the obligation to pay the reimbursement fee.

**Section 9. Contesting the Reimbursement District.** No legal action intended to contest the formation of the district or the reimbursement fee, including the amount of the charge designated for each parcel, shall be filed after sixty (60) days following the adoption of a resolution establishing a reimbursement district and any such legal action shall be exclusively by Writ of Review pursuant to ORS 34.010 to ORS 34.102.

**Section 10. Obligation to Pay Reimbursement Fee.**

A. The applicant for a permit related to property within any reimbursement district shall pay the City, in addition to any other applicable fees and charges, the reimbursement fee established by the Council, if within 10 years after the date of the passage of the resolution forming the reimbursement district, the person applies for and receives approval from the City for any of the following activities:

1. A building permit for a new building;
2. Building permits(s) for any addition(s) modification(s), repair(s) or alteration(s) of a building, which exceed twenty five percent (25%) of the value of the building within any 12-month period. The value of the building shall be the amount shown on the most current records of the county Department of Assessment and Taxation for the building's real market value. This paragraph shall not apply to repairs made necessary due to damage or destruction by fire or other natural disaster;
3. A development permit, as that term is defined by this ordinance;
4. A City permit issued for connection to a public improvement.

B. The City's determination of who shall pay the reimbursement fee and when the reimbursement fee is due is final.

C. In no instance shall the City, or any officer or employee of the City, be liable for payment of any reimbursement fee, or portion thereof, as a result of the City's determination as to who should pay the reimbursement fee. Only those payments which the City has received from or on behalf of those properties within a reimbursement district shall be payable to the Developer. The City's general fund or other revenue sources shall not be liable for or subject to payment of outstanding and unpaid reimbursement fees imposed upon private property.

D. Nothing in this ordinance is intended to modify or limit the authority of the City to provide or require access management.

E. Nothing in this ordinance is intended to modify or limit the authority of the City to enforce development conditions which have already been imposed against specific properties.

F. Nothing in this ordinance is intended to modify or limit the authority of the City, in the future, to impose development conditions against specific properties as they develop.

G. No person shall be required to pay the reimbursement fee on an application or upon property for which the reimbursement fee has been previously paid, unless such payment was for a different type of improvement. No permit shall be issued for any of the activities listed in subsection 10(A) unless the reimbursement fee, together with the amount of accrued interest, has been paid in full. Where approval is given as specified in subsection 10(A), but no permit is requested or issued, then the requirement to pay the reimbursement fee lapses if the underlying approval lapses.

H. The date of reimbursement under this Ordinance shall extend ten (10) years from the date of the formation of a reimbursement district formation by City Council resolution.

I. The reimbursement fee is immediately due and payable to the City by property owners upon use of a public improvement as provided by this ordinance in section 10(A). If connection is made or construction commenced without required city permits, then the reimbursement fee is immediately due and payable upon the earliest date that any such permit was required.

J. Whenever the full reimbursement fee has not been paid and collected for any reason after it is due, the City Administrator shall report to the City Council the amount of the uncollected reimbursement, the legal description of the property on which the reimbursement is due, the date upon which the reimbursement was due and the property owner's name or names. The City Council shall then, by motion, set a public hearing date and direct the City Administrator to give notice of that hearing to each of the identified property owners, together with a copy of the City Administrator's report concerning the unpaid reimbursement fee. Such notice may be either by certified mail or personal service. At the public hearing, the City Council may accept, reject or modify the City Administrator's report. If the City Council determines that the reimbursement fee is due but has not been paid for whatever reason, the City Council may, at its sole discretion, act, by resolution, to take any action, it deems appropriate, including all legal or equitable means necessary to collect the unpaid amount. After the City Council has made the determination that the reimbursement fee is due but has not been paid, the Developer shall have a private cause of action against the person legally responsible for paying the reimbursement fee.

**Section 11. Public Improvements.** Public improvements installed pursuant to reimbursement district agreements shall become and remain the sole property of the City.

**Section 12. Multiple Public Improvements.** More than one public improvement may be the subject of a reimbursement district.

**Section 13. Collection and Payment; Other Fees and Charges.**

A. The Developer shall receive all reimbursement collected by the City for reimbursement district public improvements. Such reimbursement shall be delivered to the Developer for as long as the reimbursement district agreement is in effect. Such payments shall be made by the City within ninety (90) days of receipt of the reimbursements.

B. The reimbursement fee is not intended to replace or limit, and is in addition to, any other existing fees or charges collected by the City.

**Section 14. Nature of the Fees.** The City Council finds that the fees imposed by this Ordinance are not taxes subject to the property tax limitations of Article XI, section 11(b) of the Oregon Constitution.

**Section 15. Severability.** If any part of this ordinance is held invalid by a court of competent jurisdiction, the remainder of this ordinance shall remain in effect.

**Section 16.** [Emergency clause.]

*Passed by the Council and approved by the Mayor June 28, 1999.*



**ORDINANCE NO. 2424**

**AN ORDINANCE UPDATING AND REVISING THE PROCEDURES RELATED TO TREES WITHIN THE CITY OF WOODBURN; REPEALING ORDINANCE 1908; AND SETTING AN EFFECTIVE DATE.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Definitions.**

A. "Certified Arborist" means a person who has met the criteria for certification from the International Society of Arboriculture or American Society of Consulting Arborists, and maintains his or her accreditation.

B. "Park tree" means a tree, shrub, bush, or other woody vegetation in public parks or areas to which the public has free access.

C. "Person" means an individual or legal entity.

D. "Private infrastructure" means a driveway apron or paved or concrete private walkway located within the City right-of-way.

E. "Private tree" means a tree, shrub, bush, or other woody vegetation located on private property other than a dedicated right-of-way or public easement, or public parks and grounds.

F. "Public infrastructure" means public water and sewer lines, electric lines, gas lines, telephone or cable television lines, curbs, and sidewalks located within the public right-of-way, and other public improvements.

G. "Public Works Director" means the Woodburn Public Works Director or designee.

H. "Real Property Owner" means the person holding legal title to the real property or properties upon which a street tree is located.

I. "Remove" or "Removal" means to cut down a tree, or remove 50% or more of the crown, trunk, or root system of a tree; or to damage a tree so as to cause the tree to decline and/or die. Remove or removal includes topping. Remove or removal includes but is not limited to damage inflicted upon a root system by application of toxic substances, operation of equipment and vehicles, storage of materials, change of natural grade due to unapproved excavation or filling, or unapproved alteration of natural physical conditions. It does not include normal trimming or pruning.

J. "Street tree" means a tree, shrub, or other woody vegetation on land, the trunk of which is located wholly or partially within the right-of-way along either side of a street, avenue or other way or within a dedicated side of a street, avenue or other way.

K. "Topping" means the severe cutting back of a tree's limbs to stubs three inches or larger in diameter within the tree's crown to such a degree so as to remove the natural canopy and disfigure the tree.

**Section 2. Permit to Remove Trees Required.**

A. No person shall remove a street tree without obtaining a permit from the Public Works Director. Permits to remove street trees will be granted only if one of the following conditions exist:

- (1) The tree is dangerous and may be made safe only by its removal.
- (2) The tree is dead or dying, and its condition cannot be reversed.
- (3) The tree is diseased and presents a potential threat to other trees within the City, unless it is removed.
- (4) The tree is causing damage, which cannot be corrected through normal tree maintenance, to public infrastructure as defined by this Ordinance.
- (5) The tree is causing damage, which cannot be corrected through normal tree maintenance, to private infrastructure as defined by this Ordinance.

B. Any application for a permit to remove a street tree shall be supported by a report prepared by an Arborist as defined by this Ordinance and paid for by the applicant for the permit.

C. Street Tree Removal Applications and Street Tree Permits shall be prepared by the Public Works Director in a form approved by the City Attorney.

D. Street tree removal permits shall remain valid for a period of 180 days from the date of issuance. Permits that have lapsed are void. Trees removed after a tree removal permit has expired shall be considered a violation of this Ordinance.

E. Misrepresentation of any fact necessary for the City's determination for granting a tree removal permit shall invalidate the permit. The City may at any time, including after a removal has occurred, independently verify facts related to a tree removal request and, if found to be false, or misleading, may invalidate the permit and process the removal as a violation. Such misrepresentation may be related to matters including, without limitation, tree size, location, health or hazard condition, justification for issuance of permit, or owner's authorized signature.

**Section 3. Requirement for Certified Arborist.** Pruning, treating, or removing street or park trees shall be performed by or under the direct supervision of a Certified Arborist. Before a permit is granted by the Public Works Director, the arborist shall provide proof of current City business license and evidence of possession of liability insurance in the minimum amounts provided by ORS 30.270. Permits shall not be required of a City employee doing work on behalf of the City. Permits shall not be required of franchisees or other public service companies doing work in pursuit of their public service endeavors, provided that all such work is completed in conformance with any applicable franchise requirements and by or under the direct supervision of a Certified Arborist.

**Section 4. City Cost Sharing for Street Tree Removal.** Subject to the availability of funds in the City's budget, the Public Works Director is authorized to expend City funds to share in the cost of removal of street trees according to the following formula:

COST OF REMOVAL	OWNER SHARE	CITY SHARE
First \$200	100%	0%
Above \$200	50%	50%

The maximum City subsidy for one property shall not exceed \$500, except in cases where the street tree removal is done exclusively for the protection of public infrastructure where the Public Works Director is authorized to have the City pay the entire cost. No subsidy shall be provided for trees removed at a Real Property Owner's request in order to protect private infrastructure. Additional guidelines for cost sharing of tree removal may be established, and amended from time to time as needed, by resolution of the City Council.

**Section 5. Tree Replacement.** The City may require the replacement by the Real Property Owner, at the Real Property Owner's expense, of a new tree after permission has been granted by the Public Works Director for the removal of an existing street tree. Replacement trees must have a minimum caliper of 2 inches at 4-foot height, be of a species that reaches the same height at maturity as surrounding street trees, and may not be a prohibited species under the Woodburn Development Ordinance.

**Section 6. Woodburn Street Tree Planting Regulations.** All street trees shall be planted in conformance with the Woodburn Street Tree Planting Regulations which shall be adopted, enforced, and administered by the Public Works Director consistent with the terms of this Ordinance. Copies of the Woodburn Street Tree Planting Regulations shall be on file in the City Recorder's office, Public Works Department, Community Development, and the Woodburn Public Library.

**Section 7. Street Tree Species to be Planted.** No person shall plant a street tree of any species that is prohibited by the Woodburn Development Ordinance without the written permission of the Public Works Director.

**Section 8. Tree Maintenance by City.** The City shall have the right to plant, prune, maintain, and remove trees located within the public right-of-way as may be necessary to protect public safety or to preserve or enhance the appearance of public property. The City may remove, or order to be removed at the expense of the Real Property Owner, any tree or part thereof which is in an unsafe condition or which by reason of its nature is injurious to sewers, electrical power lines, telephone or cable television lines, natural gas lines, water lines, or other public improvements, or is affected with any injurious fungus, insect, or other pest.

**Section 9. Street Tree Maintenance by Owner.**

A. In consideration of the value and benefits derived from the beauty and enjoyment of a street tree, the Real Property Owner shall have the responsibility, control, and shall bear the cost of maintenance and care of the street tree, and shall regularly inspect and remove defective conditions as necessary.

B. The Real Property Owner shall prune the branches of a street tree so that the branches do not obstruct the light from a street light or obstruct the view of any street intersection. The Real Property Owner shall maintain a clear space of 15 feet above the surface of the street and 10 feet above the surface of any sidewalk. The Real Property Owner shall remove all dead, diseased, or dangerous, or broken or decayed limbs which constitute a danger to the safety of the public.

C. The Real Property Owner shall be liable for injury, damage, or loss to persons or property caused by the Real Property Owner's failure to comply with subsection A or B of this section.

D. The City of Woodburn shall not be liable for injury, damage, or loss to person or property caused in whole or part by the defective or dangerous condition of any tree located in or upon a right-of-way. The Real Property Owner shall defend and hold harmless the City from all claims for loss and damage arising from the Real Property Owner's failure to comply with subsection A or B of this section.

**Section 10. Mutilation and Topping of Trees.**

A. Mutilation. Unless specifically authorized in writing by the Public Works Director, no person shall intentionally damage, cut, carve, transplant, or remove any park tree or street tree; attach or place any rope or wire (other than one used to support the tree itself), sign, poster, handbill, or other thing to it; allow any gaseous liquid or solid substance which is harmful to such trees to come in contact with it; or set fire or permit any fire to burn when such fire or the heat thereof will injure any portion of any such tree.

B. Tree Topping. No person shall top any park tree or street tree, except as authorized by the Public Works Director.

**Section 11. Removal of Stumps.** All stumps of street and park trees shall be removed below the surface of the ground so that the top of the stump shall not project above the surface of the ground. The costs of removing stumps shall be borne by the Real Property Owner.

**Section 12. Summary Powers for Removal of Dangerous or Nuisance Trees.**

A. The City may prune a private tree when it interferes with the spread of light along the street from a street light, or interferes with the visibility of any traffic control device or sign.

B. The City may require or initiate removal of all or part of any dead, dangerous or diseased park, private or street tree when the tree constitutes a hazard to life, property, or harbors insects or disease which constitutes a potential threat to other trees within the City.

C. The City may remove or trim a tree described in this section or may require the property owner to remove or trim any such tree on private property, or in a dedicated right-of-way or utility easement abutting upon the owner's property. Failure of the property owner to remove or trim the tree within 30 days after receiving notice by the City Administrator is a violation of this Ordinance, and the Public Works Department may then remove or trim the tree and assess the costs as a lien against the property.

**Section 13. Nuisance Abatement.** All street trees that the Public Works Director requires to be removed pursuant to this Ordinance, constitute nuisances and are subject to the abatement and lien procedure contained in Ordinance 2338, the City of Woodburn Nuisance Ordinance.

**Section 14. Enforcement.**

A. Civil Infraction. In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class I Civil Infraction which shall be processed according to the procedures contained in the Woodburn Civil Infraction Ordinance.

B. Civil Proceeding Initiated by City Attorney. The City Attorney, after obtaining authorization from the City Council, may initiate a civil proceeding on behalf of the city to enforce the provisions of this Ordinance. This civil proceeding may include, but is not limited to, injunction, mandamus, abatement, or other appropriate proceedings to prevent, temporarily or permanently enjoin or abate any violations of this Ordinance.

**Section 15. Separate Offenses.** Each day during which a violation of this Ordinance continues shall constitute a separate offense for which a separate penalty may be imposed.

**Section 16. Appeal.** If the Public Works Director refuses to issue any permit under this Ordinance, or requires the removal of a tree, the Public Works Director shall provide written notification to the applicant who may appeal to the City Council in writing within ten calendar days after the date of the written notification from the Public Works Director. The City Council shall proceed to hear and determine the appeal, based upon information submitted by the permit applicant and the Public Works Director. Any review of the City Council's final decision shall be to the Marion County Circuit Court pursuant to ORS Chapter 34.

**Section 17. Severability.** The sections and subsections of this Ordinance are severable. The invalidity of any section or subsection shall not affect the validity of the remaining sections and subsections.

**Section 18. Repeal.** Ordinance 1908 is hereby repealed.

**Section 19. Saving Clause.** Notwithstanding the repeal of Ordinance 1908, Ordinance 1908 shall remain in force for the purpose of authorizing the prosecution of a person who violated Ordinance 1908 prior to the effective date of this Ordinance.

**Section 20. Effective Date.** This Ordinance shall take effect on November 1, 2007.

*Passed by the Council September 10, 2007 and approved by the Mayor September 12, 2007.*

---

ORDINANCE NO. 1866**AN ORDINANCE ESTABLISHING REGULATIONS AND RATES FOR THE CITY WATER SYSTEM;  
AND REPEALING ORDINANCE NO. 1378, 1595, 1596, 1622 AND 1804.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1.     Definitions.**

(1)     Customer. The owner of property which is served by the City water system. A person, corporation, association or agency which rents or leases premises shall be considered an agent of the property owner.

(2)     Mains. Distribution pipe lines that are part of the City water system.

(3)     Premises. The integral property or area, including improvements thereon, to which water service is or will be provided.

(4)     Service Connection. The pipe, valves and other equipment by means of which the City conducts water from its mains to and through the meter to the property line, but not including piping from the property line to the premises served.

**Service Provided****Section 2.     Regular Service.**

(1)     The City shall furnish and install a service connection of such size and location as a customer requests, provided that the request is reasonable. The service will be installed from the main to a point between the curb line and the property line of the premises if the main is in the street, or to a point in a City right-of-way or easement.

(2)     The customer shall, at his own risk and expense, furnish, install and keep in good and safe condition equipment that may be required for receiving, controlling, applying and utilizing water. The City shall not be responsible for loss or damage caused by the improper installation of the equipment, or the negligence, want of proper care or wrongful act of the customer in installing, maintaining, using, operating or interfering with the equipment.

(3)     The City shall not be responsible for damage to property caused by a spigot, faucet, valve or other equipment that is open when the water is turned on at the meter.

(4)     A customer making any material change in the size, character or extent of the equipment or operation utilizing water service, or whose change in operations results in a large increase in the use of water, shall immediately give the City written notice of the nature of the change and, if requested, amend his application.

(5) The service connection, whether located on public or private property, is the property of the City; and the City reserves the right to repair, maintain and replace it.

### **Section 3. Temporary Service.**

(1) Charges for water furnished through a temporary service connection shall be the established rates for other customers.

(2) The applicant for temporary service will be required:

(a) To pay to the City, in advance at the option of the City, the estimated cost of installing and removing the facilities to furnish the service.

(b) To deposit an amount sufficient to cover bills for water during the entire period temporary service may be used, or to establish credit approved by the City.

(c) To deposit with the City an amount equal to the value of equipment loaned by the City. This deposit shall be refundable, less cost of any necessary repairs as provided in Subsection (3).

(3) The customer shall use all possible care to prevent damage to the meter or other equipment loaned by the City which are involved in furnishing the temporary service from the time they are installed until they are removed, or until 48 hours notice in writing has been given to the City that the contractor or other person is through with the meter and other equipment. If the meter or other equipment is damaged, the cost of making repairs shall be paid by the customer.

(4) Temporary service connections shall be disconnected and terminated within six months after installation unless an extension of time is granted in writing by the City.

## **Meters**

### **Section 4. Meters.**

(1) Meters shall be furnished and owned by the City.

(2) No rent or other charges shall be paid by the City for a meter or other equipment located on the customer's premises.

(3) Meters may be sealed by the City at the time of installation, and no seal shall be altered or broken except by one of its authorized agents.

(4) If a change in size of a meter and service is required, the installation shall be accomplished on the basis of a new connection.



**Section 5. Meter Error.** A customer may request the City to test the meter serving his premises. The customer shall deposit an amount to cover the reasonable cost of the test. This deposit will be returned if the meter is found to register more than 2 per cent fast. The deposit required of a customer requesting a meter test shall be as follows:

5/8 inch - 3/4 inch	\$ 20.00
1 inch	30.00
1-1/2 inch	65.00
2 inch	100.00
3 inch	130.00
4 inch	150.00
6 inch	165.00
8 inch	175.00

### **Fees, Charges and Rates**

**Section 6. Applications.**

(A) All water service connections, installations and alterations in the City shall be initiated by written application of each water customer. Each application shall be filed with the City and shall be accompanied by full payment of a water service installation charge and a water systems capacity fee in the amounts required by this ordinance.

(B) The Council may establish by motion a policy of connecting to an undersized main and recovery of associated costs. Yearly increases may be added to the established costs.

**Section 7. Water Service Installation Charges.**

(1) The water service installation charges in the City shall be as follows:

(a) For installation of a 3/4-inch service line and a 5/8-inch water meter: \$150.00.

(b) For installation of a 1-inch service line, including meter: \$300.00

(c) For installation of 1-1/2-inch and larger service lines and meters, the charge shall be actual cost of labor and materials furnished by the City, plus 15 per cent of said cost for administrative and overhead expense. Each [applicant] shall deposit the amount estimated by the water division with the application, and the final amount may be adjusted after installation is completed.

(2) All payments received by the City under the provisions of this section shall be deposited in, and credited to, the water fund of the City.

**Section 8. Water System Capacity Fee.**

(1) The water system capacity fee of the City shall be as follows:

(a) For single-family dwellings, trailers, manufactured dwelling units: \$750.00.

(b) (i) For apartments and other multiple-family dwellings: \$750.00 for the first unit and \$375.00 for each unit in excess of one.

(b) (ii) For motel, hotel and R.V. park units: \$750.00 for the first unit and \$210.00 for each unit in excess of one.

(c) All other structures and facilities shall be charged according to options below:

(i) Requiring meter sizes up to 1½ inches: \$750.000 plus \$30.00 for each 1,000 square feet of area, or portion thereof, in excess of 2,000 square feet.

(ii) Requiring meter sizes above 1½ inches:

<u>Size of Meter</u>	<u>System Capacity Fee</u>
2"	\$ 1,200.00
3"	2,625.00
4"	4,500.00
6"	9,750.00
Above 6"	Council approval necessary

(iii) The demand increase by a larger size meter will require an amount equal to the new size fee less the old size fee.

(d) No system capacity fee shall be charged to the services used for fire protection only, if the regular system capacity fee has been charged to serve the premises.

(e) All existing structures constructed prior to May 1977, and remaining on the same site to which the City was unable to provide a connection shall be charged greater of one-half the rate outlined above, or \$375.00.

(2) All payments received by the City under the provisions of this section shall be deposited in, and credited to, the Capital Improvement Water Fund. [Section 8 amended by Ordinance No. 1973, passed April 13, 1987.]

**Section 9. Water Rates.** The rates and charges for the supply and use of water from the water system and mains of the City of Woodburn shall be as follows:

(a) Metered Services:

<u>Service Size (Inches)</u>	<u>Quantity Allowed (Cubic Feet)</u>	<u>Minimum Monthly Charge ( Dollars)</u>
5/8" - 3/4"	400	\$4.50
1"	800	6.80
1-1/2"	1,800	12.20
2"	3,200	19.95
3"	7,500	41.55
4"	15,000	83.10
6"	32,000	171.70
8"	57,000	299.10

These minimum charges are based on the size of service line, from main to meter, and entitle the user to the quantity shown per month.

(b) Water Consumed above minimum quantity allowed per month - \$0.52 per 100 cubic feet.

(c-i) Single Residential: As per subsections "a" and "b" above.

(c-ii) Multiple Residential: \$4.50 per unit per month in establishing the minimum for each service. Quantity allowed shall be the number of units times 400 cubic feet, or the above established quantity allowed for size of service, whichever is greater. Unless water service to premises is disconnected entirely, the minimum charge will apply to all units whether occupied or not. However, an adjustment may be made for the unoccupied units of a newly constructed multiple structure for a period of 6 months from the date of first occupancy. The owner is responsible for providing written information and facilitating City's inspection.

(c-iii) Commercial and Industrial. Rate shall be based on the size of the service line and quantity used as established in [subsections] "a" and "b" of this [section].

(c-iv) Flat Rate. Residential accounts shall be \$8.05 per month. All flat rate accounts having water meters shall be billed as regular metered accounts starting January 1, 1988. [Section 9 (c-iv) amended by Ordinance No. 1975, passed April 13, 1987.]

(d) Fire Sprinkler Connections. \$3.00 per diameter inch of service line per month.

(e) Bulk Rate. For first 500 cubic feet, the minimum charge shall be \$20.00, including one time turn-on and turn-off of meter and valve device each day at one location. These charges will be doubled for the services necessitated on the week-ends, holidays and after 4:00 p.m. on regular work days. Public Works Department may make estimates for small flows. Summer bulk rate sale shall be limited by the Public Works Department, allowed generally in the early mornings. Public right-of-way construction and other public use may be exempted from the bulk rate charge.

(f) Minimum Charge at Start/Closing. The bills shall be prorated according to the usage, however, the minimum charge shall accrue to the end of the billing period for the services turned off during a billing cycle for nonpayment.

(g) Outside City Limits. A factor of 1.5 shall be applied to all rates and charges for services outside the City.

(h) The monies collected pursuant to the provisions of this section shall be used to pay the costs of operation, maintenance and expansion of the water supply and distribution systems, and related facilities and services, including administrative and engineering costs.

**Section 10. Prior Agreements.** All prior Council approved service agreements between the City and a customer will remain in force for the term of the agreement. However, the requirements of this ordinance and other applicable ordinances, including the rate increase provisions, must be met. [Section 10 added by Ordinance No. 1933, passed December 11, 1985.]

[Sections 11 through 33 renumbered by Ordinance No. 1933, passed December 11, 1985.]

**Section 11. Leak Adjustments.** In case of leakage, an adjustment for one billing or a two month period [shall] be made if the leak has been promptly repaired and the request for leak adjustment has been made within 6 months. Such adjustments shall not exceed 100% of the estimated excess flow attributable to the leak. A charge of \$10.00 will be made for leak adjustment service after the current flat rate services have been metered.

**Section 12. Rate and Fee Increases.** Unless otherwise modified by the City Council, all rates and charges detailed in Section 9(a) and 9(d) shall be automatically increased by approximately five and one-half percent (5.5%) effective with the billings for service beginning December 1, 1985, and again by said percentage beginning December 1, 1986. Thereafter, rate adjustments will be established by Council action at a frequency and amount determined to be fiscally responsible to support service obligations. [Section 12 amended by Ordinance No. 1933, passed December 11, 1985.]

### **Discontinuance of Service**

#### **Section 13. Unsafe Apparatus.**

(1) The City may refuse to furnish water and may discontinue service to a premises where an apparatus, appliance or other equipment using water is dangerous, unsafe or is being used in violation of laws, ordinances or legal regulations.

(2) The City does not assume liability for inspecting apparatus on the customer's property. The City does reserve the right of inspection, however, if there is reason to believe that unsafe or illegal apparatus is in use.

**Section 14. Service Detrimental to Others.** The City may refuse to furnish water and may discontinue service to premises where excessive demand by one customer will result in inadequate service to others.

**Section 15. Fraud and Abuse.** The City shall have the right to refuse or to discontinue water service to a premises to protect itself against fraud or abuse.

**Section 16. Noncompliance.** The City may discontinue water service to a customer for noncompliance with a City regulation if the customer fails to comply with the regulation within five days after receiving written notice of the City's intention to discontinue service. If such noncompliance affects matters of health or safety or other conditions that warrant such action, the City may discontinue water service immediately.

**Section 17. Water Waste.** Where wasteful or negligent water use seriously affects the general service, the City may discontinue the service if such conditions are not corrected within five days after the customer is given written notice. Knowingly allowing water to leak and not repairing it will constitute water waste.

**Section 18. Abandoned and Nonrevenue-producing Services.** When a service connection to a premises has been abandoned or not used for a period of one year or longer, the City may remove it or the City may start charging the minimum fee. New service shall be placed only upon the customer's applying and paying for a new service connection and water system capacity fee.

**Section 19. Materials Used.** Sizes of meters, pipes and other materials to be used in water connection and installation shall be determined by the City.

### **General**

**Section 20. Pools and Tanks.** When an abnormally large quantity of water is desired for filling a swimming pool, log pond or for other purposes, arrangements shall be made with the City prior to taking such water. Permission to take water in unusual quantities shall be given only if it can be safely delivered and if other customers will not be inconvenienced.

**Section 21. Damage to City Property.** The customer shall be liable for damage to a meter or other equipment or property owned by the City which is caused by an act of the customer, his tenants or agents. The damage shall include the breaking or destruction of seals by the customer on or near a meter and damage to a meter that may result from hot water or steam from a boiler or heater on the customer's premises. The City shall be reimbursed by the customer for such damage promptly on presentation of a bill.

**Section 22. Water Source Development.** No water source development will be made within the City limits without prior approval from the City Engineer.

**Section 23. Cross Connections.**

(A) Health regulations. Unprotected cross connections between the public water supply and any unapproved source of water are prohibited.

(B) Definition. A cross connection is defined as an interconnection between the utility water supply and any unapproved water supply, or a connection between a water distribution pipe and any fixture installed in such a manner that unsafe water, waste or sewage may be drawn into the utility water system. Cross connections may be divided into two classifications as follows:

(1) Connections in which pure and impure water are separated by gate valves, check valves, or both.

(2) Connections which permit pollution to enter when the pressure in the utility water system falls below atmospheric pressure, thus creating a vacuum. This process of water pollution is known as back siphonage.

(C) Use of private water and City water. Customers desiring to use both a utility water supply and a supply of water other than that furnished by the utility may obtain water at meter rates upon the following conditions and not otherwise. Under no circumstances shall a physical connection, direct or indirect, exist or be made in any manner, even temporarily, between the utility water supply and that of a private water supply. Where such a connection is found to exist, or where provision is made to connect the two systems by means of a spacer or otherwise, the utility water supply shall be shut off from the premises without notice. In case of such discontinuance, service shall not be re-established until satisfactory proof is furnished that the cross connection has been completely and permanently severed.

**Section 24. Access to Premises.**

(A) The City or its duly authorized agents shall at all reasonable times have the right to enter or leave the customer's premises for any cross connection inspection with the service of water to the premises.

(B) The requirements of State Health Department and other appropriate agencies will provide guidelines to the City to its enforcement responsibility.

**Water Conservation**

**Section 25. Declaration of Emergency.** When the Mayor is informed that the City water supply has become, or is about to become, depleted to such an extent as to cause a serious water shortage in the City, the Mayor shall have the authority to declare an emergency water shortage and to direct that the provisions of Section [26] through [30] of this ordinance be enforced.

**Section 26. Notice of Declaration of Emergency.** When a declaration of emergency is pronounced by the Mayor, the City Administrator or his designate shall make the declaration public in a manner reasonably calculated to provide actual notice to the public. This provision shall not be construed as requiring personal delivery or service of notice or notice by mail.

**Section 27. Prohibited Uses of Water.** When a declaration of emergency is pronounced and notice has been given in accordance with Section [25] and [26] above, the use and withdrawal of water by any person for the following purposes shall be prohibited:

- (1) Sprinkling, watering or irrigating shrubbery, trees, lawns, grass, ground covers, plants, vines, gardens, vegetables, flowers or any other vegetation.
- (2) Washing automobiles, trucks, trailers, trailerhouses, railroad cars or any other type of mobile equipment.
- (3) Washing sidewalks, driveways, filling station aprons, porches and other surfaces.
- (4) Washing the outside of dwellings; washing the inside or outside of office buildings.
- (5) Washing and cleaning any business or industrial equipment and machinery.
- (6) Operating any ornamental fountain or other structure making a similar use of water.
- (7) Swimming and wading pools not employing a filter and recirculating system.
- (8) Permitting the escape of water through defective plumbing.

**Section 28. Exemptions.** At the discretion of the Mayor, one or more of the above uses may be exempted from the provisions of this section. The exemption shall be made public as provided in Section [26] of this ordinance.

**Section 29. Exception to Maintain Sanitation.** The City Administrator shall have the authority to permit a reasonable use of water necessary to maintain adequate health and sanitation standards.

**Section 30. Enforcement.** Department of Public Works will be responsible for the interpretation and administration of this ordinance.

**Section 31. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 2 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 30 amended by Ordinance No. 2008, passed October 24, 1988.]

**Section 32. Severability.** The sections and subsections of this ordinance are severable. The invalidity of any section or subsection shall not affect the validity of the remaining sections and subsections.

**Section 33. Repeal.** Ordinance No. 1378, enacted October 8, 1973; Ordinance No. 1595, enacted March 21, 1978; Ordinance No. 1596, enacted March 21, 1978; Ordinance No. 1622, enacted June 27, 1978; and Ordinance No. 1804, enacted January 10, 1983, are repealed.

***Passed by the Council April 23, 1984, and approved by the Mayor April 24, 1984.***



## ORDINANCE NO. 1965

**AN ORDINANCE PROVIDING RULES, REGULATIONS, AND ENFORCEMENT FOR THE USE AND SUPPLY OF CITY SANITARY SEWER SERVICE AND WATER SERVICE, REPEALING ORDINANCE NO. 1931, AND DECLARING AN EMERGENCY.**

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Deposit Application.** Application for City sanitary sewer and water services, other than connection and meter installation service, shall be by written application on forms provided at the Recorder's Office. Each application for the use of sanitary sewer and water service must specifically designate the property to be served and the owner thereof and must be accompanied by a deposit in the sum of not less than \$40.00 or an amount equal to estimated 3 months bill at the discretion of the City. However, any resident of Woodburn (a person who has established credit with the City of Woodburn by having water and/or sewer service in his/her own name) will be allowed to move from one location within the City limits without having to pay a deposit if that resident has lived in Woodburn for at least three (3) years, has had City of Woodburn water and/or sewer service in his/her own name, and has not been delinquent in paying for water and/or sewer service within the past three years.

**Section 2. Deposit Refund.**

(A) A refund of the water and sewer service deposit will occur when a customer shows a satisfactory credit performance for three years. If it becomes necessary to make one or more visits to enforce collection and/or shut-off for non-payment during the three year period, the City shall retain the deposit. The deposit will be held for an additional three years from the date of the last visit to the customer's premise for collection for non-payment of a bill. (Definition of visit - hand delivery of notice of shut-off to the customer's premise. Definition of satisfactory credit - no water shut-off notices hand delivered and /or temporary shut-off service for non-payment during a three-year period).

(B) A refund of the deposit will occur upon the applicant's requesting discontinuance of service provided that all outstanding bills are paid in full. The deposit may be applied to the final bill.

(C) If an account is shut-off for non-payment, the deposit shall be held as security until the outstanding balance is paid. The deposit will only be applied to the outstanding balance when the account is closed and no further water or sewer service is required by the customer. The remaining balance of the deposit not used to pay the outstanding bill will be refunded to the customer.

(D) Upon refund of the cash deposit to the applicant for satisfactory credit performance or upon termination of service, the deposit shall be refunded together with interest thereon at the rate of one-half percent (1/2%) below the average annual interest rate received by the City. However, no interest shall be allowed or paid by the City of Woodburn on deposits which have been deposited with the City for less than 30

days. All cash deposits so paid to the City of Woodburn by water users shall be credited by the Finance Department into a special account to be known as "Water Deposit Trust Account".

### **Section 3. Disconnect Procedure.**

(A) All Charges for sanitary sewer and water service furnished or rendered by the City of Woodburn shall be chargeable to the premises or property where sanitary sewer and water service is supplied and, in addition, all persons signing an application for the use of sanitary sewer and water service shall be personally liable for all charges accrued against the property designated within the application. The City reserves the right to cut off and disconnect sanitary sewer and water service to the premises without further notice when charges for sanitary sewer and water service have not been paid within 30 days after the due date, and the expense thereof shall be borne by the property to which such service has been supplied. The City shall provide 3 to 5 days notice by a door hanger or by mail prior to water service disconnect.

(B) Fees charged for delinquency, disconnection and restoration of sanitary sewer services and water services shall be in accordance with the Master Fee Schedule. After the City water service has been disconnected for non-payment, it shall not be restored until the past due amount and all fees have been paid in full. [Section 3(B) as amended by Ordinance No. 2432 passed March 10, 2008 and effective May 1, 2008.]

(C) The charges for turn-off and/or turn-on for reasons other than non-payment of water bill shall be \$10.00. No charge shall be made for water turn-on service for a new customer with a deposit or an established three-year credit, and for the turn-on and/or turn-off services necessitated by an emergency such as waterline or equipment breakage.

(D) A renter or owner shall not be allowed to have City utility services at a new location unless the current billings have been satisfied. The non-delinquent bills after deposit deduction remains with the property.

(E) The disconnect notice shall be sent to the renter as well as the property owner at the time of termination of service for non-payment of bill. It is the property owner's responsibility to inform the City of its ownership. If the City fails to provide notice to the property owner, who has informed the City of its ownership and is on the City's current records, then the said property will not be liable for City's utility charges exceeding 15 working days beyond delinquency. Also, this provision will apply if the City fails to turn-off the water to the premises. Any charges exceeding 15 working days beyond delinquency must be collected from the renter or user of utility services, and failing to do so, the revenues shall be considered uncollectible and deleted from the City resources. The City may charge 1% interest per month on delinquent accounts.

(F) If a property served by City utilities is purchased by a bona fide purchaser with no knowledge of unpaid charges for prior utility service to the same property, the

purchaser of the property shall not be responsible for any of the charges that the former owner fails to pay.

[Section 3F added by Ordinance 2371, passed September 13, 2004.]

**Section 4. Lien Procedure.** Any and all sanitary sewer and water service bills not paid within 45 days after the due date shall be recorded by the City Recorder in the docket of City liens. When so docketed, said sum shall be a lien or charge against the estate and interest of the respective owners and the parties interested in such land which shall have been supplied with sanitary sewer and water service. Said persons shall make payment within 10 days from the time of entering the same in the docket of City liens and, if not so paid, the same shall be deemed delinquent and thereupon shall be collected in the manner provided for the collection of delinquent assessments. In addition to the City's property lien process, the City may use State statutes to collect the sewer bills.

**Section 5. Notice.** Notice to the City of the desire of any person to have the water turned off or at any premises shall be given to the Recorder at least 24 hours before the water is to be so turned on or off. In no event shall any person, other than the duly authorized employees of the City, turn on the supply of City water after the same has been shut off by the City on account of discontinuance of service for any reason whatsoever.

**Section 6. Permit.** No person supplied with sanitary sewer and water service shall be permitted to supply or furnish such services in any way to other persons or premises without a permit from the City Council.

**Section 7. Repairs.** The City reserves the right to shut off water from the mains, without notice, for repairs or other necessary purposes. For normal, routine repairs, the City shall take reasonable precaution to notify occupants of affected premises of the intention to shut off the water supply. In no event shall the City, its officers, employees or agents be responsible for any damage resulting from shutting off the City water supply. Water for steam boilers for power purposes shall not be furnished by direct pressure from the City water main. Owners of steam boilers shall maintain tanks for holding an ample reserve of water.

**Section 8. Alterations.** No person, other than an agent of the City, shall tap the City sanitary sewer or water mains, or make alterations in any conduit, pipe, or other fixture connected therewith, between the main and the property line.

**Section 9. Access.** The City shall have free access to all parts of the building or premises which are served by City sanitary sewer and water service for the purpose of inspecting the pipes and fixtures.

**Section 10. Rates.**

(A) The City Council of the City of Woodburn shall from time to time establish, by ordinance, all rates, surcharges, and connection fees for the use of the City of

Woodburn sanitary sewer and water service. The Public Works Director shall conduct an annual review of rates contained in this ordinance.

(B) Outside City Limits. A factor of 1.5 shall be applied to all rates and charges for service outside the City.

(C) Hardship Relief. Hardship cases may apply for and be granted a monthly charge reduction of 40% to the bill. Hardship may be established by submitting proof of \$6,000 or less yearly income. To remain eligible for reduction, the water consumption must not exceed the average, and the City may at its option install a meter for this monitoring.

**Section 11. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 3 civil infraction and shall be dealt with in according to the procedures established by Ordinance 1998. [Section 11 as amended by Ordinance No. 2008, passed October 28, 1988.]

**Section 12. Severability.** The sections and subsections of this ordinance are severable. The invalidity of any section or subsection shall not affect the validity of the remaining sections and subsections.

**Section 13. Repeal.** Ordinance No. 1931 is hereby specifically repealed.

**Section 14.** [Emergency clause.]

***Passed by the Council February 9, 1987, and approved by the Mayor  
February 11, 1987.***

**ORDINANCE NO. 2070****AN ORDINANCE ESTABLISHING SYSTEM DEVELOPMENT CHARGES FOR WATER AND SEWER.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1. Definitions.**

(A) "Applicant" shall mean the owner or other person who applies for a building permit, development permit, or connection to the City's water or sewer system.

(B) "Building" shall mean any structure, either temporary or permanent, built for the support, shelter or enclosure of persons, chattels or property of any kind. This term shall include tents, trailers, mobile homes or any vehicles serving in any way the function of a building. This term shall not include temporary construction sheds or trailers erected to assist in construction and maintained during the term of a building permit.

(C) "Building permit" shall mean an official document or certificate authorizing the construction or siting of any building. For purposes of this ordinance, the term "building permit" shall also include any construction or installation permits which may be required for those structures or buildings, such as a mobile home, that do not require a building permit in order to be occupied.

(D) "Capital improvements" shall mean public facilities or assets used for any of the following:

- 1) Water supply, treatment, storage, and transmission/conveyance;
- 2) Sewer collection/conveyance, treatment, and disposal; or

[Section 1(D) as amended by Ordinance 2251 passed November 22, 1999, and effective January 1, 2000.]

(E) "Citizen or other interested person" shall mean any person who is a legal resident of the City of Woodburn as evidenced by registration as a voter in the City, or by other proof of residency; or a person who owns, occupies, or otherwise has an interest in real property which is located within the city limits or is otherwise subject to the imposition of system development charges, as outlined in Section (3) of this ordinance.

(F) "Development" shall mean a building or other land construction, or making a physical change in the use of a structure or land, in a manner which increases the usage of any capital improvements or which will contribute to the need for additional or enlarged capital improvements.

(G) "Development permit" shall mean an official document or certificate, other than a building permit, authorizing development.

(H) "Dwelling unit" shall mean a building or a portion of a building designed for residential occupancy, consisting of one or more rooms which are arranged, designed or used as living quarters for one family only.

(I) "Encumbered" shall mean monies committed by contract or purchase order in a manner that obligates the City to expend the encumbered amount upon delivery of goods, the rendering of services, or the conveyance of real property provided by a vendor, supplier, contractor or owner.

(J) "Improvement fee" shall mean a fee for costs associated with capital improvements to be constructed after the effective date of this ordinance.

(K) "Owner" shall mean the person holding legal title to the real property upon which development is to occur.

(L) "Person" shall mean an individual, a corporation, a partnership, an incorporated association, or any other similar entity.

(M) "Qualified public improvement" shall mean a capital improvement that is:

- 1) Required as a condition of development approval;
- 2) Identified in the adopted capital improvement plan (CIP); and either
  - a) not located on or contiguous to property that is the subject of development approval; or
  - b) located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related.

[Section 1 (M) as amended by Ordinance 2251 passed November 22, 1999, and effective January 1, 2000.]

(N) "Reimbursement fee" shall mean a fee for costs associated with capital improvements already constructed or under construction on the effective date of this ordinance.

(O) "System development charge" shall mean a reimbursement fee, an improvement fee, or a combination thereof assessed or collected at the time of increased usage of a capital improvement or issuance of a development permit, building permit or connection to the capital improvement. System development

charges are separate from and in addition to any applicable tax, assessment, fee in lieu of assessment, or other fee or charge provided by law or imposed as a condition of development. System development charges do not include connection or hook-up fees that reimburse the City for the average cost of inspecting and installing connections to water and sewer capital improvements.

(P) "System development charge study" shall mean the study adopted pursuant to Section (3)(B), as amended and supplemental pursuant to Section (3)(H).

**Section 2. Rules of Construction.** For the purposes of administration and enforcement of this ordinance, unless otherwise stated in this ordinance, the following rules of construction shall apply:

(A) In case of any difference of meaning implication between the text of this ordinance and any caption, illustration, summary table, or illustrative table, the text shall control.

(B) The word "shall" is always mandatory and not discretionary; the word "may" is permissive.

(C) Words used in the present tense shall include the future; words used in the singular shall include the plural and the plural the singular, unless the context clearly indicates the contrary; and use of the masculine gender shall include the feminine gender.

(D) The phrase "used for" includes "arranged for", "designed for", "maintained for", or "occupied for".

(E) Unless the context clearly indicates the contrary, where a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and", "or" or "either...or", the conjunction shall be interpreted as follows:

(1) "And" indicates that all the connected terms, conditions, provisions or events shall apply.

(2) "Or" indicates that the connected items, conditions, or provisions or events may apply singly or in any combination.

(3) "Either...or" indicates that the connected items, conditions, provisions or events shall apply singly but not in combination.

(F) The word "includes" shall not limit a term to the specific example, but is intended to extend its meaning to all other instances or circumstances of like kind or character.

**Section 3. Imposition of System Development Charges.** System development charges are hereby imposed, subject to the following conditions.

(A) Development Subject to Charges. System Development Charges are imposed on all development within the city for capital improvements for water and sewer. System Development Charges are imposed on any development outside the city boundary for water and sewer capital improvements, if such development connects to or otherwise uses the city's water or sewer systems. The System Development Charges shall be paid in addition to all other fees, charges and assessments due for development, and are intended to provide funds only for capital improvements necessitated by new development.

(Section 3 (A) as amended by Ordinance 2251 passed November 22, 1999, and effective January 1, 2000.)

(B) Rates of Charges:

(1) For the purpose of setting Water and Sewer System Development Charges, the city hereby adopts and incorporates by reference the study entitled "System Development Charges for Woodburn, Oregon" dated July 29, 1991, particularly the assumptions, conclusions and findings in such study as to the determination of anticipated costs of capital improvements required to accommodate growth and the rates for system development charges to reimburse the city for such capital improvements.

(Section 3 (B)(1) as amended by Ordinance 2251 passed November 22, 1999, and effective January 1, 2000.)

(2) System development charges shall be imposed and calculated for the alteration, expansion or replacement of a building or dwelling unit if such alteration, expansion or replacement results in an increase in the use of capital improvements compared to the present use of the development. The amount of the system development charge to be paid shall be the difference between the rate for the proposed development and the rate that would be imposed for the development prior to the alteration, expansion or replacement.

(3) The City shall, based upon the study referred to in subsection (1) above, adopt by resolution the amounts of system development charges.

(C) Payment of Charges. Except as otherwise provided in this ordinance, applicants for building permits, development permits, or connection to City water or sewer systems shall pay the applicable system development charges prior to the issuance of the permit or connection by the City unless charges are financed pursuant to a City approved installment or deferral program. (Section 3(C) as amended by Ordinance 2457 passed June 22, 2009)

(D) Alternative Rate Calculation. Applicants may submit alternative rates for system development charges, subject to the following conditions:

(1) In the event an applicant believes that the impact on City capital improvements resulting from his development is less than the fee established in Section



(3)(B), such applicant may submit a calculation of an alternative system development charge to the City Council.

(2) The alternative system development charges rate calculations shall be based on data, information and assumptions contained in this ordinance and the adopted system development charges study or an independent source, provided that the independent source is a local study supported by a data base adequate for the conclusions contained in such study performed pursuant to a generally accepted methodology and based upon generally accepted standard sources of information relating to facilities planning, cost analysis and demographics.

(3) If the City Council determines that the data, information and assumptions utilized by the applicant to calculate the alternative system development charges rates comply with the requirements of this Section by using a generally accepted methodology, the alternative system development charges rates shall be paid in lieu of the rates set forth in Section (3)(B).

(4) If the City Council determines that the data, information and assumptions utilized by the applicant to calculate the alternative system development charges rates do not comply with the requirements of this Section or were not calculated by a generally accepted methodology, then the City Council shall provide to the applicant (by certified mail, return receipt requested) written notification of the rejection of the alternative system development charges rates and the reason therefor.

(5) Any applicant who has submitted a proposed alternative system development charges rate pursuant to this Section and desires the immediate issuance of a building permit, development permit, or connection shall pay the applicable system development charges rates pursuant to Section (3)(B). Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any right of review. Any difference between the amount paid and the amount due, as determined by the Council, shall be refunded to the applicant.

(E) Exemptions. The following development shall be exempt from payment of the system development charges:

(1) Alterations, expansion or replacement of an existing dwelling unit where not additional dwelling units are created and no change in use has occurred.

(2) The construction of accessory buildings or structures which will not create additional dwelling units and which do not create additional demands on the City's capital improvements.

(3) The issuance of a permit for a mobile home installation on the property which applicable system development charges have previously been made for such installation as documented by receipts issued by the City for such prior payment.

(4) Development with vested rights, determined as follows:

(a) Any owner of land which was the subject of a building permit or development permit issued prior to the effective date of this ordinance may petition the City for a vested rights determination which would exempt the landowner from the provisions of this ordinance. Such petition shall be evaluated in writing by the City Attorney and a decision made by the City Council based on the following criteria:

(i) The existence of a valid, unexpired permit issued by the City authorizing the specific development for which a determination is sought;

(ii) Substantial expenditures or obligations made or incurred in reliance upon the authorizing governmental act;

(iii) Other factors that demonstrate it is highly inequitable to deny the owner the opportunity to complete the previously approved development under the conditions of approval by requiring the owner to comply with the requirement of this ordinance. For the purposes of this paragraph, the following factors shall be considered in determining whether it is inequitable to deny the owner the opportunity to complete the previously approved development:

(aa) Whether the injury suffered by the owner outweighs the public cost of allowing the development to go forward without payment of the system development charges required by this ordinance; and

(bb) Whether the expenses or obligations for the development were made or incurred prior to the effective date of this Ordinance.

(F) Credits for Development Contributions of Qualified Public Improvements. The City shall grant a credit against the system development charges imposed pursuant to Section (3)(A) and (B) for the donation of land as permitted by Ordinance 1807, or for the construction of any qualified public improvements. Such land donation and construction shall be subject to the approval of the City.

(1) The amount of developer contribution credit to be applied shall be determined according to the following standards of valuation:

(a) The value of donated lands shall be based upon a written appraisal of fair market value by a qualified and professional appraiser based upon comparable sales of similar property between unrelated parties in a bargaining transaction; and

(b) The cost of anticipated construction of qualified public improvements shall be based upon cost estimates certified by a professional architect or engineer.

(2) Prior to issuance of a building permit, development permit, or connection, the applicant shall submit to the City Administrator a proposed plan and estimate of cost for contributions of qualified public improvements. The proposed plan and estimate shall include:

(a) A designation of the development for which the proposed plan is being submitted;

(b) A legal description of any land proposed to be donated pursuant to Chapter 39 of the Woodburn Zoning Ordinance, Ordinance 1807, and a written appraisal prepared in conformity with subsection (1)(a) of this Section.

(c) A list of the contemplated capital improvements contained within the plan;

(d) An estimate of proposed construction costs certified by a professional architect or engineer; and

(e) A proposed time schedule for completion of the proposed

(3) The City Administrator shall determine if the proposed qualified public improvement is:

(a) Required as a condition of development approval;

(b) Identified in the adopted capital improvement plan (CIP); and either

i) Not located on or contiguous to property that is the subject of development approval; or

ii) Located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related.

(Section 3 (F)(3) as amended by Ordinance 2251 passed November 22, 1999, and effective January 1, 2000.)

(4) Any applicant who submits a proposed plan pursuant to this Section and desires the immediate issuance of a building permit, development permit, or connection, shall pay the applicable system development charges. Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any review rights. Any difference between the amount paid the amount due, as determined by the City Administrator, shall be refunded to the applicant. In no event shall a refund by City under this subsection exceed the amount originally paid by the applicant.

(5) In the event the amount of developer contribution determined to be applicable by the City Administrator pursuant to an approved plan of contribution exceeds the total amount of system development charges due by the applicant, the City may execute with the applicant an agreement for future reimbursement of the excess of such contribution credit from future receipts by the City of other system development charges. Such agreement of reimbursement shall be subject to City

Council Approval and not be for a period in excess of five years from the date of completion of the approved plan of contribution and shall provide for a forfeiture of any remaining reimbursement balance at the end of such five year period.

(G) Appeals and Review Hearings.

(1) An applicant who is required to pay system development charges shall have the right to request a hearing to review the denial by the City Administrator of any of the following:

(a) A proposed credit for contribution of qualified public improvements pursuant to Section (3)(F).

(2) Such hearing shall be requested by the applicant within fifteen (15) days of the date of first receipt of the denial by the City Administrator. Failure to request a hearing within the time provided shall be deemed a waiver of such right.

(3) The request for hearing shall be filed with the City Administrator and shall contain the following:

(a) The name and address of the applicant;

(b) The legal description of the property in question;

(c) If issued, the date the building permit, development permit, or connection was issued;

(d) A brief description of the nature of the development being undertaken pursuant to the building permit, development permit, or connection;

(e) If paid, the date the system development charges were paid; and

(f) A statement of the reasons why the applicant is requesting the hearing.

(4) Upon receipt of such request, the City Administrator shall schedule a hearing before the City Council at a regularly scheduled meeting or a special meeting called for the purpose of conducting the hearing and shall provide the applicant written notice of the time and place of the hearing. Such hearing shall be held within forty-five (45) days of the date the request for hearing was filed.

(5) Such hearing shall be before the City Council and shall be conducted in a manner designed to obtain all information and evidence relevant to the requested hearing. Formal rules of civil procedures and evidence shall not be applicable; however, the hearing shall be conducted in a fair and impartial manner with each party having an opportunity to be heard and to present information and evidence.

(6) Any applicant who requests a hearing pursuant to this Section and desires the immediate issuance of a building permit, development permit, or connection shall pay prior to or at the time the request for hearing is filed the applicable system development charges pursuant to Section (3)(B). Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any review rights.

(7) An applicant may request a hearing under this Section without paying the applicable system development charges, but no building permit, development permit, or connection shall be issued until such system development charges are paid in the amount initially calculated or the amount approved upon completion of the review provided in this Section.

(H) Review of Study and Rates. This ordinance and the system development charges study shall be reviewed at least once every four years. The review shall consider new estimates of population and other socioeconomic data, changes in the cost of construction and land acquisition, and adjustments to the assumptions, conclusions or findings set forth in the study adopted by Section (3)(B). The purpose of this review is to evaluate and revise, if necessary, the rates of the system development charges to assure that they do not exceed the reasonably anticipated costs of the City's capital improvements. In the event the review of the ordinance or the study alters or changes the assumptions, conclusions and findings of the study, or alters or changes the assumptions, conclusions and findings of the study, or alters or changes the amount of system development charges, the study adopted by reference in Section (3)(B) shall be amended and updated to reflect the assumptions, conclusions and findings of such reviews and Section (3)(B) shall be amended to adopt by reference such updated studies.

#### **Section 4. Receipt and Expenditure of System Development Charges.**

(A) Trust Accounts. The city hereby establishes a separate trust account for each type of System Development Charge to be designated as the "Water SDC Account" and the "Sewer SDC Account," which shall be maintained separate and apart from all other accounts of the city. All System Development Charge payments shall be deposited into the appropriate trust account immediately upon receipt.

(Section 4 (A) as amended by Ordinance 2251 passed November 22, 1999, and effective January 1, 2000.)

(B) Use of System Development Charges. The monies deposited into the trust accounts shall be used solely for the purpose of providing capital improvements necessitated by development, including, but not limited to:

- (1) Design and construction plan preparation;
- (2) Permitting and fees;

- (3) Land and materials acquisition, including any costs of acquisition or condemnation;
- (4) Construction of improvements and structures;
- (5) Design and construction of new drainage facilities required by the construction of capital improvements and structures;
- (6) Relocating utilities required by the construction of improvements and structures;
- (7) Landscaping;
- (8) Construction management and inspection;
- (9) Surveying, soils and material testing;
- (10) Acquisition of capital equipment;
- (11) Repayment of monies transferred or borrowed from any budgetary fund of the City which were used to fund any of the capital improvements as herein provided;
- (12) Payment of principal and interest, necessary reserves and costs of issuance under any bonds or other indebtedness issued by the City to fund capital improvements;
- (13) Direct costs of complying with the provisions of ORS 223.297 to 223.314, including the costs of developing system development charges methodologies and providing an annual accounting of system development charges expenditures.

(C) Prohibited Uses of System Development Charges. Funds on deposit in system development charge trust accounts shall not be used for:

- (1) Any expenditure that would be classified as a routine maintenance or repair expense; or
- (2) Costs associated with the construction of administrative office facilities that are more than an incidental part of other capital improvements.

(D) Capital Improvements Authorized to be Financed by System Development Charges. Any capital improvement being funded wholly or in part with system development charges revenue shall be included in the City's capital improvement program. The capital improvement program shall:

- (1) List the specific capital improvement projects that may be funded with system development charges revenue;

(2) Provide the cost of each capital improvement project, and an estimate of the amounts of each revenue source, including system development charges, that will be used to fund each project;

(3) Provide the estimated timing of each capital improvement project;  
and

(4) Be updated at least once every four years.

(E) Investment of Trust Account Revenue. Any funds on deposit in system development charges trust accounts which are not immediately necessary for expenditure shall be invested by the City. All income derived from such investments shall be deposited in the system development trust accounts and used as provided herein.

(F) Refunds of System Development Charges. System development charges shall be refunded in accordance with the following requirements:

(1) An applicant or owner shall be eligible to apply for a refund if:

a) The building permit, development permit or connection has expired and the development authorized by such permit is not complete; or

b) The system development charges have not been expended or encumbered prior to the end of the fiscal year immediately following the ninth anniversary of the date upon which such charges were paid. For the purposes of this section, system development charges were paid. For the purposes of this section, system development charges collected shall be deemed to be expended or encumbered on the basis of the first system development charges in shall be the first system development charges out.

(2) The application for refund shall be filed with the City Administrator and contain the following:

a) The name and address of the applicant;

b) The location of the property which was the subject of the system development charges;

c) A notarized sworn statement that the petitioner is the then current owner of the property on behalf of which the system development charges were paid, including proof of ownership, such as a certified copy of the latest recorded deed;

d) The date the system development charges were paid;

e) A copy of the receipt of payment for the system development charges; and, if appropriate;

f) The date the building permit, development permit, or connection was issued and the date of expiration.

(3) The application shall be filed within ninety (90) days of the expiration of the building permit, development permit, or connection, or within ninety (90) days of the end of the fiscal year following the ninth anniversary of the date upon which the system development charges were paid. Failure to timely apply for a refund of the system development charges shall waive any right to a refund.

(4) Within thirty (30) days from the date of receipt of a petition for refund, the City Administrator will advise the petitioner of the status of the request for refund, and if such request is valid, the system development charges shall be returned to the petitioner.

(5) A building permit, development permit, or connection which is subsequently issued for a development on the same property which was the subject of a refund shall pay the systems development charges as required by Section (3).

(G) Annual Accounting Reports. The City shall prepare an annual report accounting for system development charges, including the total amount of system development charges revenue collected in each trust account, and the capital improvement projects that were funded.

(H) Challenge of Expenditures. Any citizen or other interested person (as defined in Section (1) (F) may challenge an expenditure of system development charges revenues.

(1) Such challenge shall be submitted, in writing, to the City Administrator for review within two years following the subject expenditure, and shall include the following information:

a) The name and address of the citizen or other interested person challenging the expenditure;

b) The amount of the expenditure, the project, payee or purpose, and the approximate date on which it was made; and

c) The reason why the expenditure is being challenged.

(2) If the City Administrator determines that the expenditure was not made in accordance with the provisions of this ordinance and other relevant laws, a reimbursement of system development charges trust account revenues from other revenue sources shall be made within one year following the determination that the expenditures were not appropriate.

(3) The City Administrator shall make written notification of the results of the expenditure review to the citizen or other interested person who requested the review within ten (10) days of completion of the review.



---

**Section 5. Severability.** If any clause, section or provision of this ordinance shall be declared unconstitutional or invalid for any reason or cause, the remaining portion of said ordinance shall be in full force and effect and be valid as if such invalid portion thereof had not been incorporated herein.

*Passed by the Council September 9, 1991 and approved by the Mayor  
September 10, 1991.*

## ORDINANCE NO. 2111

**AN ORDINANCE ESTABLISHING A METHODOLOGY FOR TRAFFIC IMPACT FEES (TIF) AND STORMWATER DRAINAGE SYSTEM DEVELOPMENT CHARGES; AND REPEALING ORDINANCE NO. 1842.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1. Definitions.** The following definitions apply:

(A) "Applicant" shall mean the owner or other person who applies for a building permit or development permit.

(B) "Bancroft Bond" shall mean a bond issued by the city to finance a capital improvement in accordance with ORS 223.205 - 223.295.

(C) "Building" shall mean any structure, either temporary or permanent, built for the support, shelter or enclosure of persons, chattels or property of any kind. This term shall include tents, trailers, mobile homes or any vehicles serving in any way the function of a building. This term shall not include temporary construction sheds or trailers erected to assist in construction and maintained during the term of a building permit.

(D) "Building Permit" shall mean an official document or certificate authorizing the construction or siting of any building. For purposes of this ordinance, the term "Building Permit" shall also include any construction or installation permits which may be required for those structures or buildings, such as a mobile home, that do not require a building permit in order to be occupied.

(E) "Capital Improvements" shall mean public facilities or assets used for stormwater drainage.

(Section 1 (E) as amended by Ordinance 2249 passed November 22, 1999, effective January 1, 2000.)

(F) "Citizen or Other Interested Person" shall mean any person who is a legal resident of the City of Woodburn as evidenced by registration as a voter in the city, or by other proof of residency; or a person who owns, occupies, or otherwise has an interest in real property which is located within the city limits or is otherwise subject to the imposition of system development charges, as outlined in Section 3 of this ordinance.

(G) "City" shall mean the City of Woodburn, Oregon.

(H) "Credit" shall mean the amount of money by which the TIF or Stormwater Drainage SDC for a specific development may be reduced because of construction of eligible capital facilities as outlined in this ordinance.

(I) "Development" shall mean a building or other land construction, or making a change in the use of a structure or land, in a manner which increases the usage of any capital improvements or which will contribute to the need for additional or enlarged capital improvements.

(J) "Development Permit" shall mean an official document or certificate, other than a building permit, authorizing development.

(K) "Dwelling Unit" shall mean a building or a portion of a building designed for residential occupancy, consisting of one or more rooms which are arranged, designed or used as living quarters for one family only.

(L) "Encumbered" shall mean monies committed by contract or purchase order in a manner that obligates the city to expend the encumbered amount upon delivery of goods, the rendering of services, or the conveyance of real property provided by a vendor, supplier, contractor or Owner.

(M) "Improvement Fee" shall mean a fee for costs associated with capital improvements to be constructed after the effective date of this ordinance. Notwithstanding anything in this ordinance to the contrary, it is an incurred charge or cost based upon the use of or the availability for use of the systems and capital improvements required to provide services and facilities necessary to meet the routine obligations of the use and ownership of property, and to provide for the public health and safety upon development.

(N) "Off-site" shall mean not located on or contiguous to property that is the subject of development approval.

(O) "On-site" shall mean located on or contiguous to property that is the subject of developmental approval.

(P) "Owner" shall mean the person holding legal title to the real property upon which development is to occur.

(Q) "Person" shall mean an individual, a corporation, a partnership, an incorporated association, or any other similar entity.

(R) "Prime Rate of Interest" shall mean the base rate on corporate loans posted by at least 75% of the nation's 30 largest banks as posted in the Wall Street Journal.

(S) "Qualified Public Improvement" shall mean a capital improvement that is:

- 1) Required as a condition of residential development approval;
- 2) Identified in the adopted capital improvement plan (CIP); and

either

a) not located on or contiguous to property that is the subject of development approval; or

b) located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related

(Section 1 (S) as amended by Ordinance 2249 passed November 22, 1999, effective January 1,2000.)

(T) "Right-of-Way" shall mean that portion of land that is dedicated for public use.

(U) "System Development Charge" shall mean an improvement fee assessed or collected at the time of increased usage of a capital improvement or issuance of a development permit or building permit. System development charges are separate from and in addition to any applicable tax, assessment, fee in lieu of assessment, or other fee or charge provided by law or imposed as a condition of development.

(V) This subsection was repealed by Ordinance 2249 passed November 22, 1999.

(W) "Traffic Impact Fee and Stormwater Drainage System Development Charge Methodology Report" shall mean the report adopted pursuant to Section (3)(B), as amended and supplemented pursuant to Section (3)(H).

**Section 2. Rules of Construction.** For the purposes of administration and enforcement of this ordinance, unless otherwise stated in this ordinance, the following rules of construction shall apply:

(A) In case of any difference of meaning or implication between the text of this ordinance and any caption, illustration, summary table, or illustrative table, the text shall control.

(B) The word "shall" is always mandatory and not discretionary; the word "may" is permissive.

(C) Words used in the present tense shall include the future; words used in the singular shall include the plural and the plural the singular, unless the context clearly indicates the contrary; and use of the masculine gender shall include the feminine gender.

(D) The phrase "used for" includes "arranged for", "designed for", "maintained for", or "occupied for".

(E) Unless the context clearly indicates the contrary, where a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and", "or" or "either...or", the conjunction shall be interpreted as follows:

1) "And" indicates that all the connected terms, conditions, provisions or events shall apply.

2) "Or" indicates that the connected items, conditions, provisions or events may apply singly or in any combination.

3) "Either"...or" indicates that the connected items, conditions, provisions or events shall apply singly but not in combination.

(F) The word "includes" shall not limit a term to the specific example, but is intended to extend its meaning to all other instances or circumstances of like kind or character.

**Section 3. Imposition of System Development Charges.** System development charges are hereby imposed, subject to the following conditions:

(A) Development Subject to Charges. System development charges are imposed on all new development within the city for capital improvements for transportation and stormwater drainage. The system development charges shall be paid in addition to all other fees, charges and assessments due for development, and are intended to provide funds only for capital improvements necessitated by new development.

(B) Rates of Charges.

1) The city hereby adopts and incorporates by reference the report entitled "City of Woodburn Traffic Impact Fee and Stormwater Drainage System Development Charges Methodology Report", dated June 30, 1993, particularly the assumptions, conclusions and findings in such study as to the determination of anticipated costs of capital improvements required to accommodate growth and the rates for system development charges to reimburse the city for such capital improvements.

2) System development charges shall be imposed and calculated for the change in use, alternation, expansion or replacement of a building or dwelling unit if such change in use, alternation, expansion or replacement results in an increase in the use of capital improvements compared to the present use of the development. The amount of the system development charges to be paid shall be the difference between the rate for the proposed development and the rate that would be imposed for the development prior to the change in use, alternation, expansion or replacement.

3) The city shall, based upon the report referred to in subsection (1) above, adopt by resolution the amounts of system development charges.

4) An additional systems development charge may be assessed by the city if the demand placed on the city's capital facilities exceeds the amount initially estimated at the time systems development charges are paid. The additional charge shall be for the increased demand or for the demand above the underestimate, and it shall be based upon the fee that is in effect at the time the additional demand impact is determined, and not upon the fee structure that may have been in effect at the time the initial systems development charge was paid. This provision does not apply to single family or other residential units unless additional rental units are created.

(C) Payment of Charges. Applicants for building permits or development permits shall pay the applicable system development charges prior to the issuance of the permits by the city unless charges are financed pursuant to a City approved installment or deferral program.

(Section 3 (C) as amended by Ordinance 2249 passed November 22, 1999, effective January 1, 2000 and Ordinance 2457 passed June 22, 2009, effective June 24, 2009.)

(D) Alternative Rate Calculation. Applicants may submit alternative rates for system development charges, subject to the following conditions:

1) In the event an applicant believes that the impact on city capital improvements resulting from a development is less than the fee established in Section (3) (b), the applicant may submit alternative system development charge rate calculations, accompanied by the alternative rate review fee established by resolution for this purpose, to the City Administrator. The city may hire a consultant to review the alternative system development charge rate calculations, and may pay the consulting fees from system development charges revenues.

2) The alternative system development charge rate calculations shall be based on data, information and assumptions contained in this ordinance and the adopted system development charges study or an independent source, provided that the independent source is a local study supported by a data base adequate for the conclusions contained in such study performed pursuant to a generally accepted methodology and based upon generally accepted standard sources of information relating to facilities planning, cost analysis and demographics.

3) If the city council determines that the data, information and assumptions utilized by the applicant to calculate the alternative system development charges rates comply with the requirements of this section by using a generally accepted methodology, the alternative system development charges rates shall be paid in lieu of the rates set forth in Section (3)(B).

4) If the city council determines that the data, information and assumptions utilized by the applicant to calculate the alternative system development charges rates do not comply with the requirements of this section or were not calculated by a generally accepted methodology, then the city council shall provide to the applicant (by certified mail, return receipt requested) written notification of the rejection of the alternative system development charges rates and the reason therefor.

5) Any applicant who has submitted a proposed alternative system development charges rate pursuant to this section and desires the immediate issuance of a building permit or development permit shall pay the applicable system development charges rates pursuant to Section (3)(B). Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any right of review. Any difference between the amount paid and the amount due, as determined by the city council, shall be refunded to the applicant.

(E) Exemptions. The following development shall be exempt from payment of the system development charges:

1) Alternations, expansion or replacement of an existing dwelling unit where no additional dwelling units are created.

2) The construction of accessory buildings or structures which will not create additional dwelling units and which do not create additional demands on the city's capital improvements.

3) The issuance of a permit for a mobile home on which applicable system development charges have previously been made as documented by receipts issued by the city for such prior payment.

4) Development with vested right, determined as follows:

a) Any owner of land which was the subject of a building permit or development permit issued prior to the effective date of this ordinance may petition the city for a vested rights determination which would exempt the landowner from the provision of this ordinance. Such petition shall be evaluated by the City Attorney and a decision made by the city council based on the following criteria:

i) The existence of a valid, unexpired permit issued by the city authorizing the specific development for which a determination is sought;

ii) Substantial expenditures or obligations made or incurred in reliance upon the authorizing governmental act;

iii) Other factors that demonstrate it is highly inequitable to deny the owner the opportunity to complete the previously approved development under the conditions of approval by requiring the owner to comply with the requirements of this ordinance. For the purposes of this paragraph, the following factors shall be considered in determining whether it is inequitable to deny the owner the opportunity to complete the previously approved development:

aa) Whether the injury suffered by the owner outweighs the public cost of allowing the development to go forward without payment of the system development charges required by this ordinance; and

bb) Whether the expenses or obligations for the development were made or incurred prior to the effective date of this ordinance.

(F) Credits for Developer Contributions of Qualified Public Improvements. The city shall grant a credit, not to exceed 100% of the applicable TIF or SDC, against the system development charges imposed pursuant to Section (3)(A) and (B) for the donation of land as permitted by Ordinance 1807, or for the construction of any qualified public improvements. Such land donation and construction shall be subject to the approval of the city.

1) The amount of developer contribution credit to be applied shall be determined according to the following standards of valuation:

a) The value of donated lands shall be based upon a written appraisal of fair market value by a qualified and professional appraiser based upon comparable sales of similar property between unrelated parties in a bargaining transaction; and

b) The cost of anticipated construction of qualified public improvements shall be based upon cost estimates certified by a professional architect or engineer.

2) Prior to issuance of a building permit or development permit, the applicant shall submit to the City Administrator a proposed plan and estimate of cost for contributions of qualified public improvements. The proposed plan and estimate shall include:

a) a designation of the development for which the proposed plan is being submitted.

b) a legal description of any land proposed to be donated pursuant to Chapter 39 of the Woodburn Zoning Ordinance, Ordinance 1807, and a written appraisal prepared in conformity with subsection (1)(a) of this section;

c) a list of the contemplated capital improvements contained within the plan;

d) an estimate of proposed construction costs certified by a professional architect or engineer; and

e) a proposed time schedule for completion of the proposed plan.

3) The City Administrator shall determine if the proposed qualified public improvement is:

a) Required as a condition of development approval;



b) Identified in the adopted capital improvement plan (CIP);  
and either

i) Not located on or contiguous to property that is the subject of development approval; or

ii) Located in whole or in part on or contiguous to property that is the subject of development approval and required to be built large or with greater capacity than is necessary for the particular development project to which the improvement fee is related.

c) Not located on or contiguous to property that is the subject of residential development approval.

4) The decision of the City Administrator as to whether to accept the proposed plan of contribution and the value of such contribution shall be in writing and issued within fifteen (15) working days of the review. A copy shall be provided to the applicant.

5) A proposed improvement which does not meet all three (3) of the criteria included in Section 3(F)(3) above shall not be considered a qualified public improvement and the city is not required under ORS 223.297 - 223.314 to provide a credit for such an improvement. However, the city shall grant a credit, in an amount not to exceed fifty percent (50%) of the total amount of the applicable SDC, for certain other contributions of capital facilities under the following conditions:

a) The capital facilities being contributed must exceed the local stormwater drainage capacity (for SDC) required for the specific type of development (i.e., residential, industrial, etc.); and

b) Only the value of the contribution which exceeds the local stormwater drainage capacity (for SDC) required for the specific type of development (i.e., residential, industrial, etc.) shall be considered when calculating the credit; and

c) Donations for on-site right-of-way are not eligible for the credit.

(Section 3(F)(5) as amended by Ordinance 2259 passed November 22, 1999, effective January 1, 2000.)

6) Any applicant who submits a proposed plan pursuant to this section and desires the immediate issuance of a building permit or development permit, shall pay the applicable system development charges. Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any review rights. Any difference between the amount paid and the amount due, as determined by the City Administrator, shall be refunded to the applicant. In no event shall a refund by city under this subsection exceed the amount originally paid by the applicant.

---

(G) Appeals and Review Hearings.

1) An applicant who is required to pay system development charges shall have the right to request a hearing to review the denial by the City Administrator of a proposed credit for contribution of qualified public improvements pursuant to Section (3)(F).

(Section 3 (G)(1) as amended by Ordinance 2249 passed November 22, 1999, effective January 1, 2000.)

2) Such hearing shall be requested by the applicant within fifteen (15) days of the date of first receipt of the denial by the City Administrator. Failure to request a hearing within the time provided shall be deemed a waiver of such right.

3) The request for hearing shall be filed with the City Administrator and shall contain the following:

- a) The name and address of the applicant;
- b) The legal description of the property in question;
- c) If issued, the date the building permit or development permit was issued;
- d) A brief description of the nature of the development being undertaken pursuant to the building permit or development permit;
- e) If paid, the date the system development charges were paid; and
- f) A statement of the reasons why the applicant is requesting the hearing.

4) Upon receipt of such request, the City Administrator shall schedule a hearing before the city council at a regularly scheduled meeting or a special meeting called for the purpose of conducting the hearing and shall provide the applicant written notice of the time and place of the hearing. Such hearing shall be held within forty-five (45) days of the date the request for hearing was filed.

5) Such hearing shall be before the city council and shall be conducted in a manner designed to obtain all information and evidence relevant to the requested hearing. Formal rules of civil procedures and evidence shall not be applicable; however, the hearing shall be conducted in a fair and impartial manner with each party having an opportunity to be heard and to present information and evidence.

6) Any applicant who requests a hearing pursuant to this section and desires the immediate issuance of a building permit or development permit shall pay prior to or at the time the request for hearing is filed the applicable system development charges pursuant to Section (3)(B). Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any review rights.

7) An applicant may request a hearing under this section without paying the applicable system development charges, but no building permit or development permit shall be issued until such system development charges are paid in the amount initially calculated or the amount approved upon completion of the review provided in this section.

(H) Review of Study and Rates. This ordinance and the Traffic Impact Fee and Stormwater Drainage System Development Charge Methodology Report shall be reviewed at least once every five (5) years. The review shall consider new estimates of population and other socioeconomic data, changes in the cost of construction and land acquisition, and adjustments to the assumptions, conclusions or findings set forth in the report adopted by Section (3)(B). The purpose of this review is to evaluate and revise, if necessary, the rates of the system development charges to assure that they do not exceed the reasonably anticipated costs of the city's capital improvements. In the event the review of the ordinance or the report alters or changes the assumptions, conclusions and findings of the report, or alters or changes the amount of system development charges, the report adopted by reference in Section (3)(B) shall be amended and updated to reflect the assumptions, conclusions and findings of such reviews and Section (3)(B) shall be amended to adopt by reference such updated reports.

#### **Section 4. Receipt and Expenditure of System Development Charges.**

(A) Trust Accounts. The City hereby establishes a separate trust account for each type of system development charge to be designated as the "Stormwater SDC", which shall be maintained separate and apart from all other accounts of the city. All system development charge payments shall be deposited into the appropriate trust account immediately upon receipt.

(Section 4(A) as amended by Ordinance 2249 passed November 22, 1999, effective January 1, 2000.)

(B) Use of System Development Charges. The monies deposited into the trust accounts shall be used solely for the purpose of providing capital improvements necessitated by development, including, but not limited to:

- 1) design and construction plan preparation;
- 2) permitting and fees;
- 3) land and materials acquisition, including any costs of acquisition or condemnation;

- 
- 4) construction of improvements and structures;
  - 5) design and construction of new drainage facilities required by the construction of capital improvements and structures;
  - 6) relocating utilities required by the construction of improvements and structures;
  - 7) landscaping;
  - 8) construction management and inspection;
  - 9) surveying, soils and material testing;
  - 10) acquisition of capital equipment;
  - 11) repayment of monies transferred or borrowed from any budgetary fund of the city which were used to fund any of the capital improvements as herein provided;
  - 12) payment of principal and interest, necessary reserves and costs of issuance under any bonds or other indebtedness issued by the city to fund capital improvements;
  - 13) direct costs of complying with the provisions of ORS 223.297 to 223.314, including the costs of developing system development charges methodologies and providing an annual accounting of system development charges expenditures.
  - 14) consulting costs for the review of alternative rates as provided for in Section (3)(D) of this ordinance.

(C) Prohibited Uses of System Development Charges. Funds on deposit in system development charge trust accounts shall not be used for:

- 1) any expenditure that would be classified as a routine maintenance or repair expense; or
- 2) costs associated with the construction of administrative office facilities that are more than an incidental part of other capital improvements.

(D) Capital Improvements Authorized to be Financed by System Development Charges. Any capital improvement being funded wholly or in part with system development charges revenue shall be included in the city's capital improvement program. The capital improvement program shall:

- 1) list the specific capital improvement projects that may be funded with system development charges revenues;

2) provide the cost of each capital improvement project, and an estimate of the amounts of each revenue source, including system development charges, that will be used to fund each project;

3) provide the estimated timing of each capital improvement project;  
and

4) be updated at least once every five (5) years.

(E) Investment of Trust Account Revenue. Any funds on deposit in system development charges trust accounts which are not immediately necessary for expenditure shall be invested by the city. All income derived from such investments shall be deposited in the system development charges trust accounts and used as provided herein.

(F) Refunds of System Development Charges. System development charges shall be refunded in accordance with the following requirements:

1) An applicant or owner shall be eligible to apply for a full or partial refund if:

a) The building permit or development permit has expired and the development authorized by such permit is not complete;

b) An error was made in calculating the amount of the system development charges resulting in overpayment, and the error is discovered within three months of the date the SDC was paid. The amount of the refund will be limited to the amount collected in excess of the appropriate SDC.

c) The system development charges have not been expended or encumbered prior to the end of the fiscal year immediately following the ninth anniversary of the date upon which such charges were paid. For the purposes of this section, system development charges collected shall be deemed to be expended or encumbered on the basis of the first system development charges in shall be the first system development charges out.

2) The application for refund shall be filed with the City Administrator and contain the following:

a) The name and address of the applicant;

b) The location of the property which was the subject of the system development charges;

c) A notarized sworn statement that the petitioner is the then current owner of the property on behalf of which the system development charges were paid, including proof of ownership, such as a certified copy of the latest recorded deed;

d) The date the system development charges were paid;

e) A copy of the receipt of payment for the system development charges; and, if appropriate,

f) The date the building permit or development permit was issued and the date of expiration.

3) The application shall be filed within ninety (90) days of the expiration of the building permit or development permit or within ninety (90) days of the end of the fiscal year following the ninth anniversary of the date upon which the system development charges were paid. Failure to timely apply for a refund of the system development charges shall waive any right to a refund.

4) Within thirty (30) days from the date of receipt of a petition for refund, the City Administrator will advise the petitioner of the status of the request for refund, and if such request is valid, the system development charges shall be returned to the petitioner.

5) Refunds will not be granted based on a change in use of the property which results in a reduced impact on the city's capital facilities.

6) A building permit or development permit which is subsequently issued for a development on the same property which was the subject of a refund shall pay the systems development charges as required by Section (3).

(G) Annual Accounting Reports. The city shall prepare an annual report accounting for system development charges, including the total amount of system development charges revenue collected in each trust account, and the capital improvement projects that were funded.

(H) Challenge of Expenditures. Any citizen or other interested person may challenge an expenditure of system development charges revenues.

1) Such challenge shall be submitted, in writing, to the City Administrator for review within two years following the subject expenditure, and shall include the following information:

a) The name and address of the citizen or other interested person challenging the expenditure;

b) The amount of the expenditure, the project, payee or purpose, and the approximate date on which it was made; and

c) The reason why the expenditure is being challenged.

2) If the City Administrator determines that the expenditure was not made in accordance with the provisions of this ordinance and other relevant laws, a reimbursement of system development charges trust account revenues from other revenue sources shall be made within one year following the determination that the expenditures were not appropriate.

3) The City Administrator shall make written notification of the results of the expenditure review to the citizen or other interested person who requested the review with ten (10) days of completion of the review.

**Section 5. Severability.** If any clause, section, or provision of this ordinance shall be declared unconstitutional or invalid for any reason or cause, the remaining portion of said ordinance shall be in full force and effect and be valid as if such invalid portion thereof had not been incorporate herein.

**Section 6. Repeal.** Ordinance No. 1842 shall be repealed at 11:59 p.m. on December 31, 1993.

*Passed by the Council September 13, 1993 and approved by the Mayor  
September 16, 1993.*

## ORDINANCE NO. 2250

**AN ORDINANCE ESTABLISHING A METHODOLOGY FOR PARKS AND RECREATION SYSTEM DEVELOPMENT CHARGES; AND SETTING AN EFFECTIVE DATE.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1. Definitions.** The following definitions apply:

(A) "Applicant" shall mean the owner or other person who applies for a building permit or development permit.

(B) "Bancroft Bond" shall mean a bond issued by the city to finance a capital improvement in accordance with ORS 223.205 - 223.295.

(C) "Building" shall mean any structure, either temporary or permanent, built for the support, shelter or enclosure of persons, chattels or property of any kind. This term shall include tents, trailers, mobile homes or any vehicles serving in any way the function of a building. This term shall not include temporary construction sheds or trailers erected to assist in construction and maintained during the term of a building permit.

(D) "Building Permit" shall mean an official document or certificate authorizing the construction or siting of any building. For purposes of this ordinance, the term "Building Permit" shall also include any construction or installation permits which may be required for those structures or buildings, such as a mobile home, that do not require a building permit in order to be occupied.

(E) "Capital Improvements" shall mean public facilities or assets used for Parks and Recreation.

(F) "Citizen or Other Interested Person" shall mean any person who is a legal resident of the City of Woodburn as evidenced by registration as a voter in the city, or by other proof of residency; or a person who owns, occupies, or otherwise has an interest in real property which is located within the city limits or is otherwise subject to the imposition of system development charges, as outlined in Section 3 of this ordinance.

(G) "City" shall mean the City of Woodburn, Oregon.

(H) "Credit" shall mean the amount of money by which the SDC for a specific development may be reduced because of construction of eligible capital facilities as outlined in this ordinance.



(I) "Development" shall mean a building or other land construction, or **making a change in the use** of a structure or land, in a manner which increases the usage of any capital improvements or which will contribute to the need for additional or enlarged capital improvements.

(J) "Development Permit" shall mean an official document or certificate, other than a building permit, authorizing development.

(K) "Dwelling Unit" shall mean a building or a portion of a building designed for residential occupancy, consisting of one or more rooms which are arranged, designed or used as living quarters for one family only.

(L) "Encumbered" shall mean monies committed by contract or purchase order in a manner that obligates the city to expend the encumbered amount upon delivery of goods, the rendering of services, or the conveyance of real property provided by a vendor, supplier, contractor or Owner.

(M) "Improvement Fee" shall mean a fee for costs associated with capital improvements to be constructed after the effective date of this ordinance. Notwithstanding anything in this ordinance to the contrary, it is an incurred charge or cost based upon the use of or the availability for use of the systems and capital improvements required to provide services and facilities necessary to meet the routine obligations of the use and ownership of property, and to provide for the public health and safety upon development.

(N) "Off-site" shall mean not located on or contiguous to property that is the subject of development approval.

(O) "On-site" shall mean located on or contiguous to property that is the subject of developmental approval.

(P) "Owner" shall mean the person holding legal title to the real property upon which development is to occur.

(Q) "Person" shall mean an individual, a corporation, a partnership, an incorporated association, or any other similar entity.

(R) "Prime Rate of Interest" shall mean the base rate on corporate loans posted by at least 75% of the nation's 30 largest banks as posted in the Wall Street Journal.

(S) "Qualified Public Improvement" shall mean a capital improvement that is:

- 1) Required as a condition of development approval;
  - 2) Identified in the adopted capital improvement plan (CIP);and
- either

3) a) Not located on or contiguous to property that is the subject of development approval; or

b) Located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related

(T) "Right-of-Way" shall mean that portion of land that is dedicated for public use.

(U) "System Development Charge" shall mean an improvement fee assessed or collected at the time of increased usage of a capital improvement or issuance of a development permit or building permit. System development charges are separate from and in addition to any applicable tax, assessment, fee in lieu of assessment, or other fee or charge provided by law or imposed as a condition of development.

(V) "Parks and Recreation System Development Charges Executive Summary, Methodology, and Rate Study Update" shall mean the report adopted pursuant to Section (3)(B), as amended and supplemented pursuant to Section (3)(H).

**Section 2. Rules of Construction.** For the purposes of administration and enforcement of this ordinance, unless otherwise stated in this ordinance, the following rules of construction shall apply:

(A) In case of any difference of meaning or implication between the text of this ordinance and any caption, illustration, summary table, or illustrative table, the text shall control.

(B) The word "shall" is always mandatory and not discretionary; the word "may" is permissive.

(C) Words used in the present tense shall include the future; words used in the singular shall include the plural and the plural the singular, unless the context clearly indicates the contrary; and use of the masculine gender shall include the feminine gender.

(D) The phrase "used for" includes "arranged for", "designed for", "maintained for", or "occupied for".

(E) Unless the context clearly indicates the contrary, where a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and", "or" or "either...or", the conjunction shall be interpreted as follows:

1) "And" indicates that all the connected terms, conditions, provisions or events shall apply.

2) "Or" indicates that the connected items, conditions, provisions or events may apply singly or in any combination.

3) "Either"...or" indicates that the connected items, conditions, provisions or events shall apply singly but not in combination.

(F) The word "includes" shall not limit a term to the specific example, but is intended to extend its meaning to all other instances or circumstances of like kind or character.

**Section 3. Imposition of System Development Charges.** System development charges are hereby imposed, subject to the following conditions:

(A) Development Subject to Charges. System development charges are imposed on all new development within the city for capital improvements for transportation. The system development charges shall be paid in addition to all other fees, charges and assessments due for development, and are intended to provide funds only for capital improvements necessitated by new development.

(B) Rates of Charges.

1) The city hereby adopts and incorporates by reference the report entitled "Parks and Recreation Systems Development Charges Executive Summary, Methodology, and Rate Study Update" dated September 30, 1999, particularly the assumptions, conclusions and findings in such study as to the determination of anticipated costs of capital improvements required to accommodate growth and the rates for system development charges to reimburse the city for such capital improvements.

2) System development charges shall be imposed and calculated for the change in use, alternation, expansion or replacement of a building or dwelling unit if such change in use, alternation, expansion or replacement results in an increase in the use of capital improvements compared to the present use of the development. The amount of the system development charges to be paid shall be the difference between the rate for the proposed development and the rate that would be imposed for the development prior to the change in use, alternation, expansion or replacement.

3) The city shall, based upon the report referred to in subsection (1) above, adopt by resolution the amounts of system development charges.

4) An additional systems development charge may be assessed by the city if the demand placed on the city's capital facilities exceeds the amount initially estimated at the time systems development charges are paid. The additional charge shall be for the increased demand or for the demand above the underestimate, and it shall be based upon the fee that is in effect at the time the additional demand impact is determined, and not upon the fee structure that may have been in effect at the time the initial systems development charge was paid. This provision does not apply to single family or other residential units unless additional rental units are created.

5) Notwithstanding any other provision, the SDC rates adopted pursuant to this ordinance may on January 1<sup>st</sup> of each year, after the first year that the ordinance is effective, be adjusted by the City Administrator to account for changes in the costs of acquiring and constructing facilities. The adjustment factor shall be based on the change in average market value of all land in the city, according to the records of the County Tax Assessor, and the change in construction costs according to the engineering News Record (ENR) Northwest (Seattle, Washington) Construction Cost Index; and shall be determined as follows:

$$\begin{array}{rcl} & \text{Change in Average Market Value X 0.50} & \\ + & \text{Change in Construction Cost Index X 0.50} & \\ = & \text{System Development Charge Adjustment Factor} & \end{array}$$

The System Development Charge Adjustment Factor shall be used to adjust the System Development Charge rates, unless they are otherwise adjusted by action of the City Council based on adoption of an updated methodology or capital improvements plan (master plan).

(C) Payment of Charges. Applicants for building permits or development permits shall pay the applicable system development charges prior to the issuance of the permits by the city unless charges are financed pursuant to a City approved installment or deferral program.

(Section 3 (C) as amended by Ordinance 2457 passed June 22, 2009, effective June 24, 2009.)

(D) Alternative Rate Calculation. Applicants may submit alternative rates for system development charges, subject to the following conditions:

1) In the event an applicant believes that the impact on city capital improvements resulting from a development is less than the fee established in Section (3) (B), the applicant may submit alternative system development charge rate calculations, accompanied by the alternative rate review fee established by resolution for this purpose, to the City Administrator. The city may hire a consultant to review the alternative system development charge rate calculations, and may pay the consulting fees from system development charges revenues.

2) The alternative system development charge rate calculations shall be based on data, information and assumptions contained in this ordinance and the adopted system development charges study or an independent source, provided that the independent source is a local study supported by a data base adequate for the conclusions contained in such study performed pursuant to a generally accepted methodology and based upon generally accepted standard sources of information relating to facilities planning, cost analysis and demographics.

3) If the city council determines that the data, information and assumptions utilized by the applicant to calculate the alternative system development charges rates comply with the requirements of this section by using a generally

accepted methodology, the alternative system development charges rates shall be paid in lieu of the rates set forth in Section (3)(B).

4) If the city council determines that the data, information and assumptions utilized by the applicant to calculate the alternative system development charges rates do not comply with the requirements of this section or were not calculated by a generally accepted methodology, then the city council shall provide to the applicant (by certified mail, return receipt requested) written notification of the rejection of the alternative system development charges rates and the reason therefor.

5) Any applicant who has submitted a proposed alternative system development charges rate pursuant to this section and desires the immediate issuance of a building permit or development permit shall pay the applicable system development charges rates pursuant to Section (3)(B). Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any right of review. Any difference between the amount paid and the amount due, as determined by the city council, shall be refunded to the applicant.

E) Exemptions. The following development shall be exempt from payment of the system development charges:

1) Alternations, expansion or replacement of an existing dwelling unit where no additional dwelling units are created.

2) The construction of accessory buildings or structures which will not create additional dwelling units and which do not create additional demands on the city's capital improvements.

3) The issuance of a permit for a mobile home on which applicable system development charges have previously been made as documented by receipts issued by the city for such prior payment.

(F) Credits for Developer Contributions of Qualified Public Improvements. The city shall grant a credit, not to exceed 100% of the applicable Parks and Recreation SDC, against the system development charges imposed pursuant to Section (3)(A) and (B) for the donation of land as permitted by Ordinance 1807, or for the construction of any qualified public improvements. Such land donation and construction shall be subject to the approval of the city.

1) The amount of developer contribution credit to be applied shall be determined according to the following standards of valuation:

a) The value of donated lands shall be based upon a written appraisal of fair market value by a qualified and professional appraiser based upon comparable sales of similar property between unrelated parties in a bargaining transaction; and

b) The cost of anticipated construction of qualified public improvements shall be based upon cost estimates certified by a professional architect or engineer.

2) Prior to issuance of a building permit or development permit, the applicant shall submit to the City Administrator a proposed plan and estimate of cost for contributions of qualified public improvements. The proposed plan and estimate shall include:

a) a designation of the development for which the proposed plan is being submitted.

b) a legal description of any land proposed to be donated pursuant to Chapter 39 of the Woodburn Zoning Ordinance, Ordinance 1807, and a written appraisal prepared in conformity with subsection (1)(a) of this section;

c) a list of the contemplated capital improvements contained within the plan;

d) an estimate of proposed construction costs certified by a professional architect or engineer; and

e) a proposed time schedule for completion of the proposed plan.

3) The City Administrator shall determine if the proposed qualified public improvement is:

a) Required as a condition of development approval;

b) Identified in the adopted capital improvement plan (CIP); and either

c) i) Not located on or contiguous to property that is the subject of development approval; or

ii) Located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related

4) The decision of the City Administrator as to whether to accept the proposed plan of contribution and the value of such contribution shall be in writing and issued within fifteen (15) working days of the review. A copy shall be provided to the applicant.

5) A proposed improvement which does not meet all three (3) of the criteria included in Section 3(F)(3) above shall not be considered a qualified public improvement and the city is not required ORS 223.297 - 223.314 to provide a credit for such an improvement. However, the city shall grant a credit, in an amount not to exceed fifty percent (50%) of the total amount of the applicable Parks and Recreation SDC, for certain other contributions of capital facilities under the following conditions:

a) The capital facilities being contributed must exceed the city standard required for the specific type of development (i.e., residential, industrial, etc.); and

b) Only the value of the contribution which exceeds the city standard required for the specific type of development (i.e., residential, industrial, etc.) shall be considered when calculating the credit; and

6) Any applicant who submits a proposed plan pursuant to this section and desires the immediate issuance of a building permit or development permit, shall pay the applicable system development charges. Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any review rights. Any difference between the amount paid and the amount due, as determined by the City Administrator, shall be refunded to the applicant. In no event shall a refund by city under this subsection exceed the amount originally paid by the applicant.

(G) Appeals and Review Hearings.

1) An applicant who is required to pay system development charges shall have the right to request a hearing to review the denial by the City Administrator of a proposed credit for contribution of qualified public improvements pursuant to Section (3)(F).

2) Such hearing shall be requested by the applicant within fifteen (15) days of the date of first receipt of the denial by the City Administrator. Failure to request a hearing within the time provided shall be deemed a waiver of such right.

3) The request for hearing shall be filed with the City Administrator and shall contain the following:

- a) The name and address of the applicant;
- b) The legal description of the property in question;
- c) If issued, the date the building permit or development permit was issued;
- d) A brief description of the nature of the development being undertaken pursuant to the building permit or development permit;
- e) If paid, the date the system development charges were paid; and
- f) A statement of the reasons why the applicant is requesting the hearing.

4) Upon receipt of such request, the City Administrator shall schedule a hearing before the city council at a regularly scheduled meeting or a special meeting called for the purpose of conducting the hearing and shall provide the

applicant written notice of the time and place of the hearing. Such hearing shall be held within forty-five (45) days of the date the request for hearing was filed.

5) Such hearing shall be before the city council and shall be conducted in a manner designed to obtain all information and evidence relevant to the requested hearing. Formal rules of civil procedures and evidence shall not be applicable; however, the hearing shall be conducted in a fair and impartial manner with each party having an opportunity to be heard and to present information and evidence.

6) Any applicant who requests a hearing pursuant to this section and desires the immediate issuance of a building permit or development permit shall pay prior to or at the time the request for hearing is filed the applicable system development charges pursuant to Section (3)(B). Said payment shall be deemed paid under "protest" and shall not construed as a waiver of any review rights.

7) An applicant may request a hearing under this section without paying the applicable system development charges, but no building permit or development permit shall be issued until such system development charges are paid in the amount initially calculated or the amount approved upon completion of the review provided in this section.

(H) Review of Study and Rates. This ordinance and the Parks and Recreation System Development Charges Executive Summary, Methodology, and Rate Study shall be reviewed at least once every five (5) years. The review shall consider new estimates of population and other socioeconomic data, changes in the cost of construction and land acquisition, and adjustments to the assumptions, conclusions or findings set forth in the report adopted by Section (3)(B). The purpose of this review is to evaluate and revise, if necessary, the rates of the system development charges to assure that they do not exceed the reasonably anticipated costs of the city's capital improvements. In the event the review of the ordinance or the report alters or changes the assumptions, conclusions and findings of the report, or alters or changes the amount of system development charges, the report adopted by reference in Section (3)(B) shall be amended and updated to reflect the assumptions, conclusions and findings of such reviews and Section (3)(B) shall be amended to adopt by reference such updated reports.

#### **Section 4. Receipt and Expenditure of System Development Charges.**

(A) Trust Accounts. The City hereby establishes a separate trust account for each type of system development charge to be designated as the "Parks and Recreation SDC" which shall be maintained separate and apart from all other accounts of the city. All system development charge payments shall be deposited into the appropriate trust account immediately upon receipt.

(B) Use of System Development Charges. The monies deposited into the trust accounts shall be used solely for the purpose of providing capital improvements necessitated by development, including, but not limited to:

- 1) design and construction plan preparation;



- 2) permitting and fees;
- 3) land and materials acquisition, including any costs of acquisition or condemnation;
- 4) construction of improvements and structures;
- 5) design and construction of new drainage facilities required by the construction of capital improvements and structures;
- 6) relocating utilities required by the construction of improvements and structures;
- 7) landscaping;
- 8) construction management and inspection;
- 9) surveying, soils and material testing;
- 10) acquisition of capital equipment;
- 11) repayment of monies transferred or borrowed from any budgetary fund of the city which were used to fund any of the capital improvements as herein provided;
- 12) payment of principal and interest, necessary reserves and costs of issuance under any bonds or other indebtedness issued by the city to fund capital improvements;
- 13) direct costs of complying with the provisions of ORS 223.297 to 223.314, including the costs of developing system development charges methodologies and providing an annual accounting of system development charges expenditures.
- 14) consulting costs for the review of alternative rates as provided for in Section (3)(D) of this ordinance.

(C) Prohibited Uses of System Development Charges. Funds on deposit in system development charge trust accounts shall not be used for:

- 1) any expenditure that would be classified as a routine maintenance or repair expense; or
- 2) costs associated with the construction of administrative office facilities that are more than an incidental part of other capital improvements.

(D) Capital Improvements Authorized to be Financed by System Development Charges. Any capital improvement being funded wholly or in part with

system development charges revenue shall be included in the city's capital improvement program. The capital improvement program shall:

- 1) list the specific capital improvement projects that may be funded with system development charges revenues;
  - 2) provide the cost of each capital improvement project, and an estimate of the amounts of each revenue source, including system development charges, that will be used to fund each project;
  - 3) provide the estimated timing of each capital improvement project;
- and
- 4) be updated at least once every five (5) years.

(E) Investment of Trust Account Revenue. Any funds on deposit in system development charges trust accounts which are not immediately necessary for expenditure shall be invested by the city. All income derived from such investments shall be deposited in the system development charges trust accounts and used as provided herein.

(F) Refunds of System Development Charges. System development charges shall be refunded in accordance with the following requirements:

- 1) An applicant or owner shall be eligible to apply for a full or partial refund if:
  - a) The building permit or development permit has expired and the development authorized by such permit is not complete;
  - b) An error was made in calculating the amount of the system development charges resulting in overpayment, and the error is discovered within three months of the date the SDC was paid. The amount of the refund will be limited to the amount collected in excess of the appropriate SDC.
  - c) The system development charges have not been expended or encumbered prior to the end of the fiscal year immediately following the ninth anniversary of the date upon which such charges were paid. For the purposes of this section, system development charges collected shall be deemed to be expended or encumbered on the basis of the first system development charges in shall be the first system development charges out.
- 2) The application for refund shall be filed with the City Administrator and contain the following:
  - a) The name and address of the applicant;
  - b) The location of the property which was the subject of the system development charges;

c) A notarized sworn statement that the petitioner is the then current owner of the property on behalf of which the system development charges were paid, including proof of ownership, such as a certified copy of the latest recorded deed;

d) The date the system development charges were paid;

e) A copy of the receipt of payment for the system development charges; and, if appropriate,

f) The date the building permit or development permit was issued and the date of expiration.

3) The application shall be filed within ninety (90) days of the expiration of the building permit or development permit or within ninety (90) days of the end of the fiscal year following the ninth anniversary of the date upon which the system development charges were paid. Failure to timely apply for a refund of the system development charges shall waive any right to a refund.

4) Within thirty (30) days from the date of receipt of a petition for refund, the City Administrator will advise the petitioner of the status of the request for refund, and if such request is valid, the system development charges shall be returned to the petitioner.

5) Refunds will not be granted based on a change in use of the property which results in a reduced impact on the city's capital facilities.

6) A building permit or development permit which is subsequently issued for a development on the same property which was the subject of a refund shall pay the systems development charges as required by Section (3).

(G) Annual Accounting Reports. The city shall prepare an annual report accounting for system development charges, including the total amount of system development charges revenue collected in each trust account, and the capital improvement projects that were funded.

(H) Challenge of Expenditures. Any citizen or other interested person may challenge an expenditure of system development charges revenues.

1) Such challenge shall be submitted, in writing, to the City Administrator for review within two years following the subject expenditure, and shall include the following information:

a) The name and address of the citizen or other interested person challenging the expenditure;

b) The amount of the expenditure, the project, payee or purpose, and the approximate date on which it was made; and

---

c) The reason why the expenditure is being challenged.

2) If the City Administrator determines that the expenditure was not made in accordance with the provisions of this ordinance and other relevant laws, a reimbursement of system development charges trust account revenues from other revenue sources shall be made within one year following the determination that the expenditures were not appropriate.

3) The City Administrator shall make written notification of the results of the expenditure review to the citizen or other interested person who requested the review with ten (10) days of completion of the review.

**Section 5. Severability.** If any clause, section, or provision of this ordinance shall be declared unconstitutional or invalid for any reason or cause, the remaining portion of said ordinance shall be in full force and effect and be valid as if such invalid portion thereof had not been incorporate herein.

**Section 6. Effective Date.** This ordinance shall be legally effective on January 1, 2000.

*Passed by the Council and approved by the Mayor November 23, 1999.*

## ORDINANCE NO. 2405

**AN ORDINANCE ESTABLISHING POLICY FOR THE PROVISION OF MUNICIPAL SEWER AND WATER SERVICE TO PROPERTIES LOCATED OUTSIDE CITY BOUNDARIES.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** Municipal water and/or sewer service will not be provided to properties located outside City boundaries except as provided in this Ordinance.

**Section 2.** Property outside City boundaries that is not currently provided water and/or sewer service by the City may obtain a connection to municipal water and/or sewer service only if the property is first annexed into the City.

**Section 3.** Property outside City boundaries that is currently provided water and/or sewer service by the City shall continue to receive such service unless any of the following events occur:

- A. Municipal water and/or sewer use on the property ceases for a continuous period of at least six (6) months; or
- B. A change in use; or
- C. A change in operations resulting in a material increase in the use of water and/or sewer service; or
- D. A change in ownership or title to the property

**Section 4.** Municipal water and/or sewer service will not be discontinued until notice and an opportunity for a hearing have been given to the occupant and to the owner of record of the involved property. The notice shall be personally served or mailed by certified mail and shall state that thirty (30) days after the date of which the notice is given, service to the property will be discontinued. The notice shall also state that, before such date, a hearing may be requested on the matter, in which case service will not be discontinued until after the hearing is held. If a hearing is requested, a hearing date shall be set and all interested parties shall have the opportunity to address the City Council on the discontinuance of municipal water and/or sewer service. The City Council will then decide whether service shall be discontinued.

**Section 5.** Notwithstanding Section 2 above and consistent with state law, the City has the power and authority to provide municipal water and /or sewer service to property outside the corporate City boundaries in instances where an emergency is declared by the City Council and it makes a policy determination in a specific instance that it is in the interests of the City to provide these services. (As amended by Ordinance 2459, July 30, 2009)

***Passed by the Council July 10, 2006 and approved by the Mayor July 12, 2006.***

## ORDINANCE NO. 2416

**AN ORDINANCE PROVIDING A PROCESS FOR THE FORCED CONVERSION OF ELECTRIC AND COMMUNICATION FACILITIES UNDER THE AUTHORITY DELEGATED BY THE STATE OF OREGON**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Definitions.** Whenever in this Ordinance the words or phrases defined in this Ordinance are used, they shall have the respective meanings assigned to them in the following definitions:

- A. "Commission" means the Public Utility Commission of the State of Oregon.
- B. "Underground utility district" or "district" means that area in the City within which poles, overhead wires, and associated overhead structures are prohibited as such area is described in a resolution adopted pursuant to the provisions of this Ordinance.
- C. "Person" means and includes individuals, firms, corporations, and partnerships, and their agents and employees.
- D. "Poles, overhead wires, and associated overhead structures" mean poles, towers, supports, wires, conductors, guys, stubs, platforms, cross arms, braces, transformers, insulators, cutouts, switches, communication circuits, appliances, attachments, and appurtenances located aboveground within a district and used or useful in supplying electric, communication, or similar or associated service.
- E. "Utility" or "utilities" mean all energy utilities and large telecommunications utilities as defined by OAR 860-022-0001.

**Section 2. Public Hearing.** The City Council may from time to time call public hearings to ascertain whether the public necessity, health, safety, or welfare requires the removal of poles, overhead wires, and associated overhead structures within designated areas of the City and the underground installation of wires and facilities for supplying electric, communication, or similar or associated service. The City Administrator shall notify all affected property owners, as shown on the last equalized assessment roll, and the involved utilities, by mail of the date, time, and place of such hearings at least ten days prior to the date thereof. Each such hearing shall be open to the public and may be continued from time to time. At each such hearing all persons interested shall be given an opportunity to be heard.

**Section 3. Designation of Underground Utility Districts by Resolution.** If, after any such public hearing, the City Council finds that the public necessity, health, safety, or welfare requires such removal and such underground installation within a designated area, the City Council may, by resolution, declare such designated area an underground utility district and order such removal and underground installation. Such resolution shall include a description of the area comprising such district and shall fix the date by which such removal and underground installation shall be accomplished and within which affected property owners shall be ready to receive underground service. A reasonable time shall be allowed for such removal and underground installation, having due regard for the availability of labor, materials, and equipment necessary for such removal and for the installation of such underground facilities as may be occasioned thereby. The decision of the City Council as set forth in the resolution shall be final and conclusive.

**Section 4. Unlawful Acts.** Whenever the City Council creates an underground utility district and orders the removal of poles, overhead wires, and associated overhead structures therein as provided in this Ordinance, it shall be unlawful for any person or utility to erect, construct, place, keep, maintain, continue, employ, or operate poles, overhead wires, and associated overhead structures in the district after the date when such overhead facilities are required to be removed by such resolution, except as such overhead facilities may be required to furnish service to an owner or occupant of property prior to the performance by such owner or occupant of the underground work necessary for such owner or occupant to continue to receive utility service as provided in this Ordinance.

**Section 5. Emergency or Unusual Circumstances.** Notwithstanding the provisions of this Ordinance, overhead facilities may be installed and maintained for a period, not to exceed 10 days, without authority of the City Administrator, in order to provide utilities in the event of an emergency or unusual circumstances. The City Administrator may, under such emergency or unusual circumstances, extend or grant special permission, on such terms as the City Administrator may deem appropriate, without discrimination as to any person or utility, to erect, construct, install, maintain, use, or operate poles, overhead wires, and associated overhead structures on a temporary or permanent basis. Any such decisions by the City Administrator shall be subject to appeal to the City Council by filing a written notice of appeal with the office of the City Administrator within 10 days after the City Administrator's decision is mailed.

**Section 6. Exceptions.** The provisions of this Ordinance and any resolution adopted pursuant to the provisions of this Ordinance shall, unless otherwise provided in such resolution, not apply to the following types of facilities:

- A. Any municipal facilities or equipment installed under the supervision and to the satisfaction of the City Administrator;
- B. Poles or fixtures and other appurtenances used exclusively for street lighting;

C. Overhead wires (exclusive of supporting structures) crossing any portion of a district within which overhead wires have been prohibited, or connecting to buildings on the perimeter of a district, where such wires originate in an area from which poles, overhead wires, and associated overhead structures are not prohibited;

D. Poles, overhead wires, and associated overhead structures used for the transmission of electric energy at nominal voltages in excess of 35,000 volts;

E. Overhead wires attached to the exterior surface of a building by means of a bracket or other fixture and extending from one location on the building to another location on the same building or to an adjacent building without crossing any public street;

F. Antennae, associated equipment, and supporting structures used by a utility for furnishing communication services;

G. Equipment appurtenant to underground facilities, such as pad mounted switches, surface-mounted transformers, pedestal-mounted terminal boxes and meter cabinets, and concealed ducts; and

H. Temporary poles, overhead wires, and associated overhead structures used or to be used in conjunction with construction projects.

**Section 7. Notices to Property Owners and Utilities.** Within 10 days after the effective date of a resolution adopted pursuant to this Ordinance, the City Administrator shall notify all affected utilities and all persons owning real property within the district created by such resolution of the adoption thereof. The City Administrator shall further notify such affected property owners of the necessity that, if they or any person occupying such property desire to continue to receive electric, communication, or similar or associated service, they or such occupant shall provide all necessary facility changes on their premises so as to receive such service from the lines of the supplying utility or utilities at a new location, subject to the applicable rules, regulations, and tariffs of the respective utility or utilities on file with the Commission. Notification by the City Administrator shall be made by mailing a copy of the resolution adopted pursuant to this Ordinance to affected property owners as such are shown on the last equalized assessment roll and to the affected utilities.

**Section 8. Responsibility of Utility Companies.** If utility poles, overhead wires, and associated overhead structures must be removed and replaced with underground facilities and equipment in order to continue utility service within a district created by any resolution adopted pursuant to this Ordinance, the supplying utility shall, at its cost, perform such conversion in accordance with its applicable rules, regulations, and tariffs on file with the Commission.



**Section 9.     Responsibility of Property Owners.**

A.     Every person owning, operating, leasing, occupying, or renting a building or structures within a district shall perform construction and provide that portion of the service connection on their property between the facilities referred to in this Ordinance and the termination facility on or within such building or structure being served, all in accordance with the applicable rules, regulations, and tariffs of the respective utility or utilities on file with the Commission.

B.     In the event any person owning, operating, leasing, occupying, or renting such property does not comply with the provisions of this Ordinance within the time provided for in the resolution enacted pursuant to this Ordinance, the City Administrator shall post written notice on the property being served and thirty days thereafter shall have the authority to order the disconnection and removal of any and all overhead service wires and associated facilities supplying utility service to such property. A decision by the City Administrator to order the disconnection and removal of overhead service shall be subject to appeal to the City Council by filing a written notice of appeal with the office of the City Administrator within ten days of the posting of such written notice.

**Section 10.   Responsibility of City.** The City shall remove, at its own expense, all City-owned equipment from all poles required to be removed hereunder in ample time to enable the owner or user of such poles to remove the same within the time specified in the resolution enacted pursuant to this Ordinance.

**Section 11.   Penalties.**

A.     Abatement. Any use or structure established, operated, erected, moved, altered, enlarged, painted, or maintained contrary to this Ordinance is unlawful and a public nuisance, and may be abated.

B.     Civil Proceeding Initiated by City Attorney. The City Attorney, after obtaining authorization from the City Council, may initiate a civil proceeding on behalf of the City to enforce the provisions of this Ordinance. This civil proceeding may include, but is not limited to, injunction, mandamus, abatement, or other appropriate proceedings.

C.     Civil Infraction. In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class 1 Civil Infraction which shall be processed according to the procedures contained in the Woodburn Civil Infraction ordinance.

D.     Separate Infractions. Each violation of this Ordinance constitutes a separate Civil Infraction, and each day that a violation of this Ordinance is committed or permitted to continue shall constitute a separate Civil Infraction.

E.     Remedies – Cumulative. The remedies provided for in this Section are cumulative and not mutually exclusive.

---

**Section 12. Severability.** If any section, subsection, sentence, clause, or phrase of this Ordinance is for any reason held to be invalid, such decision shall not affect the validity of the remaining portions of this Ordinance. The City Council hereby declares that it would have adopted this Ordinance and each section, subsection, sentence, clause, or phrase thereof, irrespective of the fact that anyone or more sections, subsections, sentences, clauses, or phrases be declared invalid.

*Passed by the Council July 10, 2006 and approved by the Mayor March 12, 2007.*

## ORDINANCE NO. 2438

AN ORDINANCE IMPOSING TRANSPORTATION SYSTEM DEVELOPMENT CHARGES BASED UPON AN ESTABLISHED METHODOLOGY; PROVIDING PROCESSES FOR ALTERNATIVE CALCULATIONS; AND REQUIRING THAT FUNDS BE ACCOUNTED FOR AND USED PURSUANT TO STATE LAW; AND REPEALING ORDINANCE 2248

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. General Findings.** The City Council makes the following General Findings regarding Transportation SDCs.

A. Development within the City contributes to the need for capacity increases for roads, multi-modal transportation and related transportation improvements.

B. Development should pay its fair share for the cost of these improvements and additions to transportation facilities necessary to accommodate the capacity needs created by growth.

C. ORS 223.297 et. seq. grants to the City the authority to impose Transportation SDCs to equitably spread the costs of essential capacity increasing Capital Improvements.

D. Transportation SDCs are incurred upon application to develop property for a specific use or at a specific density and are collected by the City when a building permit is issued. The decision regarding uses, densities, and/or intensities causes direct and proportional changes in the amount of the incurred charge.

E. Transportation SDCs are separate from other fees provided by law or imposed as a condition of development.

F. Transportation SDCs are fees for service because they contemplate a development's receipt of transportation services based upon the nature of that development.

G. Transportation SDCs are imposed by this Ordinance not as a tax on property or on a property owner as a direct consequence of ownership of property within the meaning of Article XI, Section 11b of the Oregon Constitution or legislation implementing that section.

**Section 2. Findings for Interchange Development Charge.** The City Council makes the following Findings regarding the IDC:

A. In 2005, the cost of the needed improvements to the Woodburn Interchange was estimated to be \$50 million.

B. Pursuant to Intergovernmental Agreement No. 23,240, which serves as a funding plan for completion of the Woodburn Interchange modernization, the City must provide a total of \$8 million towards completion of this project.

C. The IDC is established under this Ordinance under the authority of ORS 223.297-223.314.

D. The City Council finds that developing properties within the IDC boundary will create a greater impact on the Woodburn Interchange than similarly zoned developing properties located in the City but outside of the IDC boundary.

E. The City Council finds that developing properties within the IDC boundary will receive greater benefit by an improved Woodburn Interchange than similarly zoned developing properties located in the City but outside of the IDC boundary.

F. Based upon their greater developmental impact on the Woodburn Interchange and the greater benefit that they will receive when the Woodburn Interchange is improved, the City Council, consistent with ORS 223.297-223.314, makes the determination that it is fair and equitable to impose the IDC.

G. The IDC is an "improvement fee" as defined in ORS 223.299 since the charge to the developer is for costs associated with Capital Improvements yet to be constructed.

H. An argument was raised before the City Council that the IDC is unlawful because it "represents the effective establishment of a transportation special district without undergoing the adoption methods required by ORS Chapter 267.510 *et seq.*" The City Council finds that this argument is not well founded in law because the City is asserting no jurisdictional authority outside of its corporate boundary.

I. Pursuant to ORS Chapter 267.510 *et seq.*, a transportation district, like other special districts, exercises jurisdictional authority within the area of its boundary. By establishing the IDC boundary, the City Council, consistent with ORS 223.297-223.314, is merely establishing a charge that is collectible within the City. A Transportation SDC must be paid only: (1) if the involved property is annexed to the City, and (2) if the involved property develops. This is legal and within the City's jurisdiction.

J. Another argument was raised before the City Council that the IDC charge is inequitable. As stated above, the City Council finds that this is not the case because developing properties within the IDC boundary will create a greater developmental impact and also will receive a greater benefit by an improved Woodburn Interchange.

K. Finally, an argument was raised before the City Council that the IDC charge violates constitutional principles. The City Council finds that this argument is also not well founded in law. In *Roger's Machinery v. Washington County*, 181 Or.App 369, 45 P.3d 966 (2002), the Court addressed the argument that traffic impact fees imposed under ORS 223.297-223.314 constituted an unconstitutional taking in violation of the Fifth

Amendment. The Court ruled that the traffic impact fees were not physical exactions and were not subject to *Dolan's* heightened scrutiny test, which is used to determine whether a property development condition constitutes an improper taking under the Fifth Amendment. The Court stated that no individualized determination was required before assessing the fee against a particular property in compliance with the Oregon SDC statutes.

**Section 3     Definitions.** The following definitions apply:

A.     APPLICANT. A person seeking to obtain a Building Permit or to develop property within the City.

B.     BUILDING. Any structure, either temporary or permanent, built for the support, shelter or enclosure of persons, chattels or property of any kind. This term shall include tents, trailers, mobile homes or any vehicles serving in any way the function of a building. This term shall not include temporary construction sheds or trailers erected to assist in construction and maintained during the term of a Building Permit.

C.     BUILDING PERMIT. A permit issued by the Building Department for the construction, alteration, repair or placement of any Building under the state building code.

D.     CAPITAL IMPROVEMENT PLAN. A plan prepared by the City pursuant to ORS 223.309.

E.     CAPITAL IMPROVEMENTS. Public facilities or assets used for transportation.

F.     CITY. The City of Woodburn, Oregon.

G.     CREDIT. The amount of money by which the charge for a specific development may be reduced because of construction of eligible capital facilities as outlined in this Ordinance.

H.     DEVELOPMENT. Any man-made change to improved or unimproved real estate which has the effect of generating additional weekday or weekend trips.

I.     DIRECTOR. The Woodburn Public Works Director or designee.

J.     DWELLING UNIT. A Building or a portion of a Building designed for residential occupancy, consisting of one or more rooms which are arranged, designed or used as living quarters for one family only.

K.     IMPROVEMENT FEE. A fee for costs associated with Capital Improvements to be constructed after the date the fee is adopted pursuant to this Ordinance.

L. INTERESTED PERSON. Any person who is a legal resident of the City of Woodburn as evidenced by registration as a voter in the City, or by other proof of residency; or a person who owns, occupies, or otherwise has an interest in real property which is located within the city limits or is otherwise subject to the imposition of charges under this Ordinance.

M. OWNER. The owner or owners of record title or the purchaser or purchasers under a recorded land sale agreement.

N. PERSON. Any natural person, firm, partnership, association or corporation.

O. QUALIFIED PUBLIC IMPROVEMENT. A Capital Improvement that is:

1. Required as a condition of development approval;

2. Identified in the Capital Improvement Plan and is either:

a. Not located on or contiguous to property that is the subject of development approval; or

b. Located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related.

P. REIMBURSEMENT FEE. A fee for costs associated with Capital Improvements already constructed or under construction when the fee is adopted pursuant to this Ordinance for which the City determines that capacity exists.

Q. TRANSPORTATION SYSTEM DEVELOPMENT CHARGE ("Transportation SDC") or SYSTEM DEVELOPMENT CHARGE ("SDC"). An improvement fee and/or a reimbursement fee and/or the IDC assessed or collected at the time of increased usage of a Capital Improvement or issuance of a Building Permit. System Development Charges are separate from and in addition to any applicable tax, assessment, fee in lieu of assessment, or other fee or charge provided by law or imposed as a condition of development.

#### **Section 4. Imposition of Transportation System Development Charges.**

A. Unless otherwise exempted by this Ordinance or state law, a Transportation SDC is hereby imposed on all Development within the City.

B. Unless otherwise exempted by this Ordinance or state law, an Interchange Development Charge is hereby imposed on all Development within the City and located within the Interchange Development Charge boundary. The Interchange Development Charge boundary is depicted on Exhibit B, which is attached to this Ordinance and incorporated.

---

**Section 5.     Methodology.**

A.     The methodology used to calculate Transportation System Development Charges and the Interchange Development Charge is set forth in the "Transportation System Development Charge Study" ("the Methodology") dated March 2008, which is attached as Exhibit "A" to this Ordinance and incorporated.

**Section 6.     System Development Charge Rate Schedule.**

A.     A Rate Schedule for Transportation System Development Charges and the Interchange Development Charge shall be adopted by resolution based on the Methodology attached as Exhibit "A" and incorporated into this Ordinance.

B.     The Rate Schedule may on January 1<sup>st</sup> of each year, after the first year that the resolution adopting it is effective, be adjusted by the Director to account for changes in the costs of acquiring and constructing facilities. The adjustment factor shall be based on the change in construction costs according to the Engineering News Record (ENR) Northwest (Seattle, Washington) Construction Cost Index.

**Section 7.     Collection.**

A.     System Development Charges are due and payable at the time that the City issues the Building Permit unless charges are financed pursuant to a City approved installment or deferral program. (Section 7 (A) as amended by Ordinance 2457 passed June 22, 2009.)

**Section 8.     Exemptions.**

A.     The following development is exempt from System Development Charges:

1.     Remodeling or replacement of any single family structure, including mobile homes.
2.     Multifamily structure remodeling or replacement if no additional Dwelling Units are added.
3.     Remodeling or replacement of office, business and commercial, industrial or institutional structures if such remodeling or replacement does not result in additional peak hour trips.

**Section 9.     Credits for Qualified Public Improvements.**

A.     The City shall grant a credit, not to exceed 100% of the applicable System Development Charges for the construction of any Qualified Public Improvements.

B. Prior to issuance of a Building Permit, the Applicant shall submit to the Director a proposed plan and estimate of cost for contributions of Qualified Public Improvements. The proposed plan and estimate shall include:

1. A designation of the Development for which the proposed plan is being submitted.
2. A list of the contemplated Capital Improvements contained within the plan;
3. An estimate of proposed construction costs certified by a professional architect or engineer; and
4. A proposed time schedule for completion of the proposed plan.

C. The Director shall determine if the proposed Qualified Public Improvement is:

1. Required as a condition of development approval;
2. Identified in the Capital Improvement Plan and is either:
  - a. Not located on or contiguous to property that is the subject of development approval; or
  - b. Located in whole or in part on or contiguous to property that is the subject of development approval and required to be built larger or with greater capacity than is necessary for the particular development project to which the improvement fee is related

D. The decision of the Director as to whether to accept the proposed plan of contribution and the value of such contribution shall be in writing and issued by the Director within 30 days after the Applicant submits the proposed plan.

E. Any Applicant who submits a proposed plan pursuant to this Section and desires the immediate issuance of a Building Permit, shall pay the applicable System Development Charges. Said payment shall be deemed paid under "protest" and shall not be construed as a waiver of any review rights. Any difference between the amount paid and the amount due, as determined by the Director, shall be refunded to the Applicant. In no event shall a refund by City under this subsection exceed the amount originally paid by the Applicant.

**Section 10. Alternative Calculation for SDC Rate, Credit or Exemption.**

A. Pursuant to this Ordinance, an Applicant may request an alternative SDC calculation, alternative SDC credit determination or alternative SDC exemption, but only under the following circumstances:



1. The Applicant believes the number of vehicle trips resulting from the development is, or will be, less than the number of trips established in the Methodology, and for that reason the Applicant's SDC should be lower than that calculated by the City.

2. The Applicant believes the City improperly excluded from consideration a Qualified Public Improvement that would qualify for credit, or the City accepted for credit a Qualified Public Improvement, but undervalued that improvement and therefore undervalued the credit.

3. The Applicant believes the City improperly rejected a request for an exemption for which the Applicant believes it is eligible.

B. Alternative SDC Rate Request:

1. If an Applicant believes the number of trips resulting from the Development is less than the number of trips established in the Methodology, the Applicant must request an alternative SDC rate calculation, under this Section, within 90 days after Building Permit issuance for the Development. The City shall not consider such a request filed after 90 days after Building Permit issuance for the Development. Upon the timely request for an alternative SDC rate calculation, the Director shall review the Applicant's calculations and supporting evidence and make a determination within 30 days of submittal as to whether the Applicant's request satisfies the requirements of this Section.

2. In support of the Alternative SDC rate request, the Applicant must provide complete and detailed documentation, including verifiable trip generation data, analyzed and certified to by a Professional Traffic Engineer. The Applicant's supporting documentation must rely upon generally accepted sampling methods, sources of information, cost analysis, traffic and growth projections and techniques of analysis as a means of supporting the proposed alternative SDC rate. The proposed Alternative SDC Rate calculation shall include an explanation by a registered engineer explaining with particularity why the rate established in the City methodology does not accurately reflect the Development's impact on the City's Capital Improvements

3. The Director shall apply the Alternative SDC Rate if, in the Director's opinion, the following are found:

a. The evidence and assumptions underlying the Alternative SDC Rate are reasonable, correct and credible and were gathered and analyzed by a suitable, competent professional in compliance with generally accepted engineering principles and methodologies and consistent with this Section, and

b. The calculation of the proposed Alternative SDC rate was by a generally accepted methodology, and

c. The proposed alternative SDC rate better or more realistically reflects the actual traffic impact of the Development than the rate set forth in the Methodology.

4. If, in the Director's opinion, all of the above criteria are not met, the Director shall provide to the Applicant by certified mail, return receipt requested, a written decision explaining the basis for rejecting the proposed alternative SDC rate.

C. Alternative SDC Credit Request:

1. If an Applicant has requested an SDC Credit and that request has either been denied by the City or approved but at a lower value than desired, the Applicant may request an Alternative SDC Credit calculation, under this Section. Any request for an Alternative SDC Credit calculation must be filed with the Director in writing within 10 calendar days of the written decision on the initial credit request. The City shall not consider such a request filed after 10 calendar days of the written decision on the initial credit request. Upon the timely request for an Alternative SDC Credit calculation, the Director shall review the Applicant's calculations and supporting evidence and make a determination within 30 days of submittal as to whether the Applicant's request satisfies the requirements of this Section.

2. In support of the Alternative SDC credit request, the Applicant must provide complete and detailed documentation, including appraisals, cost analysis or other estimates of value, analyzed and certified to by an appropriate professional, for the improvements for which the Applicant is seeking credit. The Applicant's supporting documentation must rely upon generally accepted sources of information, cost analysis and techniques of analysis as a means of supporting the proposed Alternative SDC credit.

3. The Director shall grant the Alternative SDC Credit if, in the Director's opinion, the following are found:

a. The improvement(s) for which the SDC Credit is sought are Qualified Public Improvement(s), and

b. The evidence and assumptions underlying the Applicant's Alternative SDC Credit request are reasonable, correct and credible and were gathered and analyzed by an appropriate, competent professional in compliance with generally accepted principles and methodologies, and

c. The proposed alternative SDC Credit is based on realistic, credible valuation or benefit analysis.

4. If, in the Director's opinion, any one or more of the above criteria is not met, the Director shall deny the request and provide to the Applicant by certified mail, return receipt requested, a written decision explaining the basis for rejecting the Alternative SDC Credit proposal.

---

D. Alternative SDC Exemption Request:

1. If an Applicant has requested a full or partial exemption under this Ordinance, and that request has been denied, the Applicant may request an Alternative SDC Exemption under this Section. Any request for an Alternative SDC Exemption calculation must be filed with the Director in writing within 10 calendar days of the written decision on the initial credit request. The City shall not consider such a request filed after 10 calendar days of the written decision on the initial credit request. Upon the timely request for an Alternative SDC Exemption, the Director shall review the Applicant's request and supporting evidence and make a determination within 30 days of submittal as to whether the Applicant's request satisfies the requirements under this Ordinance for exemptions.

2. In support of the Alternative SDC Exemption request, the Applicant must provide complete and detailed documentation demonstrating that the Applicant is entitled to one of the exemptions described in this Ordinance.

3. The Director shall grant the exemption if, in the Director's opinion, the Applicant has demonstrated with credible, relevant evidence that it meets the pertinent criteria.

4. If, in the Director's opinion, any one or more of the above criteria is not met, the Director shall deny the request and provide to the Applicant by certified mail, return receipt requested, a written decision explaining the basis for rejecting the Alternative SDC Exemption proposal.

**Section 11. Review of Methodology and Rates.**

A. This Ordinance and the Methodology shall be reviewed at least once every five (5) years. The purpose of this review is to evaluate and revise, if necessary, the rates of the System Development Charges to assure that they do not exceed the reasonably anticipated costs of the City's Capital Improvements.

**Section 12. Authorized Expenditure of System Development Charges.**

A. Reimbursement fees may be spent only on capital improvements associated with the systems for which the fees are assessed including expenditures relating to repayment of indebtedness.

B. Improvement fees may be spent only on capacity increasing capital improvements, including expenditures relating to repayment of debt for such improvements. An increase in system capacity may be established if a capital improvement increases the level of performance or service provided by existing facilities or provides new facilities. The portion of the improvements funded by improvement fees must be related to the need for increased capacity to provide service for future users.

C. System development charges may not be expended for costs associated with the construction of administrative office facilities that are more than an incidental part of other capital improvements or for the expenses of the operation or maintenance of the facilities constructed with system development charge revenues.

D. Any capital improvement being funded wholly or in part with system development charge revenues must be included in the Capital Improvement Plan.

E. System Development Charge revenues may be expended on the costs of complying with the provisions of ORS 223.297-223.314, including the costs of developing system development charge methodologies and providing an annual accounting of system development charge expenditures.

**Section 13. Deposit of System Development Charge Revenues; Annual Accounting.**

A. System development charge revenues must be deposited in accounts designated for such moneys. The City shall provide an annual accounting, to be completed by January 1 of each year, for system development charges showing the total amount of system development charge revenues collected for each system and the projects that were funded in the previous fiscal year.

B. The annual accounting shall include:

1. A list of the amount spent on each project funded, in whole or in part, with system development charge revenues; and

2. The amount of revenue collected by the local government from system development charges and attributed to the costs of complying with the provisions of ORS 223.297-223.314, as described in ORS 223.307.

**Section 14. Challenge of Expenditures.** In accordance with ORS 223.302, any interested person may challenge an expenditure of SDC revenues.

A. Such challenge shall be submitted, in writing, to the Director for review within two years following the subject expenditure, and shall include the following information:

1. The name and address of the interested person challenging the expenditure;

2. The amount of the expenditure, the project, payee or purpose, and the approximate date on which it was made; and

3. The reason why the expenditure is being challenged.

B. If the Director determines that the expenditure was not made in accordance with the provisions of this Ordinance and other relevant laws, a reimbursement of System Development Charges trust account revenues from other revenue sources shall be made within one year following the determination that the expenditures were not appropriate.

C. The Director shall make written notification of the results of the expenditure review to the interested person who requested the review with ten (10) days of completion of the review.

**Section 15. Institution of Legal Proceedings.** The City Attorney, acting in the name of the City, may maintain an action or proceeding in a court of competent jurisdiction to compel compliance with or restrain by injunction the violation of any provision of this Ordinance as an additional remedy.

**Section 16. Exclusive Review in Marion County Circuit Court.** All determinations made under this Ordinance shall be final and subject only to Writ of Review in the Marion County Circuit Court pursuant to ORS Chapter 34.

**Section 17. Effect on Monies Previously Collected.** The provisions of this Ordinance do not apply to System Development Charges collected prior to its effective date. SDCs previously collected shall be governed by the law in effect at the time of collection.

**Section 18. Severability.** If any clause, section, or provision of this Ordinance shall be declared unconstitutional or invalid for any reason or cause, the remaining portion shall be in full force and effect and be valid as if such invalid portion thereof had not been incorporate herein.

**Section 19. Repeal.** Ordinance 2248 is hereby repealed.

***Passed by the Council April 28, 2008 and approved by the Mayor April 30, 2008.***

---

ORDINANCE NO 1084

---

AN ORDINANCE RELATING TO DISPOSAL OF SEWAGE, WASTE, AND FILTH; THE DRAINING OF ROOF WATER AND CRAWL SPACE; REQUIRING SEWER CONNECTIONS; DECLARING CERTAIN DEPOSITORIES OF WASTE AND FILTH TO BE NUISANCES; PROVIDING FOR ABATEMENT THEREOF AND PROVIDING FOR THE ASSESSMENT AND COLLECTION OF THE COST OF ABATING SUCH NUISANCES; REPEALING ORDINANCES NO. 776, 963, AND 971; AND PRESCRIBING PENALTIES.

**THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:**

**Section 1.** That no privy vault or cesspool will be permitted within the city of Woodburn and the owner, owners, renters, or occupants of property upon which is located a privy vault or cesspool shall cease to deposit or cause to be deposited or permit to be deposited therein sewage, waste, or other drainage matter.

**Section 2.** That the owner or owners of property within the corporate limits of the city of Woodburn, which property is used by human beings for residential, educational, religious, business, industrial, or other purposes and is within 100 feet of a city sewer declared by the common council of the city of Woodburn to be a sanitary sewer adequate for the disposal of raw sewage, will cause the property to be connected to said sewer at the expense of the owner or owners of said property and that all raw sewage, wastes, and drainage matter shall be deposited directly into the city sewer, except as otherwise provided herein.

**Section 3.** That no person shall cause or permit any of the following to flow into, or to be disposed of in, the sanitary sewer system of the city of Woodburn.

- (1) Temporary or permanent drainage of excavations.
- (2) Drainage from roofs, storm sewers, or storm drains.
- (3) Greases, oils, or sludge from service stations, garages, repair shops, machine shops, cleaning establishments, or other industries or establishments.
- (4) Explosives, volatile or inflammable liquids and gases.
- (5) Acids, alkalis, or other corrosive liquids or substances of sufficient strength to damage sewers, manholes, pumping stations, or treatment plant equipment.
- (6) Paints or waste products from paint manufacture.
- (7) Cannery or industrial wastes other than as specified in Subsection (17) of this section.
- (8) Any substance which will form deposits or obstructions in the sewer system, or which, when mixed with sewage, will precipitate materials causing deposits in sewer lines.

- (9) Ashes, cinders, sand, earth, coal, rubbish or metals of any kind.
- (10) Live steam, exhaust steam or water having a temperature above 140°
- (11) Cull fruits or vegetables, or pits or seeds from peaches, apricots, cherries, prunes, pumpkins, squash, or nuts of any kind, unless properly processed through a properly constructed and installed garbage disposal unit.
- (12) Stable or barn manure.
- (13) Effluent from septic tanks or dry wells.
- (14) Offal from slaughter houses.
- (15) Dead animals, or fowl or fish.
- (16) Sulphate or sulphite liquor.
- (17) Effluent waste water from food processing plants, unless it has been passed through a 20-mesh screen prior to entry into the sewer system.

**Section 4.** Grease, oil and sand traps and settling basins shall be provided by property owners in connection with sewer inlets when, in the opinion of the city engineer, they are necessary for the proper handling of liquid wastes containing grease in excessive amounts, flammable wastes, sand or other harmful ingredients, except that such traps and settling basins shall not be required for private living quarters or dwelling units. All such traps and settling basins shall be of a type and capacity approved by the city engineer and shall be so located as to be readily and easily accessible for cleaning and inspection. Grease and oil traps shall be constructed of impervious materials capable of withstanding abrupt and extreme changes in temperature. They shall be of substantial construction, watertight and equipped with easily removable covers which, when bolted in place, shall be gastight and watertight. Where installed, all grease, oil and sand traps and settling basins shall be maintained by the owner, at his expense, in continuously efficient operation. [Section 4 added by Ordinance No. 1347, §1, passed February 26, 1973.]

**Section 5.** That all construction, reconstruction, remodeling and repair commenced after the effective date of this ordinance shall comply with the following:

- (1) All crawl spaces provided in connection with buildings or building types shall be leveled and graded to a drain inlet, from where positive drainage shall be secured at all times. The drain inlet shall be protected by a gravel bed or a catch basin with corrosion-resistant screening 4 mesh per inch, applied over tile end. Drain lines from this area to the storm sewer, gutter, ditch or other permanent adequate outfall shall consist of cast iron, vitrified clay, concrete, cement, asbestos or bituminized fibre, sealed joint type of adequate size but not less than four inches in diameter, laid with a slope of not less than ¼ inch per foot.

(2) All downspouts shall be connected to underground drain lines extended to the storm sewer, street gutter, ditch or other permanent adequate outfall. Drain lines shall be of cast iron, vitrified clay, concrete, cements asbestos or bituminized fibre, sealed joint pipe of adequate size, but not less than three inches in diameter, laid with a slope of not less than ¼ inch per foot.

(3) All pipe shall be laid on a good firm foundation with ends abutting and true to a line and grade. Backfilling in trenches shall be carefully deposited and solidly tamped to avoid settlement.

(4) When sheet metal downspouts are connected to underground drain lines, such drain lines shall extend above the finish grade and the joint between downspout and drain line shall be sealed.

(5) Drain lines from downspouts may be interconnected or connected to the drain line from the crawl space. The point of connection between downspout drain line and crawl space drain line shall be at least 10 feet downstream from the dwelling and at least six inches below the drain inlet in the crawl space. Connection of drain lines shall be made with proper fittings.

(6) The outfall of drain lines on the lot or in easements established for drainage purposes shall terminate in a gravel bed or trench.

(7) In all cases where gutters and downspouts are installed, a sealed drainage line from each downspout to a dry well located at least 10 feet from the building shall be the minimum requirement.

**Section 6. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 1 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 6 as amended by Ordinance 2008, passed October 24, 1988.]

**Section 7.** In addition to the penalty provisions of this ordinance, the procedures of Ordinance No. 1616 may be followed to abate and to secure the cost of the abatement of a public nuisance under this ordinance. [Section 7 as amended by Ordinance No. 1612, §1, passed June 5, 1978.]

**Section 8.** That if any person shall be aggrieved by the notice of the marshal, he may take an appeal to the city council within 24 hours notice from the receipt of such notice, and, upon 24 hours notice, a hearing will be held and a decision rendered forthwith thereon.

**Section 9.** That if any clause, sentence, section or portion of this ordinance shall for any reason be adjudged invalid by a court of competent jurisdiction, such adjudication shall not affect, impair or invalidate any other provisions of this ordinance, but shall be confined in its operation to the controversy directly involved in such adjudication.



**Section 10.** That Ordinances No. 776. 963 and 971 be, and they thereby are, repealed and that Ordinances No. 942 and 956 are not revived by the repealing of Ordinance No. 963.

[Sections No. 4 - 10 renumbered by Ordinance No. 1347, §2, passed February 26, 1973.]

*Passed by the council and approved by the mayor December 3, 1963.*

## ORDINANCE NO. 1678

**AN ORDINANCE PROVIDING FOR SANITARY SEWER CONNECTION FEES IN THE CITY OF WOODBURN, REPEALING ORDINANCE NO. 1354; AND DECLARING AN EMERGENCY.**

The people of the City of Woodburn do ordain:

**Section 1. Sewer Connection Required.** That the owner of any residence, building, structure dwelling or other thing discharging sewage within the City of Woodburn shall initiate connection of such residence, building, structure, dwelling or thing to the sanitary sewer system of the City of Woodburn by written application to the City.

**Section 2. Connection Fees.** That upon submission of such application, each applicant shall pay to the City of Woodburn, in addition to the regular monthly surcharge and actual construction costs of connection, a connection fee (capacity fee) in the amount specified herein as follows:

(a) For single-family dwellings, manufactured dwelling units, the amount specified in Schedule A hereunder.

(b) For apartments and other multiple-family dwellings, the amount specified in Schedule A for first unit and Schedule B for each additional unit in excess of one.

(c) For motel, hotel, and R.V. park units, the amount specified in Schedule A for the first unit and Schedule D. for each additional unit in excess of one. Laundry facilities will be charged at Schedule C for each machine in addition to the above.

(d) All others, except those provided for under Section 3 of this ordinance, the amount specified in Schedule A, plus the amount specified in Schedule C, for each toilet facility in excess of two toilet facilities shall be paid. Each laundry machine shall be considered as one toilet facility and charged as specified in Schedule C.

(e) Schedules:

<u>Schedule A</u>	<u>Schedule B</u>	<u>Schedule C</u>	<u>Schedule D</u>
\$1,000.00	\$ 750.00	\$ 500.00	\$ 410.00

(f) All existing structures constructed prior to May 1977, and remaining on the same site to which City was unable to provide a connection shall be charged at one-half the rate outlined above.

(e) All existing structures constructed prior to May 1977, and remaining on the same site to which City was unable to provide a connection shall be charged at one-half the rate outlined above. [Section 2 as amended by Ordinance 1972, passed April 13, 1987.]

**Section 3. Excessive Demand on Sewer System.** That the provisions of Section 2 herein shall not apply to a particular residence, building, structure or thing when it is determined by the City that such residence, building, structure or thing is of a nature that by its ordinary usage it may place a demand exceeding 1,000 gallons of sewage flow per day, 800 milligrams per litre suspended solids sewage concentration, or 800 milligrams per litre BOD sewage concentration the connection fee shall be determined according to the following formula:

$$C = \$1.46F + \$1.69BOD + \$1.49SS$$

Where:

C	=	connection
F	=	gallons of average sewage flow per day for peak month.
SS	=	suspended solids concentration in milligrams per litre, average value for peak month.
BOD	=	biochemical oxygen demand in milligrams per litre, average value for peak month.

In no case shall the fee charged be less than \$1,000.

When it is determined by the City that a residence, building, structure or thing is of a nature that by its ordinary usage it may place an unusually heavy demand on the municipal sanitary sewer system through the discharge of pollutants other than flow, BOD, or suspended solids, the City shall determine a fee based upon the excessive pollutant or pollutants discharged, and said fee shall be payable as in Section 2 herein.

**Section 4. Disposition of Funds.** That all money collected pursuant to the provisions of this ordinance shall be deposited in and credited to a fund to be used for the purpose of paying the costs of expanding the capacity of municipal sewage collection and treatment system, its maintenance facilities and engineering costs. The first priority for expenditure of these funds will be for retirement of capital improvement bonds' principal and interest.

**Section 5. Repeal.** That Ordinance No. 1354 is hereby repealed and Ordinances 1140 and 1239 are not revived.

**Section 6.** [Emergency clause.]

***Passed by the Council August 13, 1979, and approved by the Mayor August 14, 1979.***

## ORDINANCE NO. 1692

AN ORDINANCE PROVIDING FOR AN INDUSTRIAL COST RECOVERY SYSTEM FOR FEDERAL CONSTRUCTION GRANTS FOR SEWERAGE AND SEWAGE TREATMENT WORKS, RATES AND CHARGES FOR SAME; THE ADMINISTRATION THEREOF; REPEALING ORDINANCE NO. 1690; AND DECLARING AN EMERGENCY.

THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1. Industrial Cost Recovery System Established.** An industrial cost recovery system is hereby established to recover from industrial sewer users those portions of construction grants provided under Public Law 92-500, present or future, which are allocable to such users.

**Section 2. Applicability of Provisions.** Industrial cost recovery provisions shall apply only to any nongovernmental, non-residential user of publicly owned treatment works which discharges more than the equivalent of 25,000 gallons per day of sanitary wastes and which is identified in the "Standard Industrial Classification Manual," 1972, Office of Management and Budget, as amended and supplemented, under one of the following divisions:

- Division A. Agricultural, Forestry and Fishing.
- Division B. Mining.
- Division D. Manufacturing.
- Division E. Transportation, Communications, Electric, Gas and Sanitary Services.
- Division I. Services.

**Section 3. Recovery Period.** The industrial cost recovery period shall be equal to 30 years, or the design useful life of the treatment works, whichever is the lesser.

**Section 4. User's Share of Cost.** An industrial user's share shall include only that portion of grant assistance allocable to its use or to capacity firmly committed for its use.

**Section 5. Letters of Intent.** Any significant industrial users responsible for more than 10 percent of design flow, or of design pollutant loading of the treatment works shall be required to sign letters of intent stating that the user will pay that portion of the grant amount allocable to the treatment of its wastes.

**Section 6. Criteria for Share Determination.** An industrial user's share shall be based on those factors significantly influencing the cost of the treatment works, such as volume or rate of flow, strength or concentration of waste loading, or any other load factor including those unique to such user.

**Section 7. Schedule of Payments.** Each user shall be required to pay his industrial cost recovery payments at regular intervals, not exceeding six months apart, with first payment to be made within six months after the user first begins use of the treatment works, or has been determined to be subject to the industrial cost recovery program.

**Section 8. Collection and Disbursement of Funds.** Allocation of users' shares and the collection and disbursement or distribution of industrial cost recovery funds shall be in accordance with the rules and regulations of the Environmental Protection Agency, or successor, as administrator of the construction grants program.

**Section 9. Measurement and Sampling.** To evaluate and monitor effluent loadings, the city may require the installation by users of measurement and sampling equipment at the user's expense, for which user shall provide reasonable access to the City Engineer, or his designate, during hours of operation for the purpose of inspecting and monitoring such measurement and sampling.

**Section 10. Administration of System.** The City Engineer shall be charged with administration of the industrial cost recovery system, including allocation of recovery charges.

**Section 11. Delinquency Liens.** Any industrial cost recovery charges remaining unpaid for 60 days after the due date shall be entered on the City Lien Docket and shall be recovered as any other city lien, as provided in the City Charter.

**Section 12. Severability.** If any clause, sentence, paragraph, section or portion of this ordinance for any reason shall be adjudged invalid by a court of competent jurisdiction, such judgement shall not affect, impair, or invalidate any of the remainder of this ordinance.

**Section 13. Repeal.** That Ordinance No. 1690 of the City of Woodburn is hereby repealed.

**Section 14.** [Emergency clause.]

***Passed by the Council December 17, 1979, and approved by the Mayor  
December 18, 1979.***

## ORDINANCE NO. 1790

AN ORDINANCE REGULATING THE DISCHARGE OF WASTES TO THE SANITARY AND STORM SEWER SYSTEMS OF THE CITY, LIMITING SUCH DISCHARGES ONLY TO THOSE OF ACCEPTABLE TYPES, CHARACTERISTICS, OR CONCENTRATIONS, ESTABLISHING A SYSTEM OF WASTE DISCHARGE PERMITS, PROVIDING FOR ENFORCEMENT.

## THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1. Declaration of Policy.** It is the policy of the City of Woodburn to provide adequate sewerage facilities for the transportation, treatment and disposal of wastes from within the City and to operate the sewerage systems in a manner which protects public health and the environment. In carrying out this policy, the objectives of this ordinance are:

(a) Preclude pollutants from entering the sewerage systems which will interfere with normal operations or contaminate the resulting sludge or effluent;

(b) Preclude the introduction of pollutants into the sewerage systems which may not be adequately treated and may pass through into the environment;

(c) To enhance the opportunity for recycling and reclamation of wastewater and sludge. It is the intent of the City to provide needed sewerage services to industry while meeting the outlined objectives. This ordinance provides the structure under which the service will be provided for industrial waste so that the systems are protected and can continue to provide efficiently for the waste treatment and disposal [needs] of the City.

**Section 2. Definitions.**

(a) Biochemical Oxygen Demand (BOD). The words "biochemical oxygen demand," or abbreviation thereof as "BOD," shall mean the quantity of oxygen required in the biochemical oxidation of organic matter.

(b) Branch Sewer. The words "branch sewer" shall mean a conduit extending from the plumbing or drainage system of a building or buildings to and connecting with a public or private sanitary or storm sewer, within a street right-of-way.

(c) Categorical Pretreatment Standards. National pretreatment standards specifying quantities or concentrations of pollutants or pollutant properties which may be discharged or introduced into a public sewer system by specific industrial dischargers.

(d) City Engineer. The term "City Engineer" shall mean the City Engineer of the City of Woodburn, Oregon, or his duly authorized deputy or agent.

(e) City or City of Woodburn. The words "City" or "City of Woodburn" shall mean the municipality of Woodburn, Oregon, a municipal corporation of the State of Oregon, acting through its Common Council or any board, committee, body, official or person to whom the Council shall have lawfully delegated the power to act for, or on behalf of, the City. Unless a particular board, committee, body, official or person is specifically designated in these rules and regulations, wherever action by City is explicitly required or implied herein, it shall be understood to mean action by the City Engineer of Woodburn, Oregon or his duly authorized deputy or agent.

(f) Combined Sewer. The words "combined sewer" or "combined sewer system" shall mean a conduit or system of conduits in which both wastewater and stormwater are transported.

(g) Compatible Pollutant. The words "compatible pollutant" shall mean wastes having biochemical oxygen demand, suspended solids and pH within tolerable limits, fecal coliform bacteria, and such additional pollutants which the City treatment works are designed to treat.

(h) Industrial Discharger/User. Any discharger who discharges other than household wastes directly or indirectly into the City sewer system.

(i) Industrial Waste. The words "industrial waste" shall mean any liquid, solid, or gaseous substance, or combination thereof, resulting from any process of industry, manufacturing, commercial food processing, business, agriculture, trade or research, including but not limited to the development, recovering or processing of natural resources and leachate from landfills or other disposal sites, or any other discharge other than domestic sanitary waste.

(j) Industrial Waste Discharge Permit. A permit to discharge industrial wastes into the City sewer system issued under the authority of this ordinance and which prescribes certain discharge requirements and limitations.

(k) Interference. The inhibition or disruption of the City sewer system collection system, treatment processes or operations.

(l) pH. The symbol "pH" shall mean the reciprocal of the logarithm of the hydrogen ion concentration. The concentration is the weight of hydrogen ions in moles per liter of solution. Neutral water, for example, has a pH of 7 and a hydrogen ion concentration of  $10^{-7}$ .

(m) Person. The word "person" shall mean any individual, company, enterprise, partnership, corporation, association, society, or group, and the singular term shall include the plural.

(n) Pretreatment. The reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater to a less harmful state prior to or in lieu of discharging or otherwise introducing such pollutants into the City sewerage systems.

(o) Restaurant. Any establishment or premises, other than a single-family residential unit, equipped or used for the preparation or serving of food, whether operated on a intermittent or sustained basis.

(p) Sewerage System. The entire sewage collection and treatment systems, exclusive of branch sewers. This includes all conduits, pumps, treatment equipment and any other components involved in the transportation, collection, treatment and disposal of sanitary and industrial wastewater and sludge. This includes both sanitary and storm water systems.

(q) Slugload. Any substance released in a discharge at a rate and/or concentration which causes interference to City sewerage or disposal systems.

(r) Suspended Solids. The words "suspended solids" shall mean total suspended matter that is in suspension in water or wastewater and that is removable by laboratory filtering.

(s) Toxic Pollutants. Those substances listed by the City Engineer as toxic pollutants. The list is based upon the priority pollutant list prepared by the U.S. Environmental Protection Agency and any additional information available which indicates toxicity or hazard level of particular substances.

(t) Upset. An exceptional incident in which a discharge unintentionally and temporarily is in a state of non-compliance with the discharge requirements set forth in this ordinance due to factors beyond the reasonable control of the discharger, and excluding non-compliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation thereof.

(u) Wastewater. Industrial waste, or sewage or any other waste including that which may be combined with any ground water, surface water or storm water, that may be discharged to the City sewerage systems.

### **Section 3. General Discharge Prohibitions.**

(a) Use of restricted sewers. It shall be unlawful to discharge, permit the discharge, or allow a connection which will result in the discharge of sanitary sewage or industrial waste into a public sewer under City control which has been designated by the City Engineer to be used solely for storm drainage. It shall be unlawful for any person to discharge or permit the discharge or cause or allow a connection which will result in the discharge of storm drainage or uncontaminated water from refrigeration or cooling processes or steam condensate, into a public sewer under City control designated by the City Engineer to be used solely for sanitary sewage.

(b) Prohibited Discharges. It shall be unlawful to discharge, cause or allow to discharge directly or indirectly into the City sewage systems any of the following:



(1) Waters or wastes containing substances in such concentrations that they inhibit or interfere with the operation or performance of any sewage treatment process, are not amenable to treatment or reduction by the sewage treatment process employed, or are only partially amenable to treatment such that the sewage treatment plant effluent cannot meet the requirements of any other agency having jurisdiction over its discharge to the receiving waters or that prevents the use or disposal of sewage treatment plant sludge in accordance with applicable State and Federal regulations.

(2) Any liquids, solids, or gases, which by reason of their nature or quantity, are, or may be sufficient, either alone or by interaction, to cause fire or explosion or to be injurious in any other way to the operation of the sewer system. Prohibited materials include, but are not limited to, gasoline, benzene, naphtha, alcohols, fuel oil, mineral oil and other flammable or explosive substances.

(3) Any solid or viscous substances capable of obstructing sewage which will or may cause obstruction to the flow of sewage or interference with the operation of the sewerage works or treatment facilities. These substances include, but are not limited to, ashes, cinders, sand, mud, straw, insoluble shavings, metal, glass, rags, feathers, tar, creosote, plastics, wood, animal paunch contents, offal, blood, bones, meat trimmings and wastes, fish or fowl heads, entrails, trimmings and wastes, lard, tallow, baking dough, chemical residues, paint residues, cannery waste bulk solids, hair and fleshings, or plastic or paper dishes, cups, or food or beverage containers, whether whole or ground.

(4) Any noxious or malodorous liquids, gases, solids, or other substances when either singly, or by interaction with other wastes, are capable of creating a public nuisance or hazard to life or health, or preventing entry into any sewer, manhole, or pump station.

(5) Any water or waste containing a toxic or poisonous substance in sufficient quantity, either singly or by interaction with other substances, to injure or interfere with any sewage treatment process; to constitute a hazard to humans or animals; or to create any hazard in, or adversely affect the receiving waters; or result in unacceptable concentrations of these substances being discharged in combined sewer overflows or sewage treatment plant effluents.

(6) Any wastes, waste waters or substances having a pH less than 6.0 or more than 10.0, or having any other corrosive property capable of causing damage or hazard to piping, structures, equipment, or personnel of the sewerage systems. This includes, but is not limited to, battery or plating acids and waste, copper sulfate, chromium salts and compounds, or salt brine. [Section 3(b)(6) amended by Ordinance 2074, passed January 13, 1992.]

(7) Any liquid or vapor having a temperature higher than 150° F or containing heat in amounts which will inhibit biological activity, resulting in septage in sewers, or interference at treatment plants. In no case shall there be heat in such quantities that the temperature of sewage inflow at any lift station exceeds 104° F.

(8) Any material from a cesspool or septic tank, except such material received at a City treatment plant under City permit.

(9) Any water or waste which contains in excess of one hundred milligrams per litre, or a lesser amount as fixed by the City Engineer, for a particular establishment, of fat waste, oil or grease, whether or not emulsified, ether-soluble or n-hexane soluble matter, or any substance which may solidify or become discernibly viscous at temperatures above 32N F.

(10) Any domestic garbage that has not been properly comminuted to 1/8-inch, or less, in any dimension.

(11) Any slugload, which means any pollutant, including oxygen-demanding pollutants (BOD, etc.), released in a single discharge episode of such volume or strength as to cause interference to the sewerage systems.

(12) Any substances with objectionable color not removed in the treatment process, such as, but not limited to, dye wastes and vegetable tanning solutions.

(13) Any wastewater which may cause a hazard to human health, or may create a public nuisance.

(14) Any unusual concentrations of inert suspended solids which may interfere with the operation of the sewerage systems, such as, but not limited to, fuller's earth, lime slurries, or lime residue.

(15) Any unusual concentrations of dissolved solids which may interfere with the operation of the sewerage systems, such as, but not limited to, sodium chloride, calcium chloride, and sodium sulfate.

(16) Any radioactive material, except in compliance with the current "Oregon Regulations for the Control of Radiation" (OAR 333-22-150).

(17) Any food-processing wastes retained on a 20-mesh screen. If material retained on a 20-mesh screen is being discharged, the industrial sewage rate for suspended solids may be estimated on the basis of concentrated dip-samples of such effluent, but this shall not bar correction of the discharge condition under the provisions of Section 11.

(18) Any grease or fat from any restaurant. Such establishments shall install, within 60 days from the date of notice, adequate grease-traps from all sinks and dish washers. Such grease traps shall be of such capacity as to require cleaning not more than twice a week. Each such establishment shall maintain a log, signed by the servicing employee, of all service and cleaning, available to City personnel inspecting.

(19) Any oil, grease, distillate, gasoline, or any other petroleum product which may be discharged to any sanitary or drainage system. Such systems shall be protected by adequate, approved, oil separators, or alternative disposal. All establishments selling motor oil shall provide facilities for draining and disposal of waste oil, or provide sufficient supervision of parking areas that no waste oil be discharged to sanitary or storm sewerage systems. Such establishments shall obtain industrial pollution permits, citing their provisions for preventing pollution. One discharge of waste oil shall be sufficient cause for injunctive relief for cessation of such offerage of motor oil for sale.

#### **Section 4. Discharge Limitations**

(a) It shall be unlawful for a discharger who has an effective Industrial Waste Discharge Permit pursuant to Section [7] to discharge wastes to the sewer system in excess of the limitations established in the permit. The City Engineer shall establish Industrial Waste Discharge Permit limitations to the extent necessary to enable the City to comply with current National Pollutant Discharge Elimination System categorical and general standards and waste discharge requirements as promulgated by the U.S. Environmental Protection Agency and the Oregon State Department of Environmental Quality; to protect the public health and safety; to protect the receiving water quality; to protect the sewerage system; and to comply with all other applicable Federal and State laws.

(b) It shall be unlawful to discharge into the sewerage systems concentrations of the following materials in excess of the specified limits, unless the discharger has in effect an Industrial Waste Discharge Permit from the State of Oregon which establishes a different limitation for a specific pollutant.

<u>Pollutant</u>	<u>Concentration Limit</u>
Arsenic	1.0 mg/l
Cadmium	1.0 mg/l
Chromium (Total)	5.0 mg/l
Copper	2.0 mg/l
Cyanid	1.0 mg/l
Iron	10.0 mg/l
Lead	2.0 mg/l
Nickel	3.0 mg/l
Phenols or Cresols	1.0 mg/l
Zinc	4.0 mg/l

(c) It shall be unlawful for a discharger to increase the use or addition of potable or process water as a partial or complete substitute for adequate treatment to achieve compliance with the standards and limitations set forth in this Chapter or in an Industrial Waste Discharge Permit issued pursuant hereto.

**Section 5.     Pretreatment Facilities.**

(a) If treatment facilities, operation changes or process modifications at an industrial discharger's facility are needed to comply with any requirements under this section, or are necessary to meet any applicable State or Federal requirements, the City Engineer may require that such facilities be constructed or modifications or changes be made within the shortest reasonable time, taking into consideration construction time, impact of the untreated waste on the City sewerage systems, economic impact on the facility, impact of the waste on the marketability of the City treatment plant sludge, and any other appropriate factors.

(b) Any requirement in Section 5 may be incorporated as part of an Industrial Waste Discharge Permit issued under Section 7 and made a condition of issuance of such permit or may be incorporated in a contractual agreement between the City and the affected facility and made a condition of the acceptance of the waste from that facility.

(c) Plans, specifications and other information relating to construction or installation of preliminary treatment facilities or optional disposal required by the City Engineer under this Chapter shall be submitted to the City Engineer and the Oregon Department of Environmental Quality. No construction or installation thereof shall commence until written approval of plans and specifications by the City Engineer and the Oregon Department of Environmental Quality is obtained. No person, by virtue of such approval, shall be relieved of compliance with other laws of the City and of the State relating to construction and to permits. Every facility for the preliminary treatment or handling of industrial wastes shall be constructed in accordance with the approved plans and specifications, and shall be installed and maintained at the expense of the occupant of the property discharging the industrial wastes.

(d) Any person constructing a preliminary treatment facility, as required by the City Engineer, shall also install and maintain at his own expense sampling manhole(s) for checking and investigating the discharge from the preliminary treatment facility to the public sewer. The sampling manhole(s) shall be placed in a location designated by the City Engineer and in accordance with specifications approved by the City Engineer.

**Section 6.     Reporting Requirements.****(a)     Initial Compliance Report.**

(1) Within ninety (90) days after receiving notification that an Industrial Waste Discharge Permit is required, the discharger subject to this Chapter shall submit a report to the City Engineer which indicates the nature and concentration of all prohibited or regulated substances contained in its discharge and the average and maximum daily flow in gallons. The report shall also state whether the applicable pretreatment standards or requirements are being met on a consistent basis and, if not, what additional operations and maintenance and/or pretreatment is necessary to

bring the discharger into compliance with the applicable standards and requirements. This statement shall be signed by an authorized representative of the discharger and certified to by a qualified professional.

(2) Such reports shall be completed in compliance with the current General Pretreatment Regulations for Existing and New Sources of Pollution.

(3) If the information required in Section 6 has already been provided to the City Engineer and that information is still accurate, the discharger shall reference the submitted information and is not required to submit it again.

(b) Periodic Compliance Reports.

(1) Any discharger that is required to have an Industrial Waste Discharge Permit pursuant to Section 7 shall submit to the City Engineer during the months of June and December, unless required on other dates and/or more frequently by the City Engineer, a report indicating the nature of the effluent over the previous six month period. The report shall include, but is not limited to, the concentration (and mass if limited in the permit) of the limited pollutants and a record of all daily flow measurements which exceeded the average daily flow reported in Section 6.

(2) The frequency of the monitoring shall be determined by the City Engineer and specified in the Industrial Waste Discharge Permit. If there is an applicable effective Federal Categorical Pretreatment Standard, the frequency shall be not less than that prescribed in the standard.

(3) Flows shall be reported on the basis of actual measurement, provided, however, where cost or feasibility considerations justify, the City Engineer may accept reports of average and maximum flows estimated by verifiable techniques.

(4) The City Engineer may require reporting by dischargers that are not required to have an Industrial Waste Discharge Permit if information and/or data is needed to establish a sewer rate charge, determine the treatability of the effluent or determine any other factor which is related to the operation and maintenance of the sewerage systems.

(c) Confidential Information. Information and data furnished to the City Engineer with respect to the nature and frequency of discharge shall be available to the public or other governmental agency without restriction unless the discharger specifically requests and is able to demonstrate to the satisfaction of the City Engineer that the release of such information would divulge information, processes or methods of production entitled to protection as trade secrets or proprietary information of the discharger. When requested by a discharger furnishing a report, the portions of a report which may disclose trade secrets or secret processes shall not be made available for inspection by the public but shall, upon written request, be made available to governmental agencies for uses related to this ordinance, National Pollutant Discharge Elimination System, State waste disposal requirements and/or the Pretreatment

Program; provided, however, that such portions of a report shall be available for use by the State or any State agency in judicial review or enforcement proceedings involving the discharger furnishing the report. Wastewater constituents and characteristics will not be recognized as confidential information. Information accepted by the City Engineer as confidential, shall not be transmitted to any governmental agency, nor to the general public, by the City Engineer until and unless a ten-day notification be given to the discharger.

**Section 7. Industrial Waste Discharge Permits.**

(a) Requirement for a Permit.

(1) Except as provided in this section any waste discharger shall have an Industrial Waste Discharge Permit prior to discharging into the City sewer system, if:

(a) The discharge is subject to promulgated National Categorical Pretreatment Standards; or,

(b) The discharge is significant in the opinion of the City Engineer. Significant discharges include, but are not limited to, the following:

(i) Discharges containing compatible pollutants in concentrations or quantities that are subject to extra strength charges; or,

(ii) Discharges containing incompatible pollutants in concentrations or quantities which may interfere with the operation of the sewerage systems or increase the costs of operation; or,

(iii) Discharges which have a maximum instantaneous flow which exceeds ten percent of the capacity of the available lateral or appropriate trunk sewer.

(c) The discharger is required to provide and maintain any form of pre-treatment or any separation process, including grease traps or oil separators.

(2) Existing Discharges.

(a) Discharges that were in existence prior to the date that an Industrial Waste Discharge Permit was required shall be notified in writing by the City Engineer that such a permit is required. Such existing dischargers shall be allowed to continue discharging into the City sewer system without an Industrial Waste Discharge Permit until a permit issued or denied provided that the discharger files a completed application for an Industrial Waste Discharge Permit within 90 days of the receipt of such notice.

(b) Discharges allowed under Section 7 shall meet all other applicable requirements of this code.

(b) Application for an Industrial Waste Discharge Permit.

(1) Application for an Industrial Waste Discharge Permit shall be made to the City Engineer on forms provided by the Department of Public Works. The application shall not be considered as complete until all information identified on the form is provided, unless specific exemptions are granted by the City Engineer.

(2) Completed applications shall be made within 90 days of the date requested by the City Engineer or, for new discharges, at least 90 days prior to the date the discharge is to begin.

(c) Issuance of Industrial Waste Discharge Permits.

(1) Industrial Waste Discharge Permits shall be issued or denied by the City Engineer within 90 days after a completed application is filed.

(2) Industrial Waste Discharge Permits shall contain conditions which meet the requirements of this code as well as those of applicable State and Federal laws and regulations.

(3) If pretreatment facilities are needed to meet the discharge criteria of the discharge permit, the permit shall require the installation of such facilities.

(4) Whenever a discharge permit requires installation or modification of monitoring or metering equipment, or of treatment facilities, or of process changes necessary to meet discharge standards, or for spill control requirements, a compliance schedule shall be included which establishes the dates for completion of the changes and all appropriate interim dates. Interim dates shall be no more than 90 days apart.

(5) Discharge permits shall expire no later than 5 years after the effective date of the permit.

(6) The City Engineer may deny the issuance of any discharge permit if the discharge may result in violation of any City, State, or Federal law or regulation, may overload or cause damage to any portion of the City sewerage systems, or may create any imminent, latent, or potential hazard to personnel, the public, or the environment.

(d) Modification of Permits.

(1) An Industrial Waste Discharge Permit may be modified for good and valid cause at the written request of the permittee and at the discretion of the City Engineer.

(2) Permittee modification requests shall be submitted to the City Engineer and shall contain a detailed description of all proposed changes in the discharge. The City Engineer may require any additional information needed to adequately evaluate the modification or assess its impact.

(3) The City Engineer may deny a request for modification if the change may result in a violation of City, State or Federal laws or regulations, may overload or cause damage to any portion of the City sewerage systems, or may create any imminent or potential hazard to health, or the environment.

(4) If a permit modification be made at the direction of the City Engineer, the permittee shall be notified in writing of the proposed modification at least 30 days prior to its effective date and shall be informed of the reasons of the change.

(e) Change in a Permitted Discharge. Any modification to the permittee's discharge permit must be issued by the City Engineer before any significant change is made in the volume or level of pollutants in an existing permitted discharge to the City sewerage system. Changes in the discharge involving the introduction of a waste stream not previously included in the Industrial Waste Discharge Permit or involving the addition of new pollutants shall be considered as a new discharge, requiring application under Section 7.

(f) Permit Fees. Permit fees and renewal fees, shall be as established by the Common Council, by motion, upon recommendation of the City Engineer. All monies received for Waste Discharge Permit Fees shall be expended only for the administration, monitoring or enforcement of the provisions of this ordinance.

## **Section 8. Inspection and Sampling.**

### **(a) Inspection.**

(1) Authorized City representatives may inspect the monitoring facilities of any industrial waste discharger to determine compliance with the requirements of this ordinance. The discharger shall allow the City or its authorized representatives to enter upon the premises of the discharger at all reasonable hours, for the purpose of inspection, sampling, or records examination. The City shall also have the right to set up on the discharger's property any such devices as are necessary to conduct sampling, inspection, compliance monitoring and/or metering operations. The right-of-entry shall include access to all portions of the premises that contain facilities for sampling, measuring, treating, transporting or otherwise handling wastes, and for storing records, reports or documents relating to the treatment, sampling, or discharge of the wastes. The City Engineer, or his authorized deputy, shall have the power to make such inspections, without warrant, during any time of operation of the facility.

### **(2) Conditions of Entry.**

(a) The authorized City representative shall present appropriate credentials at the time of entry;



(b) The purpose of the entry shall be for inspection, observation, measurement, sampling or testing in accordance with the provisions of this ordinance;

(c) The entry shall be made at reasonable times during any operating or business hours unless an emergency situation exists as determined by the City Engineer.

(d) All valid safety, security and sanitary requirements of the facility to be inspected shall be complied with by the City representative(s) entering the premises.

(b) Sampling.

(1) Samples of wastewater being discharged into the sewerage systems shall be representative of the discharge and shall be taken after treatment, if any, and before dilution by other water. The sampling method shall be one approved by the City Engineer and done in accordance with good engineering practice.

(2) Samples that are taken by City personnel for the purpose of determining compliance with the requirements of this ordinance may be split with the discharger (or a duplicate sample provided in the instance of fats, oils and greases), if requested before or at the time of sampling.

(3) All sample analyses shall be performed in accordance with the procedures set forth in 40 CFR, Part 136 and any amendments thereto or with any other test procedures approved by the Administrator of the Environmental Protection Agency. If there are no approved test procedures for a particular pollutant, then analyses shall be performed using other validated procedures approved by the City Engineer.

(c) Sampling Manhole. The City Engineer may require a discharger to install and maintain, at the discharger's expense, suitable manhole(s) in the discharger's branch sewer(s) to allow observation, sampling and measurement of all industrial wastes being discharged into the City sewer system. They shall be constructed in accordance with plans approved by the City Engineer and shall be designed so that flow measuring and sampling equipment may be conveniently used or installed. Access to the manhole shall be available to City representatives at all times. It shall be located in a street right-of-way or on an easement with ready access from a street, not behind any fence or gate, except for which the City shall be provided a key or keys.

**Section 9. Spill Prevention and Control.**

(a) Notification. Any person becoming aware of spills or uncontrolled discharges of prohibited or restricted substances, directly or indirectly, into the City sewerage systems, shall immediately report such discharge by telephone to the City Engineer.

(b) Posted Notice. A notice informing employees of the notification requirement and containing a telephone number for the individual to contact in the event of such a discharge shall be posted in a conspicuous place, visible to all employees that may reasonably be expected to observe such a discharge.

(c) Preventive Measures. Direct or indirect connections or entry points which could allow spills or uncontrolled discharges of prohibited or restricted substances to enter the City sewer system shall be eliminated, labeled, or controlled, so as to prevent the entry of wastes in violation of this ordinance. The City Engineer may require the industrial user to install or modify equipment or make other changes necessary to prevent such discharges as a condition of issuance of an Industrial Waste Discharge Permit or as a condition of continued discharge into the City sewer system. A schedule of compliance shall be established by the City Engineer which requires completion of the required actions within the shortest reasonable period of time. Violation of the schedule without an extension of time by the City Engineer shall be a violation of this ordinance.

(d) Spill Prevention and Control Plans.

(1) Industrial users that handle, store or use prohibited or restricted substances on their sites shall prepare a spill prevention plan within 90 days of notice by the City Engineer directed at preventing the entrance of those substances, directly or indirectly, into the City sewerage systems. The plan, as approved by the City Engineer, shall be posted and available for inspection at the facility during normal business hours and shall include, but not be limited to, the following elements:

(i) A description of the potential points of entry into the City sewerage systems;

(ii) A description of the measures to be taken to prevent entry at the described points before a spill occurs;

(iii) Measures to be taken to contain a spill of prohibited or restricted materials;

(iv) A description of employee training in the prevention and control of spills. A valid SPCC plan required under the Federal Clean Water Act may be acceptable in lieu of developing a new spill control plan, provided the plan adequately addresses the elements required.

(2) If any user has a spill or uncontrolled discharge of prohibited or restricted substances into the City sewer, the City Engineer may require the user's spill prevention and control plan to be resubmitted, may require revisions to be made in the plan, and may require any such user, even residential, to fully comply with the requirements of this ordinance.

**Section 10. Acceptance of Extra-Strength Industrial Waste.** The City Engineer may agree to accept industrial wastewater which exceeds the limitations set forth in Section 4, provided that:

(a) Limitations established in compliance with promulgated Federal Pretreatment Standards under the Clean Water Act or under Section 3 of this ordinance are not exceeded; and,

(b) Adequate treatment capacity exists at the waste treatment plant for effectively treating the additional waste strength; and,

(c) The commercial or industrial discharger requests the City Engineer to accept the industrial wastes on the basis of payment to the City of extra-strength charges as determined by him; and,

(d) The wastewater is being discharged to a sanitary or combined sewer; and,

(e) The discharger shall affirm responsibility for all other provisions of this ordinance; and,

(f) All other sewage rates shall be in accordance with the Woodburn sewer rate ordinance; and,

(g) All additional charges for extra-strength discharges shall be as determined by the City Engineer.

**Section 11. Enforcement.**

(a) Violations.

(1) A violation shall have occurred when any requirement of this ordinance has not been met; when a written demand of the City Engineer, made under the authority of this ordinance, is not met within the specified time; when a condition of a permit, or contract, issued under the authority of this ordinance is not met within the specified time; when effluent limitations are exceeded, regardless of intent or accident; or when false information has been provided by the discharger.

(2) Each day a violation occurs shall be considered as a separate violation.

(b) Notice of Violation. Upon determination by the City Engineer that a violation has occurred, or is occurring, the City Engineer may issue a written Notice of Violation to the discharger which shall outline the violation and the potential liability. The Notice may further request correction of the violation within a specified time and/or require written confirmation of the correction or of efforts being made to correct the violation, by a specified date. The Notice shall be personally delivered to the discharger's premises or be sent certified or registered mail, return receipt requested.

(c) Judicial Action. The City Engineer may initiate appropriate civil or criminal action through the City Attorney in a Court of competent jurisdiction to enjoin a violation and obtain corrective measures and any other appropriate relief.

(d) Termination or Suspension of a Discharge.

(1) The City Engineer may terminate a discharge into the City sewer system or suspend such discharge for a specified length of time or terminate water and sewer services to the premises, if:

(i) The discharge presents or may present an imminent and substantial endangerment to the health or welfare of persons or the environment, or causes interference with the operation of the City sewer system; or,

(ii) The permit to discharge into the City sewer system was obtained by misrepresentation of any material fact or by lack of full disclosure; or,

(iii) Directed by a Court of competent jurisdiction.

(2) Notice of termination or suspension shall be provided to the discharger prior to terminating or suspending the discharge.

(i) In situations that are not emergencies, the notice shall be in writing, shall contain the reasons for the termination or suspension, the effective date, and the name, address and telephone number of a City contact, shall be signed by the City Engineer, and shall be received at the business address of the discharger no less than thirty days prior to the date specified for termination or suspension.

(ii) In situations that are determined to be emergencies by the City Engineer, the initial notice may be verbal or written and shall contain the information required above. If verbal notice is given, it shall be delivered to the owner or operator of the discharging facility and shall be followed within 2 working days by a written notice that is mailed or delivered to the business address of the discharger. The effective date of the termination or suspension in emergency situations may be immediately after verbal or written notice has been given as required in this paragraph.

(iii) For the purposes of this section, an emergency situation is defined as a situation in which action must be taken as rapidly as possible in order to prevent or reduce a present or potential danger or hazard to health, safety, sewerage systems, treatment processes, or receiving streams.

(e) Cost Recovery.

(1) The City Engineer may recover all reasonable costs of repairing damages to the City sewerage systems, extra treatment required, restoration of inhibited or disrupted treatment processes, and of paying fines or penalties which result from a discharge not in compliance with the requirements of EPA or DEQ, the Waste Discharge Permit, or of this ordinance.

(2) Claim for the costs shall be by letter to the discharger; sent certified or registered mail, return receipt requested, which shall state the specific violation(s), the damages and penalties sustained by the City, the costs of those damages and penalties, and all other costs the City Engineer has determined as attributable to the discharge and, therefore, billed to the discharger.

(3) The costs are due and payable by the discharger upon receipt of the letter. If not paid within 30 calendar days, water and sewer services to the premises may be physically disconnected and the amount due and the cost of disconnection shall be assessed against the property on the docket of City liens.

(f) Operating Upsets. Any discharger who experiences an upset in operations which places the discharger in a temporary state of non-compliance with this ordinance or an Industrial Wastewater Discharge Permit issued pursuant to Section 7 shall inform the City Engineer of the upset within 2 hours of the first awareness of it. Where such information is given orally, a written follow-up report shall be filed by the discharger with the City Engineer within five days. The report shall specify:

(1) Description of the upset, the cause thereof and the upset's impact on the discharger's compliance status.

(2) Duration of non-compliance, including exact dates and times of non-compliance, and if the noncompliance continues, the time by which compliance is reasonably expected to occur.

(3) All steps taken or to be taken to reduce, eliminate or prevent recurrence of such an upset or other conditions of non-compliance.

**Section 12. Records Retention.** All dischargers subject to this ordinance shall retain and preserve for no less than three years, all records, books, documents, memoranda, reports, correspondence, and any and all summaries thereof, relating to monitoring, sampling and chemical analyses made by or in behalf of a discharger in connection with its discharge. All records which pertain to matters which are the subject of any enforcement or litigation activities brought by the City Engineer pursuant hereto shall be retained and preserved by the discharger until all enforcement activities have concluded and all periods of limitation with respect to any and all appeals have expired.

**Section 13. Conflict.** All other ordinances and parts of other ordinances inconsistent or conflicting with any part of this ordinance are hereby repealed to the extent of such inconsistency or conflict.

**Section 14. Severability.** If any provision, paragraph, word, section or chapter of this ordinance is invalidated by any Court of competent jurisdiction, the remaining provisions, paragraphs, words, sections, and chapters shall not be affected and shall continue in full force and effect.

**Section 15. Penalties.**

(1) Violation of any provision of this ordinance constitutes a class 1 infraction and shall be dealt with according to the procedures established by Ordinance No. 1610.

(2) Each day a violation of this ordinance continues shall be considered a separate violation. [Section 15 as amended by Ordinance 2008, passed October 24, 1988.]

***Passed by the Council September 13, 1982, and approved by the Mayor  
September 14, 1982.***

---

ORDINANCE NO. 2058

**AN ORDINANCE ALLOWING A SEWER CAPACITY FEE PAYMENT PLAN FOR CERTAIN PROPERTIES UTILIZING SUBSURFACE SEWAGE DISPOSAL SYSTEMS AND DECLARING AN EMERGENCY.**

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.**     Definitions. The following definitions apply:

- (A)     "City Engineer" shall mean the City Engineer of the City of Woodburn.
- (B)     "Finance Director" shall mean the Finance Director of the City of Woodburn.
- (C)     "Local Government Investment Pool" shall have the meaning given that term in ORS 294.805 to 294.895.
- (D)     "Owner" shall mean any person, firm, corporation, or other entity having legal title to real property subject to the applicable sewer capacity fee and possessing legal authority to authorize the docketing of a lien against said property.
- (E)     "Sewer Capacity Fee" shall mean a non-refundable fee charged by the city to allow an owner to use a portion of the city's sewerage capacity, also known as a sanitary sewer connection fee or systems development charge.
- (F)     "Subsurface Sewage Disposal System" shall have the meaning given that term in ORS 454.605.

**Section 2.**     General Provisions

- (A)     The owner of real property utilizing a subsurface sewage disposal system incorporating twenty (20) or more dwelling units has the option of paying sewer capacity fees utilizing a four-year payment plan.
- (B)     The first installment of said fees described above is due and payable at the time of connection, with the remaining installments payable on the basis determined by the City according to the payment plan.
- (C)     This installment payment plan of sewer capacity fees is exercised at the option of the owner. Written application for such option must be filed by the owner, and approved by the city prior to connection.
- (D)     The owner is responsible to insure that all scheduled payments are made when due. The owner is not relieved of this obligation even though the city may allow the due date to pass without receiving payment. The city may declare the remaining balance due and payable in full when the owner fails to make scheduled payments on

time. At the city's option, failure to make scheduled payments may result in disconnection.

(E) If the installment payment option is utilized, the balance owed to the city, including interest thereon, may be paid in advance by the owner at any time without penalty.

**Section 3. Administration.** The City Engineer shall be responsible for implementation of this ordinance by allowing the connections to the city sewerage system and by making other technical and payment plan decisions. The Finance Director shall be responsible to program the servicing plan so that bills are sent to owners. The City Engineer shall provide documents needed by the Finance Director for serving of the payment plan.

**Section 4. Interest Rate.** Interest shall be fixed at the date of inception of the plan at the rate quoted by the local government investment pool (per annum) plus 1½% rounded to the nearest one-tenth of one percent.

**Section 5. Severability.** If any section, clause, or phrase of this ordinance is determined by any court of competent jurisdiction to be invalid or unenforceable for any reason, such determination shall not affect the validity of the remainder of this ordinance which shall continue to be in full force and effect.

**Section 6.** [Emergency clause.]

***Passed by the Council April 8, 1991, approved by the Mayor April 9, 1991.***



## ORDINANCE NO. 2157

AN ORDINANCE APPROVING PLACEMENT OF CHARGES ON WASTEWATER DISCHARGE UTILIZING WATER USE MONITORING OR OTHER ESTIMATING METHODS FOR THE OPERATION AND MAINTENANCE OF MUNICIPAL SEWERAGE SYSTEMS, PROVIDING FOR SUCH CHARGES AND THE COLLECTION THEREOF, REPEALING ORDINANCE NO. 2059, AND SETTING AN EFFECTIVE DATE.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. General Provisions.** That a charge, as provided in this ordinance, will be added to each municipal water bill or statement issued by the City of Woodburn. Such charges will apply to all monthly periods of water use and service received from the City, and such charges will be collected from water users in the same manner and under the same provisions of law as other charges for water use and services. Such charges will be levied against each water account, excepting those accounts providing only fire or irrigation service, and other services which do not utilize the city sewerage system for their wastewater treatment and disposal.

A like charge may be made to all premises within the city limits which are supplied with water from sources other than the city water system. A separate charge will be collected from all premises outside the City which discharge to the city sewerage system. The premises connected to a water system other than the city system may be required to provide metering devices for the waste discharge calculations. An additional charge will be collected for "recreational vehicle waste water discharge" stations. All city municipal service buildings will continue to be exempted from the charges outlined in this ordinance unless modified by council action. Interpretation and administration of this ordinance and its provisions will be the responsibility of the City Engineer.

This ordinance also deals with permitted industrial/commercial loading-related service charges. However, the city-issued waste discharge permits that reflect EPA and DEQ requirements and other capacity connection fee requirements related to loadings, are not covered by this ordinance.

(Section 1 as amended by Ordinance 2286 passed May 14, 2001)

**Section 2. Abbreviations & Definitions:**

BOD	=	Biochemical oxygen demand
SBOD	=	Soluble BOD
cu. ft.	=	cubic feet
gal.	=	gallon(s)
TSS	=	Total suspended solids
POTW	=	Public Owned Treatment Works
EPA	=	Environmental Protection Agency
DEQ	=	Department of Environmental Quality

- Single Family Unit: A stick built or manufactured house, designed for permanent occupation by a single family which includes kitchen and bathroom facilities, on its own lot, with or without accessory structures.
- Multi family Unit: 1) Any dwelling unit designed for separate, permanent occupation by more than one family and which each separate unit includes kitchen and bathroom facilities.
- 2) Any recreation room with bathroom, sink, and cooking facilities.

**Section 3. Treatment Capability and Acceptance of Sewage:** The City, at its discretion, may refuse to accept sewage loadings from industrial/commercial users or septage haulers, if such loading is beyond permitted loading or if such loading, in the opinion of the City, reasonably places the treatment process at risk or may cause violation of the City's permit.

**Section 4. Industrial User Billing:** Industrial users may be required to install metering and sampling devices to monitor flow, BOD, suspended solids and any other necessary constituents. The industry may be required to combine all effluent lines to a single point for such metering/sampling and to monitor their effluent discharge. The City may bill on an estimated basis if the user fails to perform the required monitoring and sampling. Any or all of the following criteria may be used to determine if an industry is to be billed as an industrial user:

- A. The user is permitted to discharge more than 0.8 percent (0.8%) of the designed average dry weather hydraulic, organic or solid handling load to the City's POTW.
- B. The user has a non-domestic flow of 25,000 gallons or more per average work day.
- C. The user is determined by the POTW Superintendent to have a significant impact upon POTW operations.
- D. The user comes under the national categorical pretreatment standards promulgated by the EPA.
- E. The City has issued the user an industrial discharge permit.

**Section 5. Monthly Sewerage Charge:** The monthly sewerage charges required by Section 1 of this ordinance will be according to the following schedule:

- A. All sewer charges for residential, commercial and industrial customers will be based on a minimum plus volume of sewage discharged method. In addition, industrial customers will also be charged for BOD and TSS.

B. Residential minimum plus volume method will be the average consumption of water for the four (4) winter months (November/December through February/March) and it will be considered as the amount of sewage discharged from each dwelling unit. The winter month average will be determined by the water meter readings taken or other needed estimating methods by Public Works for unusual cases. General estimating and billing methods are outlined below:

1. In the first year of the minimum plus volume method implementation, the November/December through February/March bills will be based on the actual consumption for each month. Starting in March/April, each of the following twelve (12) months will be billed based on the average of the three (3) low months out of the four (4) recent winter months (November/December through February/March). Every year a new average will be calculated using the immediately preceding winter month's consumption. (Section 5(B)(1) amended by Ordinance 2164 passed March 25, 1996.)

2. For residential units where a full four (4) months of consumption readings are not available for averaging, such as vacations or vacancies due to change in ownership, a minimum of three (3) full months of readings may be used for averaging or two full months of readings supplemented by partial month daily water consumption outlined under Section 5(B)(9). (Section 5(B)(2) amended by Ordinance 2164 passed March 25, 1996.)

3. Residential structures that are served by the city sewerage system, but not connected to city water, will be billed at the city wide residential average consumption rate of 700 cu. ft. per unit

4. If the winter average exceeds three other consecutive months average, then at the request of the property owner, the city may replace the winter average with the average of three other consecutive months for the remaining future annual billing cycle. No credit shall be given for the prior billings and there shall be no extra charge for the adjustment. Also, Public Works shall make adjustments to wastewater charges for properties disrupted by natural disaster that affects the flow of wastewater to the city system. (Section 5(B)(4) amended by Ordinance 2164 passed March 25, 1996.)

a. Replacement of residential winter average with average of other three consecutive months and adjustment of charges:

i. If the winter average exceeds three other consecutive months average, then at the request of the property owner, the city may replace the winter average with the average of three other consecutive months for the remaining future annual billing cycle.

ii. The wastewater charges to an account when three-month average is implemented to replace winter average shall be adjusted as outlined below:

Amount of credit shall be limited to the summation of actual revenue received in three months under consideration less summation of calculated revenue in the same three-month period that is used to develop lower billing average. (Section 5(B)(4)(a) added by Ordinance 2171 passed June 10, 1996.)

b. Adjustment to wastewater charges for properties disrupted by a natural disaster affecting wastewater flow:

i. Public Works will evaluate the disruption to wastewater flow because of a natural disaster and make adjustment accordingly. During the period while a structure is being rehabilitated and there is no wastewater flow, there shall be no wastewater charge based on the winter average, otherwise an estimate that reflects the use of least flow will be used. (Section 5(B)(4)(b) added by Ordinance 2171 passed June 10, 1996.)

5. If there is no occupancy of buildings during the winter months, then the aver of the two (2) prior months, i.e., September and October, or 700 cu. ft., whichever is less, may be used for billing purposes, until and unless a representative average of the winter months is developed or estimated.

6. For new structures or new customers, the city-wide residential average of 700 cubic feet per unit per month may be used until an actual average can be calculated using three (3) full months following occupancy. If the calculated average is below 700 cu. ft., then the calculated average will be used for billing, and a credit shall be given deducting the summation of the three-month average from the actual revenue received during that period. If the calculated average is above 700 cu. ft., then the city-wide residential average of 700 cul ft. will be used for billing purposes until the next winter average is calculated. For new structures, the sewer charges begin when the certificate of occupancy is issued, or three (3) months after the installation of the water meter unless the owner notifies the city that the building is not occupied. (Section 5(B)(6) amended by Ordinance 2171 passed June 10, 1996.)

7. All sewer structures located within 300 feet of an adequate city sewer main, and experiencing septic system failure, must connect to the city sewer system. No new subsurface wastewater treatment and disposal (septic tank system) shall be allowed within the city limits. (Section 5(B)7 as amended by Ordinance 2286 passed May 14, 2001.)

8. There will be no additional charge for consumption analysis and adjustments other than that for leak adjustments as outlined in Section 9.

9. When a dwelling unit has been occupied for not less than 10 days and/or the water consumption for the month is below 100 cu. ft., then partial month daily water consumption method may be used to project consumption for that month under consideration for averaging purposes.

C. Commercial bills will be based on the actual water use for that month. Commercial structures that are connected to city water and are located within 100 feet of an adequate sewer line but not connected to the sewer, will be charged the minimum usage of 600 cu. ft. per unit.

D. Industrial bills will be based on the actual consumption for that month plus the loading charges (BOD and TSS).

E.	<u>RATES:</u> <u>Customer Class</u>	<u>Minimum</u> <u>Charge</u>	<u>Minimum</u> <u>Volume</u>	<u>Volume Charge/</u> <u>Above Minimum</u>
	<b>1. <u>RESIDENTIAL</u></b>			
	a. Single Family, Churches PER UNIT	\$20.20	500 cu. ft.	\$3.59/100 cu.ft.
	b. Multi Family, Apartments, Mobile Home in a Park, Condos, Motel, Hotel PER UNIT	\$20.20	500 cu. ft.	\$3.59/100 cu.ft.
	c. Residential unit not on City metered water system, PER UNIT	\$27.38	-----	-----
	(NOTE: Above is based on estimate discharge of 700 cu. ft./mo. City may require metering if higher discharge is estimated by the City Engineer)			
	<b>2. <u>COMMERCIAL</u></b>			
	Businesses, Schools, R.V. Parks, Care Centers, etc. PER METER	\$25.54	600 cu. ft.	\$5.49/100 cf.
				<u>Above Minimum</u>
				a) Volume Charge
	<b>3. <u>INDUSTRIAL</u></b>	\$54.62	1,000 cu. ft.	\$2.27/100 cu.ft.
	(includes first 25 lbs. BOD and 9 lbs. TSS)			b) BOD Charge: \$0.85/lb.
				c) TSS Charge: \$0.25/lb.
	<b>4. <u>ABANDONED OR NON REVENUE PRODUCING SERVICE:</u></b>			
	Abandonment procedures may be started by the City, if a building is unoccupied for a period of 18 months, with proper notification to the property owner, as outlined in Resolution No. 1100, and/or minimum billing may be started for the building under consideration.			
	<b>5. <u>WASTEWATER DISCHARGE STATION - RV, etc.</u></b>			(in addition to standard charge)
	a. Residential type sewage discharge station at commercial establishments,			

PER MONTH

- |                                     |         |                                      |
|-------------------------------------|---------|--------------------------------------|
| i. For multiple RV dump stations    | \$25.54 | Minimum/connection                   |
| ii. For individual RV units in Park | \$2.75  | Minimum/connection<br>per 50 cu. ft. |

6. **SEPTAGE** - per truck load

- |                            |          |              |
|----------------------------|----------|--------------|
| a. Residential, PER GALLON | \$0.0625 | \$28.00/min. |
| b. Commercial, PER GALLON  | \$0.0825 | \$28.00/min. |

Effective July 1, 2005 the septage rate will be:

- |                            |         |              |
|----------------------------|---------|--------------|
| a. Residential, PER GALLON | \$0.070 | \$30.00/min. |
| b. Commercial, PER GALLON  | \$0.095 | \$30.00/min. |

Septage rates above apply only to the service area identified in the Pudding River Service Provider Study, March 1995. Other areas will be charged \$0.085 PER GALLON for residential or commercial septage.

[Section 5.E.6 as amended by Ordinance 2367, passed July 26, 2004.]

7. **Individual Recreational Vehicles discharging at Wastewater Treatment Plant**

Per vehicle	NO CHARGE
-------------	-----------

8. **Mixed Residential/Commercial Accounts**

This category uses the residential or commercial rates outlined under subsections "1" to "3" above. The criteria for using a mixed residential/commercial method are outlined below:

- a) If no monitoring device is available, then the City may reasonably estimate charges based on the available facts, such as number of employees, product, or other criteria.
- b) If one City monitoring device serves more than one category of user, then the charges will be as follows:
  - 1) If separation of service is not practical (as determined by the City Engineer), then the service charge will be at the residential rate for the first 700 cubic feet of water, for each residential unit. The remaining will be at the commercial rate.
  - 2) If service monitoring separation is practical but not utilized, then the charge for the entire service will be at the commercial rate. The customer may request the City for a separate monitoring device for each category of service by paying the established meter installation fee.

**Section 6. Capital Cost Recovery Agreements.** The City, at its discretion, may enter into agreements with industrial dischargers for the purpose of recovering the City's incurred or anticipated costs used to modify POTW that benefit the industry. This cost, after Council's approval, may be divided into a number of payments, and added to the monthly invoice, rather than one lump sum payment. The cost recovery agreements may reflect the construction costs, interest, engineering and administration costs for POTW modifications needed to accommodate industrial growth.

**Section 7. Large Septage Load Charge:** The intent of this charge is to discourage users from discharging large loads (lbs./day) of permitted waste to the city system during the dry weather season (June, July, August, September, October) that could reduce reliability of the city sewerage system. Prior to the construction of the new treatment plant, if septage waste is accepted at the present treatment system during the dry weather season, and if such loads will not place the treatment process at risk, the septage hauler rate may be multiplied by a factor of two (2). If the load will place risk to treatment process, then the City may choose not to accept such a load.

**Section 8. Unauthorized Connection and Service:**

A. Unauthorized Connection: A 25 percent (25%) administrative charge may be added to the service connection or capacity fee if a property is connected to the system without first obtaining the proper permit and paying the required fees. This 25 percent (25%) may be added to the regular fee in effect at the time the unauthorized connection is discovered by the City. The added surcharge may be excused if the property owner volunteers the information and comes forward to pay the required connection fee.

B. Unauthorized Service: An administrative charge of 25 percent (25%) may be added to the City utility service charge if a property receives City service and the customer does not inform the City to start the billing. The charge calculated will be limited to a twelve (12) month period. The City may make a reasonable estimate of the amount due.

C. This section will not be construed to limit the City's right to pursue any and all available legal remedies in regards to unauthorized connections or service.

**Section 9. Customer Billing Adjustments.** If the City, in the preceding twelve (12) months, has overcharged a customer for the sewer service, and it is brought to the attention of the City Engineer, then he will make an adjustment using available records of the past year. The adjustment will be limited to a period of four (4) months falling within the past year. A similar adjustment for undercharge maybe made but it will be limited to a period of two (2) months. In the case of water leakage, an adjustment for a one or two month period will be made if the leak has been promptly repaired and the request for leak adjustment has been made within six (6) months. Such adjustments will not exceed 100% of the estimated excess flow attributable to the leak. A charge of \$10.00 will be added for any sewer charge adjustment due to water leaks.

**Section 10. Installation of Monitoring Clean Out:** If the City wants to install a clean out on the service line near the house or business for infiltration monitoring and reduction, it may do so if a ten (10) day notice prior to construction activity has been provided to the property owner. The City may not charge for the installation of the clean out or for monitoring and infiltration reduction although it may be located on the private property.

**Section 11. Increase in Rates and Charges.** Future rate adjustments will be established by Council action at a frequency and in an amount determined to be fiscally responsible for supporting service obligations, ensure POTW compliance with EPA/DEQ regulations, and to protect the environment and public health.

**Section 12. Service Agreements.** All prior Council-approved service agreements between the City and a customer will remain in force for the term of the agreement. However, the requirements of this ordinance and other applicable ordinances, including the rate increase provisions, must be met.

**Section 13. Use of Monies Collected.** That the monies collected pursuant to the provisions of this ordinance will be used to pay the costs of construction, operation, maintenance and expansion of sanitary and storm sewers, sewage treatment plants, pumping stations, and related facilities and services, including necessary administrative and engineering costs.

**Section 14. Administration.** Interpretation and administration of this ordinance and its provisions will be the responsibility of the City Engineer.

**Section 15. Severability Clause.** If any clause, sentence, paragraph, section or portion of this ordinance for any reason may be adjudged invalid by a court of competent jurisdiction, such judgment will not affect, impair, or invalidate any of the remainder of this ordinance.

**Section 16. Repeal.** Ordinance No. 2059 is hereby repealed.

**Section 17. Effective Date.** This ordinance is effective on November 1, 1995.

***Passed by the Council September 11, 1995, and approved by the Mayor  
September 12, 1995.***



---

ORDINANCE NO. 2176

**AN ORDINANCE REGULATING THE DISCHARGE OF WASTES TO THE SANITARY AND STORM SEWER SYSTEMS OF THE CITY, LIMITING SUCH DISCHARGES ONLY TO THOSE OF ACCEPTABLE TYPES, CHARACTERISTICS, OR CONCENTRATIONS, ESTABLISHING A SYSTEM OF WASTE DISCHARGE PERMITS, PROVIDING FOR ENFORCEMENT AND DECLARING AN EMERGENCY.**

**SECTION 1 - GENERAL PROVISIONS****1.1 Purpose and Policy**

This ordinance sets forth uniform requirements for direct and indirect discharges of pollutants into the wastewater collection, storm water collection and treatment system for the City of Woodburn and enables the City to comply with all applicable State and Federal laws including the Clean Water Act (Act 33 U.S.C. 1251 et seq.), the General Pretreatment Regulations (40 CFR Part 403) and Oregon Administrative Rules (OAR) Chapter 340. The objectives of this ordinance are:

- (1) To prevent the introduction of pollutants into the municipal wastewater and storm water system which will interfere with the operation of the system;
- (2) To prevent the introduction of pollutants into the municipal wastewater and storm water system which will pass through the system, inadequately treated, into receiving waters or the atmosphere or otherwise be incompatible with the system;
- (3) To ensure that the quality of the wastewater treatment plant sludge is maintained at a level which allows it's beneficial use;
- (4) To protect both municipal personnel who may come into contact with sewage, sludge and effluent in the course of their employment as well as protecting the general public;
- (5) To preserve the hydraulic capacity of the municipal wastewater system;
- (6) To improve the opportunity to recycle and reclaim wastewater and sludge from the system;
- (7) To provide for equitable distribution of the cost of operation, maintenance and improvements of the municipal wastewater

system; and

- (8) To ensure the City complies with its NPDES permit conditions, sludge use and disposal requirements and any other Federal or State laws which the municipal wastewater system is subject.

This ordinance provides for the regulation of direct and indirect discharge to the municipal wastewater collection system through the issuance of permits to certain non-domestic users and through enforcement of general requirements for other users, authorizes monitoring and enforcement activities, establishes administrative review procedures, requires user reporting, and provides for the setting of fees for the equitable distribution of costs resulting from the program established herein.

This ordinance shall apply to the City and to persons outside the City who, by contract or agreement with the City, are included as users of the municipal wastewater system.

## 1.2 Administration

Except as otherwise provided herein, the Superintendent shall administer, implement and enforce the provisions of this ordinance. Any powers granted to or duties imposed upon the Superintendent may be delegated by the City Engineer or Superintendent to other City personnel.

## 1.3 Definitions

Unless the context specifically indicates otherwise, the following terms and phrases, as used in this ordinance shall have the meanings hereinafter designated;

- (1) Act or "the Act". The Federal Water Pollution Control Act, also known as the Clean Water Act, as amended, 33 U.S.C.1251 et seq.
- (2) Approval Authority. The Oregon Department of Environmental Quality (DEQ)
- (3) Authorized Representative of the Industrial User.
  - A. If the industrial user is a corporation, authorized representative shall mean:
    - i) The president, secretary, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or

decision-making functions for the corporation, or

- ii) The manager of one or more manufacturing, production, or operation facilities employing more than 250 persons or having gross annual sales or expenditures exceeding \$25 million (in second-quarter 1980 dollars), if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
  - B. If the industrial user is a partnership, association, or sole proprietorship, an authorized representative shall mean a general partner or the proprietor.
  - C. If the individual user is representing Federal, State or local governments, or an agent thereof, an authorized representative shall mean a director or highest official appointed or designated to oversee the operation and performance of the activities of the government facility.
  - D. The individuals described in subsections A-C above may designate another authorized representative if the authorization is in writing, the authorization specifies the individual or position responsible for the overall operation of the facility from which the discharge originates or having overall responsibility for environmental matters for the company, and the authorization is submitted to the City.
- (4) Biochemical Oxygen Demand (BOD) The quantity of oxygen utilized in the biochemical oxidation of organic matter under standard laboratory procedure, five (5) days at 20° centigrade expressed in terms of weight and concentration (milligrams per liter mg/l).
  - (5) Building Sewer. A sewer conveying wastewater from the premises of a user to the POTW.
  - (6) Categorical Pretreatment Standard or Categorical Standard. Any regulation containing pollutant discharge limits promulgated by the USEPA in accordance with Section 307 (b) and (c) of the Act (33 U.S.C. 1317) which applies to a specific category of industrial users and which appears in 40 CFR Chapter I, Subchapter N, Parts 405-471, incorporated herein by reference.
  - (7) City. City of Woodburn, Oregon, a municipal corporation of the State of Oregon, acting through its City Council or any board,

- committee, body, official, or person to whom the Council shall have lawfully delegated the power to act for or on behalf of the City.
- (8) City Engineer. The City Engineer (Public Works Director) of the City of Woodburn, Oregon, or his duly authorized agent(s).
- (9) Color The optical density at the visual wave length of maximum absorption, relative to distilled water. One hundred percent (100%) transmittance is equivalent to zero (0.0) optical density.
- (10) Composite Sample. The sample resulting from the combination of individual wastewater samples taken at selected intervals based on either an increment of flow or time.
- (11) Control Authority. The term "Control Authority" shall refer to the Superintendent once the City has a pretreatment program approved by Oregon DEQ according to the provisions of 40 CFR 403.11.
- (12) Continuing Violation. Each day a violation occurs may be considered as a separate violation.
- (13) Cooling Water. The water discharged from any use such as air conditioning, cooling or refrigeration, to which the only pollutant added is heat.
- (14) Department of Environmental Quality or DEQ. The Oregon Department of Environmental Quality or where appropriate, the term may also be used as a designation for the Director of the Department or other duly authorized official of the Department.
- (15) Discharge. The discharge or the introduction of pollutants into the municipal wastewater system from any non-domestic source regulated under Section 307 (b), (c) or (d), of the Act.
- (16) Environmental Protection Agency or U.S. EPA. The U.S. Environmental Protection Agency or, where appropriate, the term may also be used as a designation for the Regional Water Management Division Director or other duly authorized official of said agency.
- (17) Existing Source. Any source of discharge, the construction or operation of which commenced prior to the publication of proposed categorical pretreatment standards under section 307 (b) and (c) (33 U.S.C. 1317) of the Act which will be applicable to such source if the standard is thereafter promulgated in accordance

---

with Section 307 of the Act.

- 18) Grab Sample. A sample which is taken from a wastestream on a one-time basis without regard to the flow in the wastestream and without consideration of time.
- 19) Holding Tank Waste. Any waste from holding tanks such as vessels, chemical toilets, campers, trailers, septic tanks, and vacuum-pump tank trucks.
- 20) Industrial User. Any person which is a source of discharge.
- 21) Industrial Waste Coordinator. The person designated by the City to carry out certain duties and responsibilities associated with the pretreatment program. This person is the duly authorized representative of the Superintendent in accordance with Section 1.3 (47) of this ordinance.
- 22) Industrial Waste Water. A non-domestic wastewater originating from a nonresidential source.
- 23) Infiltration. Any water other than wastewater which enters the sewage treatment system (including service connections) from the ground, typically from broken pipes, or defective joints in pipes and manhole walls.
- 24) Inflow. Any water from storm water runoff which directly enters the sewage system during or immediately after rainfall. Typical points of entry include, but are not limited to, connections with roof and area drains, storm drain connections, holes in manhole covers in flooded streets, cooling water discharges, catch basins, and drainage from springs and swampy areas.
- 25) Interference. A discharge which, alone or in conjunction with a discharge or discharges from other sources, both:
  - A. Inhibits or disrupts the municipal wastewater system, its treatment processes or operations, or its sludge processes; use or disposal; and
  - B. Therefore is a cause of a violation of any requirements of the NPDES permit (including an increase in the magnitude or duration of a violation) or of the prevention of sewage sludge use or disposal in compliance with the following statutory provisions and regulations or permits issued thereunder (or more stringent State or local regulations): Section 405 of the

Clean Water Act, the Solid Waste Disposal Act (SWDA) (including Title II, more commonly referred to as the Resource Conservation and Recovery Act (RCRA), and including State regulations contained in any State sludge management plan prepared pursuant to Subtitle D of the SWDA), the Clean Air Act, the Toxic Substances Control Act, and the Marine Protection research and Sanctuaries Act.

- 26) Local Limits / Specific Pollutant Limitations. Enforceable local requirements developed by POTWs to address federal standards as well as state and local regulations.
- 27) Medical Waste. Isolation wastes, infectious agents, human blood and blood byproducts, pathological wastes, sharps, body parts, fomites, etiologic agents, contaminated bedding, surgical wastes, potentially contaminated laboratory wastes and dialysis wastes.
- 28) Municipal Wastewater System or System. A "treatment works" as defined in Section 212 of the Act, (33 U.S.C. 1292) which is owned by the State or municipality. This definition includes any devices or systems used in the collection, storage, treatment, recycling and reclamation of sewage or industrial wastes and any conveyances which convey wastewater to a treatment plant. The term also means the municipal entity having the responsibility for the operation and maintenance of the system.
- 29) National Pretreatment Standard. National pretreatment standard is defined in 40 CFR 403.3 (j) as any regulation containing pollutant discharge limits promulgated by EPA under Section 307 (b) and (c) of the Clean Water Act applicable to industrial users, including the general and specific prohibition found in 40 CFR 403.5.
- 30) New Source.
  - A. Any building, structure, facility or installation from which there is or may be a discharge of pollutants, the construction of which commenced after the publication of proposed Pretreatment Standards under Section 307 (c) of the Act which will be applicable to such source if such Standards are thereafter promulgated in accordance with that section, provided that:
    - i) The building, structure, facility or installation is constructed at a site at which no other source is located; or

- ii) The building, structure, facility or installation completely replaces the process or production equipment that causes the discharge of pollutants at an existing source; or
  - iii) The production or wastewater generating processes of the building, structure, facility or installation are substantially independent of an existing source at the same site in determining whether these are substantially independent, factors such as the extent to which the new facility is integrated with the existing plant, and the extent to which the new facility is engaged in the same general type of activity as the existing source should be considered.
- B. Construction on a site at which an existing source is located results in a modification rather than a new source if the construction does not create a new building, structure, facility or installation meeting the criteria of paragraphs (i), (ii), (iii) of this section but otherwise alters, replaces, or adds to existing process or production equipment.
- C. Construction of a new source as defined under this paragraph has commenced if the owner or operator has:
  - i) Begun, or caused to begin as part of a continuous on-site construction program;
    - (a) Any placement, assembly, or installation of facilities or equipment; or
    - (b) Significant site preparation work including clearing, excavation, or removal of existing buildings, structures, or facilities which is necessary for the placement, assembly, or installation of new sources facilities or equipment; or
  - ii) Entered into a binding contractual obligation for the purchase of facilities or equipment which are intended to be used in its operation within a reasonable time. Options to purchase or contacts which can be terminated or modified without substantial loss, and contracts for feasibility, engineering, and design studies do not constitute a contractual obligation under this paragraph.

31) Non-domestic Pollutants. Any substances other than human

excrement and household gray water (shower, dish washing operations, etc.). Non-domestic pollutants include the characteristics of the wastewater (i.e., pH, temperature, TSS, turbidity, color, BOD, COD, toxicity, odor).

- 32) Pass Through. A discharge which exits the treatment plant effluent into waters of the U.S. in quantities or concentrations which, alone or in conjunction with a discharge or discharges from other sources, is a cause of a violation of any requirement of the City's NPDES (including an increase in the magnitude or duration of a violation).
- 33) Person. Any individual, partnership, CO-partnership, firm, company, corporation, association, joint stock company, trust, estate, governmental entity or any other legal entity, or their legal representatives, agents or assigns. This definition includes all Federal, state, or local governmental entities.
- 34) pH. The logarithm (base 10) of the reciprocal of the hydrogen ion concentration expressed in moles per liter of solution.
- 35) Pollutant. Any dredged spoil, solid waste, incinerator residue, sewage, garbage, sewage sludge, munitions, medical wastes, chemical wastes, industrial wastes, biological materials, radioactive materials, heat, wrecked or discharged equipment, rock, sand, cellar dirt and agricultural wastes, anything that contaminates.
- 36) Pretreatment or Treatment. The reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater prior to or in lieu of introducing such pollutants into the municipal wastewater system. This reduction or alteration may be obtained by physical, chemical or biological processes, by process changes or by other means.
- 37) Pretreatment Requirement. Any substantive or procedural requirements related to pretreatment, other than national pretreatment standards, imposed on an industrial user.
- 38) Pretreatment Standards or Standards. Pretreatment standards shall mean prohibited discharge standards, categorical pretreatment standards, and local limits.
- 39) Prohibited Discharge Standard or Prohibited Discharges. Absolute prohibitions against the discharge of certain types or characteristics of wastewater as established by EPA, DEQ and/or the Superintendent.



- 
- 40) Receiving Stream or Water of the State. All streams, lakes, ponds, marshes, watercourses, waterways, wells, springs, reservoirs, aquifers, irrigation systems, drainage systems, and all other bodies or accumulations of water, surface or underground, natural or artificial, public or private, which are contained within, flow through, or border upon the State of Oregon or any portion thereof.
- 41) Domestic Sewage. Human excrement and gray water (household showers, dish washing operations, etc.)
- 42) Significant Industrial User.
- A. Except as provided in paragraph B of this section the term Significant Industrial User means:
- i) All industrial users subject to categorical pretreatment standards under 40 CFR 403.6 and 40 CFR chapter I, subchapter N; and
- ii) Any other industrial user that: discharges an average of 25,000 gallons per day or more of process wastewater to the POTW (excluding sanitary, non-contact cooling and boiler blow down wastewater); contributes a process wastestream which makes up 5 percent or more of the average dry weather hydraulic or organic capacity of the POTW treatment plant; or is designated as such by the Control Authority as defined in 40 CFR 403.12(a) on the basis that the industrial user has a reasonable potential for adversely affecting the POTW's operation or for violating any pretreatment standard or requirement (in accordance with 40 CFR 403.8(f)(6)).
- B. Upon a finding that an industrial user meeting the criteria in paragraph A. (ii) of this section has no reasonable potential for adversely affecting the municipal waste water system's operation or for violating any pretreatment standard or requirement, the Control Authority (as defined in 40 CFR 403.12(a)) may at any time, on its own initiative or in response to a petition received from an industrial user or POTW, and in accordance with 40 CFR 403.8(f)(6), determine that such industrial user is not a significant industrial user.
- 43) Slug Load. Any pollutant (including BOD) released in a non-routine, episodic, or non-customary batch discharge at a flow rate or concentration which has the potential to cause a violation of the specific discharge prohibitions in Section 2 of this Ordinance.

- 
- 44) State. State of Oregon
- 45) Storm Water. Any flow occurring during or following any form of natural precipitation and resulting therefrom, including snow melt.
- 46) Suspended Solids or Total Suspended Solids (TSS). The total suspended matter that floats on the surface of, or is suspended in, water, wastewater, or other liquid, and which is removable by laboratory filtering.
- 47) Superintendent. The person designated by the City to supervise the operation of the municipal wastewater system and who is charged with certain duties and responsibilities by this article or his duly authorized representative.
- 48) Toxic Pollutant. One of the pollutants or combination of those pollutants listed as toxic in regulations promulgated by the Environmental Protection Agency under the provision of Section 307 (33 U.S.C. 1317) of the Act.
- 49) Treatment Plant. That portion of the municipal wastewater system designed to provide treatment of sewage and industrial waste.
- 50) Treatment Plant Effluent. Any discharge of pollutants from the municipal wastewater system into waters of the state.
- 51) User. Any person who contributes, or causes or allows the contribution of sewage or industrial wastewater into the municipal wastewater system, including persons who contribute such wastes from mobile sources.
- 52) Violation. Shall have occurred when any requirement of this ordinance has not been met; or when a written request of the Superintendent, made under the authority of this ordinance, is not met within the specified time; or when a condition of a permit or contract issued under the authority of this ordinance is not met within the specified time; or when permitted effluent limitations are exceeded, regardless of intent or accident; or when false information has been provided by the discharger.
- 53) Wastewater. The liquid and water-carried industrial wastes, or sewage from residential dwellings, commercial buildings, industrial and manufacturing facilities, and institutions, whether treated or untreated, which is contributed to the municipal wastewater system.

This ordinance is gender neutral and the masculine gender shall include the feminine and vice versa. Shall is mandatory; may is permissive or discretionary. The use of the singular shall be construed to include the plural and the plural shall include the singular as indicated by the context of its use.

#### 1.4 Abbreviations

The following abbreviations shall have the designated meanings:

- BOD Biochemical Oxygen Demand
- CFR Code of Federal Regulations
- COD Chemical Oxygen Demand
- DEQ Oregon Department of Environmental Quality
- EPA U.S. Environmental Protection Agency
- gpd Gallons Per Day
- LC<sub>50</sub> Lethal Concentration for Fifty Percent (50%)  
of the Test Organisms
- l Liter
- mg Milligrams
- mg/l Milligrams per liter
- NPDES National Pollutant Discharge Elimination System
- O&M Operation and Maintenance
- POTW Publicly Owned Treatment Works
- RCRA Resource Conservation and Recovery Act
- SIC Standard Industrial Classification
- SWDA Solid Waste Disposal Act (42 U.S.C. 6901, et seq.)
- TSS Total Suspended Solids
- USC United States Code

## SECTION 2 - GENERAL SEWER USE REQUIREMENTS

#### 2.1 Prohibited Discharge Standards

No user shall contribute or cause to be contributed, directly or indirectly, any pollutant or wastewater which will cause interference or pass through. These general prohibitions apply to all users of the municipal wastewater system whether or not the user is subject to categorical pretreatment standards or any other National, State or local pretreatment standards or requirements. Furthermore, no user shall contribute the following substances to the system:

- (1) Any liquids, solids, or gases which by reason of their nature or quantity are, or may be, sufficient, either alone or by interaction with other substances, to cause fire or explosion or be injurious in

any other way to the municipal wastewater system. Included in this prohibition are wastestreams with a closed cup flash point of less than 140° F (60° C) using the test methods prescribed in 40 CFR 261.21.

- (2) Solid or viscous substances in amounts which will cause interference with the flow in a sewer but in no case solids greater than one half inch (2") (1.27 centimeters) in any dimension.
- (3) Any fat, oils or greases, including but not limited to petroleum oil, non-biodegradable cutting oil, or products of mineral oil origin, in amounts that will cause interference or pass through.
- (4) Any wastewater from a grab sample having a pH less than 5.5 su. or more than 10.0 su., or which may otherwise cause corrosive structural damage to the system, city personnel or equipment.

IUs using continuous pH monitoring devices are prohibited from discharge when:

- A. The total time pH values are outside the range of 5.5 su. to 10.0 su. exceeds 16 hours in any calendar month. In no case shall the pH fall below 5.0 su. or above 12.5 su.
  - B. No individual excursion from pH range of 5.5 su. to 10.0 su. shall exceed 60 minutes for any single duration. In no case shall the pH fall below 5.0 su. or above 12.5 su.
- (5) Any wastewater containing pollutants in sufficient quantity (flow or concentration), either singly or by interaction with other pollutants, to pass through or interfere with the municipal wastewater system, any wastewater treatment or sludge process, or constitute a hazard to humans or animals.
  - (6) Any noxious or malodorous liquids, gases, or solids or other wastewater which, either singly or by interaction with other wastes, are sufficient to create a public nuisance or hazard to life or are sufficient to prevent entry into the sewers for maintenance and repair.
  - (7) Any substance which may cause the treatment plant effluent or any other residues, sludge, or scum, to be unsuitable for reclamation and reuse or to interfere with the reclamation process. In no case, shall a substance discharged to the system cause the City to be in noncompliance with sludge use or disposal regulations or permits issued under Section 405 of the Act; the Solid Waste

---

Disposal Act, the Clean Air Act, the Toxic Substances Control Act, or other State requirements applicable to the sludge use and disposal practices being used by the City.

- (8) Any wastewater which imparts color which cannot be removed by the treatment process, such as, but not limited to, dye wastes and vegetable tanning solutions, which consequently imparts color to the treatment plants effluent thereby violating the City's NPDES permit.
- (9) Any wastewater having temperature greater than 150° F (65° C), or which will inhibit biological activity in the treatment plant resulting in interference, but in no case wastewater which causes the temperature at the introduction into the treatment plant to exceed 104° F (40° C).
- (10) Any wastewater containing any radioactive waste or isotopes except as specifically approved by the Superintendent in compliance with applicable State and Federal regulations.
- (11) Any pollutants which result in the presence of toxic gases, vapor or fumes within the system in a quantity that may cause worker health and safety problems.
- (12) Any hauled pollutants, except at discharge points designated by the City in accordance with Section 3.6 of this Ordinance.
- (13) Storm water, surface water, groundwater, artisan well water, roof runoff, subsurface drainage, swimming pool drainage, condensate, deionized water, cooling water and unpolluted industrial wastewater, unless specifically authorized by the Superintendent.
- (14) Any sludge, screening, or other residues from the pretreatment of industrial wastes.
- (15) Any medical wastes, except as specifically authorized by the Superintendent in a wastewater permit.
- (16) Any material containing ammonia, ammonia salts, or other chelating agents which will produce metallic complexes that interfere with the municipal wastewater system.
- (17) Any material identified as hazardous waste according to 40 CFR Part 261 except as specifically authorized by the Superintendent.
- (18) Any wastewater causing the treatment plant effluent to

demonstrate toxicity to test species during a bio-monitoring evaluation.

- (19) Recognizable portions of the human body or animal anatomy.
- (20) Any wastes containing detergents, surface active agents, or other substances which may cause excessive foaming in the municipal wastewater system.

Waste prohibited by this section shall not be processed or stored in such a manner that these waste could be discharged to the municipal wastewater system.

## 2.2 Federal Categorical Pretreatment Standards

Users subject to categorical pretreatment standards are required to comply with applicable standards set out in 40 CFR Chapter 1, Subchapter N, Parts 405-471 and incorporated herein.

- (1) Where a categorical pretreatment standard is expressed only in terms of either the mass or the concentration of a pollutant in wastewater, the Superintendent may impose equivalent concentration or mass limits in accordance with 40 CFR 403.6(c)
- (3) When wastewater subject to a categorical pretreatment standard is mixed with wastewater not regulated by the same standard, the Superintendent shall impose an alternate limit using the combined wastestream formula in 40 CFR 403.6(e).
- (4) A user may obtain a variance from categorical pretreatment standard if the user can prove, pursuant to the procedural and substantive provisions in 40 CFR 403.13, that factors relating to its discharge are fundamentally different from the factors considered by EPA when developing the categorical pretreatment standard.
- (5) A user may obtain a net gross adjustment to a categorical standard in accordance with 40 CFR 403.15.

## 2.3 State Requirements

Users are required to comply with applicable State pretreatment standards and requirements set out in OAR Chapter 340 and incorporated herein.

## 2.4 "Local Limits" Specific Pollutant Limitations

No person (user) shall discharge wastewater containing restricted

substances into the municipal wastewater system in excess of limitations specified in its Wastewater Discharge Permit or published by the Superintendent. The more stringent of either the categorical standards or the specific pollutant limitations "Local Limits" for a given pollutant will be placed in the permit.

The Superintendent shall publish and revise from time to time standards for specific restricted substances "Local Limits". These standards will be adopted or rejected through resolution by the City Council. These standards shall be developed in accordance with 40 CFR Section 403.5 and shall implement the objectives of this ordinance. Standards published in accordance with this section will be deemed Pretreatment Standards for the purposes of Section 307 (d) of the Act. At the discretion, of the Superintendent mass or permit specific limitations may be imposed in addition to or in place of the concentration based limitations referenced above.

## 2.5 City's Right to Revision

The City reserves the right to establish, by ordinance or in wastewater permits, more stringent limitations or requirements for discharge to the municipal wastewater system if deemed necessary to comply with the objectives presented in Section 1.1 of this Ordinance or the general and specific prohibitions in Section 2.1 of this Ordinance.

## 2.6 Special Agreement

The City reserves the right to enter into special agreements with users setting out special terms under which the industrial user may discharge to the system. In no case will a special agreement waive compliance with a pretreatment standard. However, the industrial user may request a net gross adjustment to a categorical standard in accordance with 40 CFR 403.15. Industrial users may also request a variance from the categorical pretreatment standard from US EPA. Such a request shall be approved only if the user can prove that factors relating to its discharge are fundamentally different from the factors considered by US EPA when establishing that pretreatment standard. An industrial user requesting a fundamentally different factor variance must comply with the procedural and substantive provisions in 40 CFR 403.13.

## 2.7 Dilution

No user shall ever increase the use of process water, or in any way attempt to dilute, a discharge as a partial or complete substitute for adequate treatment to achieve compliance with a discharge limitation unless expressly authorized by an applicable pretreatment standard, or any other pollutant-specific limitation developed by the City.

## 2.8 Deadline for Compliance with Categorical Standards

Compliance by existing sources with categorical pretreatment standards shall be within three (3) years of the date the standard is effective unless a shorter compliance time is specified in the appropriate subpart of 40 CFR Chapter I Subchapter N.

New sources shall install and have in operating condition, and shall start-up all pollution control equipment required to meet applicable pretreatment standards before beginning to discharge. Within the shortest feasible time (not to exceed 90 days), new sources must meet all applicable pretreatment standards.

## 2.9 Inflow and Infiltration

All property owners and responsible users identified by the City as contributors to excessive or improper infiltration or inflow into the treatment works shall be advised of their infiltration or inflow problems. All such properties shall be provided a 180-day grace period in which to correct the identified infiltration and inflow problems, said 180-day grace period to extend from the date of notification. By the end of the 180-day grace period, each property owner shall notify the City that corrective actions have been taken or are in progress, and describe the actions being taken.

A property owner failing to notify the City of corrective actions prior to the end of the 180-day grace period shall be subject to termination of service without further notice, and water service shall be immediately discontinued and shut off until the violations shall have been corrected in accordance to federal, state, and City regulations.

In the event any instance of excessive infiltration or inflow into the treatment works of the City shall continue beyond the 180-day grace period, it is hereby declared that such continuing infiltration or inflow is a public nuisance, that the City Engineer shall have the right to abate such a public nuisance, to enter upon any private property within the City for such a purpose, and to assess the cost of such abatement as a lien against the property upon which such infiltration and inflow occurs. The City Engineer shall assess the cost of such abatement to the property from which infiltration and inflow occurs. An administration fee of \$350.00 dollars or 5% of the cost, whichever is greater, shall be assessed by the City Engineer in addition to all cost of abatement. The assessment of all cost shall be levied by the filing of a statement of such costs together with the description of the property or properties to be assessed and the name of the owner(s) thereof with the City Recorder. The City Recorder shall enter



the assessment as a lien against such property in the Lien Docket of the City.

No new connections from inflow sources into the water pollution control facilities shall be permitted without the approval of the City Engineer.

### **SECTION 3 - PRETREATMENT OF WASTEWATER**

#### **3.1 Pretreatment Facilities**

Industrial users shall provide necessary wastewater treatment as required to comply with this Ordinance and shall achieve compliance with all categorical pretreatment standards, local limits and the prohibitions set out in Section 2 above, within the time limitations specified by the Superintendent. Any facilities required to pretreat wastewater to a level acceptable to the City shall be provided, operated, and maintained at the industrial user's expense. Detailed plans showing the pretreatment facilities and operating procedures shall be submitted to the City for review, and shall be acceptable to the City before construction of the facility. The review of such plans and operating procedures shall in no way relieve the user from the responsibility of modifying the facility as necessary to produce an acceptable discharge to the City under the provisions of this Ordinance.

#### **3.2 Additional Pretreatment Measures**

Whenever deemed necessary, the Superintendent may require industrial users to restrict the industrial user's discharge during peak flow periods, designate that certain wastewater be discharged only into specific sewers, relocate and/or consolidate points of discharge, separate sewage wastestreams from industrial wastestreams, and such other conditions as may be necessary to protect the municipal wastewater system and determine the industrial user's compliance with the requirements of this Ordinance.

- (1) Each person discharging, into the municipal wastewater system greater than 100,000 gallons per day or greater than five percent (5%) of the average daily flow in the system, whichever is lesser, may be required by the Superintendent to install and maintain, on his property and at his expense, a suitable storable and flow control facility to ensure equalization of flow over a twenty-four (24) hour period. The facility shall have a capacity for at least fifty percent (50%) of the daily discharge volume and shall be equipped with alarms and a rate of discharge controller, the regulation of which shall be directed by the Superintendent. A wastewater permit may be issued solely for flow equalization.

(2) Grease, oil and sand interceptors shall be provided, when, in the opinion of the Superintendent, they are necessary for the proper handling of wastewater containing excessive amounts of grease, flammable substances, sand, or other harmful substances; except that such interceptors shall not be required for residential users. All interception units shall be of type and capacity approved by the Superintendent and shall be so located to be easily accessible for cleaning and inspection. Such interceptors shall be inspected, cleaned, and repaired regularly, as needed, by the owner, at his expense.

- (3) Industrial users with the potential to discharge flammable substances may be required to install and maintain an approved combustible gas detection meter.

### 3.3 Spill Prevention

Each industrial user shall provide protection from accidental or intentional discharges of prohibited materials or other substances regulated by this Ordinance. Significant Industrial users that handle, store or use prohibited or restricted substances on their sites shall prepare a spill prevention plan for the Superintendent's approval within 90 days of notice. The plan shall be posted and available for inspection at the facility during normal business hours.

(1) Spill Prevention Plan

At least once every two (2) years the Superintendent shall evaluate industrial users that handle, store, or use prohibited or restricted substances on their sites. The Superintendent will use the evaluation to determine the need for the Industrial User to develop a spill prevention plan. Alternatively, the Superintendent may develop such a plan for any user and require the plan's implementation. An accidental discharge/sludge control plan shall address, at a minimum, the following:

- A. Description of discharge practices, including non-routine batch discharges;
- B. Description of stored chemicals;
- C. Procedures for immediately notifying the Superintendent of any accidental or slug discharge, as required by Section 6.6 of this ordinance;
  - i. Procedures for any person becoming aware of spill, treatment upset or uncontrolled discharges of prohibited or restricted substances, directly or

indirectly, into the City sewerage systems immediately reporting such discharge to the POTW Superintendent. Where such information is given orally a written follow-up report within (5) five days may be required.

- ii. A notice informing employees of the notification requirement and containing a telephone number for the individual to contact in the event of such a discharge shall be posted in a conspicuous place visible to all employees that may reasonable be expected to observe such a discharge

D. Procedures to prevent adverse impact from any accidental or slug discharge. Such procedures include, but are not limited to, inspection and maintenance of storage areas, handling and transfer of materials, loading and unloading operations, control of plant site runoff, worker training, building of containment structures or equipment, measures for containing toxic organic pollutants, including solvents, and or measures and equipment for emergency response.

(2) Spill Prevention Facilities

Facilities to prevent the discharge of prohibited materials shall be provided and maintained at the owner's or user's own cost and expense. Detailed plans showing facilities and operating procedures to provide this protection shall be submitted to the Superintendent for review and shall be approved by the Superintendent before construction of the facility. Review and approval of such plans and operating procedures shall not relieve the industrial user from the responsibility to modify the user's facility as necessary to meet the requirements of this Ordinance.

(3) Preventive Measures

If any user has a spill or uncontrolled discharge of prohibited or restricted substances into the City sewer, the POTW Superintendent may require the user's spill prevention and control plan to be resubmitted, with revisions, in order to fully comply with the requirements of this ordinance. The POTW may also require the industrial user to install, modify equipment and/or make other changes necessary to prevent such discharges as a condition of issuance of and Industrial Waste Discharge Permit or as a condition of continued discharge into the City sewer system. A schedule of compliance for construction completion may be established by the POTW Superintendent.

The Superintendent may require connections or entry points which could allow spills or uncontrolled discharges of prohibited or restricted substances to enter the City sewer systems to be eliminated, labeled, or controlled, so as to prevent the entry of wastes in violation of this ordinance.

### 3.4 Tenant Responsibility

Any person who shall occupy an industrial user's premises as a tenant under any rental or lease agreement shall be jointly and severally responsible for compliance with the provisions of this Ordinance in the same manner as the Owner.

### 3.5 Separation of Domestic and Industrial Wastestreams

All domestic wastewaters from rest rooms, showers, drinking fountains, etc. unless specifically included as part of a categorical pretreatment standard, shall be kept separate from all industrial wastewaters until the industrial wastewaters have passed through a required pretreatment system and the industrial user's monitoring facility. When directed to do so by the Superintendent, industrial users must separate existing domestic wastestreams.

### 3.6 Hauled Wastewater

Septic tank waste (septage) will be accepted into the municipal wastewater system at a designated receiving structure within the POTW area, and at such times as are established by the Superintendent, provided such wastes do not contain toxic or hazardous pollutants, and provided such discharge does not violate any other requirements established by the City. Permits for individual vehicles to use such facilities shall be issued by the Superintendent.

- (1) All waste haulers, regardless of the origin of the hauled wastes, shall be considered "industrial users" for the purposes of this ordinance and required to apply for a waste hauler permit.
- (2) The discharge of domestic septage wastes from commercial or industrial sites requires prior approval of the Superintendent. The Superintendent shall have authority to prohibit the disposal of such wastes, if such disposal would interfere with the treatment plant operation.
- (3) Fees for the discharge of septage will be established as part of the user fee system as authorized in Section 14.

### 3.7 Vandalism

No person shall maliciously, willfully or negligently break, damage, destroy, uncover, deface, tamper with or prevent access to any structure,

appurtenance or equipment, or other part of the municipal wastewater system. Any person found in violation of this requirement shall be subject to the sanctions set out in Section 10, below.

### 3.8 Grease Interceptors

The City may inspect grease interceptors (i.e., traps, oil/water separators) to insure proper installation and maintenance. Users may be required to reimburse the City for cleaning and additional maintenance of public sewer mains due to discharge of grease caused by noncompliance with these rules and regulations.

- (1) In the event the City, during routine line maintenance, discovers an accumulation of grease in a public line sufficient to restrict the normal flow of waste, upstream IUs shall be inspected. When the City determines which user was responsible for the grease or oil discharge, the user may be required to cease discharge of the prohibited waste, install an interceptor, maintain the interceptor, and may be charged for the cost of cleaning the line.

## **SECTION 4 - WASTEWATER PERMIT ELIGIBILITY**

### 4.1 Wastewater Survey

When requested by the Superintendent all industrial users must submit information on the nature and characteristics of their wastewater by completing a wastewater survey prior to commencing their discharge. The Superintendent is authorized to prepare a form for this purpose and may periodically require industrial users to update the survey. Failure to complete this survey shall be considered a violation of this ordinance and subjects the industrial user to the sanctions set out in Section 10.

### 4.2 Wastewater Permit Requirement

It shall be unlawful for significant industrial users to discharge wastewater into the City's sanitary sewer system without first obtaining a wastewater permit from the Superintendent. Any violation of the terms and conditions of wastewater permit shall be deemed a violation of this Ordinance and subjects the industrial user to the sanctions set out in Section 10. Obtaining a wastewater permit does not relieve a permittee of its obligation to obtain other permits required by Federal, State or local law.

The Superintendent may require other non-domestic users, including liquid waste haulers, to obtain waste water permits as necessary to carry out the purposes of this chapter.

#### 4.3 Permitting Existing Connections

Any significant industrial user, without a current industrial discharge permit, which discharges industrial waste into the municipal wastewater system prior to the effective date of this ordinance and who wishes to continue such discharges in the future, shall, within ninety (90) days after said date, apply to the City for a wastewater permit in accordance with Section 4.6 below, and shall not cause or allow discharges to the system to continue after one hundred eighty (180) days of the effective date of this Ordinance except in accordance with a permit issued by the Superintendent.

#### 4.4 Permitting New Connections

Any significant industrial user proposing to begin or recommence discharging industrial wastes into the municipal wastewater system must obtain a wastewater permit prior to beginning or recommencing such discharge. An application for this permit must be filed at least ninety (90) days prior to the anticipated start up date.

#### 4.5 Permitting Extra-Jurisdictional Industrial Users

Any existing significant industrial user located beyond the City limits shall submit a permit application, in accordance with Section 4.6 below, within ninety (90) days of the effective date of this Ordinance. New significant industrial users located beyond the City limits shall submit such applications to the Superintendent ninety (90) days prior to any proposed discharge into the municipal system. Upon review of such application, the Superintendent may enter into a contract with the industrial user which requires the industrial user to subject itself to and abide by this Chapter, including all permitting, compliance monitoring, reporting, and enforcement provisions herein. Alternately, the Superintendent may enter into an agreement with the neighboring jurisdiction in which the significant industrial user is located to provide for the implementation and enforcement of pretreatment program requirements against said user.

#### 4.6 Wastewater Permit Application Contents

In order to be considered for a wastewater permit, all industrial users required to have a permit must submit the following information on an application form approved by the Superintendent.

- 
- (1) Name, mailing address, and location if different from the mailing address);
  - (2) Environmental control permits held by or for the facility;
  - (3) Standard Industrial Classification (SIC) codes for pretreatment the industry as a whole and any processes for which categorical pretreatment standards have been promulgated.
  - (4) Description of activities, facilities, and plant processes on the premises, including a list of all raw materials and chemicals used at the facility which are or could accidentally or intentionally be discharged to the municipal system;
  - (5) Number and type of employees, and hours of operation, and proposed or actual hours of operation of pretreatment system.
  - (6) Each product by type, amount, process or processes and rate of production;
  - (7) Type and amount of raw materials process (average and maximum per day);
  - (8) The site plans, floor plans and mechanical and plumbing plans and details to show all sewers, floor drains, and appurtenances by size, location and elevation, and all points of discharge.
  - (9) Time and duration of the discharge.
  - (10) Measured average daily and maximum daily flow, in gallons per day, to the municipal system from regulated process streams and other streams as necessary to use the combined wastestream formula in 40 CFR 403.6(e);
  - (11) Daily maximum, daily average, and monthly average wastewater flow rates, including daily, monthly, and seasonable variations, if any;
  - (12) Wastewater constituents and characteristics, including any pollutants in the discharge which are limited by Federal, State, and local standards, pretreatment standards applicable to each regulated process; and nature and concentration (or mass if pretreatment standard requires) of regulated pollutant in each regulated process (daily maximum and average concentration or mass when required by a pretreatment standard) Sampling and analysis shall be undertaken in accordance with 40 CFR Part 136; and certified that sampling is representative of normal work cycles

and expected pollutant discharges.

- (13) A statement reviewed by an authorized representative of the user and certified to by a qualified professional indicating whether or not the pretreatment standards are being met on a consistent basis, and if not, what additional pretreatment is necessary.
- (14) If additional pretreatment and/or O&M will be required to meet the standards, then the industrial user shall indicate the shortest time schedule necessary to accomplish installation or adoption of such additional treatment and/or O&M. The completion date in this schedule shall not be longer than the compliance date established for the applicable pretreatment standard. The following conditions apply to this schedule;
  - A. The schedule shall contain progress increments in the form of dates for the commencement and completion of major events leading to the construction and operation of additional pretreatment required for the user to meet the applicable pretreatment standards (such events include hiring an engineer, completing preliminary plans, completing final plans, executing contracts for major components, commencing construction, completing construction, beginning operation, and conducting routine operation). No increment referred to above shall exceed nine (9) months nor shall the total compliance period exceed thirty-six (36) months.
  - B. No later than 14 days following each date in the schedule and the final date for compliance, the user shall submit a progress report to the Superintendent including, at a minimum, whether or not it complied with the increment of progress, the reason for any delay, and if appropriate, the steps being taken by the user to return to the established schedule. In no event shall more than nine (9) months elapse between such progress reports to the Superintendent.
- (15) Any other information as may be deemed by the Superintendent to be necessary to evaluate the permit application.
- (16) A new source discharger may provide estimates as to the character and volume of pollutants described in 4.6 (10)(11)(12). Incomplete or inaccurate applications shall not be processed and shall be returned to the industrial user for revision.



#### 4.7 Application Signatories and Certification

All permit applications and industrial user reports must contain the following certification statement and be signed by an authorized representative of the industrial user.

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

#### 4.8 Wastewater Permit Decisions

The Superintendent will evaluate the data furnished by the industrial user and may require additional information. Within sixty (60) days of receipt of a complete permit application, the Superintendent will determine whether or not to issue a wastewater permit. If no determination is made within this time period, the application will be deemed denied.

If any waters or wastes are discharged, or area proposed to be discharged to the public sewers, which waters contain the substances or possess the characteristics enumerated in Section 2, and which in the judgment of the Superintendent, may have a deleterious effect upon the municipal treatment system, processes, equipment, or receiving waters, or which otherwise create a hazard to life or constitute a public nuisance, the Superintendent may take any of the following actions:

- (1) Reject the wastes,
- (2) Require pretreatment to an acceptable condition for discharge to the public sewers,
- (3) Require control over the quantities and rates of discharge, and/or
- (4) Require payment to cover the added cost of handling and treating the wastes not covered by existing taxes or sewer charges.

### **SECTION 5 - WASTEWATER PERMIT ISSUANCE PROCESS**

#### 5.1 Wastewater Permit Duration

Permits shall be issued for a specific time period, not to exceed five (5) years. A permit may be issued for a period less than five (5) years, at the discretion of the Superintendent. Each permit shall indicate a specific date upon which it will expire.

## 5.2 Wastewater Permit Contents

Wastewater permit shall include such conditions as are reasonably deemed necessary by the Superintendent to prevent pass through or interference and to implement the objectives of this Ordinance.

(1) Wastewater Permits shall contain the following conditions:

- A. A statement that indicates permit duration, which in no event shall exceed 5 years.
- B. A statement that the permit is nontransferable without prior notification to and approval from the City and provisions for furnishing the new owner or operator with a copy of the existing permit.
- C. Effluent limits applicable to the user based on applicable standards in Federal, State and local law.
- D. Self monitoring, sampling, reporting, notification and record keeping requirements. These requirements shall include an identification of pollutants to be monitored, sampling location, sampling frequency, and sample type based on Federal, State and local law.
- E. Statement of applicable civil and criminal penalties for violation of pretreatment standards and requirements, and any applicable compliance schedule. Such schedules may not extend the compliance date beyond applicable federal deadlines.

(2) Permits may contain, but need not be limited to, the following:

- A. Limits on the average and/or maximum rate of discharge, time of discharge, and/or requirements for flow regulations and equalization.
- B. Limits on the instantaneous, daily and monthly average and/or maximum concentration, mass, or other measure of identified wastewater pollutants or properties.

- 
- C. Requirements for the installation of pretreatment technology or construction of appropriate containment devices, etc., designed to reduce, eliminate, or prevent the introduction of pollutants into the treatment works.
  - D. Development and implementation of spill control plans or other special conditions including management practices necessary to adequately prevent accidental, unanticipated, or routine discharges.
  - E. Development and implementation of waste minimization plans to reduce the amount of pollutants discharged to the municipal wastewater system.
  - F. The unit charge or schedule of user charges and fees for the management of the wastewater discharged to the system.
  - G. Requirements for installation and maintenance of inspection and sampling facilities and equipment.
  - H. Specifications for monitoring programs which may include sampling locations, frequency of sampling, number, types, and standards for tests, and reporting schedules.
  - I. Requirements for immediate reporting of any instance of noncompliance and for automatic re-sampling and reporting within thirty (30) days where self-monitoring indicates a violation(s).
  - J. Compliance schedules for meeting pretreatment standards and requirements.
  - K. Requirements for submission of periodic self- monitoring or special notification reports.
  - L. Requirements for maintaining and retaining plant records relating to wastewater discharge as specified in Section 6.12 and affording the Superintendent, or his representatives, access thereto.
  - M. Requirements for prior notification and approval by the Superintendent of any new introduction of wastewater pollutants or of any change in the volume or character of the wastewater prior to introduction in the system.
  - N. Requirements for the prior notification and approval by the

Superintendent of any change in the manufacturing and/or pretreatment process used by the permittee.

- O. Requirements for immediate notification of excessive, accidental, or slug discharges, or any discharge which could cause any problems to the system.
- P. A statement that compliance with permit does not relieve the permittee of responsibility for compliance with all applicable federal and state pretreatment standards, including those which become effective during the term of the permit.
- Q. Other conditions as deemed appropriate by the Superintendent to ensure compliance with this ordinance, and state and federal laws, rules, and regulations; the term of the permit.

### 5.3 Wastewater Permit Appeals

Any person including the industrial user may petition the Superintendent to reconsider the terms of the permit within ten (10) days of the issuance of the final permit.

- (1) Failure to submit a timely petition for review shall be deemed to be a waiver of the administrative appeal.
- (2) In its petition, the appealing party must indicate the permit provisions objected to, the reasons for this objection, and the alternative conditions, if any, it seeks to place in the permit.
- (3) The effectiveness of the permit shall not be stayed pending the appeal.
- (4) If the Superintendent fails to act within fifteen (15) days, the request for reconsideration shall be deemed denied.
- (5) Aggrieved parties seeking judicial review of the final administrative permit decision must do so by petitioning for a Writ of Review in the Marion County Circuit Court, pursuant to ORS Chapter 34, within sixty (60) days of the final administrative decision.

### 5.4 Wastewater Permit Modifications

The Superintendent may modify the permit for good cause including, but not limited to, the following:

- 
- (1) To incorporate any new or revised federal, state, or local pretreatment standards or requirements.
  - (2) To address significant alterations or additions to the industrial user's operation, processes, or wastewater volume or character since the time of permit issuance.
  - (3) A change in the municipal wastewater system that requires either a temporary or permanent reduction or elimination of the authorized discharge.
  - (4) Information indicating that the permitted discharge poses a threat to the City's municipal wastewater system, City personnel, or the receiving waters.
  - (5) Violation of any terms or conditions of the wastewater permit.
  - (6) Misrepresentation or failure to disclose fully all relevant facts in the permit application or in any required reporting.
  - (7) Revisions of or a grant of variance from categorical pretreatment standards pursuant to 40 CFR 403.13.
  - (8) To correct typographical or other errors in the permit.
  - (9) To reflect a transfer of the facility ownership and/or operation to a new owner/operator.

The filing of a request by the permittee for a permit modification does not stay any permit condition.

#### 5.5 Wastewater Permit Transfer

Permits may be reassigned or transferred to a new owner and/or operator with prior approval of the Superintendent if the permittee gives at least thirty (30) days advance notice to the Superintendent. The notice must include provision for furnishing the new owner or operator with a copy of the existing permit and a written certification by the new owner which:

- (1) States that the new owner has no immediate intent to change the facility's operations and processes.
- (2) Identifies the specific date on which the transfer is to occur.
- (3) Acknowledges full responsibility for complying with the existing permit.

Failure to provide advance notice of a transfer renders the wastewater permit terminated.

#### 5.6 Wastewater Permit Revocation

The Superintendent may revoke a wastewater discharge permit for good cause, including, but not limited to, the following reasons:

- (1) Failure to notify the City of significant changes to the wastewater prior to the changed discharge;
- (2) Falsifying self-monitoring reports;
- (3) Tampering with monitoring equipment;
- (4) Refusing to allow the City timely access to the facility premises and records;
- (5) Failure to meet effluent limitations;
- (6) Failure to pay administrative penalties;
- (7) Failure to pay sewer charges;
- (8) Failure to meet compliance schedules;
- (9) Failure to complete a wastewater survey;
- (10) Failure to provide advance notice of the transfer of a permitted facility;
- (11) Violations of any pretreatment standard or requirement or any terms of the permit or the ordinance.
- (12) Failure to provide prior notification to the Superintendent of changed conditions pursuant to Section 6.5 of this Ordinance.
- (13) Misrepresentation of, or failure to fully disclose all relevant facts in the wastewater discharge permit application.
- (14) Failure to complete a wastewater discharge permit application.

Wastewater discharge permits shall be voidable upon cessation of operations, or transfer of business ownership. All wastewater discharge permits issued to a particular user are void upon the issuance of a new wastewater permit to that user.

### 5.7 Wastewater Permit Reissuance

A significant industrial user shall apply for permit reissuance by submitting a complete permit application in accordance with Section 4.6 a minimum of ninety (90) days prior to the expiration of the user's existing permit.

### 5.8 Regulation of Wastewater Received from other Jurisdictions

If another municipality, or user(s) locate within another municipality or jurisdiction, contribute(s) wastewater to the municipal wastewater system, the Superintendent shall enter into an intermunicipal or interjurisdictional agreement with the contributing municipality or jurisdiction, or enter into a contract with the user(s), in accordance with requirements specified in the City's pretreatment procedures.

## SECTION 6 - REPORTING REQUIREMENTS

### 6.1 Baseline Monitoring Reports

Within 180 days after the effective date of a categorical pretreatment standard, or 180 days after the final administrative decision on a category determination under 40 CFR 403.6(a)(4), whichever is later, existing significant industrial users subject to such categorical pretreatment standards and currently discharging to or scheduled to discharge to the municipal system shall be required to submit to the City a report which contains the information listed in paragraph 6.1(1), below. At least ninety (90) days prior to commencement of their discharge, new sources, including existing users which have changed their operation or processes so as to become new sources, shall be required to submit to the City a report which contains the information listed in paragraph 6.1(1). A new source shall also be required to report the method it intends to use to meet applicable pretreatment standards. A new source shall also give estimates of its anticipated flow and quantity of pollutants discharged.

- (1) The information required by this section includes:
  - A. Identifying Information. The user shall submit the name and address of the facility including the name of the operator and owners;
  - B. Permits. The user shall submit a list of any environmental controls permits held by or for the facility;
  - C. Description of Operation. The user shall submit a brief description of the nature, average rate of production, and

standard industrial classifications of the operation(s) carried out by such industrial user. This description should include a schematic process diagram which indicates points of discharge to the system from the regulated processes.

- D. Flow Measurement. The user shall submit information showing the measured average daily and maximum daily flow, in gallons per day, to the system from regulated process streams and other streams as necessary to allow use of the combined wastewater formula set out in 40 CFR 403.6 (e).
- E. Measurement of Pollutant.
- (i) The industrial user shall identify the categorical pretreatment standards applicable to each regulated process;
  - (ii) In addition, the industrial user shall submit the results of sampling and analysis identifying the nature and concentration (and/or mass, where required by federal, state or City standards or the Superintendent) of regulated pollutants in the discharge from each regulated process. Instantaneous, daily maximum and long term average concentrations (or mass, where required by federal, state or City standards or the Superintendent) shall be reported. The sample shall be representative of daily operations and shall be performed in accordance with procedures set out in 40 CFR Part 136.
  - (iii) A minimum of four (4) grab samples must be used for pH, cyanide, total phenols, oil and grease, sulfide, and volatile organic. All other pollutants shall be measured by composite samples obtained through flow proportional sampling technique. If flow proportional composite sampling is infeasible, samples may be obtained through time proportional sampling techniques or through four (4) grab samples if the user proves such a sample will be representative of the discharge.
- F. Special Certification. A statement, reviewed by an authorized representative of the industrial user and certified to by a qualified professional, indicating whether pretreatment standards are being met on a consistent basis, and, if not, whether additional operations and maintenance



(O&M) and/or additional pretreatment is required in order to meet the pretreatment standards and requirements; and

- G. Compliance Schedule. If additional pretreatment and/or O&M will be required to meet the pretreatment standards; the shortest schedule by which the industrial user will provide such additional pretreatment and/or O&M. The completion date in this schedule not be later than the compliance date established for the applicable pretreatment standard. A compliance schedule pursuant to this section must meet the requirements set out in Section 4.6 (14) of this Ordinance.
- H. All baseline monitoring reports must be signed and certified in accordance with Section 4.7.
- I. Where reports containing this information already have been submitted to the control authority, the industrial user will not be required to submit this information again.

## 6.2 Compliance Schedule Progress Reports

The following conditions shall apply to the compliance schedule required by Section 6.1(G) of this ordinance:

- A. The schedule shall contain progress increments in the form of dates for the commencement and completion of major events leading to the construction and operation of additional pretreatment required for the user to meet the applicable pretreatment standards (such events include, but are not limited to, hiring an engineer, commencing and completing construction, and beginning and conducting routine operation).
- B. No increment referred to above shall exceed nine (9) months.
- C. The user shall submit a progress report to the Superintendent no later than fourteen (14) days following each date in the schedule and the final date of compliance including, as a minimum, whether or not it complied with the increment of progress, the reason for any delay, and, if appropriate, the steps being taken by the user to return to the established schedule.
- D. In no event shall more than nine (9) months lapse between such progress reports to the Superintendent.

## 6.3 Reports on Compliance with Categorical Pretreatment Standard Deadline

Within ninety (90) days following the date for final compliance with applicable categorical pretreatment standards, or in the case of a new source, following commencement of the introduction of wastewater into the municipal (POTW) wastewater system, any user subject to such pretreatment standards and requirements shall submit to the Superintendent a report containing the information described in section 6.1 (1) D-F of this ordinance. For users subject to equivalent mass or concentration limits established in accordance with the procedures in 40 CFR 403.6(c), this report shall contain a reasonable measure of the user's long term production rate. For all other industrial users subject to categorical pretreatment standards expressed in terms of allowable pollutant discharge per unit of production (or other measure of operation), this report shall include the user's actual production during the appropriate sampling period. All compliance reports must be signed and certified in accordance with Section 4.7 and 6.1(F).

#### 6.4 Periodic Compliance Reports

Any significant industrial users subject to a pretreatment standard shall, at a frequency determined by the Superintendent but in no case less than year, submit a report indicating the nature and concentration of pollutants in the discharge which are limited to such pretreatment standards and the measured or estimated average and maximum daily flows for the reporting period. All periodic compliance reports must be signed and certified in accordance with Section 4.7.

- (1) All wastewater samples must be representative of industrial user's discharge. Wastewater monitoring and flow measurement facilities shall be properly operated, kept clean, and maintained in good working order at all times. The failure of an industrial user to keep its monitoring facility in good working order shall not be grounds for the industrial user to claim that sample results are unrepresentative of its discharge.
- (2) In the event an industrial user's monitoring results indicate a violation has occurred, the industrial user shall immediately (within 24 hours of becoming aware of the violation) notify the Superintendent and shall re-sample its discharge. The industrial user shall report the results of the repeated sampling within thirty (30) days of discovering the first violation.

#### 6.5 Report of Changed Conditions

Each industrial user shall notify the Superintendent of any planned significant changes to the industrial user's operations or system which

might alter the nature, quality or volume of its wastewater at least 30 days before the change. Notification of any changes in the listed or characteristic hazardous wastes for which the user has submitted initial notification under 40 CFR 403.12 (p) must also be reported.

- (1) The Superintendent may require the industrial user to submit such information as may be deemed necessary to evaluate the changed condition, including the submission of a waste water permit application under Section 4.6, if necessary.
- (2) The Superintendent may issue a wastewater permit under Section 4.8 or modify an existing waste water permit under Section 5.4.
- (3) No industrial user shall implement the planned changed condition(s) until and unless the Superintendent has responded to the industrial user's notice.
- (4) For purposes of this requirement, flow or loading increases of twenty (20%) or greater and the discharge of any previously unreported pollutant shall be deemed significant.

#### 6.6 Reports of Potential Problems

- (1) In the case of an accidental or other discharge which may cause potential problems for the municipal wastewater system, it is the responsibility of the user to immediately telephone and notify the City POTW Superintendent of the incident. This notification shall include the location of discharge, type of waste, concentration and volume, if known, and corrective actions taken by the user.
- (2) Within five (5) days following an accidental discharge, the user shall, unless waived by the Superintendent, submit a detailed written report describing the cause(s) of the discharge and the measures to be taken by the user to prevent similar future occurrences. Such notification shall not relieve the user of any expense, loss, damage, or other liability which may be incurred as a result of damage to the system, natural resources, or any other damage to person or property; nor shall such notification relieve the user of any fines, civil penalties, or other liability which may be imposed by this Ordinance.
- (3) Failure to notify the City of potential problem discharges shall be deemed a separate violation of this Ordinance.
- (4) A notice shall be permanently posted on the user's bulletin board or other prominent place advising employees whom to call in the

event of a discharge described in paragraph (1), above. Employers shall ensure that all employees who may cause or suffer such a discharge to occur are advised of the emergency notification procedure.

#### 6.7 Reports from Unpermitted Users

All industrial users not subject to categorical pretreatment standards and not required to obtain a wastewater permit shall provide appropriate reports to the City as the Superintendent may require.

#### 6.8 Sample Collection

Wastewater samples collected for purposes of determining industrial user compliance with pretreatment standards and requirements shall be obtained using flow proportional composite collection techniques. In the event flow proportional sampling is infeasible, the Superintendent may authorize the use of time proportional sampling. Samples for oil and grease, temperature, pH, cyanide, phenols, toxicity, sulfides, and volatile organic chemicals shall be obtained using grab collection techniques. All sampling shall be certified that such sampling is representative of normal work cycles and expected pollutant discharges to the POTW.

#### 6.9 Analytical Requirements

All pollutant analyses, including sampling techniques, to be submitted as part of a permit application or report shall be performed in accordance with the techniques prescribed in 40 CFR Part 136 or, if 40 CFR part 136 does not contain sampling or analytical techniques for the pollutant in question, in accordance with procedures approved by the EPA, DEQ and the City.

#### 6.10 Monitoring Charges

The City Engineer may recover the City's expenses incurred in collecting and analyzing samples of the industrial user's discharge by adding the City's expenses to the industrial user's sewer charges.

#### 6.11 Timing

Written reports shall be deemed to have been transmitted at the time of deposit, postage prepaid, into a mail facility services by the United States Postal Service.

#### 6.12 Record Keeping

Industrial users shall retain, and make available for inspection, and copying, all records and information required to be retained under 40 CFR 403.12(o). These records shall remain available for a period of at least three (3) years. This period shall be automatically extended for the duration of any litigation concerning compliance with this Ordinance, or where the industrial user has been specifically notified of a longer retention period by the Superintendent, DEQ or EPA.

#### 6.13 Reporting of Additional Monitoring

If an industrial user subject to the reporting requirements of 40 CFR 403.12(e) or (h), which requires submission of periodic compliance reports, monitors any pollutant more frequently than required by the City, using the procedures prescribed in 40 CFR Part 136, the results of this monitoring shall be included in the report, as required by 40 CFR 403.12(g)(5).

#### 6.14 Notification of Significant Production Change

An industrial user operating under a waste discharge permit incorporating equivalent mass or concentration limits calculated from a production based standard shall notify the Superintendent within two (2) business days after the user has a reasonable basis to know that the production level will significantly change within the next calendar month. Any user not notifying the Superintendent of such anticipated change shall be required to meet the mass or concentration limits in its permit that were based on the original estimate of the long term average production rate.

#### 6.15 Notification of the Discharge of Hazardous Waste

- (1) Any user who commences the discharge of hazardous waste shall notify the City, the EPA Regional Waste Management Division Director, of any discharge into the municipal wastewater system of a substance which, if otherwise disposed of, would be a hazardous waste under 40 CFR Part 261. Such notification must include the name of the hazardous waste as set forth in 40 CFR Part 261, the EPA hazardous waste number, and the type of discharge (continuous, batch, or other). If the user discharges more than one hundred (100) kilograms of such waste per calendar month to the municipal wastewater system, the notification also shall contain the following information to the extent such information is known and readily available to the user: an identification of the hazardous constituents contained in the wastes, an estimation of the mass and concentration of such constituents in the wastestream discharged during that calendar month, and an estimation of the mass of constituents in the wastestream expected to be discharged during the following twelve (12) months. All notifications must take place

no later than one hundred and eighty (180) days after the discharge commences. Any notification under this paragraph need be submitted only once for each hazardous waste discharged. However, notifications of changed conditions must be submitted under Section 6.5 of this Ordinance. The notification requirement in this Section does not apply to pollutants already reported by industrial users subject to categorical pretreatment standards under the self-monitoring requirements of Sections 6.1, 6.3, and 6.4 of this Ordinance.

- (2) Dischargers are exempt from the requirements of this paragraph (1), above, during a calendar month in which they discharge no more than fifteen (15) kilograms of hazardous waste, unless the wastes are acute hazardous waste as specified in 40 CFR 261.30 (d) and 261.33 (e). Discharge of more than fifteen (15) kilograms of non-acute hazardous waste in a calendar month, or of any quantity of acute hazardous waste as specified in 40 CFR 261.30 (d) and 261.33 (e), requires a one - time notification. Subsequent months during which the user discharges more than such quantities of any hazardous waste do not require additional notification.
- 3) In the case of any new regulations under Section 3001 of the RCRA identifying additional characteristics of hazardous waste or listing any additional substance as a hazardous waste, the user must notify the Director, the EPA Regional Waste Management Division Director, and DEQ Solid and Hazardous Waste Division Director, of the discharge of such substance within ninety (90) days of the effective date of such regulations.
- (4) In the case of any notification made under this Section, the user shall certify that it has a program in place to reduce the volume and toxicity of hazardous wastes generated to the degree it has determined to be economically practical.
- (5) This provision does not create a right to discharge any substance not otherwise permitted to be discharged by this Ordinance, a permit issued hereunder, or any applicable Federal or State law.

## SECTION 7 - COMPLIANCE

### 7.1 Inspection and Sampling

The City shall have the right to enter the facilities of any industrial user to enforce the provisions of this ordinance or any wastewater permits or orders issued hereunder. Industrial users shall allow the Superintendent or

his representatives ready access to all parts of their premises for the purposes of inspection, sampling, records examination and copying, and the performance of any additional duties.

- (1) Where a user has security measures in force which require proper identification and clearance before entry into their premises, the industrial user shall make necessary arrangements with its security guards so that, upon presentation of suitable identification, personnel from the City, State, and US EPA will be permitted to enter, without delay, for the purposes of performing their official duties.
- (2) The City, State, and US EPA shall have the right to set up or require installation of, on the industrial user's property, such devices as are necessary to conduct sampling, and/or metering of the user's operations.
- (3) The City may require the industrial user to install monitoring equipment, as necessary. The facility's sampling and monitoring equipment shall be maintained at all times in a safe and proper operating condition by the industrial user at the industrial user's expense. All devices used to measure wastewater flow and quality shall be calibrated periodically to ensure their accuracy.
- (4) Any temporary or permanent obstruction to safe and easy access to the industrial facility to be inspected and/or sampled shall be promptly removed by the industrial user at the written or oral request of the Superintendent and shall not be replaced. The costs of clearing such access shall be borne by the industrial user.
- (5) Unreasonable delays in allowing City personnel access to the industrial user's premises shall be a violation of this Ordinance.

## 7.2 Search Warrants

If the Superintendent has been refused access to a building, structure or property or any part thereof, and if the Superintendent has probable cause to believe that there may be a violation to this Ordinance, or that there is a need to inspect as part of a routine inspection program of the city designed to protect the overall public health, safety and welfare of the community, the Superintendent shall contact the City Attorney who may then apply for an administrative search warrant from a court of competent jurisdiction.

## SECTION 8 - CONFIDENTIAL INFORMATION

Information and data on an industrial user obtained from reports, questionnaires, permit applications, permits, and monitoring programs, and from City inspections and sampling activities shall be available to the public without restriction unless the industrial user specifically requests and is able to demonstrate to the satisfaction of the City that the release of such information would divulge information, processes or methods of production entitled to protection as trade secrets under applicable State laws.

(1) Wastewater constituents and characteristics and other "effluent data" as defined by 40 CFR 2.302 shall not be recognized as confidential information and shall be available to the public without restriction.

(2) When requested and demonstrated by the industrial user furnishing a report that such information should be held confidential, the portions of a report which might disclose trade secrets or secret processes shall not be made available for inspection by the public but shall be made available immediately upon request to governmental agencies for uses related to this Ordinance, the National Pollutant Discharge Elimination System (NPDES) program, and in enforcement proceedings involving the person furnishing the report.

## **SECTION 9 - PUBLICATION OF USERS IN SIGNIFICANT NONCOMPLIANCE**

The City shall annually publish, in the largest daily newspaper circulated in the area where the municipal wastewater system is located, a list of the industrial users which, during the previous 12 months, were in significant noncompliance with applicable pretreatment standards and requirements. The term significant noncompliance shall mean:

- (1) Sixty six percent (66%) or more of wastewater measurements taken during a 6 month period exceed the discharge limit for the same pollutant by any amount.
- (2) Thirty three percent (33%) or more of wastewater measurements taken during a 6 month period equal or exceed the product of the daily maximum limit or the average limit multiplied by the applicable criteria (1.4 for BOD, TSS, fats, oils and grease, and 1.2 for all other pollutants except pH).
- (3) Any other discharge violation that the City believes has caused, alone or in combination with other discharges, interference or pass through (including endangering the health of City personnel or the general public).
- (4) Any discharge of pollutants that has caused imminent



endangerment to the public or to the environment, or has resulted in the City's exercise of its emergency authority to halt or prevent such a discharge.

- (5) Failure to meet, within 90 days of the scheduled date, a compliance schedule milestone contained in a permit or enforcement order for starting construction, completing construction, or attaining final compliance.
- (6) Failure to provide, within 30 days after the due date, any required reports, including baseline monitoring reports, 90 day compliance reports, periodic self monitoring reports, and reports on compliance with compliance schedules.
- (7) Failure to accurately report noncompliance.
- (8) Any other violation(s) which the City has reason to believe is significant.

## SECTION 10 - ADMINISTRATIVE ENFORCEMENT REMEDIES

### 10.1 Industrial User Violation Process

Whenever the Superintendent determines that a violation of this Ordinance, any permit issued hereunder, or any order issued by the City pursuant to this Ordinance, has occurred or is taking place, it may initiate enforcement action as provided in this Section. In addition, any enforcement action or remedy provided in state or federal law may be employed. If the Superintendent believes a violation has occurred or is occurring, a representative of the City shall make a reasonable effort to notify the user of the violation. All violations including the first violation shall receive a written Notice of Violation, and may also incur a monetary penalty.

- (1) All written Notices of Violations shall describe the violation and any potential penalty (monetary or additional pretreatment). The written notice may further require that a response to the violation be submitted to the City within a ten (10) day time period.
- (2) If a written Notice of Violation requires submittal of a response, the response shall include an explanation of the cause of the violation, a plan for its satisfactory correction and prevention of future such violations, and specific corrective or preventive actions. Submission of this plan in no way relieves the user of liability for any violations occurring before or after receipt of the Notice of violations occurring before or after receipt of the Notice of Violation. Nothing

in this section shall limit the authority of the Superintendent to initiate emergency action or other enforcement action without first issuing a Notice of Violation.

## 10.2 Violation

- (1) A violation of limitations established under this Ordinance, any applicable federal, state or pretreatment standards, or specific requirements of a discharge permit shall constitute a violation of this Ordinance and shall be cause for enforcement action by the City, including but not limited to levying of administrative penalties as described in Section 10 regardless of the intent of the user. Each day of a continuing violation shall constitute a separate offense for purposes of computing the applicable penalty.
- (2) Whenever the Superintendent finds that any IU has violated or is violating this Ordinance, a wastewater permit or order issued hereunder, or any other pretreatment requirement, the Superintendent shall cause to be served upon said IU a written Notice of Violation. The Notice of Violation shall be delivered to the user's premises or be sent by certified mail to the address of the permit holder on record with the City.

## 10.3 Violation of Permit Parameters

- (1) For the maximum daily allowable concentration, if the concentration of any single sample (whether grab or a sample within a series) exceed the limitations, a violation will have occurred.
- (2) For the monthly average allowable concentration, if the average of all sample(s) (grab or composite) taken exceeds the limitation, a violation will have occurred. One sample collected may constitute a monthly average violation.

## 10.4 Additional Violation Parameters

A violation of this Ordinance shall also be deemed to occur:

- (1) For noncompliance with any special reporting requirements established by permit, written request of the City, or as specified by general federal pretreatment standards (40 CFR 403.12).
- (2) Pollutants prohibited by this Ordinance are discharged into the system.

- (3) Failure to apply for and obtain a permit prior to discharge of industrial wastewater into the system.

10.5 IU Notice to City of Violation

If sampling performed by an industrial user indicates a violation, the industrial user shall notify the Superintendent within 24 hours of becoming aware of the violation. The user shall also resample and report the results within 30 days of becoming aware of violation pursuant to 40 CFR 403.12(g)(2). Resampling must continue until it is evident that the discharge is within compliance.

10.6 Consent Orders

The Superintendent may enter into Consent Orders, assurance of voluntary compliance, or other similar documents establishing an agreement with an IU not in compliance with any permit parameter or provision of this Ordinance. such orders will include specific action to be taken by the IU to correct the noncompliance within a time period also specified by the order. Consent Orders shall have the same force and effect as administrative orders and upon issuance, such orders shall be judicially enforceable.

10.7 Show Cause Hearing

The Superintendent may order any user which causes or contributes to violation(s) of this Ordinance, wastewater permits or order issued hereunder or any other pretreatment requirement, to appear before the Superintendent and show cause why a proposed enforcement action should not be taken. Notice shall be served on the IU specifying the time and place for the hearing, the proposed enforcement action, the reasons for such action, and an order that the IU show cause why this proposed enforcement action should not be taken.

The notice of the hearing shall be served personally or by registered mail (return receipt requested) at least ten (10) days prior to the hearing. Such notice may be served on any authorized representative of the IU. Whether or not the IU appears at the hearing, the Superintendent may pursue enforcement action following the hearing date.

10.8 Compliance Orders

When the Superintendent finds that an IU has violated or continues to violate the Ordinance, permits or orders issued hereunder, or any other pretreatment requirement, an order may be issued to the IU directing that, following a specific time period, sewer service shall be discontinued unless adequate treatment facilities, devices, or other related

appurtenances are installed and properly operated. Compliance orders may also contain such other requirements as might be reasonably necessary and appropriate to address the noncompliance, including additional self-monitoring, and management practices designed to minimize the amount of pollutants discharged to the sewer.

In addition to such Compliance Orders, the Superintendent may require additional self-monitoring for at least ninety (90) days after consistent compliance has been achieved, after which time the self-monitoring conditions in the discharge permit shall control.

#### 10.9 Cease and Desist Orders

When the Superintendent finds that an industrial user has violated or continued to violate this Ordinance, any permit or order issued hereunder, or any other pretreatment requirement, the Superintendent may issue an order to the industrial user directing it to cease and desist all such violations and directing the user to:

- (1) Immediately comply with all requirements.
- (2) Take such appropriate remedial or preventative action as may be needed to properly address a continuing or threatened violation, including halting operations and/or terminating the discharge.

#### 10.10 Administrative Fines

- (1) When the Superintendent finds that a user has violated, or continues to violate, any provision of this ordinance, a wastewater discharge permit or order issued hereunder, or any other pretreatment standard or requirement, the Superintendent may fine such user in an amount not to exceed one thousand dollars (\$1000.00). Such fines shall be assessed on a per violation, per day basis. In the case of monthly or long term average discharge limits, fines shall be assessed for each day during the period of violation.
- (2) Unpaid charges, fines and penalties shall, after thirty (30) calendar days, be assessed an additional penalty of twenty percent (20%) of the unpaid balance, and interest shall accrue thereafter at a rate of seven percent (7%) per month. A lien against the user's property will be sought for unpaid charges, fines, and penalties.
- (3) Users desiring to dispute such fines must file a written request for the Superintendent to reconsider the fine along with full payment of the Fine amount within fifteen (15) days of being notified of the fine. Where a request has merit, the Superintendent may convene a

hearing on the matter. In the event the user's appeal is successful, the payment, together with any interest accruing thereto, shall be returned to the user. The Superintendent may add the cost of preparing administrative enforcement actions, such as notices and orders, to the fine.

- (4) Issuance of an administrative fine shall not be a bar against, or a prerequisite for, taking any other action against the user.

#### 10.11 Emergency Suspensions

The Superintendent may immediately suspend an industrial user's discharge and the industrial user's wastewater discharge permit, after informal notice to the industrial user, whenever such suspension is necessary in order to stop an actual or threatened discharge which reasonably appears to present or cause an imminent or substantial endangerment to the health or welfare of persons. The Superintendent may also immediately suspend an industrial user's discharge and the industrial user's wastewater discharge permit, after notice and opportunity to respond, that threatens to interfere with the operation of the municipal waste water system, or which presents or may present an endangerment to the environment.

- (1) Any industrial user notified of a suspension of its wastewater permit shall immediately stop or eliminate its contribution. In the event of an industrial user's failure to immediately comply voluntarily with the suspension order, the Superintendent shall take such steps as deemed necessary, including immediate severance of the sewer connection, to prevent or minimize damage to the system, its receiving stream, or endangerment to any individuals. The Superintendent shall allow the industrial user to recommence its discharge when the user has demonstrated to the satisfaction of the Superintendent that the period of endangerment has passed, unless the termination proceedings set forth in Section 10.12 are initiated against the user.
- (2) An industrial user which is responsible, in whole or in part, for any discharge presenting imminent endangerment shall submit a detailed written statement describing the causes of the harmful contribution and the measures taken to prevent any future occurrence to the Superintendent prior to the date of any show cause or termination hearing under Section 10.7 and 10.12

#### 10.12 Termination of Permit

In addition to those provisions in Section 5.6 of this Ordinance, any

industrial user which violates the following conditions of this Ordinance, wastewater permits, or orders issued hereunder is subject to permit termination:

- (1) Violation of permit conditions.
- (2) Failure to accurately report the wastewater constituents and characteristics of its discharge.
- (3) Failure to report significant changes in operations or wastewater volume, constituents and characteristics prior to discharge.
- (4) Refusal of reasonable access to the user's premises for the purpose of inspection, monitoring or sampling.

Non-complying industrial users shall be notified of the proposed termination of their wastewater permit and be offered an opportunity to show cause under Section 10.7 of this Ordinance why the proposed action should not be taken.

## SECTION 11 - JUDICIAL ENFORCEMENT REMEDIES

### 11.1 Injunctive Relief.

Whenever an industrial user has violated, threatens to violate, or continues to violate the provisions of this Ordinance, permits or orders issued hereunder, or any other pretreatment requirements, the Superintendent may petition the courts for the issuance of a temporary or permanent injunction, as may be appropriate, which restrains or compels the specific performance of the wastewater permit, order, or other requirement imposed by this Ordinance on activities of the industrial user. Such other action as may be appropriate for legal and/or equitable relief may also be sought by the City. The Court shall grant an injunction without requiring a showing of a lack of an adequate remedy at law.

### 11.2 Civil Penalties

Any industrial user which has violated or continues to violate this Ordinance, any order or permit hereunder, or any other pretreatment requirement shall be liable to the City for a maximum civil penalty of one thousand dollars (\$1,000) per violation per day. In the case of a monthly or other long term average discharge limit, penalties shall accrue for each calendar day during the period of this violation.

- A. The court may award reasonable attorney fees, court costs, and other expenses associated with enforcement activities, including

sampling and monitoring expenses, and the cost of any actual damages incurred by the City.

- B. In determining the amount of civil penalty, the court shall take into account all relevant circumstances, including, but not limited to, the extent of harm caused by the violation, corrective actions by the industrial user, economic benefit to the user of noncompliance, the compliance history of the user, and any other factors as justice requires.
- C. Where appropriate, the city may accept mitigation projects in lieu of the payment of civil penalties where the project provides a valuable service to the City and the industrial user's expense in undertaking the project is at least one hundred and fifty percent (150%) of the civil penalty.

### 11.3 Criminal Prosecution

Any industrial user who willfully or negligently violates any provisions of the Ordinance, any orders or permits issued hereunder, or any other pretreatment requirement shall, upon conviction, be guilty of a misdemeanor, punishable by a fine of not more than one thousand dollars (\$1,000) per violation per day or imprisonment for not more than (1) one year, or both.

- (1) Any industrial user who knowingly makes any false statement, representations or certification in any application, record, report, plan or other documentation filed or required to be maintained pursuant to the Ordinance or wastewater permit, or who falsifies, tampers with or knowingly renders inaccurate any monitoring device or method required under this Ordinance shall, upon conviction, be punished by a fine of not more than one thousand dollars (\$1,000) per violation per day or imprisonment for not more than (1) one year, or both.
- (2) In the event of a second conviction, the user shall be punishable by a fine not to exceed three thousand dollars (\$3,000) per violation per day or imprisonment for not more than (3) three years, or both.

### 11.4 Remedies Nonexclusive

- (1) A City Enforcement Response Plan will be developed by the Superintendent in accordance with 40 CFR section 403.8 and submitted to the City Engineer for approval and certification. The Superintendent will implement the plan after receiving approval

from the City Engineer.

- (2) The remedies provided for in this ordinance are not exclusive. The Superintendent may take any, all, or any combination of these actions against a noncompliant user. Enforcement of pretreatment violations will be in accordance with the City of Woodburn's Enforcement Response Plan. However the Superintendent may take other action against any user when the circumstances warrant. Further, the Superintendent is empowered to take more than one enforcement action against any noncompliant user.

## SECTION 12 - SUPPLEMENTAL ENFORCEMENT ACTIONS

### 12.1 Performance Bonds

The Superintendent may decline to reissue a permit to any industrial user which has failed to comply with the provisions of this Ordinance, any orders, or a previous permit issued hereunder unless such user first files a satisfactory bond, payable to the City, in a sum not to exceed a value determined by the Superintendent to be necessary to achieve consistent compliance.

### 12.2 Liability Insurance

The Superintendent may decline to reissue a permit to any industrial user which has failed to comply with the provisions of this Ordinance, any orders, or a previous permit issued hereunder, unless the industrial user first submits proof that it has obtained financial assurance sufficient to restore or repair damage to the municipal wastewater system caused by its discharge.

### 12.3 Water Supply Severance

When an industrial user has violated the provisions of this Ordinance, orders, or permits issued hereunder, water service to the industrial user may be severed by the City Engineer and service will only recommence, at the user's expense, after it has satisfactorily demonstrated its ability to comply.

### 12.4 Public Nuisance

Any violation of the prohibitions or effluent limitations of this Ordinance, permits, or orders issued hereunder is hereby declared a public nuisance and shall be corrected or abated as directed by the City Engineer or his designee. Any person(s) creating a public nuisance shall be subject to the provisions of the City Ordinance 1616 governing such nuisance,



including reimbursing the City for any costs incurred in removing, abating or remedying said nuisance.

### 12.5 Contractor Listing

Subject to other applicable law, industrial users which have not achieved consistent compliance with applicable pretreatment standards and requirements are not eligible to receive contract awards for the sale of goods or services to the City.

## SECTION 13 - AFFIRMATIVE DEFENSES TO DISCHARGE VIOLATIONS

### 13.1 Affirmative Defenses

A user shall have those affirmative defenses in any action brought against it alleging a violation as provided by federal regulations.

### 13.2 Upset

- (1) For the purpose of this section, "upset" means an exceptional incident in which there is unintentional and temporary noncompliance with categorical pretreatment standards because of factors beyond the reasonable control of the user. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
- (2) An upset shall be an affirmative defense to an enforcement action brought for noncompliance with categorical pretreatment standards and requirement if the following conditions are met:
- (3) A user who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:
  - A. The user can identify the cause of the upset.
  - B. The facility was operating in a prudent and workman-like manner at the time of the upset and was in compliance with applicable O&M procedures; and
  - C. The user submits the following information to the Superintendent within 24 hours of becoming aware of the upset, If this report is given orally, the user must also submit a written report containing

such information within five (5) days unless waived by the Superintendent:

- i) A description of the discharge and its causes of noncompliance;
  - ii) The period of noncompliance including exact dates and time or, if not corrected, the anticipated time the noncompliance is expected to continue;
  - iii) Steps being taken and/or planned to reduce, eliminate and prevent recurrence of the noncompliance.
- (4) In any enforcement proceeding, the user seeking to establish the occurrence of an upset shall have burden of proof.
- (5) Users will have the opportunity for judicial determination on any claim of upset only in an enforcement action for noncompliance with categorical pretreatment standards.
- (6) User shall control production of all discharges to the extent necessary to maintain compliance with categorical pretreatment standards upon reduction, loss, or failure of its treatment facility until the facility is restored or an alternative method of treatment is provided. This requirement applies in the situation where, among other things, the primary source of power of the treatment facility is reduced, lost, or fails.

### 13.3 General/Specific Prohibitions

An industrial user shall have an affirmative defense to an enforcement action brought against it for noncompliance with the general and specific prohibitions in Section 2.1 first paragraph of this Ordinance or the specific prohibitions in Sections 2.1 (2-3), (5-11), (13-20) of this ordinance if it can

prove that it did not know or have reasons to know that its discharge, alone or in conjunction with discharges from other sources would cause pass through or interference and that either: (a) a local limit exists for each pollutant discharged and the user was in compliance with each limit directly prior to and during the pass through or interference, or (b) no local limit exists, but the discharge did not change substantially in nature or constituents from the user's prior discharge when the City was regularly in compliance with its NPDES permit, and in the case of interference, in compliance with applicable sludge use or disposal requirements.

### 13.4 Bypass

- 
- (1) For the purposes of this section,
- A. "Bypass" means the intentional diversion of wastestreams from any portion of a user's treatment facility.
  - B. "Severe property damage" means substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
- (2) A user may allow any bypass to occur which does not cause pretreatment standards or requirements to be violated, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provision of paragraphs (A), (B) and (C) of this section.
- A. If a user knows in advance of the need for a bypass, it shall submit prior notice to the Superintendent, at least ten (10) days before the date of the bypass, if possible.
  - B. A user shall submit oral notice to the superintendent of an unanticipated bypass that exceeds applicable pretreatment standards within twenty-four (24) hours from the time it becomes aware of the bypass. A written submission shall also be provided within five (5) days of the time the user becomes aware of the bypass. The written submission shall contain a  
  
description of the bypass and its cause; the duration of the bypass, including exact dates and times, and if the bypass has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the bypass. The Superintendent may waive the written report on a case-by-case basis if the oral report has been received within twenty-four (24) hours.
  - C. Bypass is prohibited, and the Superintendent may take an enforcement action against a user for bypass, unless
    - i) Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
    - ii) There were no feasible alternatives to the bypass, such

- as the use of auxiliary treatment facilities, retention of untreated waste, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate backup equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and
- iii) The user submitted notices required under paragraph (3) of this section.

- D. The Superintendent may approve an anticipated bypass, after considering its adverse effects, if the Superintendent determines that it will meet the three conditions listed in paragraph (4) (A) of this section.

## SECTION 14 - MISCELLANEOUS PROVISIONS

### 14.1 Pretreatment Charges and Fees

The City may adopt reasonable charges and fees for reimbursement of costs of setting up and operating the City's Pretreatment Program which may include:

- (1) Fees for permit applications including the cost of processing such applications;
- (2) Fees for monitoring, inspection and surveillance procedures including the cost of reviewing monitoring reports submitted by industrial users;
- (3) Fees for reviewing and responding to accidental discharge procedures and construction;
- (4) Fees for filing appeals;
- (5) Other fees as the City may deem necessary to carry out the requirements contained herein. These fees relate solely to the matters covered by this Ordinance and are separate from all other fees, fines and penalties chargeable by the City.

### 14.2 Severability

If any provision of this Ordinance is invalidated by any court of competent jurisdiction, the remaining provisions shall not be affected and shall

continue in full force and effect.

#### 14.3 Conflicts with other Ordinances

To the extent that an inconsistency exists between the terms of this ordinance and another existing ordinance, this ordinance shall be deemed to preempt the other ordinance and the terms of this ordinance shall control.

#### 14.4 Emergency Clause

This ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor.

***Passed by the Council September 9, 1996 and approved by the Mayor  
September 10, 1996.***

---

ORDINANCE NO. 2242**AN ORDINANCE PROVIDING FOR CROSS CONNECTION CONTROL AND BACKFLOW PREVENTION PROCEDURES; COMPLYING WITH OREGON ADMINISTRATIVE RULES 333-61-0070; AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Title.** This ordinance shall be known as the "City of Woodburn Cross Connection Control and Backflow Prevention Ordinance".

**Section 2. Policy and Purpose.** As required by the Oregon Health Division, pursuant to Oregon Administrative Rules 333-61-0070, and in order to prevent any possibility of backflow contaminating the water system, it shall be the policy of the City of Woodburn to require the installation of backflow prevention devices, and inspections of those devices, as set forth in this ordinance. The City of Woodburn shall also administratively implement a local cross connection program as further specified in the Oregon Administrative Rules and the City of Woodburn Cross Connection Implementation Manual.

**Section 3. Definitions.** The words and phrases used in this ordinance shall have the meaning provided in Oregon Administrative Rules 333-061-0020.

**Section 4. Records and Reports.** The City shall maintain current records of backflow assemblies installed, inspections completed, and backflow assembly test results, and shall report such data as may be required by State law.

**Section 5. Discontinuance of Service for Violations of Policy.**

A. After proper notice to the customer as required by this ordinance, and until the violation has been corrected, the City shall discontinue water service to any premises under any of the following circumstances:

- (1) For failure to install an approved backflow prevention device;
- (2) For failure to conduct an annual test on the backflow device;
- (3) When the City has reasonable cause to believe that an existing or potential cross connection is located on the user's premises, until an appropriate backflow prevention assembly is installed or until the cause of the hazard is eliminated.
- (4) For any other violation of this ordinance.

B. This section shall not in any way be construed to impair the City's ability to immediately discontinue water service in the event of imminent threat to the City's water system or other emergency situations.

**Section 6. Backflow Prevention; When Required.**

A. Backflow prevention assemblies shall be installed at the service connection to premises where an approved airgap does not exist and:

(1) There is an auxiliary water supply which is, or can be, connected to the potable water piping; or

(2) There is piping for conveying liquids other than potable water, and where that piping is under pressure and is installed in proximity to potable water piping; or

(3) There is intricate plumbing which makes it impractical to ascertain whether or not cross connections exist; or

(4) There is backsiphonage potential; or

(5) Cross connections or potential cross connections exist.

**Section 7. Approved Devices and Installation Thereof; Required Methods of Backflow Prevention.**

A. New Assemblies. All backflow prevention assemblies required under this ordinance shall be of a type and model approved by the Oregon Health Division, and shall be installed in accordance with Oregon Administrative Rules 333-61-0071 Sections (1) through (4), as now existing or later amended. Suitable pressure-relief devices to prevent damage from thermal expansion shall be required in conjunction with the installation of all new backflow prevention assemblies.

B. Existing Assemblies. Backflow prevention assemblies installed before the adoption of this ordinance and which were approved by the Oregon Health Division at the time they were installed, but are not on the current list of approved assemblies, shall be permitted to remain in service provided they are properly maintained, are commensurate with the degree of hazard, are tested at least annually, and perform satisfactorily. When assemblies of this type are moved, or require more than minimum maintenance or are on services that are modified, changed size or remodeled, they shall be replaced by assemblies which are on the Oregon Health Division list of approved assemblies.

C. Required Backflow Prevention Methods. The method of backflow prevention required under this ordinance shall at a minimum be commensurate with the degree of hazard which exists, and not less than the following:

(1) When the substance which could backflow could be hazardous to health, an approved air gap of at least twice the inside diameter, but not less than one inch, of the incoming supply line measured vertically above the top rim of the vessel shall be installed, or an approved reduced pressure backflow (RPBA) assembly shall be installed.

(2) When the substance which could backflow is objectionable but does not pose an unreasonable risk to health, an approved double check valve

assembly (DCVA) shall be installed. An approved double check valve assembly shall be the minimum protection for fire sprinkler systems using piping material that is not approved for potable water use and /or which does not provide for periodic flow through during each 24 hour period.

(3) An approved pressure vacuum breaker assembly (PVBA) or an atmospheric vacuum breaker (AVB) shall be installed where the substance which could backflow is objectionable but does not pose an unreasonable risk to health and where there is no possibility of backpressure in the downstream piping. A shutoff valve may be installed on the line downstream of a pressure vacuum breaker but shall not be installed downstream of an atmospheric vacuum breaker.

#### **Section 8. Testing Required.**

**A. When Required.** The water user or the owner of the premises where one or more reduced pressure assembly (RPBA), double check valve assembly (DCVA), or pressure vacuum breaker (PVBA) have been installed shall have the assemblies tested by a certified tester at least once per year. Assemblies installed at facilities which pose an extreme health risk and assemblies which repeatedly fail shall be tested on a more frequent basis as determined by the City. Backflow assemblies which have been moved or which have been installed shall be tested before use.

**B. Malfunctioning Assemblies.** Backflow prevention assemblies found not to be functioning properly shall be promptly repaired by the owner or water user, and failure to do so may result in the denial or discontinuance of service as provided in this ordinance.

**C. Test Procedures and Reports.** Tests performed by certified testers shall be in conformance with procedures adopted under OAR 333-061-0070 (10), as now existing or later amended. Reports on the tests shall be prepared by the certified tester and copies shall be provided to the City and to the water user or owner of the premises.

**Section 9. Administrative Subsidy Program.** Consistent with the terms of this ordinance and subject to the City budget, the City Engineer may authorize administrative subsidies for the installation of required backflow prevention devices after a finding that such installation will protect the City water system and will benefit the public interest.

**Section 10. Severability.** The provisions of this ordinance are severable. If a portion of this ordinance is for any reason held by a court of competent jurisdiction to be invalid, such decision shall not affect the validity of the remaining portions of the ordinance.



**Section 11.** [Emergency clause.]

*Passed by the Council and approved by the Mayor August 24, 1999.*

## ORDINANCE NO. 1187

AN ORDINANCE DEFINING, REGULATING, AND LICENSING SOLICITORS AND PEDDLERS; REPEALING ALL ORDINANCES OR PARTS OF ORDINANCES IN CONFLICT HERewith; AND PROVIDING PENALTIES FOR VIOLATIONS OF THIS ORDINANCE.

THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1. Permit and License Required.** It shall be unlawful for any person to engage in business as a peddler or solicitor, as defined in this ordinance, within the corporate limits of the city of Woodburn, without first obtaining a license as herein provided.

**Section 2. Definitions.**

(a) Person shall include the singular, plural, firm, corporation, association, partnership, society, or other organization.

(b) Peddler includes any person traveling by any means from place to place, house to house, or street to street offering or exposing goods, wares, merchandise, or services for sale, or making sales, and delivering articles to purchasers.

(c) Solicitor includes any person traveling by any means from place to place, house to house, or street to street taking or attempting to take orders for sale of goods, wares, merchandise, or services for future delivery or to be furnished in the future, regardless of the method of payment.

(d) Exemptions. The terms of this ordinance shall not be held to include the acts of persons selling personal property at wholesale to dealers in such articles, nor to newsboys, nor the acts of local merchants or their employees in delivering goods in the regular course of business, nor shall the terms of this ordinance be held to include or apply to any farmer or truck gardener who shall vend, sell, or dispose of, or offer to sell, vend, or dispose of the products of the farm or garden occupied and cultivated by him within the state of Oregon. Nothing contained in this ordinance shall be held to prohibit any sale required by statute or by order of any court, or to prevent any person from conducting a bona fide auction sale pursuant to law.

(e) Nonprofit organizations, religious organizations, fraternal organizations, civic organizations, and clubs, wishing to canvass for funds, or sell from door to door, to an occupant or occupants of residences, to raise funds to be used solely for the purpose for which the organization or club is created, and from which no individual third party receives a profit, shall, in lieu of all other application and licensing provisions of this ordinance, apply to the council for a permit, which application shall contain such information as the city recorder may require, or is demanded by the council; and the council may, after an investigation as to the purpose of the project and the use to which the funds so raised are to be put, reject the application or approve it and direct the permit be issued. It shall be and is hereby declared to be a violation of this

ordinance for any person or party to canvass for funds or sales for any such organization or club from door to door of the occupant or occupants of residences until the council has approved the application and the permit has been issued. Such permit shall be issued without charge to the applicant.

### **Section 3.     Applications.**

(a)     A person desiring to be licensed under this ordinance must file with the city recorder a sworn application, in writing, on a form to be furnished by the city recorder, which shall give the following information and material:

(1)     The name and description of the applicant.

(2)     The permanent address of the applicant and, if this is not a local address, the local address, if any, to be used by the applicant.

(3)     A brief description of the nature of business and the goods or services to be sold. In the case of products of farms or orchards, a statement whether the produce to be sold is grown by the applicant.

(4)     If the applicant is employed, the name and address of the employer, together with credentials establishing an exact relationship.

(5)     A photograph or snapshot of the applicant shall have been taken within 60 days immediately prior to the date of the filing of the application, showing the head and shoulders of the applicant in a clear and distinguishing manner.

(6)     The fingerprints of the applicant.

(7)     The names of at least two reliable persons who will vouch for the applicant's good character and the business he represents.

(b)     At the time of filing the application, a fee of \$25.00 shall be paid to the city recorder to cover the cost of investigation. [Subsection (b) as amended by Ordinance No. 1624, passed June 26, 1978.]

### **Section 4.     Investigation and Issuance.**

(a)     Upon receipt of an application, the same shall be referred to the chief of police, who shall cause investigation of the applicant's business and moral character to be made as shall be deemed necessary for the protection of the public interest.

(b)     The chief of police, within five days from the date of the application, shall endorse the application as "satisfactory" or "unsatisfactory" and, if the same shall be endorsed "unsatisfactory;" the reason for such endorsement shall be set forth thereon. If the application is not returned to the city recorder within five days, the endorsement shall be presumed to be "satisfactory."

(c) Where the application is endorsed "satisfactory," or if five days shall have elapsed without the return of the application by the chief of police, the city recorder shall issue a license card to the applicant for the conduct of the activity for which application was made. Such license shall contain the signature and seal of the issuing officer and shall show the name, address, and photograph or snapshot of the licensee, the kind and goods to be sold thereunder, the date of issuance and the expiration date of the license. The city recorder shall keep a permanent record of all licenses for a period of two years from the date of issuance.

(d) If the application is returned from the chief of police endorsed "unsatisfactory," the city recorder shall notify the applicant that his application has been disapproved and the reasons therefor.

**Section 5. Crew Licenses and Bonds.** In lieu of an application being filed by each solicitor or peddler, the employer of any solicitors or peddlers may file separate applications for each solicitor or peddler employed by him and, upon satisfactory compliance with the requirements of this section and the payment of the license fee prescribed by Section 6 of this ordinance for each member of the crew, a crew license shall be issued to the employer designating the name of the employer and the solicitors or peddlers named in the application; and separate licenses or identification cards may be issued to each solicitor or peddler. The employer may make substitutions of solicitors or peddlers or add additional solicitors or peddlers from time to time within the limits of such crew license, and, upon filing an appropriate application as aforesaid, may have the city recorder transfer such licenses or identification cards from one solicitor or peddler employed by him to another so employed without paying any additional license fee. The city recorder may, in his discretion, in lieu of an investigation and the payment of an application fee, accept a corporate surety bond satisfactory to the city attorney in the sum of \$1,000.00, conditioned upon:

(a) The observance by the applicant of the provisions of Sections 1, 8, 9, 10, 12 and 14 of this ordinance and all laws of the state of Oregon.

(b) The truth of all representations made in connection with the application for a license.

(c) A guarantee that the person named in the bond will return the purchase price of any article or service purchased or ordered to the purchaser or person ordering upon return of the article purchased or relinquishment of the order and upon proof that any false or misleading statement or representation has been made concerning any personal property or any service or any subscription sold or offered for sale to said purchaser or person ordering. In the instance of a crew license, the employer may, instead of filing a separate bond for each peddler or solicitor, file one bond in a sum equal to \$2,000.00.

**Section 6. License Fee.**

(a) All peddlers and solicitors shall pay an annual license fee of \$15.00. Licenses may be renewed on an annual basis upon payment of the license fee.

(b) All licenses shall run from January 1 to December 31, inclusive. One-half of the annual license fee shall be charged for licenses issued after July 1. [Section 6 as amended by Ordinance No. 1618, passed June 13, 1978.]

**Section 7. Transfer.** No license shall be used at any time by any person other than the one to whom it is issued, unless it shall have been transferred pursuant to Section 5 of this ordinance.

**Section 8. Exhibition of License.** Peddlers and solicitors are required to exhibit their license cards at the request of any citizen.

**Section 9. Posting Premises.** Any resident of the city of Woodburn who wishes to exclude peddlers and solicitors from residence premises occupied by him may place upon or near the usual entrance to such premises a printed placard or sign bearing the words "Peddlers and Solicitors Prohibited," or other similar notice. Such notice shall be reasonably visible with normal eyesight for a distance of four feet. Any peddler or solicitor who goes into or approaches within four feet of such posted notice upon a private residence property in the city of Woodburn that has been duly posted pursuant to this section for the purpose of soliciting orders for the sale of goods, services, wares or merchandise or for the purpose of disposing of or hawking the same shall be in violation of this ordinance.

**Section 10. Duties of Police to Enforce.** It shall be the duty of any police officer of the city of Woodburn to require any person seen peddling or soliciting and who is not known by such officer to be duly licensed to produce his license card and to enforce the provisions of this ordinance against any person found to be violating the same.

**Section 11. Revocation of License.**

(a) Licenses may be revoked by the city recorder, after notice of hearing for any of the following causes:

(1) Fraud or misrepresentation or false statement contained in an application for license.

(2) Fraud or misrepresentation or false statement made in the course of carrying on the business as peddler or solicitor.

(3) Any violation of this ordinance.

(4) Conviction of any crime or misdemeanor involving moral turpitude.

(5) Conducting the business of peddling or soliciting in an unlawful manner or in such a manner as to constitute a menace to the health, safety, or general welfare of the public.

(b) Notice of hearing for revocation of a license shall be given in writing setting forth the grounds of the complaint and the time and place for hearing. Such notice shall be mailed, postage prepaid, to the licensee at his last known address at least five days prior to the date set for hearing.

**Section 12. Appeal.** Any person aggrieved by the action of the chief of police or the city recorder in denial or revocation of his license shall have the right to appeal to the council of the city or Woodburn. Such appeal shall be taken by filing with the council, within 14 days after notice of the action complained of has been mailed to such person's last known address, a written statement setting forth fully the grounds for the appeal. The council shall set a time and place for the hearing of such appeal and notice of such hearing shall be given to the appellant in the same manner as notice of revocation. The decision and order of the council on such appeal shall be final and conclusive.

**Section 13. Selling by Public Outcry.** Hawking or selling display goods on the public streets in the city of Woodburn by public outcry is hereby specifically prohibited; except that this section shall not apply to special promotional sales when such sales have been requested by or through the chamber of commerce and have been approved by the common council.

**Section 14. Severability.** The provisions of this ordinance are declared to be severable and if any section, sentence, clause, or phrase of this ordinance shall, for any reason, be held to be invalid or unconstitutional, such decision shall not effect the validity of the remaining sections, sentences, clauses, and phrases of this ordinance and they shall remain in effect.

**Section 15. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 4 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 15 as amended by Ordinance 2008, passed October 24, 1988.]

**Section 16. Repealing Clause.** That portion of Section 1, Ordinance No. 892, relating to license fees for "Vending and peddling from house to house except products produced from premises owned or operated by such vendor or peddler" is hereby repealed.

***Passed by the Council and approved by the Mayor February 18, 1969.***

## ORDINANCE NO. 1900

## AN ORDINANCE DESCRIBING CERTAIN MUNICIPAL VIOLATIONS, PROVIDING PENALTIES, REPEALING ORDINANCE NO. 1887, AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Drinking in Public Places.** No person shall drink or consume alcoholic liquor in or on a street, alley, mall, parking lot, or structure, motor vehicle, public grounds or other public place unless the place has been licensed for that purpose by the Oregon Liquor Control Commission.

**Section 2. Public Indecency.** No person shall, while in or in view of a public place, perform an act of urination or defecation, except in toilets provided for that purpose. [Section 2 amended by Ordinance No. 1938, passed February 10, 1986.]

**Section 3.** (Section 3 repealed by Ordinance 2312)

**Section 4. Children Confined in Vehicles.**

(1) No person who has under his control or guidance a child under 10 years of age shall lock or confine, or leave the child unattended, or permit the child to be locked or confined or left unattended in a vehicle for a period of time longer than 15 consecutive minutes.

(2) A peace officer, finding a child confined in violation of subsection (1) shall have the authority to enter the vehicle and remove said child using such force as is reasonably necessary to effect an entrance to the vehicle.

**Section 5. Discharge of Weapons.**

(1) Except at firing ranges approved by the Chief of Police, no person other than a peace officer shall fire or discharge a gun, including spring or air-activated pellet guns, air guns or BB guns, firearm or other weapon which propels a projectile by use of gun powder or other explosive, jet or rocket propulsion.

(2) "Firearm" means a weapon, by whatever name known, which is designed to expel a projectile by the action of powder and which is readily capable of use as a weapon.

(3) Notwithstanding subsection 1 of this section, the City Council may approve or deny applications for the ceremonial discharge of a firearm or firearms when blank ammunition is used. Applications for the ceremonial discharge of firearms shall be made to the Chief of Police according to an administrative procedure established by the Police Department. The denial of an application may be appealed to the City Council. (Section 5 as amended by Ordinance No. 2274, passed November 13, 2000.)

**Section 6. Obstructing a Peace Officer.** No person shall, by use of violence, force, physical interference, or obstacle, intentionally obstruct, impair, or hinder the enforcement of the law by a peace officer acting within the scope of the officer's official authority. [Section 6 added by Ordinance No. 1909, passed February 25, 1985.]

(Sections 7 to 14 reserved for expansion)

**Section 15. Penalties.** A person who violates any section of this ordinance commits a violation punishable by a fine of not more than \$250.00.

**Section 16. Severability.** Each portion of this ordinance shall be deemed severable from any other portion. The unconstitutionality or validity of any portion of this ordinance shall not invalidate the remainder of the ordinance.

**Section 17. Repeal and Saving Clause.**

(1) Ordinance No. 1887 is hereby repealed.

(2) Notwithstanding subsection (1) of this section, Ordinance No. 1887 shall remain valid and in force for the purpose of authorizing the arrest, prosecution, conviction and punishment of a person who violated Ordinance No. 1887 prior to the effective date of this ordinance.

**Section 18.** [Emergency clause.]

*Passed by the Council October 8, 1984, and approved by the Mayor October 9, 1984. Amended by Ordinance 2312 passed April 8, 2002.*



## ORDINANCE 1996

## AN ORDINANCE PROHIBITING AND REGULATING GAMBLING WITHIN THE CITY OF WOODBURN, REPEALING ORDINANCE 1889 AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Gambling Prohibited.** Except as provided in this ordinance, gambling is prohibited in the City of Woodburn, pursuant to Ordinance No. 1987 (which adopts the provisions of the Oregon Criminal Code as municipal offenses).

**Section 2. Bingo and Lotto.** Bingo and lotto, when conducted by a charitable, fraternal, or religious organization, pursuant to the provisions of Oregon state law, is permitted in the City of Woodburn.

**Section 3. Social Games.** Social games as defined in ORS 167.117(13)(a) are permitted in the City of Woodburn without a license, but social games as defined in ORS 167.117(13)(b) are prohibited and, if held, constitute gambling in violation of Ordinance No. 1987.

**Section 4. Severability.** Each portion of this ordinance shall be deemed severable from any other portion. The unconstitutionality or invalidity of any portion of this ordinance shall not invalidate the remainder of this ordinance.

**Section 5. Repeal and Saving Clause.**

(1) Ordinance No. 1889, as amended is hereby repealed.

(2) Notwithstanding subsection (1) of this section, Ordinance No. 1889 shall remain valid and in force for the purpose of authorizing the arrest prosecution, conviction and punishment of a person who violated Ordinance No. 1889 prior to the effective date of this ordinance.

**Section 6.** [Emergency clause.]

*Passed by the Council April 25, 1988, and approved by the Mayor April 27, 1988.*

## ORDINANCE NO. 2032

**AN ORDINANCE DESCRIBING MUNICIPAL OFFENSES, PROVIDING PENALTIES, REPEALING ORDINANCE 1987 AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Adoption of the Oregon Criminal Code.** The Oregon Criminal code (hereinafter ORS 133.075, ORS Chapter 475, and ORS Chapters 161, 162, 163, 164, 165, 166, and 167, as it is now constituted) is hereby adopted by the City of Woodburn. Provisions of the above-mentioned chapters relating to defenses, burden of proof, general principles of criminal liability, parties, and general principles of justification apply to offenses defined and made punishable by this ordinance.

**Section 2. Violation of code as City Offense.** Violation of any provision adopted in section 1 of this ordinance, except where an offense is classified under state law as a felony or where a court other than a municipal court is vested with exclusive jurisdiction, constitutes a municipal offense against the City of Woodburn.

**Section 3. Jurisdiction of the Municipal Court.** The Woodburn Municipal Judge, pursuant to the Woodburn City Charter, Oregon law and the home rule authority of the City of Woodburn, is given original and exclusive jurisdiction over any alleged violation of this ordinance.

**Section 4 Penalty for Violation.** Upon finding that an offense has been committed under this ordinance, the Woodburn Municipal Judge shall impose a penalty not to exceed the penalty provided by state law as it is now constituted.

**Section 5. Severability.** Each portion of this ordinance shall be deemed severable from any other portion. The unconstitutionality or invalidity of any portion of this ordinance shall not invalidate the remainder of this ordinance.

**Section 6. Repeal and Saving Clause.**

(1) Ordinance 1987, as amended, is hereby repealed.

(2) Notwithstanding subsection (1) of this section, Ordinance No. 1987 shall remain valid and in force for the purpose of authorizing the arrest, prosecution, conviction, and punishment of a person who violated Ordinance No. 1987 prior to the effective date of this ordinance.

**Section 7.** [Emergency clause.]

***Passed by the Council November 13, 1989 and approved by the Mayor November 15, 1989.***

## ORDINANCE NO. 2048

## AN ORDINANCE PROHIBITING UNLAWFUL PROSTITUTION PROCUREMENT ACTIVITIES AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.** As used in this ordinance, "prostitution" means that unlawful conduct defined in ORS 167.007. As used in this ordinance, "prostitution procurement activity" means any conduct by any person that constitutes a substantial step in furtherance of an act of prostitution. Such activity includes, but is not limited to lingering in or near any street or public place, repeatedly circling an area in a motor vehicle or repeatedly beckoning to, contacting, or attempting to stop pedestrians or motor vehicle operators.

**Section 2. Prostitution Procurement Activity.** It is unlawful for any person to engage in any prostitution procurement activity with an intent to induce, entice, solicit, procure, locate, or contact another person to commit an act of prostitution.

**Section 3. Penalty.** Violation of this ordinance is punishable, upon conviction, by a fine of not more than \$500.00 or by imprisonment not exceeding six months, or both. However, no greater penalty shall be imposed than the penalty prescribed by Oregon statute for the same act or omission.

**Section 4.** [Emergency clause.]

*Passed by the Council November 7, 1990 and approved by the Mayor  
November 9, 1990.*

## ORDINANCE NO. 2049

**AN ORDINANCE PROHIBITING LOITERING TO SOLICIT PROSTITUTION AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Definition of prostitution.** As used in this ordinance, "prostitution" means engaging in, offering to engage in, or agreeing to engage in an act of sexual conduct or sexual contact as those terms are defined in ORS 167.002(4) and (5), with a person not married to the actor, in return for the payment of a fee.

**Section 2. Loitering to solicit prostitution prohibited.** It is unlawful for any person to loiter in or near any street or public place in a manner and under circumstances manifesting the purpose of inducing, enticing, soliciting, or procuring another to commit an act of prostitution. Among the circumstances which may be considered in determining whether such purpose is manifested are that the person repeatedly beckons to, stops or attempts to stop, or engages in conversation, passersby or repeatedly stops or attempts to stop motor vehicle operators by hailing them or gesturing to them.

**Section 3. Penalty for Violation.** Violation of this ordinance is punishable, upon conviction, by a fine of not more than \$500.00, or by imprisonment not exceeding six months, or both. However, no greater penalty shall be imposed than the penalty prescribed by Oregon statute for the same act or omission.

**Section 4.** [Emergency clause.]

*Passed by the Council November 7, 1990 and approved by the Mayor  
November 9, 1990.*

## ORDINANCE NO. 2060

**AN ORDINANCE RELATING TO THE USE OF PARK AREAS: PROVIDING FOR PENALTIES FOR VIOLATION THEREOF; REPEALING ORDINANCE 1918 AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Policy.** The City of Woodburn may develop, construct, improve, operate and maintain park and recreation facilities in a manner which will best afford the public with necessary conveniences and accommodations. In order to protect the health, safety and well-being of the public, and insure the greatest use and benefits from such areas, it is necessary to make regulations and provisions the City Council deems necessary.

**Section 2. Definitions**

(1) Board. The Woodburn Recreation and Parks Board.

(2) Council. The Woodburn City Council.

(3) Director. The person hired by the City of Woodburn who is in charge of the Community Services Department of the City of Woodburn or his designee.

[Section 2 (3) as amended by Ordinance 2412, passed November 13, 2006.]

(4) Park Area. A City Park, wayside area, community rest areas, scenic or historical areas, public park open spaces and greenbelt areas.

(5) Park Employee. Any employee of the City of Woodburn Community Services Department.

[Section 2 (5) as amended by Ordinance 2412, passed November 13, 2006.]

(6) Person. A natural person, firm, partnership, association, or corporation.

**Section 3. General Rules and Regulations.** The general rules and regulations for City of Woodburn Parks shall be as follows:

(1) Fires in park areas:

No person shall build a fire in any park area unless said fire is confined to:

(a) Park camp stoves or fireplaces.

(b) Portions of parks designated as permitting fires.

(c) Portable stoves in established picnic areas and designated where fires are permitted.

(d) No fire shall be left unattended, and every fire shall be extinguished before its user leaves the park area.

(2) No person in a park area shall hunt, pursue, trap, kill, injure or molest any birds or animals or disturb their habitat. [Section 3(2) as amended by Ordinance 2083, passed May 26, 1992.]

(3) No person shall pick, cut, mutilate or remove from any park area flowers, shrubs, foliage, trees, plant life, barkdust, or products of any type without the written permission of the Director or his authorized agent.

(4) No person shall, except in areas designated by City Council, erect signs, markers, or inscriptions of any type within a park area without permission from the Director.

(5) No person in a park area shall sell, peddle or offer for sale any food liquids, edibles for human consumptions, or any goods, wares, service or merchandise within the park area except under permit by the Director, and then only subject to such laws and regulations as may now or hereafter exist.

(6) No person shall, except duly authorized peace officers in the course of their duties, drive, lead or keep a horse or other farm animal in any park area, except on such roads, trails or other areas designated for that purpose. No horse or such animal shall be hitched to any tree or shrub in such manner that may cause damage to such tree or shrub. The only exception to this rule would be during a parade line-up or a special event, and only after obtaining written permission from The Director.

(7) No person shall wash any clothing, or materials or other substances, or clean any fish in a park area or in a lake, stream or river, or in a park area. Park sinks, faucets and hydrants within the confines of parks or park restrooms shall not to be used for washing clothes of any type.

(8) No person shall use park sinks, other than those provided in public restrooms, for personal hygiene. Faucets, drinking fountains, hose outlets and hydrants shall not be used for this purpose.

(9) No person shall clog picnic shelter sinks in a park area with food, debris, grease or any other substances

(10) No person shall camp in a park area except by written approval of the Director.

(11) The Director may restrict to designated zone areas certain activities, including but not limited to, swimming, picnicking, group picnicking, boating, water skiing, fishing, camping, group camping, hiking and horseback riding.

(12) No person shall enter or remain in a park area anytime between the hours of 10:00 p.m. and 7:00 a.m. the following morning during April 1 through September 30 of the calendar year, or between the hours of 7:00 p.m. and 7:00 a.m. the following morning during October 1 through March 31 of the calendar year. This section shall not apply to:

- (a) Persons attending an event for which a permit has been issued.
- (b) Participants or spectators of athletic events in park areas lighted for these events; or
- (c) Persons attending events sponsored by the City.

[Section 3(12) as amended by Ordinance 2083, passed May 26, 1992.]

(13) No person shall have in their possession, any alcoholic beverages or intoxicating liquor, or consume such liquor while in a park area except that the use of alcoholic beverages may be permitted in Centennial Park in compliance with a Special Event Park Use Permit where the city has issued the permit and the premises have been licensed for the service of alcoholic beverages by the Oregon Liquor Control Commission.

[Section 3(13) as amended by Ordinance 2083, passed May 26, 1992 and by Ordinance 2321, passed July 8, 2002.]

(14) Nothing in this ordinance shall in any manner restrict the authority of the City of Woodburn to enforce all State statutes and City Ordinances relating to the use and control of alcoholic beverages.

(15) The Director, any Park employee, Code Enforcement officer, or member of the Woodburn Police Department is authorized to issue a civil infraction citation for a violation of this ordinance.

(16) The Council, City Administrator or The Director shall have the authority to close a park area or a portion of a park area to the public at any time and without notice for any reasonable and necessary circumstance including, but not limited to, construction and maintenance in the park area and for the existence of a hazardous condition.

**Section 4. Fees.** Fees may be charged for certain services and privileges, and for the use of designated areas, buildings or facilities. No person shall enter or use such areas, buildings, services or facilities or to be granted those privileges unless the appropriate fee or fees have been paid.

**Section 5. Rules of Conduct.** The Community Services Department may adopt administrative rules for the conduct of persons participating in City Programs in the park areas, the Aquatic Center, or the Community Center. All persons participating in City Programs shall be registered. The Rules of Conduct shall be administered by the Director, or a park employee.

[Section 5 as amended by Ordinance 2412, passed November 13, 2006.]

**Section 6. Animals.**

(1) Persons owning, keeping or harboring a dog within a par(k) area are responsible for the dogs behavior and shall comply with the following regulations:

(a) A dog shall be on a leash not more than eight (8) feet in length, or confined in a vehicle at all times.

(b) A vicious dog shall not be permitted.

(c) A dog may not deposit solid waste matter on any improved park property unless the person owning, keeping, or harboring the dog immediately removes the solid waste.

(2) The Director or a park employee may require a person in charge of any animal to undertake any measure, including the removal of an animal from the park area to prevent interference by the animal with the safety, comfort or well being of park area visitors or resources.

(3) No farm animal, including, but not limited to, horses, cattle, sheep and goats is allowed in a park area except by permission of the Director.

**Section 7. Glass Beverage Containers.** Except by written authorization from the Director or designated park employee, no person shall possess a beverage container made of glass in any park area.

**Section 8. Additional Prohibited Activities.** In addition to any other prohibitions in this ordinance, no person in a park area shall:

(1) Set or use a public address system without the written permission of the Director.

(2) Operate or use any noise producing device in a manner that disturbs other park visitors.

(3) Use a metal detector without the written permission of the Director.

(4) Play sports or engage in other recreational activities in areas designated by the Director as unavailable for those activities.

(5) Over crowd persons or vehicles so that necessary access to emergency vehicles is unavailable. Vehicles improperly parked will be towed at owners expense.

**Section 9. Penalty.** Any violation of this Ordinance constitutes a class 4 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998.



**Section 9A. Enhanced Penalty for Violation of Special Park Use Permit.**

Notwithstanding Section 9 of this Ordinance, which provides that a violation of the park rules established by this Ordinance constitutes a class 4 civil infraction, any violation of the terms and conditions of a Special Event Park Use Permit by the permittee shall constitute a class 1 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998, the civil infraction ordinance.

(Section 9A added by Ordinance 2321, passed July 8, 2002.)

**Section 9B.** In addition to other measures provided for violation of this Ordinance, or any of the laws of the State of Oregon, any peace officer, as defined by ORS 133.005(3), as amended, or any City of Woodburn park or parks maintenance official or employee designated by the City Administrator, may exclude any person who violates any provision of this Ordinance, any City ordinance, any of the laws of the State of Oregon, or any rule or regulation duly made and issued by the Community Services Department or the City Council from any City park for a period of not more than 30 days.

[Section 9B as amended by Ordinance 2412, passed November 13, 2006.]

(1) No person shall enter or remain in a City park at any time that a Notice of Exclusion issued under this Ordinance excluding that person from that City park is in effect

(2) An exclusion issued under the provisions of this Ordinance shall be for thirty (30) days. If the person to be excluded has been excluded from any park at any time, within two years before the date of the present exclusion, the exclusion shall be for ninety (90) days. If the person to be excluded has been excluded from one or more parks on two or more occasions within two years before the date of the present exclusion, the exclusion shall be for one-hundred eighty (180) days.

(3) Before issuing a Notice of Exclusion under this Ordinance the issuing officer shall first give the person a warning and a reasonable opportunity to desist from the violation. A Notice of Exclusion shall not be issued if the person promptly complies with the warning and desists from the violation. No warning shall be required if the person is to be excluded for committing any act punishable as a felony, or involving controlled substances or alcoholic beverages, or which has resulted in injury to any person or damage to any property. Further, no warning shall be required if the person to be excluded has been warned or excluded from the park previously for engaging in the same unlawful conduct.

(4) A Notice of Exclusion under this Ordinance shall specify the date the exclusion is to commence, the term of the exclusion, the City park that the person is to be excluded from, the provision of law that the person violated, and a brief description of the offending conduct. It shall be signed by the issuing party. The Notice of Exclusion shall provide information concerning the right to appeal the notice and to apply for a temporary waiver from the effects of the notice warning of consequences for failure to comply shall be prominently displayed on the notice.

(5) Notices of Exclusion shall take effect immediately except that if a timely appeal is filed under this Ordinance, the effectiveness of the exclusion shall be stayed pending the outcome of the appeal. If the exclusion is affirmed, the remaining period of the exclusion shall become effective immediately upon issuance of the Woodburn Municipal Court decision, unless the Court sets a later effective date.

(6) A person receiving a Notice of Exclusion may appeal to the Woodburn Municipal Court to have the notice rescinded or the exclusion period shortened. In order to be timely, an appeal must be filed within five (5) days of receipt of the Notice of Exclusion.

(a) The appeal need not be in any particular form, but should substantially comply with the following requirements:

- (i) Be in writing
- (ii) *Identify the date, time, and place of the exclusion*
- (iii) *Identify the name and address of the appealing party*
- (iv) Identify the official who issued the exclusion
- (v) Contain a concise statement as to why the Notice of Exclusion was issued in error

(b) A copy of the appeal shall be served on the City Attorney.

(c) *An appeal hearing shall be conducted by the Woodburn Municipal Court and a decision on the appeal shall be made by the Court within ten (10) days after the appeal is filed.*

(d) *At the appeal hearing the City and any interested parties shall have the right to present evidence and witnesses and be heard. After due consideration of pertinent information and testimony the Court shall issue a written decision. The decision of the Court shall be final.*

(7) *At any time within the exclusion period, a person receiving a Notice of Exclusion may apply in writing to the City Administrator for a temporary waiver from the effects of the notice for good cause shown. In exercising discretion under this section, the City Administrator shall consider the seriousness of the violation for which the person has been excluded, the particular need of the person to be in the park during some or all of the period of exclusion, such as for work or to attend or participate in a particular event (without regard to the content of any speech associated with that event), and any other criterion the City Administrator determines to be relevant to the determination of whether or not to grant a waiver. The decision of the City Administrator to grant or deny, in whole or in part, a waiver under this section is committed to the discretion of the City Administrator, and is not subject to appeal or review.*

(Section 9B added by Ordinance 2342, passed July 28, 2003; amended by Ordinance 2377, passed November 8, 2004.)

**Section 10. Severability.** Each portion of this Ordinance shall be deemed severable from any other portion. The unconstitutionality or invalidity of any portion of this Ordinance shall not invalidate the remainder of the Ordinance.

**Section 11. Repeal and Saving Clause.**

(1) Ordinance No. 1918 is hereby repealed.

(2) Notwithstanding Subsection (1) of this Section, Ordinance No. 1918 shall remain valid and in force for the purpose of authorizing arrest, prosecution, conviction and punishment of a person who violated Ordinance No. 1918 prior to the effective date of this Ordinance.

**Section 12.** [Emergency clause.]

*Passed by the Council April 22, 1991 and approved by the Mayor April 23, 1991.*

## ORDINANCE NO. 2122

## AN ORDINANCE SETTING TIMES FOR JUVENILE CURFEWS, PROVIDING FOR PENALTIES AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Curfew.** No minor under the age of 18 years shall be in or upon any street, highway, park, alley, or other public place between the hours specified in Section 2, unless:

(a) Such minor is accompanied by a parent, guardian or other person 18 years of age or over and authorized by the parent or by law to have care and custody of the minor;

(b) Such minor is then engaged in a lawful pursuit or activity which requires the presence of the minor in such public place during the hours specified in this Ordinance, or

(c) The minor is emancipated pursuant to ORS 419B.550 to 419B.558.

**Section 2. Hours of Curfew.** For minors under the age of 16 years, the curfew is between 10:00 p.m. and 6:00 a.m. of the following morning. For minors 16 years of age or older, the curfew is between 12:00 a.m. midnight and 6:00 a.m. of the following morning.

**Section 3. Responsibility of Parent or Guardian.** No parent, guardian, or person having the care and custody of a minor under the age of 18 years shall knowingly or negligently allow such minor to be in or upon any street, highway, park, alley or other public place between the hours specified in Section 2, except as otherwise provided in this Ordinance. For purposes of this section, a person negligently allows a violation if in the exercise of reasonable diligence the person should have known that a violation would occur.

**Section 4. Violation by Minor.** Any minor who violates the provisions of this ordinance may be taken into custody as provided in ORS 419C.080, 419C.085 and 419.088 and may be subjected to further proceedings as provided by law.

**Section 5. Violation by Parent or Guardian.** Violation of Section 3 of this Ordinance is a Class 2 civil infraction with a forfeiture amount not to exceed \$250.00.

**Section 6.** [Emergency clause.]

*Passed by the Council and approved by the Mayor on May 23, 1994.*

## ORDINANCE NO. 2136

## AN ORDINANCE DEFINING CHRONIC NUISANCE PROPERTY, ESTABLISHING CERTAIN REGULATIONS THEREOF, AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Title.** This ordinance shall be known as the "Chronic Nuisance Property Ordinance."

**Section 2. Incorporation of State Statute.** Any reference to state statute incorporated into this ordinance refers to the statute in effect on the effective date of this ordinance.

**Section 3. Definitions.** As used in this ordinance, the following definitions apply.

(A) "Chief of Police" means the Chief of the Woodburn Police Department or his or her designee.

(B) "City Administrator" means the City Administrator of the City of Woodburn or his or her designee.

(C) "Chronic Nuisance Property" means property upon which three or more distinct occurrences of any of the below listed behaviors occur , or whose patrons, employees, residents, owners or occupants engage in three or more of the below listed behaviors within 400 feet of the property following acts or behaviors during any 60 day period:

(1) Criminal homicide as defined in ORS 163.005 or any type of attempted criminal homicide;

(2) Rape in the First Degree as defined in ORS 163.375;

(3) Menacing as defined in ORS 163.190;

(4) Intimidation as defined in ORS 166.155 to ORS 166.165;

(5) Harassment as defined in ORS 166.065;

(6) Disorderly Conduct as defined in ORS 166.025;

(7) Discharge of Weapons as defined in Section 5, Woodburn City Ordinance 1900;

(8) Unnecessary Noise as defined in Section 3, Woodburn City Ordinance 1900;

(9) Drinking in Public Places as defined in Section 1, Woodburn City Ordinance 1900;

(10) Minor in Possession of Alcohol as defined in ORS 471.430;

(11) Assault as defined in ORS 163.160, 163.165, 163.175, or 163.185;

(12) Sexual Abuse as defined in ORS 163.415 to ORS 163.427;

(13) Public Indecency as defined in ORS 163.465;

(14) Public Indecency as defined in Section 2, Woodburn City Ordinance 1900;

(15) Criminal Trespass as defined in ORS 164.245;

(16) Criminal Mischief as defined in ORS 164.345 to ORS 164.365

(17) Unlawful Use of a Weapon as defined in ORS 166.220.

(D) "Owner" means the person or persons having legal or equitable title to the property.

(E) "Property" means any real property including land and that which is affixed, incidental or appurtenant to land, including but not limited to any premises, room, apartment, house, building or structure or any separate part or portion thereof, whether permanent or not.

(F) "Responsible party" includes each of the following:

(1) The owner of the property, or the owner's manager or agent or other person in control of the property on behalf of the owner; or

(2) The person occupying the property, including a bailee, lessee, tenant or other person having possession.

#### **Section 4. Chronic Nuisance Property.**

(A) The acts or omissions described herein are hereby declared to be public nuisances of the sort that commonly recur in relation to a given property, thereby requiring the remedies set out in this ordinance.

(B) Any property within the City of Woodburn which becomes chronic nuisance property is in violation of this ordinance and subject to its remedies.

(C) Any person who is a responsible party for property which becomes a chronic nuisance property shall be in violation of this ordinance and subject to its remedies.

**Section 5. Prefiling Notification Procedure.** After two occurrences of any of the acts or behaviors listed in Section 3(C) of this ordinance within a 60-day period, the Chief of Police shall provide notification via certified mail, stating the times and places of the alleged occurrences and the potential liability for violation of this ordinance, to all responsible parties for the property. Responsible parties for a given property shall be presumed from the following:

(A) The owner and the owner's agent, as shown on the tax rolls of Marion County.

(B) The resident of the property, as shown on the records of the City of Woodburn Water Department.

**Section 6. Compliance Agreement with Responsible Parties.**

(A) After providing notification to all responsible parties as provided in Section 5 above, the Chief of Police has the authority to obtain, on behalf of the city, voluntary agreements to comply with the provisions of this ordinance. Such compliance agreements shall be in written form and signed by all responsible parties. The Chief of Police shall sign said agreements on behalf of the city and provide copies thereof to the City Administrator.

(B) In proposing and signing compliance agreements under this Section, the Chief of Police shall consider the criteria outlined in Section 9 (B) below.

(C) This Section is strictly remedial in nature and shall not be interpreted to limit in any manner the authority of the city to commence an action against any responsible party for a violation of this ordinance, as provided below.

**Section 7. Commencement of Actions; Summon and Complaint.**

(A) Except as otherwise noted, the procedures to be used in processing an infraction under this ordinance are contained in Ordinance 1998, the Civil Infraction Ordinance.

(B) Subject to the limitations of Ordinance 1998, a default judgment may be entered against a respondent who fails to appear at the scheduled hearing. Upon such judgment, the court may prescribe the remedies described in the ordinance.

**Section 8. Remedies.**

(A) Upon finding that the respondent has violated this ordinance, the court may:

(1) Require that the chronic nuisance property be closed and secured against all use and occupancy for a period of not less than 30, but not more than 180 days; and/or

(2) Assess a civil infraction penalty not to exceed \$500.00; and/or

(3) Employ any other remedy deemed by the court to be appropriate to abate the nuisance.

(B) In lieu of closure of the property pursuant to Subsection (A) of this section, the respondent may file a bond acceptable to the court. Such bond shall be in an amount of at least \$500 and shall be conditioned upon the non-recurrence of any of the acts or behaviors listed at Section 3(C) of this ordinance for a period of one year after the judgment. Acceptance of the bond described herein is further subject to the court's satisfaction of the respondent's good faith commitment to abatement of the nuisance.

### **Section 9. Defenses; Mitigation of Civil Penalty.**

(A) It is a defense to an action brought pursuant to this ordinance that the responsible party at the time in question could not, in the exercise of reasonable care or diligence, determine that the property had become chronic nuisance property, or could not, in spite of the exercise of reasonable care and diligence, control the conduct leading to the finding that the property is chronic property. However it is no defense under this subsection that the party was not at the property at the time of the incidents leading to the chronic nuisance situation.

(B) In implementing the remedies described in this ordinance, the court may consider any of the following factors, as they may be appropriate, and shall cite those found applicable:

(1) The actions taken by the owner(s) to mitigate or correct the problem at the property;

(2) Whether the problem at the property was repeated or continuous;

(3) The magnitude or gravity of the problem;

(4) The cooperativeness of the owner(s) with the City in remedying the problem;

(5) The cost to the City of investigating and correcting or attempting to correct the condition;

(6) Any other factor deemed by the court to be relevant.



**Section 10. Closure During Pendency of Action; Emergency Closures.** In addition to any other remedy available to the City under this ordinance, in the event that the City Administrator finds that a property constitutes an immediate threat to the public safety and welfare, the City may apply to any court of competent jurisdiction for such interim relief as is deemed to be appropriate.

**Section 11. Enforcement of Closure Order; Costs; Civil Penalty.**

(A) The court may authorize the City to physically secure the property against use or occupancy in the event that the owner(s) fail to do so within the time specified by the court.

(B) The court may assess on the property owner the following costs incurred by the City in effecting a closure of property:

(1) Costs incurred in actually physically securing the property against use;

(2) Police department investigative costs;

(3) Administrative costs and attorneys fees in bringing the action for violation of this ordinance.

(C) The City Administrator may, within 14 days of written decision by the court, submit a signed and detailed statement of costs to the court for its review. If no objection to the statement is made within the period prescribed by Oregon Rule of Civil Procedure 67, a copy of the statement, including a legal description of the property shall be forwarded to the office of the City Recorder who thereafter shall enter the same in the City's lien docket.

(D) Persons assessed the costs of closure and/or civil penalty pursuant to this ordinance shall be jointly and severally liable for the payment thereof to the City.

**Section 12. Attorney Fees.** In any action brought pursuant to this ordinance, the court may, in its discretion, award reasonable attorneys fees to the prevailing party.

**Section 13. Severability.** If any provision of this ordinance, or its application to any person or circumstance, is held to be invalid for any reason, the remainder of the ordinance, or the application of its provisions to other persons or circumstances, shall not in any way be affected.

**Section 14. Nonexclusive Remedy.** The remedy described in this ordinance shall not be the exclusive remedy of the City for the acts and behaviors described in Section 3(C).

Section 15. [Emergency clause.]

*Passed by the Council December 12, 1994 and approved by the Mayor  
December 14, 1994.*

---

ORDINANCE NO. 2138**AN ORDINANCE GRANTING AUTHORITY AND ESTABLISHING PROCEDURES FOR INVENTORY SEARCHES BY THE WOODBURN POLICE DEPARTMENT AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose.** This ordinance is meant to exclusively apply to the process for conducting an inventory of the personal property in an impounded vehicle and the personal possessions of a person in police custody and shall not be interpreted to affect any other statutory or constitutional right that police officers may employ to search persons or search or seize possessions for other purposes.

**Section 2. Definitions.** For the purpose of this ordinance, the following definitions shall apply:

(A) "Valuables" means:

1. Cash in an aggregate amount of \$50.00 or more; or
2. Individual items of personal property with a value of over \$500.00.

(B) "Open container" means a container which is unsecured or incompletely secured in such a fashion that the container's contents are exposed to view.

(C) "Closed container" means a container whose contents are not exposed to view.

(D) "Police custody" means either:

1. The imposition of restraint as a result of an 'arrest' as that term is defined in ORS 133.005(1);
2. The imposition of actual or constructive restraint by a police officer pursuant to a court order;
3. The imposition of actual or constructive restraint by a police officer for purposes of taking the restrained person to an approved facility for the involuntary confinement of persons pursuant to Oregon law.

(E) "Police officer" means any peace officer, as defined by ORS 133.005 (3) who is employed by the Woodburn Police Department.

### Section 3. Inventories of Impounded Vehicles.

(A) The contents of all vehicles impounded by a police officer shall be inventoried. The inventory shall be conducted before constructive custody of the vehicle is released to a third-party towing company except under the following circumstances:

1. If there is reasonable suspicion to believe that the safety of either the police officer or another person is at risk, a required inventory shall be done as soon as safely practical; and

2. If the vehicle is being impounded for evidentiary purposes in connection with the investigation of a criminal offense, the inventory shall be done after such investigation is completed.

(B) The purposes for the inventory of an impounded vehicle are:

1. To promptly identify property to establish accountability and avoid spurious claims to property;

2. To assist in the prevention of theft of property;

3. To locate toxic, flammable or explosive substances; and

4. To reduce the danger to persons and property.

(C) Inventories of impounded vehicles shall be conducted according to the following procedure:

1. An inventory of personal property and the contents of open containers shall be conducted throughout the passenger and engine compartments of the vehicle including, but not limited to, accessible areas under or within the dashboard area, in any pockets in the doors or in the back of the front seat, in any console between the seats, under any floor mats and under the seats;

2. In addition to the passenger and engine compartments as described above, an inventory of personal property and the contents of open containers shall also be conducted in the following locations:

- a. Any other type of unlocked compartments that are a part of the vehicle including, but not limited to, unlocked vehicle trunks and unlocked car-top containers; and

- b. Any locked compartments including, but not limited to, locked vehicle trunks, locked hatchbacks and locked car-top containers, if either the keys are available to be released with the vehicle to the third-party towing company or an unlocking mechanism for such compartment is available within the vehicle.

3. An inventory shall include opening of closed containers located in the vehicle that are designed to hold valuables, including, but not limited to, backpacks, fanny packs, briefcases, laptop bags, and purses.

4. Upon completion of the inventory, the police officer shall complete a report.

5. Any valuables located during the inventory process shall be listed on a property receipt. A copy of the property receipt shall either be left in the vehicle or tendered to the person in control of the vehicle if such person is present. [Section 3 as amended by Ordinance 2408, passed August 14, 2006.]

#### **Section 4. Inventories of Persons in Police Custody.**

(A) A police officer shall inventory the personal property in the possession of a person taken into police custody and said inventory will occur:

1. At the time of booking; or

2. At the time custody of the person is transferred to another law enforcement agency, correctional facility, or "treatment facility" as that phrase is used in ORS 426.460 or such other lawfully approved facility for the involuntary confinement of persons pursuant to Oregon Revised Statute.

(B) The purposes for the inventory of a person in police custody are:

1. To promptly identify property to establish accountability and avoid spurious claims to property;

2. To fulfill the requirements of ORS 133.455 to the extent that such statute may apply to certain property held by the police officer for safekeeping;

3. To assist in the prevention of theft of property;

4. To locate toxic, flammable or explosive substances;

5. To locate weapons and instruments that may facilitate an escape from custody or endanger law enforcement personnel; and

6. To reduce the danger to persons and property.

(C) Inventories of the personal property in the possession of such persons shall be conducted according to the following procedures:

1. An inventory shall occur at the time of booking. However, if reasonable suspicion exists to believe that the safety of either the police officer or the person in custody or both are at risk, an inventory will be done as soon as safely practical prior to the transfer of custody to another law enforcement agency or facility.

2. To complete the inventory of the personal property in the possession of such person, the police officer shall remove all items of personal property from the clothing worn by such person. In addition, the officer will also remove all items of personal property from all open containers in the possession of such person.

3. A closed container in the possession of such person will have its contents inventoried only when:

a. the closed container is to be placed in the immediate possession of such person at the time that person is placed in the secure portion of a custodial facility, police vehicle or secure police holding room;

b. such person requests that the closed container be with them in the secure portion of a police vehicle or a secure police holding room; or

c. the closed container is designed for carrying money and/or small valuables on or about the person including, but not limited to, closed purses, closed coin purses, closed wallets and closed fanny packs.

(D) Valuables found during the inventory process shall be noted by the police officer in a report.

(E) All items of personal property not left in the immediate possession of the person in custody nor left with the facility or agency accepting custody of the person shall be handled by preparing a property receipt listing the property to be retained in the possession of the police department. A copy of that receipt will be tendered to the person in custody when such person is released to the facility or agency accepting custody of such person;

(F) All items of personal property not left in the immediate possession of the person in custody nor dealt with as provided in section 4(E) above, will be released to the facility or agency accepting custody of the person so that they may:

1. Hold the property for safekeeping on behalf of the person in custody, and

2. Prepare and deliver a receipt, if required by ORS 133.455, for any valuable held on behalf of the person in custody.

**Section 5.** [Emergency clause.]

***Passed by the Council February 13, 1995 and approved by the Mayor  
February 14, 1995.***

## ORDINANCE NO. 2312

**AN ORDINANCE REGULATING NOISE WITHIN THE CITY OF WOODBURN; PROVIDING FOR ENFORCEMENT OF NOISE REGULATIONS; AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose.** This ordinance is enacted to protect, preserve, and promote the health, safety, and welfare of the residents of the City of Woodburn through the reduction, control, and prevention of loud raucous noise, or any noise which unreasonably disturbs, injures, or endangers the comfort, repose, health, peace, or safety of reasonable persons of ordinary sensitivity.

**Section 2. Findings.**

A. Loud and raucous noise degrades the environment of the City of Woodburn because it is harmful to the health, welfare, and safety of its inhabitants and visitors; it interferes with the comfortable enjoyment of life and property; it interferes with the well-being, tranquility, and privacy of the home; and it can cause and aggravate health problems.

B. The effective control and elimination of loud and raucous noise are essential to the health and welfare of the City of Woodburn's inhabitants and visitors to conduct the normal pursuits of life, including recreation, work, and communications.

C. The use of sound amplification equipment creates loud and raucous noise that may, in a particular manner and in a particular time and place, substantially and unreasonably invade the privacy, peace, and freedom of the inhabitants and visitors to the City of Woodburn.

D. Some flexibility in noise restrictions is essential in order to allow for the construction and the maintenance of structures, infrastructure, and other elements necessary for the physical and commercial well-being of the City of Woodburn.

**Section 3. Scope.** This Ordinance shall be known as the Woodburn Noise Ordinance and will apply to control all sound originating within the jurisdictional limits of the City of Woodburn.

**Section 4. Definitions.** For the purposes of this ordinance, the following definitions apply:

A. A-SCALE (dBA). The sound level in decibels measured using the A-weighted network as specified in the American National Standard Specification for Sound Level Meters.

B. DECIBEL (dB). The unit for measuring the volume of a sound.

C. NOISE SENSITIVE UNIT Any authorized land use of a church, temple, synagogue, day care center, hospital, rest home, retirement home, group care home, school, dwelling unit (single-family dwelling, duplex, triplex, multi-family dwelling, or mobile home) or other use of the same general type, and rights-of-way appurtenant thereto, whether publicly or privately owned.

D. SOUND LEVEL METER. A sound measuring device, either Type 1 or Type 2, as defined by American National Standard Specification for Sound Level Meters.

E. SOUND PRODUCING DEVICE. A sound producing device includes, but is not limited to, the following:

- (1) Loudspeakers;
- (2) Radios, tape players, compact disc players, phonographs, boom boxes, television sets, or stereo systems, including those installed in a vehicle;
- (3) Musical instruments;
- (4) Sirens, bells or whistles;
- (5) Engines or motors;
- (6) Air, electrical, or gas-driven tools, including, but not limited to, drills, chainsaws, lawn mowers, saws, hammers or similar tools;
- (7) Motor vehicles, including automobiles, motorcycles, motorbikes, trucks, buses, snowmobiles, boats or any similar piece of equipment equipped with a propelling device;
- (8) Persons or animals causing sound to emanate.

#### **Section 5. Sound Measurements.**

A. When sound measurements are made for the enforcement of this Ordinance, they shall be made with a sound level meter. The sound level meter shall be an instrument in good operating condition, meeting the requirements of a Type I or Type II meter and shall contain at least an A-weighted scale, and both fast and slow meter response capability.

B. If sound measurements are made, the person making those measurements shall have completed training in the use of the sound level meter, and shall use measurement procedures consistent with that training

C. Measurements may be made at or within the boundary of the property on which a noise sensitive unit is located which is not the source of the sound.



**Section 6.     Noises Prohibited.**

A.       It shall be unlawful for any person to produce or permit to be produced, with any sound producing device which when measured at or within the boundary of the property on which a noise sensitive unit is located which is not the source of the sound, which sound exceeds the following levels:

(1)      55 dBA at any time between 9:00 p.m. and 7:00 a.m. of the following day where the property receiving the noise has a residential zoning designation.

(2)      65 dBA at any time between 7:00 a.m. and 9:00 p.m. of the same day where the property receiving the noise has a residential zoning designation.

(3)      60 dBA at any time between 9:00 p.m. and 7:00 a.m. of the following day where the property receiving the noise has a zoning designation which is not residential.

(4)      75 dBA at any time between 7:00 a.m. and 9:00 p.m. of the same day where the property receiving the noise has zoning designation which is not residential.

[Section 6A amended by Ordinance No. 2380, passed February 28, 2005.]

B.       In addition to Section 6A, any person producing or permitting to be produced the following noise disturbances, shall be found in violation of this Ordinance, regardless of the decibel level of the disturbance:

(1)      Repair and testing of a motor vehicle or other engine which is plainly audible within a noise sensitive unit between the hours of 9:00 p.m. and 7:00 a.m. of the following day.

(2)      The operation of any gong, bell or siren upon any vehicle, other than police, fire or other emergency vehicle.

(3)      The sounding of any motor vehicle audible anti-theft alarm system for a period of more than 20 minutes.

(4)      The use of a mechanical device operated by compressed air, steam or otherwise, unless the noise created thereby is effectively muffled.

(5)      The detonation of a blasting or explosive device, except as allowed under a permit issued by the appropriate governmental authority.

(6)      The keeping of an animal which by loud and frequent or continued noise disturbs the comfort and repose of a person in the vicinity.

(7) The erection, including excavation, demolition, alteration or repair of any building other than between the hours of 7:00 a.m. and 9:00 p.m. except in the case of urgent necessity in the interest of the public welfare and safety and then only with a permit granted by the City Administrator for a period not to exceed ten (10) days.

**Section 7. Exceptions.** The following constitute exceptions to this Ordinance and shall not be construed as violations:

A. Sounds created by organized athletic or other group activities, when such activities are conducted on public property generally used for such purposes, such as stadiums, schools, and athletic fields.

B. Sounds caused by emergency work, or by the ordinary and accepted use of emergency equipment, vehicles and apparatus.

C. Sounds caused by bona fide use of emergency warning devices and properly functioning alarm systems.

D. Sounds regulated by federal law, including but not limited to, sounds caused by railroads or aircraft.

E. Sounds caused by demolition activities when performed under a permit issued by appropriate governmental authorities.

F. Sounds caused by construction activity during the hours of 7:00 a.m. to 9:00 p.m. of the same day.

G. Sounds caused by regular vehicular traffic upon premises open to the public.

H. Sounds caused by air, electrical or gas-driven domestic tools, including but not limited to, lawn mowers, lawn edgers, saws, drills, blowers, and or other similar lawn or construction tools, during the hours of 7:00 a.m. to 9:00 p.m. of the same day.

I. Bells, chimes and carillons while being used for religious purposes or in conjunction with religious services, or for national celebrations or public holidays.

J. Parades for which a City permit has been issued.

K. Sounds resulting from an event conducted in a City park where a park use permit has been issued and the conditions of that permit and this Ordinance have been complied with.

L. Any noise resulting from activities of a temporary duration which is otherwise permitted by law.

## Section 8. Sound Amplification Permits

A. No person shall use or cause to be used any loudspeaker, loudspeaker system, sound amplifier or any other machine or device which produces, reproduces, or amplifies sound outside of an enclosed building without first having obtained a sound amplification permit.

B. Any person desiring to obtain a sound amplification permit shall submit a written application to the Police Chief no later than 30 days prior to proposed date for commencement of the amplified sound. The application shall include the following:

(1) A description of the activity proposed to be conducted for which the sound amplification permit is requested;

(2) A description of the amplification equipment or devices to be used;

(3) A statement of the measures that the applicant will take to insure that the sound amplification will not unreasonably disturb other people in the vicinity;

(4) The exact time periods and location where the sound amplification will take place;

(5) The name of the person who shall be responsible for monitoring and insuring compliance with the terms of any permit that is granted;

(6) Any City fee for processing the application; and

(7) Any other information that the Police Chief determines is reasonably needed to assure compliance with the provisions of this Ordinance.

C. The Police Chief may grant the sound amplification permit if he or she determines that the sound amplification will not occur within a residential zone and that it will be conducted in such a manner as not to unreasonably disturb the neighbors of other persons in the vicinity of the site and that the measures, if implemented, will be adequate. In granting a permit, the Police Chief may impose such conditions as may be appropriate or necessary to protect the public peace, safety, and welfare.

D. Any permit granted pursuant to this Ordinance shall be revocable at any time by the Police Chief for good cause.

E. Any person aggrieved by any decision rendered by the Police Chief pursuant to this Ordinance shall have the right to appeal the decision to the City Council. Any appeal shall be in writing and shall be submitted no later than ten (10) calendar days following the date of the decision.

**Section 9. Sound Amplification in City Parks.** Notwithstanding any other provisions of this Ordinance, the Director of Recreation and Parks is authorized to allow amplified sound in a City park by the issuance of a park use permit where a sound level of 80 dBA is not exceeded.

**Section 10. Authority for Enforcement.** This Ordinance shall be enforced by the Woodburn Police Department.

**Section 11. Civil Infraction Assessment.** Each violation of any provision of this Ordinance constitutes a class 1 civil infraction and shall be dealt with according to the procedures established by City ordinance.

**Section 12. Institution of Legal Proceedings.** The City Attorney, acting in the name of the City, may maintain an action or proceeding in a court of competent jurisdiction to compel compliance with or restrain by injunction the violation of any provision of this Ordinance as additional remedy.

**Section 13. Ordinance Additional to Other Law.** The provisions of this Ordinance shall be cumulative and non-exclusive and shall not affect any other claim, cause of action or remedy; nor, unless specifically provided, shall it be deemed to repeal, amend or modify any law, ordinance or regulation relating to noise or sound, but shall be deemed additional to existing legislation and common law on such subject.

**Section 14. Severability Clause.** If a portion of this Ordinance is for any reason held to be invalid, such decision shall not affect validity of the remaining portions of this ordinance.

**Section 15. Repeal.** Section 3 (Unnecessary Noise) of Ordinance 1900 is hereby repealed.

**Section 16. Saving Clause.** The repeal of any ordinance by this Ordinance shall not preclude any action against any person who violated the ordinance prior to the effective date of this Ordinance.

**Section 17. Emergency Clause.** This ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor.

***Passed by the Council April 8, 2002 and approved by the Mayor April 9, 2002.***

## ORDINANCE NO. 2338

AN ORDINANCE DEFINING NUISANCES; PROVIDING FOR NUISANCE ABATEMENT; ESTABLISHING A PENALTY; REPEALING ORDINANCE 1616 AND ORDINANCE 1822; AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

Section 1. Definitions.

A. Enforcement Officer. A police officer, code enforcement officer or other city official authorized by the City Administrator to enforce this Ordinance.

B. Junk. Broken, discarded, or accumulated objects, including but not limited to: appliances, building supplies, furniture, vehicles, or part of vehicles.

C. Junked Vehicle. A vehicle which is damaged or defective in any of the following respects which either make the vehicle immediately inoperable or would prohibit the vehicle from being operated in a reasonably safe manner:

1. Flat tires, missing tires, missing wheels, or missing or partially or totally disassembled tires and wheels;

2. Missing or partially or totally disassembled essential part or parts of the vehicle's drive train, including, but not limited to, engine, transmission, transaxle, drive shaft, differential, or axle;

3. Extensive exterior body damage or missing or partially or totally disassembled essential body parts, including, but not limited to, fenders, doors, engine hood, bumper or bumpers, windshield, or windows;

4. Missing or partially or totally disassembled essential interior parts, including, but not limited to, driver's seat, steering wheel, instrument panel, clutch, brake, gear shift lever;

5. Missing or partially or totally disassembled parts essential to the starting or running of the vehicle under its own power, including, but not limited to, starter, generator or alternator, battery, distributor, gas tank, carburetor or fuel injection system, spark plugs, or radiator;

6. The interior is being used as a container for metal, glass, paper, rags or other cloth, wood, auto parts, machinery, waste or discarded materials in such quantity, quality and arrangement that a driver cannot be properly seated in the vehicle;

7. The vehicle is lying on the ground (upside down, on its side, or at other extreme angle), sitting on block or suspended in the air by any other method;

8. The vehicle is located in an environment which includes, but is not limited to, vegetation that has grown up around, in or through the vehicle, the collection of pools of water in the vehicle, and the accumulation of other garbage or debris around the vehicle.

D. Owner. The owner of record, based on the Marion County's most recent taxation and assessment roll, of the property on which the alleged public nuisance exists at the time of the violation.

E. Person. Any natural person, firm, partnership, association or corporation

F. Person in Charge of Property. An owner, agent, occupant, lessee, tenant, manager, contract purchaser, bailee or other person having possession or control of property or the supervision of any construction project.

G. Responsible Party. The person responsible for abating, curing or remedying a nuisance shall include:

1. The owner,

2. A person in charge of property,

3. The person who is alleged to have committed the acts or omissions, created or allowed the condition to exist, or placed the object or allowed the object to exist on the property that constitutes a nuisance as defined in this Ordinance or another Ordinance of this city.

H. Vehicle. Any device in, upon or by which any person or property is or may be transported or drawn upon a public highway and includes vehicles that are propelled or powered by any means.

## **Section 2. Declaration of Public Nuisances.**

The acts, omissions, conditions or objects specifically enumerated in this Ordinance are hereby declared to be public nuisances and may be abated as provided in this Ordinance. In addition to the nuisances specifically enumerated in this Ordinance, every other thing, substance or act determined by the City Council to be offensive, harmful or detrimental to the public health, safety or welfare of the city is declared to be a public nuisance.

**Section 3. Nuisances Affecting the Public Health.** No person or responsible party shall cause or permit a nuisance affecting the public health. The following are declared to be nuisances affecting the public health:

A. Cesspools. Cesspools or septic tanks that are in an unsanitary condition or which cause an offensive odor.

B. Dead Animals. Any carcass or carcass part of any fowl or animal.

C. Garbage. As used in this subsection the term "garbage" means an accumulation of decomposed animal or vegetable matter, debris, rubbish, trash, filth, or refuse except:

1. Yard cuttings, other than grass clippings, may be accumulated on property owned or leased by the person for burning at the first available burn season. The accumulations shall meet the size and location requirements of the fire code.

2. Composting, but only if it is maintained in a way that does not attract vermin, and does not produce an offensive odor.

D. Odor. Premises that are in such a state or condition as to cause an offensive odor detectable at the property line.

E. Privies and Outdoor Toilet Facilities. Any privy or outdoor toilet facility, except a properly functioning portable toilet as that term is defined by the Oregon Department of Environmental Quality.

F. Rodent Attracting Condition. Any condition outside a building or structure which attracts or is likely to attract, feed or harbor rodents.

G. Stagnant Water. Stagnant water that affords a breeding place for mosquitoes and insect pests.

H. Surface Drainage. Drainage of liquid wastes from private premises.

I. Water Pollution. Any sewage, industrial waste or other substances placed in or near a body of water, well, spring, stream or drainage ditch in a way that may cause harmful material to pollute the water.

**Section 4. Nuisances Affecting the Public Safety.** No person or responsible party shall cause or permit a nuisance affecting the public safety. The following are declared to be nuisances affecting the public safety:

A. Razor and Electric Fences. A fence constructed of materials that could cause bodily harm, including, but not limited to, those conveying electric current, razor wire, spikes and broken glass.

B. Dangerous Trees. A standing dead or decaying tree that is in danger of falling or otherwise constitutes a hazard to the public or to any persons or property within the public right-of-way.

C. Hazardous Vegetation. Vegetation that reasonably constitutes a health hazard, fire hazard or traffic hazard.

D. Holes. A well, cistern, cesspool, excavation or other hole of a depth of four feet or more and a top width of 12 inches or more, unless it is covered or fenced with suitable protective construction.

E. Obstructions. Earth, rock and other debris and other objects that may obstruct or render the street or sidewalk unsafe for its intended use.

F. Snow and Ice. Snow or ice remaining on a sidewalk abutting the property of the owner or person in charge of property for longer than the first two hours of daylight after cessation of the snowfall or formation of the ice, unless covered with sand or other suitable material to assure safe travel.

#### **Section 5. Noxious Vegetation.**

A. The term "noxious vegetation" means:

1. Weeds more than ten inches high;
2. Grass more than ten inches high;
3. Poison oak, poison ivy, or similar vegetation;
4. Berry vines and bushes that extend into a public right-of-way.

B. Between May 1 and September 30 of any year, no owner or responsible party shall allow noxious vegetation to be on the property or in the right-of-way of a public thoroughfare abutting on the property. The owner or responsible party shall cut down or destroy grass, shrubbery, brush, bushes, weeds or other noxious vegetation as often as needed to prevent them from becoming unsightly or, in the case of weeds or other noxious vegetation, from maturing or from going to seed.

C. The term "noxious vegetation" does not include vegetation that constitutes an agricultural crop, unless that vegetation is a health hazard or a fire or traffic hazard.

**Section 6. Attractive Nuisances.** No person or responsible party shall permit on property:

A. Unguarded machinery, equipment or other devices which are attractive, dangerous, and accessible to children.

B. Lumber, logs, building material or piling placed or stored in a manner so as to be attractive, dangerous, and accessible to children.

C. An open pit, quarry, cistern or other excavation without safeguards or barriers to prevent such places from being used by children



D. A container with a compartment of more than one and one-half cubic feet capacity and a door or lid which locks or fastens automatically when closed and which cannot easily be opened from the inside which is accessible to children.

This section shall not apply to authorized construction projects conducted pursuant to applicable laws with reasonable safeguards to prevent injury or death to playing children.

**Section 7. Junked Vehicle Nuisances.**

A. Junked vehicles are hereby found to create a condition tending to reduce the value of property, to promote blight and deterioration, and invite plundering and vandalism, to create fire hazards, to constitute an attractive nuisance creating a hazard to the health and safety of minor, to create a harborage for rodents and insects, and to be injurious to the health, safety, and general welfare.

B. No person or responsible party shall park or in any other manner place and leave unattended on public property, a junked vehicle for more than forty-eight (48) continuous hours, even if the owner or operator of the vehicle did not intend to permanently desert or forsake the vehicle

C. No person or responsible party shall park, store, keep or maintain on private property a junked vehicle for more than thirty (30) days.

D. It shall be permissible to keep or permit the keeping of a junked vehicle within the city if the junked vehicle is completely enclosed within a building or is kept in connection with a licensed and legally zoned junkyard or automobile wrecking yard.

**Section 8. Open Storage of Junk.** No person or responsible party shall deposit, store, maintain or keep any junk on real property, except in a fully enclosed storage facility, building or garbage receptacle. This section shall not apply to material kept by a licensed and legally zoned junkyard or automobile wrecking yard.

**Section 9. Scattering Rubbish.** No person or responsible party shall deposit upon public or private property any kind of rubbish, trash, debris, refuse, or any substance that would mar the appearance of the property, create a stench or fire hazard, detract from the cleanliness or safety of the property or would be likely to cause injury to a person or animal.

**Section 10. Garbage and Debris – Disposition.** A person in charge of property shall dispose of perishable garbage before it becomes offensive promptly, but in any event at least bi-weekly; and not permit garbage to accumulate on or about the premises. All garbage shall be disposed of in a manner which does not create a nuisance and which is permitted by this chapter. Garbage may be disposed of by hauling or causing it to be hauled to a garbage dump.

**Section 11. Garbage Cans and Containers.**

A. A person in charge of property where garbage accumulates shall keep or cause to be kept on the premises one or more portable containers of a standard type suitable for deposit of garbage and shall deposit or cause to be deposited in the containers all garbage that accumulates on the premises.

B. Garbage containers shall be sturdy, watertight, not easily corrodible, rodent-and-insect-proof, and have handles at the sides and tightly fitting lids. When not being emptied or filled, the container shall be kept tightly closed and out of the city right-of-way. They shall be conveniently accessible to garbage haulers. Within 24 hours of garbage collection the person in charge of property shall remove all garbage containers from the collection point and place them either next to the side of the main dwelling unit or in a location out of the view of public or adjacent property. Residents whose point of collection is from an alley need not remove the container from the point of collection.

**Section 12. Abatement Notice.** Whenever a nuisance is found to exist within the corporate limits of the city and the enforcement officer elects to proceed by abatement, the enforcement officer shall give written notice, by a type of mail that requires a signed receipt, to the occupant of the property upon which the nuisance exists or upon the person causing or maintaining the nuisance. If the occupant is not the owner of the property, the same notice shall be sent, by a type of mail that requires a signed receipt, to the owner.

**Section 13. Abatement.** Upon receipt of the notice that a nuisance exists, the responsible party shall have seven days to abate the nuisance.

**Section 14. Notice Requirements.** The notice to abate a nuisance shall contain the following:

- A. An order to abate the nuisance within seven days;
- B. The location of the nuisance, if the same is stationary;
- C. A description of what constitutes the nuisance;
- D. A statement that if the nuisance is not abated within the prescribed time, the city will abate such nuisance and assess the cost thereof against the property.
- E. A statement that a person who is dissatisfied with the abatement notice has the right to judicial review under this Ordinance.

**Section 15. Request for Judicial Review.** An responsible party may object to the action intended by the city by filing a written request for judicial review in the Woodburn Municipal Court within five days of the date that the notice to abate was mailed.

**Section 16. Requirements for Request.** The request for judicial review need not be in any particular form, but should substantially comply with the following requirements:

- A. Be in writing;
- B. Identify the place and nature of the alleged nuisance;
- C. Specify the name and address of the person seeking judicial review;
- D. Identify the enforcement officer alleging that a nuisance exists.

A copy of the notice shall be served on the enforcement officer

**Section 17. Scheduling of Judicial Review.**

A. The judicial review hearing shall be held within ten (10) days after the request for judicial review is made. The day may be postponed by:

- 1. Agreement of the parties; or
  - 2. Order of the court for good cause.
- B. The court shall promptly notify:
- 1. The person requesting the review; and
  - 2. The enforcement officer.

**Section 18. Judicial Review Hearing.** At the judicial review hearing the city and any interested parties shall have the right to present evidence and witnesses and to be represented by legal counsel at their own expense. After due consideration of pertinent information and testimony, the court shall make its finding. The findings shall be based on substantial evidence relative to the criteria outlined in this Ordinance and shall be final.

**Section 19. Notification of Violation.** The responsible party shall be notified by a type of mail that requires a signed receipt postmarked no later than five days after the findings are entered by the court by personal delivery by a representative of the city. Upon notification of violation, the responsible party will have seven days to abate the nuisance.

**Section 20. Abatement by City.** Upon the failure of the responsible party to abate the nuisance pursuant to the provisions of this Ordinance, the enforcement officer shall proceed to abate such nuisance.

**Section 21. Abatement by City: Expenses.** The enforcement officer shall keep an accurate record of the expenses incurred by the city in physically abating the nuisance which shall include an additional administrative fee in the amount provided by the current Master Fee Schedule of the city.

**Section 22. Assessment of Costs.**

A. The enforcement officer, by certified or registered mail, postage prepaid, shall forward to the responsible party a notice stating:

1. The total cost of abatement, including the administrative overhead;

2. That the cost as indicated will be assessed to and become a lien against the property unless paid within 30 days from the date of the notice.

B. Upon the expiration of 10 days after the date of the notice, the court, in the regular course of business, shall hear and determine the objections to the costs assessed.

C. If the costs of the abatement are not paid within 30 days from the date of the notice, an assessment of the costs, as stated or as determined by the court, shall be made and shall thereupon be entered in the docket of city liens; and, upon such entry being made, shall constitute a lien upon the property from which the nuisance was removed or abated.

D. The lien shall be enforced in the same manner as liens for street improvements are enforced and shall bear interest at the legal rate. The interest shall commence to run from the date of the entry of the lien in the lien docket.

E. An error in the name of the person responsible shall not void the assessment, nor will a failure to receive the notice of the proposed assessment render the assessment void; but it shall remain a valid lien against the property.

**Section 23. Summary Abatement.** In addition to the abatement procedure provided by this Ordinance, the city may, in accordance with the law, proceed summarily to abate a health or other nuisance which unmistakably exists and which imminently endangers the environment, human life, health or property.

**Section 24. Notice.** Any notice required in this Ordinance shall be sufficient if the person to be notified is substantially apprised of the substance of the notice, notwithstanding any minor deficiencies or irregularities of form. Actual receipt of the notice is not required, as long as a good faith effort is made to deliver it.

**Section 25. Enforcement.**

A. Inspection and Right of Entry. When necessary to investigate a suspected violation of this Ordinance, the enforcement officer may enter on any site or into any structure open to the public for the purpose of investigation, provided entry is done in accordance with law. Absent a search warrant, no site or structure that is closed to the public shall be entered without the consent of the owner or occupant.

B. Civil Infraction. In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class I Civil Infraction which shall be processed according to the procedures contained in the Woodburn Civil Infraction Ordinance.

C. Civil Proceeding Initiated by City Attorney. The City Attorney, after obtaining authorization from the City Council, may initiate a civil proceeding on behalf of the city to enforce the provisions of this Ordinance. This civil proceeding may include, but is not limited to, injunction, mandamus, abatement, or other appropriate proceedings to prevent, temporarily or permanently enjoin or abate any violations of this Ordinance.

**Section 26. Separate Offenses.** Each day during which a violation of this Ordinance continues shall constitute a separate offense for which a separate penalty may be imposed..

**Section 27. Effect of Abatement.** The abatement of a nuisance is not a penalty for violating this Ordinance, but is an additional remedy. The imposition of a penalty assessment does not relieve a person of the duty to abate the nuisance.

**Section 28. Severability.** The sections and subsections of this Ordinance are severable. The invalidity of any section or subsection shall not affect the validity of the remaining sections and subsections.

**Section 29. Repeal.** Ordinance 1616 and Ordinance 1822 are hereby repealed.

**Section 30. Saving Clause.** Notwithstanding the repeal of Ordinance 1616 and Ordinance 1822, Ordinance 1616 and Ordinance 1822 shall remain in force for the purpose of authorizing the prosecution of a person who violated Ordinance 1616 or Ordinance 1822 prior to the effective date of this Ordinance.

**Section 31.** [Emergency clause.]

***Passed by the Council June 9, 2003 and approved by the Mayor June 11, 2003.***

## ORDINANCE NO. 2410

**AN ORDINANCE ESTABLISHING RULES OF CONDUCT FOR THE WOODBURN PUBLIC LIBRARY;  
PROVIDING FOR ENFORCEMENT PROCEDURES; AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** In addition to other measures provided by law, any peace officer, as defined by ORS 133.005(3) or any City of Woodburn Code Enforcement Officer may exclude any person from the premises of the Woodburn Public Library as provided in this Ordinance.

**Section 2.** No person shall enter or remain on the premises of the Woodburn Public Library at any time after a Notice of Exclusion issued under this Ordinance is in effect.

**Section 3.** A Notice of Exclusion issued under this Ordinance shall be for thirty (30) days. If the person to be excluded has been excluded from the premises of the Woodburn Public Library at any time, within two years before the date of the present exclusion, the exclusion shall be for ninety (90) days. If the person to be excluded has been excluded from the Woodburn Public Library on two or more occasions within two years before the date of the present exclusion, the exclusion shall be for one-hundred eighty (180) days.

**Section 4.** When there is reasonable cause to believe that a person has committed any of the following acts on the premises of the Woodburn Public Library, a Notice of Exclusion shall be issued and the person shall be directed to leave the library without first being give a warning:

- (A) Any activity that would constitute a violation of any federal or state criminal law.
- (B) Engaging in sexual conduct, as defined under ORS 167.060.
- (C) Possessing or consuming any alcoholic beverages.
- (D) Possessing or consuming any controlled substances in violation of ORS Chapter 475.

**Section 5.** When there is reasonable cause to believe that a person has committed any of the following acts on the premises of the Woodburn Public Library, a Notice of Exclusion shall be issued only after the person has first been given a warning and a reasonable opportunity to desist from the violation:

(A) Engaging in conduct that unreasonably disrupts or interferes with the normal operation of the library, or disturbs library staff or patrons. This conduct includes but is not limited to abusive or threatening language or gestures, conduct that creates unreasonable noise, or conduct that consists of loud or boisterous physical behavior.

(B) Using library materials, equipment, furniture, fixtures or buildings in a manner inconsistent with the customary use thereof; or in a destructive, abusive or potentially damaging manner, or in a manner likely to cause personal injury to the actor or others.

(C) Soliciting, petitioning, distributing written materials or canvassing for political, charitable or religious purposes.

(D) Interfering with the free passage of library staff or patrons, including but limited to, placing objects such as bicycles, skateboards, backpacks or other items in a manner that interferes with free passage.

(E) Operating roller skates, skateboards or other similar devices.

(F) Smoking or other use of tobacco.

(G) Bringing an animal into the library, except a Seeing Eye or Hearing Ear dog, or other animal trained to assist a person with a disability.

(H) Improperly using library restrooms, including but not limited to, bathing, shaving, washing hair and changing clothes.

(I) Using personal electronic equipment at a volume that disturbs others, including but not limited to, pagers, stereos, televisions and cellular phones.

(J) Failing to leave the library at closing time.

(K) Eating or drinking except as expressly allowed by the Library Director in the course of a library-approved event.

**Section 6.** Where there is reasonable cause to believe that a person has committed any of the following acts, the person may be directed to leave the premises of the Woodburn Public Library until the problem is corrected:

(A) Not wearing shoes or other footwear.

(B) Not wearing a shirt or other covering of the upper body.

**Section 7.** A Notice of Exclusion under this Ordinance shall specify the date the exclusion is to commence, the term of the exclusion, the provision of law that the person violated, and a brief description of the offending conduct. It shall be signed by the issuing party. The Notice of Exclusion shall provide information concerning the right to appeal the notice and to apply for a temporary waiver from the effects of the notice

warning of consequences for failure to comply shall be prominently displayed on the notice.

**Section 8.** Notices of Exclusion shall take effect immediately except that if a timely appeal is filed under this Ordinance, the effectiveness of the exclusion shall be stayed pending the outcome of the appeal. If the exclusion is affirmed, the remaining period of the exclusion shall become effective immediately upon issuance of the Woodburn Municipal Court decision, unless the Court sets a later effective date.

**Section 9.** A person receiving a Notice of Exclusion may appeal to the Woodburn Municipal Court to have the notice rescinded or the exclusion period shortened. In order to be timely, an appeal must be filed within five (5) days of receipt of the Notice of Exclusion.

(A) The appeal need not be in any particular form, but should substantially comply with the following requirements:

- (i) Be in writing
- (ii) *Identify the date, time, and place of the exclusion*
- (iii) *Identify the name and address of the appealing party*
- (iv) Identify the official who issued the exclusion
- (v) Contain a concise statement as to why the Notice of Exclusion was issued in error

(B) A copy of the appeal shall be served on the City Attorney.

(C) *An appeal hearing shall be conducted by the Woodburn Municipal Court and a decision on the appeal shall be made by the Court within ten (10) days after the appeal is filed.*

(D) *At the appeal hearing the City and any interested parties shall have the right to present evidence and witnesses and be heard. After due consideration of pertinent information and testimony the Court shall issue a written decision. The decision of the Court shall be final.*

**Section 10.** At any time within the exclusion period, a person receiving a Notice of Exclusion may apply in writing to the City Administrator for a temporary waiver from the effects of the notice for good cause shown. In exercising discretion under this section, the City Administrator shall consider the seriousness of the violation for which the person has been excluded, the particular need of the person to be on the premises of the Woodburn Public Library during some or all of the period of exclusion, such as for work or to attend or participate in a particular event (without regard to the content of any speech associated with that event), and any other criterion the City Administrator determines to be relevant to the determination of whether or not to grant a waiver. The decision of the City Administrator to grant or deny, in whole or in part, a waiver under this section is committed to the discretion of the City Administrator, and is not subject to appeal or review.



---

**Section 11.** [Emergency clause.]

*Passed by the Council September 25, 2006 and approved by the Mayor September 27, 2006.*

## ORDINANCE NO. 2411

AN ORDINANCE PROHIBITING GRAFFITI AND THE POSSESSION OF GRAFFITI IMPLEMENTS; CREATING THE OFFENSE OF FAILURE TO SUPERVISE A MINOR COMMITTING GRAFFITI VIOLATIONS; PROVIDING FOR THE ABATEMENT OF GRAFFITI NUISANCE PROPERTY; AND REPEALING ORDINANCE 2173

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions:**

A. "Graffiti" means any inscriptions, words, figures or designs that are marked, etched, scratched, drawn, painted, pasted or otherwise affixed to the surface of property, as defined by ORS 164.381(1).

B. "Graffiti implement" means any paint, ink, chalk, dye or other substance or any instrument or article designed or adapted for spraying, marking, etching, scratching or carving surfaces as defined by ORS 164.381(2).

C. "Graffiti nuisance property" means property to which graffiti has been applied, if the graffiti is visible from any public right-of-way, any other public or private property or from any premises open to the public, and if the graffiti has not been abated within the time required by this ordinance.

D. "Owner" means the legal owner of property or a person in charge of property.

E. "Person in charge of property" means an agent, occupant, lessee, contract purchaser or other person having possession or control of property or supervision of a construction project.

F. "Property" means any real or personal property and that which is affixed, incident or appurtenant to real property, including but not limited to any premises, house, building, fence, structure or any separate part thereof, whether permanent or not.

**Section 2. Prohibited Graffiti.** It shall be unlawful for any person to apply graffiti.

**Section 3. Unlawful Possession of Graffiti Implement.** It shall be unlawful for any person to possess a graffiti implement with the intent to apply graffiti.

**Section 4. Failure to Supervise a Minor Committing Graffiti Violations.** It shall be unlawful for a parent, guardian, or other person having the legal custody of a minor person under the age of 18 years to allow or permit the minor to be in violation of Section 2 or Section 3 of this ordinance.

**Section 5. Graffiti Nuisance Property.**

A. It is hereby found and declared that graffiti creates a visual blight and property damage. When graffiti is allowed to remain on property and not promptly removed, it invites additional graffiti, gang activity, criminal activity, and constitutes a nuisance.

B. Any property within the city which becomes graffiti nuisance property is in violation of this ordinance.

C. Any owner of property who permits said property to be a graffiti nuisance property is in violation of this ordinance.

**Section 6. Notice Procedure.**

A. When the Chief of Police believes in good faith that property within the city is a potential graffiti nuisance property, the Chief of Police shall, notify the owner in writing that the property is a potential graffiti nuisance property. The notice shall contain the following information:

(1) The street address or description sufficient for identification of the property.

(2) That the Chief of Police has found the property to be a potential graffiti nuisance property with a concise description of the conditions leading to this finding.

(3) A direction to abate the graffiti, or show good cause to the Chief of Police why the owner cannot abate the graffiti, within ten city business days from service of the notice.

(4) That if the graffiti is not abated and good cause for failure to abate is not shown, the City Council may order abatement, with appropriate conditions. The City Council may also employ any other remedy deemed by it to be appropriate to abate the nuisance, including but not limited to authorizing a civil complaint to be filed in a court of competent jurisdiction.

(5) That permitting graffiti nuisance property is a Class 2 civil infraction punishable by a civil forfeiture not to exceed \$750, pursuant to the Civil Infraction Ordinance.

(6) That the above remedies are in addition to those otherwise provided by law.

B. Service of the notice is completed by personal service or upon mailing the notice by first class mail, postage prepaid, addressed to the owner at the owner's last known address.

C. A copy of the notice shall be served on occupants of the property, if different from the owner.

D. The failure of any person or owner to receive actual notice of the determination by the Chief of Police shall not invalidate or otherwise affect the proceedings under this ordinance.

#### **Section 7. Abatement Procedures.**

A. Within ten business days of the personal service or mailing of the notice the owner shall abate the graffiti or show good cause why the owner cannot abate the graffiti within that time period.

B. Upon good cause shown, the Chief of Police may grant an extension not to exceed ten additional city business days.

C. If the owner does not comply with the provisions of this ordinance, the Chief of Police may refer the matter to the City Council for hearing as a part of its regular agenda at the next succeeding meeting. The City Recorder shall give notice of the hearing to the owner and occupants, if the occupants are different from the owner.

D. At the time set for a hearing, the owner and occupants may appear and be heard by the City Council.

E. The City Council shall determine whether the property is graffiti nuisance property and whether the owner has complied with this ordinance.

F. The city has the burden of proving by a preponderance of the evidence that the property is graffiti nuisance property.

G. The owner has the burden of proving by a preponderance of the evidence that there is good cause for failure to abate the nuisance within ten city business days of the personal service or mailing of the notice.

#### **Section 8. REMEDIES OF THE CITY.**

A. In the event that the City Council determines that the property is graffiti nuisance property, the City Council may order that the nuisance be abated. This order may include conditions under which abatement is to occur.

B. The City Council may also employ any other legal remedy deemed by it to be appropriate to abate the nuisance, including but not limited to authorizing the filing of a civil complaint in a court of competent jurisdiction.

C. The remedies provided in this section are in addition to those otherwise provided by law.

**Section 9. Civil Penalties.** Violations of this ordinance shall be processed under the Civil Infraction Ordinance with penalties consistent with Oregon state law.

A. Consistent with ORS 164.383 and ORS 153.018, a violation of Section 2 of this ordinance ("Prohibited Graffiti") constitutes a civil infraction punishable by a civil forfeiture not to exceed \$360.

B. Consistent with ORS 164.386 and ORS 153.018, a violation of Section 3 of this ordinance ("Unlawful Possession of Graffiti Implement") constitutes a civil infraction punishable by a civil forfeiture not to exceed \$90.

C. A violation of Section 4 of this ordinance ("Failure to Supervise a Minor Committing Graffiti Violations") constitutes a Class 2 civil infraction punishable by a civil forfeiture not to exceed \$500.

D. A violation of Section 5 of this ordinance ("Graffiti Nuisance Property") constitutes a Class 2 civil infraction punishable by a civil forfeiture not to exceed \$500.

**Section 10. Alternate Disposition by Court.** At the discretion of the Woodburn Municipal Court, all persons that are found to have violated Sections 2, 3, or 4 of this ordinance may have their cases resolved by the following alternate dispositions:

A. A court-approved diversion program.

B. Dismissal of the case, if a letter is received from the Marion County Juvenile Department indicating that the offender has complied with all of its requirements related to the case and the court determines that it is in the interest of justice to dismiss the case.

**Section 11. Abatement by the City.** If the owner fails to abate the nuisance as ordered by the City Council, the city may cause the nuisance to be abated as provided in the City Nuisance Ordinance, Ordinance 2338.

**Section 12. Repeal.** Ordinance 2173 is hereby repealed.

***Passed by the Council October 9, 2006 and approved by the Mayor October 11, 2006.***

## ORDINANCE NO. 2434

**AN ORDINANCE CONCERNING THE CARE AND CONTROL OF ANIMALS; ESTABLISHING REGULATIONS AND PENALTIES; AND REPEALING ORDINANCE 1638.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Definitions.** For purposes of this Ordinance, these terms are defined as follows:

- A. ANIMAL. Any nonhuman vertebrate.
- B. ANIMAL CONTROL OFFICER. A person designated by the Woodburn Chief of Police to enforce this Ordinance.
- C. AT LARGE. Any animal, excluding domestic cats, that is off the premises of its keeper and is not on a leash held by a person capable of controlling the animal.
- D. DOG. Any mammal of the canidae family excluding, for purposes of this Ordinance, any dog used by a law enforcement agency in the performance of work.
- E. EUTHANIZE. To put an animal to death in a humane manner by a licensed veterinarian or a certified euthanasia technician.
- F. FOWL. Any chicken, duck, goose, guinea fowl, peafowl, peacock, turkey, dove, pigeon, game bird, or similar bird.
- G. KEEP. To have physical custody or otherwise exercise dominion and control over.
- H. KEEPER. A person or legal entity who owns, or has a possessory property right in an animal or who harbors, cares for, exercises control over, or knowingly permits any animal to remain on premises occupied by that person.
- I. LIVESTOCK. Animals, including but not limited to the following: (1) fowl; (2) horses; (3) mules; (4) burros; (5) asses; (5) cattle; (6) sheep; (7) goats; (8) llamas; (9) emu; (10) ostriches; (11) swine; or (12) any furbearing animal bred and maintained for commercial purposes and kept in pens, cages, or hutches.
- J. MUNICIPAL JUDGE. The judge of the Woodburn Municipal Court.
- K. PEACE OFFICER. Has the meaning provided in ORS 161.015 (4).
- L. PERMIT. To allow, make possible, afford opportunity, acquiesce by failure, refusal or neglect to abate.

M. PERSON. Any natural person, association, partnership, firm or corporation.

N. PHYSICAL DEVICE OR STRUCTURE. A tether, trolley system, other physical control device or any structure made of material sufficiently strong to adequately and humanely confine the animal in a manner that would prevent it from escaping.

O. PHYSICAL INJURY. Physical impairment as evidenced by scrapes, cuts, punctures, bruises or physical pain.

P. SECURE ANIMAL SHELTER. An animal shelter that agrees to accept an animal and that agrees to the following conditions:

1. Not to release the animal from the shelter for the rest of the animal's natural life;

2. Not to allow the animal to come into contact with the general public for the rest of the animal's natural life;

3. To indemnify, defend, and hold the City harmless from any and all future claims of any kind or nature whatsoever relative to past or future care and custody of the dog and to the dog's future behavior;

4. To notify the City if the shelter goes out of business or can no longer keep the animal and to abide by the City's disposition instructions.

Q. SECURE ENCLOSURE. Shall be any of the following:

1. A fully fenced pen, kennel or structure that shall remain locked with a padlock or combination lock. Such pen, kennel or structure must have secure sides, minimum of five feet high, and a secure top attached to the sides, and a secure bottom or floor attached to the sides of the structure or the sides must be embedded in the ground no less than one foot to prevent digging under it. The structure must be in compliance with the City's building code and ordinances; or

2. A house or garage. When dogs are kept inside a house or garage as a secure enclosure, the house or garage shall have latched doors kept in good repair to prevent the accidental escape of the dog. A house, garage, patio, porch or any part of the house or condition of the structure is not a secure enclosure if the structure would allow the dog to exit the structure of its own volition

R. SERIOUS PHYSICAL INJURY. Any physical injury which creates a substantial risk of death or which causes disfigurement, or protracted loss or impairment of health or of the function of any body part or organ.

## **Section 2. Keeping of Certain Animals Prohibited.**

A. No person shall keep any of the following animals of either thoroughbred or hybrid stock or pedigree:

1. All poisonous animals, including rear-fang snakes;

2. Apes such as chimpanzee (Pan), gibbons (Hylobates), gorillas (Gorilla), orangutans (Pongo), and siamangs (Symphalangus);
3. Baboons (Papio, Mandrillus);
4. Bears (Ursidae);
5. Bison (Bison);
6. Cheetahs (Acinonyx jubatus);
7. Constrictor snakes exceeding five feet in length;
8. Crocodilians (Crocodilia);
9. Coyotes (Canis latrans);
10. Deer (Cervidae), such as white-tailed deer, elk, antelope, and moose;
11. Elephants (Elephas and Loxodonta);
12. Game cocks and other fighting birds;
13. Hippopotami (Hippopotamidae);
14. Hyenas (Hyaenidae);
15. Jaguars (Panthera onca);
16. Leopards (Panthera pardus);
17. Lions (Panthera leo);
18. Lynxes (Lynx);
19. Monkeys, old world (Cercopithecidae), new world;
20. Ostriches (Struthio);
21. Piranha fish (Characidae);
22. Pumas (Felis concolor), such as cougars, mountain lions, and panthers;
23. Raptors, such as condors, eagles, kites, falcons, osprey, owls, harriers, hawks, buzzards and vultures (Falconiformes and Stigiformes orders)
24. Rhinoceroses (Rhinocerotidae);
25. Serval Cats (Felis serval or Leptailarus serval)
26. Sharks (Class Chondrichthyes);
27. Snow leopards (Panthera uncia);
28. Tigers (Panthera tigris); or
29. Wolves (Canis lupus and hybrids).

B. The provisions of this section shall not apply to:

1. An educational or medical institution, if the animal is kept for the primary purpose of instruction, study or research; or
2. A circus, carnival or other similar itinerant show business, if the animal is kept for the primary purpose of public entertainment; or
3. A veterinarian employed by the federal government or currently licensed by the Oregon State Veterinary Examining Board, if the animal is kept for the primary purpose of diagnosis or treatment.

**Section 3. Keeping of Livestock Generally Prohibited.** Except as permitted by this Ordinance, no person shall keep livestock.

**Section 4. Keeping of Limited Number of Chickens or Ducks Permitted.** Notwithstanding Section 3 of this Ordinance, a person shall be allowed to keep a total



of three or fewer chickens or ducks. The chickens or ducks kept under this section shall be enclosed in coops or pens and kept in a clean and sanitary condition. This section shall not be construed to as to allow the keeping of roosters, which are prohibited.

**Section 5. Duties of Animal Keepers.**

A. It shall be a violation of this Ordinance for a keeper of an animal to:

1. Permit an animal to be at large.
2. Permit an animal to cause unreasonable noise at any time of the day or night by repeated barking, whining, screeching, howling, braying or other like sounds which may be heard beyond the boundary of the keeper's property.
3. Permit an animal to damage or destroy property of persons other than the keeper.
4. Fail to immediately remove any excrement or other solid waste deposited by an animal on public property or the property of another.

**Section 6. Placing of Poisonous Food Prohibited.** No person shall knowingly place food of any description containing poisonous or other injurious ingredients in any area reasonably likely to be accessible to animals, except as provided by law for nuisance, vector, or predator control.

**Section 7. Confining Animals in Motor Vehicles Prohibited.**

A. No animal shall be confined within or on a motor vehicle at any location within the city under such conditions as may endanger the health or well-being of the animal, including but not limited to dangerous temperature, lack of food, water or confinement with a dangerous animal.

B. An animal control or police officer is authorized to remove an animal from a motor vehicle when the officer reasonably believes that the animal is confined in violation of this section. Any animal so removed shall be delivered to the Marion County Animal Control Shelter after the removing officer leaves written notice of the removal and delivery, including the officer's name, in a conspicuous, secure location on or within the vehicle.

**Section 8. Dog Licensing.** Any person owning or keeping a dog within the City shall purchase for such a dog a license as required under the provisions of ORS 609.100.

**Section 9. Levels of Dangerous Dogs.**

A. For purposes of this Ordinance, the classification of various levels of dangerous dogs shall be based upon these specific behaviors exhibited by the dogs.

1. Level 1 behavior is established if a dog, while at large, is found to menace, chase, display threatening or aggressive behavior or otherwise threaten or endanger the safety of any person.

2. Level 2 behavior is established if a dog, while at large, bites or causes physical injury to any dog or cat.

3. Level 3 behavior is established if a dog bites or causes physical injury to any person.

4. Level 4 behavior is established if:

(a) A dog causes the serious physical injury or death of any person; or

(b) A dog, while at large, kills a dog or cat.

**Section 10. Keeping of Dangerous Dog; Penalty; Defenses.**

A. Any person who keeps a Level 1 Dangerous Dog commits a Class 4 civil infraction.

B. Any person who keeps a Level 2 Dangerous Dog commits a Class 3 civil infraction.

C. Any person who keeps a Level 3 Dangerous Dog commits a Class 2 civil infraction.

D. Any person who keeps a Level 4 Dangerous Dog commits a Class 1 civil infraction.

E. The following affirmative defenses may be presented:

1. The dog's behavior was the direct result of the victim abusing or tormenting the dog, or

2. The dogs' behavior was directed against a trespasser on the keeper's property.

**Section 11. Keeping of Dog Pursuant to Court Order Permitted.** Notwithstanding Section 10 of this Ordinance, dogs classified as dangerous dogs by the Municipal Judge may be lawfully kept pursuant to the terms of a Municipal Court order.

---

**Section 12. Classification of Dogs by Municipal Judge.**

A. In addition to any other penalties imposed under this Ordinance, the municipal judge shall have the power to classify dangerous dogs based upon the dogs' behavior. This classification shall be based upon evidence proving the dogs' behavior by a preponderance of the evidence.

**Section 13. Disposition of Dangerous Dog Cases.**

A. In addition to any other penalties imposed under this Ordinance, the keeper of a dog found by the municipal judge to be a dangerous dog shall be ordered by the court to do the following:

1. If the dog was found to have engaged in Level 1 behavior, the keeper shall provide a physical device or structure that prevents the dog from reaching any public right-of-way or adjoining property, and shall restrict the dog by such a device or structure whenever the dog is outside the keeper's home and not on a leash off the keeper's property.

2. If the dog was found to have engaged in Level 2 or Level 3 behavior, the keeper shall provide a secure enclosure and confine the dog within such enclosure whenever the dog is not on a leash, off the keeper's property or inside the home of the keeper.

**Section 14. Disposition of Level 3 or 4 Dangerous Dog Cases.**

A. If the dog was found by the municipal judge to have engaged in Level 3 or 4 behavior, the municipal judge shall provide an opportunity to the keeper and the City regarding the appropriate disposition of the dog.

B. If the dog was found by the Municipal Judge to have engaged in Level 4 behavior, the Municipal Judge shall order:

1. That the City euthanize the dog; or
2. That the dog be sent at the keeper's expense to a secure animal shelter; or
3. That the dog be removed from the City as specified in this Ordinance.

C. If the dog was found by the Municipal Judge to have engaged in Level 3 behavior, the Municipal Judge may order:

1. That the City euthanize the dog; or
2. That the dog be sent at the keeper's expense to a secure animal shelter; or

3. That the dog be removed from the City as specified in this Ordinance; or

4. That there be a different disposition of the case as determined to be fair and appropriate by the Court.

D. The keeper shall be responsible for all fees and charges related to the care, keeping, or euthanizing of the dog.

E. The municipal judge will consider ordering that the dog be sent to a secure animal shelter only at the request of the keeper. The keeper shall bear the burden of establishing that an animal shelter is available that meets the criteria for a secure animal shelter, that the shelter will accept the dog, and that the keeper is willing and able to pay all expenses for transporting and caring for the dog.

F. After conclusion of the hearing, the municipal judge shall issue an order finding that the dog has engaged in Level 3 or 4 behavior and providing for disposition of the dog. This order shall include findings justifying the Court's action. A copy of the order, including notice of the right to file a Writ of Review in Marion County Circuit Court shall be sent by regular and certified mail, return receipt requested, or delivered by personal service to the keeper of the dog.

**Section 15. Removal of Animals from the City** Prior to releasing an animal for removal from the City pursuant to this Ordinance the municipal judge shall require: (1) proof that an appropriate place outside of the incorporated limits of the City is available to keep the animal; (2) proof that the animal control authority in the jurisdiction to which the animal is being moved has been informed of the relocation and has had an opportunity to address the Court; (3) agreement by the animal's owner to indemnify, defend, and hold the City harmless from any and all future claims of any kind or nature whatsoever relative to past or future care and custody of the animal and to the animal's future behavior. If these requirements are not met, the Municipal Judge may order the animal seized and delivered to the Marion County Animal Control Shelter with instruction to dispose of the animal at the end of five days unless during that period, the owner sells the animal or meets the requirements under this section. The owner shall pay the costs of the action.

**Section 16. Shelter Operations; Impoundment, Release and Disposal.**

A. The Marion County Animal Control Shelter is designated as the facility to receive, care for and confine any animal delivered to its custody under the provisions of this Ordinance. This impound facility shall be operated by Marion County Animal Control for the conduct of necessary business concerning impounded animals. Impounded animals may be temporarily housed in a kennel designated by the Chief of Police prior to their transport to the Marion County Animal Shelter.

B. Impoundment is subject to the following holding period and notice requirements:

1. An animal bearing identification shall be held for five working days before any action is taken to dispose of the animal. The City shall make reasonable effort within twenty-four hours of impoundment to notify the keeper, shall send by registered or certified mail, a written notice of the impoundment to the last known address of the keeper, advising the keeper of the impoundment, the date by which redemption must be made and the fees payable prior to redemption release.

2. An animal that does not bear identification shall be held for three working days before any disposition may be made.

3. Animals held for period prescribed herein, or as otherwise required by ORS 433.340 to 433.390, and not redeemed by the keeper, shall be subject to disposal consistent with Marion County Animal Control procedures.

4. In instances where a peace officer impounds animals from a person taken into custody, the peace officer shall issue a receipt to the person reciting the redemption requirements under this Ordinance and shall serve this receipt upon the person.

C. Unless restrained by Court order, the impound facility shall release any impounded animal to the keeper or the keeper's authorized representative upon payment of all applicable impoundment, shelter, care, medical costs, license fees or other applicable fees or deposits.

**Section 17. Penalty for Unspecified Violations.** The violation of any section of this Ordinance where the penalty is not specified constitutes a Class 4 civil infraction.

**Section 18. Authorized Enforcement Officers.** The following City officials are authorized to enforce this Ordinance:

- A. An animal control officer;
- B. A peace officer; and
- C. The Woodburn City Administrator or designee.

**Section 19. Animal Nuisance Enforcement.** If there are reasonable grounds to believe that any animal constitutes a public nuisance, an action may be instituted by the City Attorney under Ordinance 2338, the Woodburn Nuisance Ordinance, as an additional remedy.

**Section 20. Institution of Legal Proceedings.** The City Attorney, acting in the name of the City, may maintain an action or proceeding in a court of competent jurisdiction to compel compliance with or restrain by injunction the violation of any provision of this Ordinance as additional remedy.

**Section 21. Exclusive Review in Marion County Circuit Court.** All determinations by the municipal judge under this Ordinance shall be final and subject only to Writ of Review in the Marion County Circuit Court pursuant to ORS Chapter 34.

**Section 22. Savings Clause.** The repeal of any ordinance by this Ordinance shall not preclude any action against any person who violated the ordinance prior to the effective date of this Ordinance.

**Section 23. Severability.** The sections and subsections of this Ordinance are severable. The invalidity of any section or subsection shall not affect the validity of the remaining sections and subsections.

**Section 24. Repeal.** Ordinance No. 1638 is hereby repealed.

*Passed by the Council March 24, 2008 and approved by the Mayor March 26, 2008.*

## ORDINANCE NO. 1856

## AN ORDINANCE APPOINTING A HEARINGS OFFICER TO PRESIDE OVER ABANDONED VEHICLE HEARINGS PURSUANT TO O.R.S. CHAPTER 483 AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Appointment.** The Council, pursuant to O.R.S. 483.357 appoints the Woodburn Municipal Judge as a hearings officer with the powers and functions set forth in O.R.S. Chapter 483.

**Section 2. Service.** The Municipal Judge shall serve in the capacity of hearings officer pursuant to O.R.S. Chapter 484 and shall serve at the pleasure of the Council.

**Section 3.** [Emergency clause.]

*Passed by the Council February 13, 1984, and approved by the Mayor  
February 14, 1984.*

## ORDINANCE NO. 1957

**AN ORDINANCE DESIGNATING TRUCK ROUTES; PROHIBITING USE GENERALLY OF OTHER STREETS, ROADS AND HIGHWAYS FOR OPERATION OF TRUCKS, OR HEAVY VEHICLES, AND PROHIBITING USE OF AIR EXHAUST BRAKES.**

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Definitions.** For the purposes of this ordinance the following definitions apply:

(1) "Motor Truck" for this ordinance means every motor vehicle used or maintained primarily for the transportation of property and having a gross weight in excess of 10,000 pounds, excluding recreational vehicles, emergency governmental vehicles, up to one-ton pickups, tow trucks, busses and city franchised vehicles.

(2) "Truck Trailer" means every vehicle without motive power which:

(a) Has a combined weight of vehicle and maximum load to be carried thereon of more than 10,000 pounds.

(b) Is designated for carrying property and for being drawn by a motor vehicle.

(3) "Truck Tractor" means any motor vehicle used or designed for use with a semi-trailer for carrying, conveying, or moving over the highways any freight, property, article or thing, and having a combined weight of vehicle and maximum load to be carried thereon of more than 10,000 pounds.

(4) "Truck Route" means a street, alley, or other public right-of-way which has been designated by this ordinance as an acceptable roadway for the through-city transportation of motor trucks, truck trailers, and truck tractors.

(5) "Truck Way" means a street, alley, or other public right-of-way which has been designated by this ordinance as an acceptable roadway for the commercial operation of motor trucks, truck trailers, and truck tractors, but does not constitute a through-city route necessary for specialized traffic directional control signs.

**Section 2. Motor Truck Traffic Prohibited.**

(1) Except as provided in subsection (2), no person shall operate any motor truck upon any public street or alley within the city unless such street or alley has been designated as a truck route or truck way.

(2) It shall be an affirmative defense to a violation of Section 2(1) that the motor truck is being operated on a public street or alley for the primary purpose of engaging in one or more of the following activities:



- 
- (a) Receiving or discharging goods at any location in the city;
  - (b) Going to or from a business in the city for the purpose of fuel, service, or repair; or
  - (3) Servicing utility facilities or construction sites in the city.

(3) Motor trucks operated on a public street or alley for the primary purpose of engaging in one or more of the activities listed in Section 3(2) shall use only designated truck routes or truck ways prior to the point where the activity requires a different route of travel. (Section 2 amended by Ordinance 2169 passed by the Council May 13, 1996.)

**Section 3. Truck Routes and Truck ways Established.**

(1) Those streets, roads, and highways located within the limits of the city of Woodburn, shown on Schedule "A" and Schedule "B" are hereby designated as truck routes and truck ways.

(2) The Public Works Director is hereby authorized and directed to erect and maintain specialized traffic directional control signs on designated truck routes in a conspicuous manner and place at each end of the roadway or section thereof in order to give notice of such regulation.

**Section 4.** The use of air exhaust brakes (jake brakes) on city streets, alleys and right-of-ways within the city of Woodburn is prohibited.

**Section 5. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 5 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 5 as amended by Ordinance 2008 passed October 24, 1988.]

***Passed by the Council July 28, 1986 and approved by the Mayor July 30, 1986.***

## ORDINANCE NO. 1988

AN ORDINANCE PROHIBITING ON-STREET AND PUBLIC PLACE PARKING IN A PORTION OF THE DOWNTOWN AREA TO PREVENT INTERFERENCE WITH STREET CLEANING OPERATIONS, PROVIDING FOR CIVIL ENFORCEMENT, REPEALING ORDINANCE 1986, AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Purpose.** The City Council finds that the public safety responsibilities associated with street cleaning and general maintenance in the downtown business district are paramount to providing for the general welfare and encouraging the flow of goods and services. In addition, the limited clearing of on-street parking spaces and public place parking spaces will facilitate a safe, effective, and efficient maintenance operation for the public's benefit.

**Section 2. Definitions.** In addition to those definitions contained in the "Oregon Vehicle Code," the following definitions apply:

- (A) "Administrator" shall mean the City Administrator or his designee.
- (B) "Public Parking Space" shall mean every public way, road, street, thoroughfare, and place open, used or intended for use by the general public for parking motor vehicles.
- (C) "Downtown Parking District" shall mean an area composed by the following street boundaries as referenced in Attachment "A".
  - (1) The East and West sides of Front Street between Cleveland and Hardcastle.
  - (2) The East and West sides of First Street between Harrison and Cleveland Streets.
  - (3) The West side of Second Street between Cleveland and Grant Streets, and the East side of Second Street between Garfield and Grant Streets.
  - (4) The North and South sides of Harrison, Lincoln, Garfield and Arthur Streets between Front and First Streets.
  - (5) The North and South sides of Grant and Hayes Streets between Front and Second Streets.
  - (6) The North side of Montgomery Street between First and Second Streets.
  - (7) The North side of Cleveland Street between First and Second Streets.

(8) The North and South sides of Cleveland Street between Front and First Street.

(D) "Enforcement Officer" shall mean the Police Chief or his designee.

### **Section 3. General Provisions.**

(A) In addition to the applicable sections of the "Oregon Vehicle Code" prohibiting parking, no person shall park or stand a motor vehicle in a public parking place within the Downtown Parking District between the hours of 3:00 a.m. - 6:00 a.m. upon the day(s) of the week so posted by a lawfully erected parking limitation sign for the clearance of motor vehicles on account of public street cleaning and maintenance operations.

(B) The prohibition contained in subsection 3(A) of this ordinance above shall not apply upon the legal holidays observed by the City of Woodburn.

### **Section 4. Administration.**

(A) The Administrator shall be responsible for the installation and maintenance of applicable parking signs and the conduct of business operations associated with street cleaning and maintenance within the Downtown Parking District.

(B) Enforcement of the provisions of this ordinance shall be the duty of the enforcement officer.

(C) A parking citation issued in violation of this ordinance shall be placed on or in such motor vehicle in accordance with the "Oregon Vehicle code".

**Section 5. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 5 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 5 as amended by Ordinance 2008 passed October 24, 1988.]

### **Section 6. Towing and Storage.**

(A) Any motor vehicle violating the provisions of this ordinance shall constitute a hazard to public safety and the enforcement officer shall cause the motor vehicle to be towed and stored at the registered owner's expense if left unattended. The registered owner shall be liable for the costs of towing and storing, even if the vehicle was parked by another person.

(B) Towing and storage of any motor vehicle pursuant to this ordinance does not preclude the issuance of a citation for a violation of any provision of this ordinance.

**Section 7. Disposal of Motor Vehicle.** After a motor vehicle is towed under the authority of this ordinance it shall be disposed of in the manner provided by ORS 819.180 to ORS 819.260.

**Section 8.     Severability.** If any section, clause, or phrase of this ordinance or its application to any statute, is determined by any court of competent jurisdiction to be invalid or unenforceable for any reason, such determination shall not affect the validity of the remainder of this ordinance or its application.

**Section 9.     Repeal.** Ordinance No. 1986 is hereby specifically repealed.

**Section 10.**   [Emergency clause.]

*Passed by the Council January 25, 1988 and approved by the Mayor  
January 27, 1988.*

## ORDINANCE NO. 2257

AN ORDINANCE PERMITTING THE USE OF GOLF CARTS IN DESIGNATED AREAS; REGULATING SUCH USE PURSUANT TO THE REQUIREMENTS OF STATE LAW; REPEALING ORDINANCE NO. 1841; AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.**

(1) "Golf cart," is defined, as it is in ORS 801.295, as a motor vehicle that has not less than three wheels in contact with the ground, has an unloaded weight less than 1,300 pounds, is designed to be and is operated at not more than 15 miles per hour, and is designed to carry golf equipment and not more than two persons, including the driver.

(2) "Senior Estates," is defined as the areas platted as Woodburn Senior Estates, which is described as follows: Woodburn Senior Estates No. 2, Subdivision of Block No. 23 of Woodburn Senior Estates No. 2; Woodburn Senior Estates No. 3; Woodburn Senior Estates No. 4; Woodburn Senior Estates No. 5; Resubdivision of a portion of Woodburn Senior Estates No. 5, Blocks 48, 49, 50, 51, 52 & 53; Woodburn Senior Estates No. 6; Woodburn Senior Estates No. 7; Woodburn Senior Estates No. 7A; Woodburn Senior Estates No. 8 as filed with Marion County.

(3) "Woodburn Crossing" is defined as the shopping center located on the commercial properties to the northwest of the intersection of Highway 214 and Country Club Road, City of Woodburn, and lying immediately adjacent to Senior Estates.

**Section 2. Where Golf Carts Are Permitted.** Golf carts are permitted to be used on all of the streets in the areas known as Senior Estates and Woodburn Crossing as described in Section 1. No such permission is intended or implied for any public way other than those within the boundaries described. Golf carts may be operated between the golf course and the place where golf carts are parked or stored or located within or bounded by Senior Estates, as provided for in ORS 810.070.

**Section 3. Qualifications of Drivers.** Drivers of golf carts shall obtain and have in their possession a valid Oregon Drivers License or Oregon Department of Motor Vehicles Golf Cart Permit when operating golf carts under this ordinance.

**Section 4. Regulations for Use of Golf Carts.** Golf carts shall be operated only during daylight hours, and shall observe all applicable requirements of state traffic law. Golf carts shall yield the right of way to motor vehicles and pedestrians when crossing a public street.

**Section 5. Oregon Highway 214.** The operation of golf carts shall not be allowed on any portion of the public highway known as Oregon Highway 214. The crossing of Highway 214 at Oregon Way and Country Club Road or any other location is prohibited. Golf carts shall use the golf course tunnel under Highway 214 to get from one side of the highway to the other.

**Section 6. Registration and Licensing Exemption.**  
Golf carts operated pursuant to this ordinance shall be exempt from registration and licensing as provided in ORS 820.210.

**Section 7. Vehicle Equipment Exemption.** Golf carts operated pursuant to this ordinance shall be exempt from vehicle equipment laws as provided for in ORS 810.070.

**Section 8. Liability.** The operation of golf carts under this Ordinance shall be totally the risk and responsibility of the operator. The City, by passing this Ordinance of permission and designation under state law, assumes no responsibility for the operation of the golf carts and shall be held harmless in any action arising from the operation of golf carts on or off any public way within the City.

**Section 9. Repeal.** Ordinance No. 1841 is hereby repealed.

**Section 10.** [Emergency clause.]

*Passed by the Council February 14, 2000 and approved by the Mayor  
February 15, 2000.*

## ORDINANCE NO. 2262

AN ORDINANCE PROHIBITING PUBLIC PLACE PARKING IN A PORTION OF THE DOWNTOWN AREA TO PREVENT INTERFERENCE WITH SATURDAY MARKET OPERATIONS, PROVIDING FOR CIVIL ENFORCEMENT, AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Purpose.** The City Council finds that the Saturday Market serves a public purpose and is conducted on premises open to the public. The limited clearing of public parking spaces will facilitate a safe, effective, and efficient operation of the Saturday Market.

**Section 2. Definitions.** In addition to those definitions contained in the "Oregon Vehicle Code," the following definitions apply:

(A) "Administrator" shall mean the City Administrator or designee.

(B) "Public Parking Space" shall mean every public way, road, street, thoroughfare, and place open, used or intended for use by the general public for parking motor vehicles.

(C) "Downtown Parking Lot" shall mean the parking lot bordered by Garfield Street on the South side, North First Street on the West Side, and West Hayes Street on the North side and which is described as Township 5 South, Range 1 West, Section 18AB of the Willamette Meridian, Tax Lots 2800 and 3200.

**Section 3. General Provisions.** In addition to the applicable sections of the "Oregon Vehicle Code," prohibited parking, no person shall park or stand a motor vehicle in a public parking place within the Downtown Parking Lot between the hours of 12:00 a.m. Friday and 3:00 p.m. Saturday as posted by a lawfully erected parking limitation sign for the clearance of motor vehicles on account of Saturday Market operations. This section shall not apply to vehicles which are necessary for Saturday Market operations.

**Section 4. Administration.** The Administrator shall be responsible for the installation and maintenance of applicable parking signs and for the enforcement of this ordinance.

**Section 5. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a Class 5 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998.

**Section 6.     Towing and Storage.**

(A)     Any motor vehicle violating the provisions of this ordinance shall constitute a hazard to the public safety and may be towed and stored at the registered owner's expense if left unattended. The registered owner shall be liable for the cost of towing and storage, even if the vehicle was parked by another person.

(B)     Towing and storage of any motor vehicle pursuant to this ordinance does not preclude the issuance of a citation for violation of any provision of this ordinance.

**Section 7.     Disposal of Motor Vehicle.** After a motor vehicle is towed under the authority of this ordinance, it shall be disposed of in the manner provided by ORS 819.180 to ORS 819.260.

**Section 8.     Severability.** If any section, clause, or phrase of this ordinance or its application to any statute, is determined by any court of competent jurisdiction to be invalid or unenforceable for any reason, such determination shall not affect the validity of the remainder of this ordinance or its application.

**Section 9.** [Emergency clause.]

*Passed by the Council May 4, 2000 and approved by the Mayor May 5, 2000.*



---

ORDINANCE 2285

AN ORDINANCE REGULATING MOTOR VEHICLE, BICYCLE AND PEDESTRIAN TRAFFIC WITHIN THE CITY OF WOODBURN; REPEALING ORDINANCES 1904, 2078 AND 2191; AND DECLARING AN EMERGENCY.

THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Short Title.** This ordinance may be cited as the "City of Woodburn Traffic Ordinance."

**Section 2. Definitions.**

(1) The definitions contained in the Oregon Vehicle Code, ORS Chapter 801, as constituted on the date this ordinance takes effect, are hereby incorporated by reference.

(2) As used in this Ordinance, the following words and phrases mean:

(a) **Bus stop.** A space on the edge of a roadway designated by sign for use by buses loading or unloading passengers.

(b) **Chief of Police.** The Chief of Police of the City of Woodburn or designee.

(c) **City.** The City of Woodburn.

(b) **City Administrator.** The City Administrator of the City of Woodburn or designee.

(d) **Council.** The City Council of the City of Woodburn.

(e) **Emergency.** A situation where an unforeseen combination of circumstances calls for immediate action in order to avoid damage to a vehicle or where a vehicle was rendered inoperable but does not include a situation where the vehicle is left standing in excess of 24 hours.

(f) **Holiday.** New Year's Day, Independence Day, Labor Day, Thanksgiving Day, Christmas Day, and any other day proclaimed by the Council to be a holiday.

(g) **Loading zone.** A space on the edge of a roadway designated by sign for the purpose of loading or unloading passengers or materials during specified hours of specified days.

(h) **Parade.** Any march, demonstration, procession or motorcade consisting of persons, animals, or vehicles or a combination thereof upon the streets, parks or other public grounds within the City with an intent of attracting public attention that interferes with the normal flow or regulation of traffic upon the streets, parks or other public grounds.

(i) **Person.** A natural person, firm, partnership, association, or corporation, company or organization of any kind.

(j) **Street.** Any place or way set aside or open to the general public for purposes of vehicular traffic.

(k) **Traffic lane.** That area of the highway used for or designated for the movement of a single line of traffic.

(l) **Truck.** A motor vehicle designed and used primarily for drawing other vehicles, such as truck trailers, or for carrying loads other than passengers, and subject to state licensing for ten thousand (10,000) pounds or more gross vehicle weight.

(m) **Truck Trailer.** Any trailer designed and used primarily for carrying loads other than passengers whether designed as a balance trailer, pole trailer, semi-trailer or self-supporting trailer.

### **Administration**

**Section 3. Powers of the Council.** Subject to state law, the Council constitutes the City road authority under ORS 810.010 and is empowered with all municipal traffic authority for the City except those powers specifically and expressly delegated herein or by another ordinance.

**Section 4. Duties of the City Administrator.** The City Administrator shall implement the ordinances, resolutions and motions of the Council. Installation of traffic control devices shall be based on the standards contained in the Oregon Manual on Uniform Traffic Control Devices for Streets and Highways.

**Section 4A. Duties of Chief of Police.** In addition to any other duties provided herein, the Council delegates to the Chief of Police the authority under ORS 810.030 to impose temporary street closures for a period not to exceed 14 days. Temporary street closures may be made because of traffic accidents or hazards, construction activity, natural disasters, special events, or any other reason where temporary closure is necessary to protect the interest and safety of the general public. (Section 4A added by Ordinance 2323 adopted July 17, 2002.)

**Section 5. Public Danger.** Under conditions constituting a danger to the public, the City Administrator may install temporary traffic control devices which are determined to be necessary.

**Section 6. Standards.** The regulations of the Mayor and City Council or its designate shall be based upon:

- (1) Traffic engineering principles and traffic investigations.
- (2) Standards, limitations and rules promulgated by the Oregon Transportation Commission.
- (3) Other recognized traffic control standards.

**Section 7. Authority to Enforce Ordinance.** Police officers as defined by ORS 801.395 and all other City employees designated by the City Administrator have the authority to enforce the provisions of this Ordinance.

**Section 8. Alteration of Traffic Control Devices Prohibited.** No unauthorized person shall install, move, remove, alter the position of, or deface or tamper with a traffic control device.

**Section 9. Presumption that Traffic Control Device was Lawfully Authorized and Installed.** A traffic control device is presumed to be lawfully authorized and installed unless the contrary is established by competent evidence.

### **General Regulations**

**Section 10. Crossing Private Property.** No operator of a vehicle shall proceed from one street to an intersecting street by crossing private property. This provision shall not apply to the operator of a vehicle who stops on the property for the purpose of procuring or providing goods or services.

**Section 11. Unlawful Riding.**

(1) No operator shall permit a passenger and no passenger shall ride on a vehicle upon a street except on a portion of the vehicle designed or intended for the use of passengers. This provision shall not apply to an employee engaged in the necessary discharge of a duty, or to a person riding within a truck body in space intended for merchandise.

(2) No person shall board or alight from a vehicle while the vehicle is in motion upon a street.

**Section 12. Prohibited Devices.** No person shall use the streets for traveling on skis, toboggans, sleds, skates, skateboards roller blades or other similar devices.

**Section 13. Removing Glass and Debris.** A party to a vehicle accident or a person causing broken glass or other debris to be deposited upon a street shall remove the glass and other debris from the street.

**Section 14. Obstructing Streets.** No unauthorized person shall obstruct the free movement of motor vehicles or pedestrians using the streets.

**Section 15. Storage of Vehicles on Streets.** No person shall store or permit to be stored on a street or other public property, without permission of the City, a vehicle or personal property. Failure to remove a vehicle or other personal property for a period of 72 hours shall constitute prima facie evidence of storage of a vehicle.

**Section 16. Storage and Parking Trucks, Trailers, Boats, Campers, Car Units and Other Vehicles.**

(1) No person shall park a truck or truck trailer upon any street, alley, avenue or public way in any residential area of the City adjacent to any residence, church, school, hospital, multiple dwelling, park or playground in any area of the City. The provisions of this section shall not be deemed to prohibit the lawful parking of such equipment upon any street, avenue or public way in the City for the actual loading or unloading of goods or to make repairs necessitated by an emergency.

(2) No person shall park a bus or vacation house trailer, camper, boat and/or boat trailer, motor home, tent trailer, utility trailer, or any motorized or unmotorized vehicle on any street or on any avenue or public way within the City for longer than 72 hours.

**Section 17. Calculation of Time of Storage.** When calculating hours under Sections 15 and 16 of this Ordinance, the continuity of time shall not be deemed broken by the movement of the motor vehicle or personal property elsewhere on the block unless the movement removes the motor vehicle or personal property from the block where it is located before it is returned.

### **Parking Regulations**

**Section 18. Method of Parking.**

(1) Where parking space markings are placed on a street, no person shall stand or park a vehicle other than in the indicated direction, and unless the size or shape of the motor vehicle makes compliance impossible, within a single marked space.

(2) The operator who first begins maneuvering a motor vehicle into a vacant parking space on a street shall have priority to park in the space, and no other motor vehicle operator shall attempt to interfere.

(3) Whenever the operator of a vehicle discovers the vehicle is parked close to a building to which the fire department has been summoned, the operator shall immediately remove the vehicle from the area, unless otherwise directed by the police or fire officers.

**Section 19. Prohibited Parking or Standing.** In addition to the state motor vehicle laws prohibiting parking, no person shall park or stand:

(1) A vehicle in an alley other than for the expeditious loading or unloading of persons or materials, and in no case for a period in excess of 30 consecutive minutes.

(2) A motor vehicle upon a street for the principal purpose of:

(a) Displaying the vehicle for sale.

(b) Repairing or servicing the vehicle, except to make repairs necessitated by an emergency.

(c) Displaying advertising from the vehicle.

(d) Selling merchandise from the vehicle, except when authorized.

(3) A motor vehicle parked in such a manner that it damages or causes to be damaged any public improvement within the City including streets, alleys, or other public ways. The person who parked the vehicle shall be liable to the City for the damage caused thereby.

**Section 20. Affirmative Defense of Emergency Repairs.** Under Sections 15, 16 and 19 of this Ordinance, it shall be an affirmative defense that the prohibited parking was necessitated by an emergency and the defendant shall have the burden of proving the existence of the emergency by a preponderance of the evidence.

**Section 21. Use of Loading Zone.** No person shall stand or park a vehicle for any purpose or length of time, other than for the expeditious loading or unloading of persons or materials, in a place designated as a loading zone when the hours applicable to that loading zone are in effect. In no case, when the hours applicable to the loading zone are in effect, shall the stop for loading and unloading of materials exceed the time limits posted. If no time limits are posted, then the use of the loading zone shall not exceed 30 minutes.

**Section 22. Unattended Vehicles.** Whenever a police officer finds a motor vehicle parked unattended with the ignition key in the vehicle, the police officer is authorized to remove the key from the vehicle and deliver the key to the person in charge of the police station.

**Section 23. Standing or Parking of Buses.** The operator of a bus shall not stand or park the vehicle upon a street in a business district at a place other than a bus stop, except that this provision shall not prevent the operator from temporarily stopping the bus outside a traffic lane while loading or unloading passengers.

**Section 24. Restricted Use of Bus Stops.** No person shall stand or park a vehicle other than a bus in a bus stop, except that the operator of a passenger vehicle may temporarily stop for the purpose of, and while actually engaged in, loading or unloading passengers when stopping does not interfere with a bus waiting to enter or about to enter the restricted zone.

**Section 25. Extension of Parking Time.** Where maximum parking time limits are designated by sign, movement of a vehicle in a block shall not extend the time limits for parking.

**Section 26. Exemption.** The provisions of this ordinance regulating the parking or standing of vehicles shall not apply to a vehicle of the city, county or state or public utility while necessarily in use for construction or repair work on a street, or a vehicle operated by the United States while in use for the collection, transportation or delivery of mail.

### **Abandoned Vehicles**

**Section 27. Authority Over Abandoned Vehicles within City.** City police officers and code enforcement personnel employed by the City and supervised by the Chief of Police shall have authority pursuant to ORS 819.140(1)(c) to take abandoned vehicles into custody and exercise powers over abandoned vehicles pursuant to state law.

**Section 28. Abandoned Vehicle Procedure.** All abandoned vehicles shall be processed under the provisions of state law.

### **Bicycles**

**Section 29. Bicycle Operating Rules.** In addition to observing all other applicable provisions of this ordinance and state law pertaining to bicycles, a person shall:

(1) Not leave a bicycle, except in a bicycle rack. If no bike rack is provided, the person shall leave the bicycle so as not to obstruct any roadway, sidewalk, driveway or building entrance. A person shall not leave a bicycle in violation of the provisions relating to the parking of motor vehicles.

(2) Not ride a bicycle upon a sidewalk within the downtown core area bounded on the north by Harrison Street, on the west by Second Street, on the south by Cleveland Street, and on the east by Front Street.

**Section 30. Licensing.** The owner or lawful possessor of a bicycle may obtain a license in the following manner:

(1) The police department shall issue licenses and in so doing, shall obtain and record the name and address of each person purchasing a license and the make, model and serial number (if any) of the bicycle.

(2) A number shall be assigned to each bicycle so licensed, and a record of the license issued shall be maintained as part of the police records. A license plate assigned shall be affixed to the frame of the bicycle.

(3) A fee for a bicycle license shall be \$1.00; all license fees collected shall be paid over to the general fund.

**Section 31. Impounding of Bicycles.**

(1) No person shall leave a bicycle on public or private property without the consent of the person in charge or the owner thereof.

(2) A bicycle left on public property for a period in excess of 24 hours may be impounded by the police department.

(3) In addition to any citation issued, a bicycle parked in violation of this ordinance may be immediately impounded by the police department.

(4) If a bicycle impounded under this ordinance is licensed, or other means of determining its ownership exist, the police shall make reasonable efforts to notify the owner.

(5) A bicycle impounded under this ordinance which remains unclaimed shall be disposed of in accordance with the city's procedures for disposal of abandoned or lost personal property.

**Pedestrians**

**Section 32. Right Angles.** A pedestrian shall cross a street at a right angle, unless crossing within a crosswalk.

**Section 33. Use of Available Crosswalk.** No pedestrian shall cross a street other than within a crosswalk in blocks with marked crosswalks or if within 150 feet of a marked crosswalk.

**Section 34. Skates, Skateboards, and Roller blades.** No person shall use skates, skateboards, roller blades or other similar devices upon a sidewalk within the downtown core area bounded on the north by Harrison Street, on the west by Second Street, on the south by Cleveland Street, and on the east by Front Street.

**Funeral Processions**

**Section 35. Funeral Processions.**

(1) A funeral procession shall proceed to the place of interment by the most direct route which is both legal and practical.

(2) The procession shall be accompanied by adequate escort vehicles for traffic control purposes.

(3) All motor vehicles in the procession shall be operated with their headlights turned on.

(4) No person shall unreasonably interfere with a funeral procession.

(5) No person shall operate a vehicle which is not a part of the procession between the vehicles of a funeral procession.

### **Parades**

**Section 36. Permit Required.** No person shall engage in or conduct any parade unless a permit is issued by the Chief of Police.

**Section 37. Parade Permit Application.**

(1) Application for a parade permit shall be made, except for a funeral procession, to the Chief of Police at least seven days prior to the intended date of parade, unless the time is waived by the Chief of Police.

In considering whether to waive the minimum time within which an application for a permit must be made, the Chief of Police shall consider the following factors:

(a) Whether the size, route or nature of the proposed parade is such that additional law enforcement or other resources are required;

(b) Time needed to inform the public of the parade in order to minimize public inconvenience.

(2) Applications shall be signed by the applicant and include the following information:

(a) The name, address and telephone number of the persons responsible for the proposed parade.

(b) The name, address and telephone number of the headquarters of the organization for which the parade is to be conducted, if any, and the authorized and responsible heads of the organization

(c) The requested date of the proposed parade.

(d) The desired route, including assembling point.

(e) A statement as to whether the parade will occupy all or only a portion of the width of the streets proposed to be traveled.



- (f) The location by street of any assembly areas for such parade.
- (g) The number of persons, vehicles and animals which will be participating in the parade.
- (h) The estimated number of spectators.
- (i) A description of any recording equipment, sound amplification equipment, banners, signs, or other attention-getting devices to be used in connection with the parade.
- (j) The intervals of space to be maintained between units of such parade.
- (k) The proposed starting and ending times.

**Section 38. Standards for Issuance**

(1) The Chief of Police shall issue a parade permit as provided for herein when, from a consideration of the application and from such other information as may otherwise be obtained, the Chief of Police finds that:

(a) The conduct of the parade will not substantially interrupt the safe and orderly movement of other pedestrian or vehicular traffic contiguous to its route or location;

(b) The conduct of the parade will not require the diversion of so great a number of City police officers to properly police the line of movement and the areas contiguous thereto as to prevent normal police protection of the City;

(c) The concentration of persons, animals, and vehicles at public assembly points of the parade will not unduly interfere with proper fire and police protection of, or ambulance service to, areas contiguous to such public assembly areas;

(d) The conduct of the parade is not reasonably likely to cause injury to persons or property;

(e) The parade is scheduled to move from its point of origin to its point of termination expeditiously and without unreasonable delays en route;

(f) Adequate sanitation and other required health facilities are or will be made available in or adjacent to any public assembly areas;

(g) There are sufficient parking places near the site of the parade to accommodate the number of vehicles reasonably expected;

(h) No parade permit application for the same time and location is already granted or has been received and will be granted.

**Section 39. Denial of Permit.** If the Chief of Police denies the permit based upon the standards for issuance specified in Section 38, written findings shall be issued specifying the reasons for the decision and a copy of the findings shall be furnished to the applicant.

**Section 40. Alternative Permit.**

(1) The Chief of Police, in denying an application for a parade permit, may authorize the conduct of the parade at a date, time, location, or route different from that named by the applicant. An applicant desiring to accept an alternate permit shall, within five (5) days after notice of the action of the Chief of Police, file a written notice of acceptance with the Chief of Police.

(2) An alternate parade permit shall conform to the requirements of, and shall have the effect of, a parade permit issued under this Ordinance.

**Section 41. Notification of Decision.**

(1) The Chief of Police shall notify the applicant of the decision within five days of receipt of the application.

(2) If the Chief of Police requires an alternate route or an alternate date or refuses to issue a permit, the applicant shall have the right to appeal this decision to the Council.

**Section 42. Appeal to Council.**

(1) The applicant may appeal the decision of the Chief of Police by filing a written request of the appeal with the City Recorder within five days after the Chief of Police has proposed alternatives or refused to issue a permit.

(2) The Council shall schedule a hearing date which shall not be later than the second regular session following the filing of the written appeal with the City Recorder and shall notify the applicant of the date and time that he may appear either in person or by a representative.

**Section 43. Public Conduct During Parades.**

(1) No person shall unreasonably hamper, obstruct or impede, or interfere with any parade or with any person, vehicle or animal participating or used in a parade.

(2) No driver of a vehicle shall drive between the vehicles or persons comprising a parade when such vehicles or persons are in motion and are conspicuously designated as a parade.

(3) The Chief of Police shall have the authority, when reasonably necessary, to prohibit or restrict the parking of vehicles along a street constituting a part of the route of a parade.

**Section 44. Prohibited Conduct.** The following prohibitions shall apply to all parades:

(1) It shall be unlawful for any person to stage, present, or conduct any parade without first having obtained a permit as herein provided;

(2) It shall be unlawful for any person to participate in a parade for which the person knows a permit has not been granted;

(3) It shall be unlawful for any person in charge of, or responsible for the conduct of, a duly licensed parade to knowingly fail to comply with any condition of the parade permit;

**Section 45. Permit Revocable.** The City Administrator may revoke a parade permit if:

(1) An imminent threat of violence and personal injury to the parade participants exists, all reasonable efforts to protect the parade participants have failed, and a request to disband the parade made to the parade organizers has been refused;

(2) Actual violence that endangers public safety has been caused by parade participants and public safety cannot be protected without revocation of the permit; or

(3) There is significant deviation from the route designated in the application or approval, or assembly at points not shown in the application or approval, which occurs without approval of the Chief of Police.

#### **Parking Citations and Owner Responsibility**

**Section 46. Citation on Illegally Parked Vehicle.** Whenever a vehicle without an operator is found parked in violation of a restriction imposed by this ordinance or state law, the officer finding the vehicle shall take its license number and any other information displayed on the vehicle which may identify its owner, and shall conspicuously affix to the vehicle a traffic citation instructing the operator to answer to the charge and at the time and place specified in the citation.

**Section 47. Owner Responsibility.** The owner of a vehicle placed in violation of a parking restriction shall be responsible for the offense, except when the use of the vehicle was secured by the operator without the owner's consent.

**Section 48. Registered Owner Presumption.** In a prosecution of a vehicle owner charging a violation of a restriction on parking, proof that the vehicle at the time of the violation was registered to the defendant shall constitute a presumption that the defendant was then the owner in fact.

### **Impoundment and Penalties**

**Section 49. Authority to Impound Improperly Parked Vehicles.** When any unattended vehicle is parked upon a street, alley or public way of the City in such a manner that it is unlawfully parked in any prohibited or restricted area or is unlawfully parked for a length of time prohibited by this Ordinance, such vehicle is declared by the Council to be a public nuisance and it shall be subject to abatement, removal and impounding in accordance with the procedures provided for abandoned vehicles pursuant to state law.

**Section 50. Civil Infraction Assessment.** Each violation of any provision of this Ordinance constitutes a class 4 civil infraction and shall be dealt with according to the procedures established by City ordinance.

### **General**

**Section 51. Severability Clause.** If a portion of this ordinance is for any reason held to be invalid, such decision shall not affect validity of the remaining portions of this ordinance.

**Section 52. Repeal.** Ordinances 1904, 2078 and 2191 are hereby repealed.

**Section 53. Saving Clause.** The repeal of any ordinance by this Ordinance shall not preclude any action against any person who violated the ordinance prior to the effective date of this ordinance.

**Section 54. Emergency Clause.** This ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor.

**ORDINANCE NO. 2404****AN ORDINANCE ESTABLISHING A POLICE TRAINING ASSESSMENT TO BE IMPOSED IN TRAFFIC VIOLATION CASES**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** Whenever the Woodburn Municipal Court imposes a fine or orders a forfeiture for a traffic violation, a Police Training Assessment in an amount of \$5.00 shall be imposed in addition to the amount of the fine or forfeiture.

**Section 2.** Proceeds from the payment of Police Training Assessments shall be used for Woodburn Police Department training.

**Section 3.** The Woodburn City Council determines that the Police Training Assessment does not constitute a tax under the Oregon Constitution and is not subject to the property tax limitation of Article XI, Section 11(b).

*Passed by the Council July 10, 2006 and approved by the Mayor July 12, 2006.*

---

**ORDINANCE NO. 2464****AN ORDINANCE PROVIDING FOR THE REGULATION OF TAXICABS; TAXICAB DRIVERS;  
TAXICAB COMPANIES; AND SETTING AN EFFECTIVE DATE****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1. Definitions**

- A. Certified Mechanic. A mechanic who meets all the following criteria:
1. Does not own, lease or drive a Taxicab;
  2. Has no financial interest in any Taxicab Company operating within the State of Oregon;
  3. Has received ASE (Automotive Service Excellence) A Series (Automobile/Light Truck Certification) master certification; and
  4. Is not employed by any Taxicab Company.
- B. City Recorder. The City of Woodburn City Recorder or designee.
- C. Driver. Any person operating Taxicabs as a Driver for any Taxicab Company regardless of whether the vehicles so operated are owned by the company, leased, or owned by individual members of the company.
- D. Finance Director. The City of Woodburn Finance Director or designee.
- E. Flat Rate. A rate that remains constant regardless of the distance traveled or the time involved.
- F. Operate. To drive a Taxicab, to use a Taxicab in the conduct of business, to receive money from the use of a Taxicab, or cause or allow another person to do the same.
- G. Person. Any individual, partnership, trust, estate, corporation, or other form of business organization recognized by Oregon law.
- H. Police Chief. The City of Woodburn Chief of Police or designee.
- I. Taxicab. Any motor vehicle used for transportation for hire where the destination and route traveled may be controlled by a passenger and the fare is calculated on the basis of any combination of an initial fee, distance traveled, waiting time, or a flat fee except for an accessible vehicle, ambulance, limousine, medical transport vehicle, shuttle or tour bus. For purposes of this section, the following definitions shall apply:
- a) "Accessible vehicle" means any motor vehicle constructed and equipped for the non-emergency transportation of persons in

- b) wheelchairs, persons using other mobility aids, or with other mobility impairments.
  - c) "Ambulance" means any motor vehicle constructed and equipped for the emergency transportation of persons because of or in connection with their illness, injury or disability.
  - d) "Limousine" means any luxury class motor vehicle that is operated for hire on a reserved, hourly basis.
  - e) "Medical transport vehicle" means any motor vehicle constructed and equipped for the non-emergency transportation of persons in connection with their illness, injury or disability.
  - f) "Shuttle" means any motor vehicle for hire that transports passengers between predetermined destinations (e.g., motels and airports), at fixed rates, and on a fixed schedule.
  - g) "Tour bus" means a motor vehicle accepting individual passengers for a fare for sightseeing or guided tours, making occasional stops at certain points of interest and returning the passengers to the point of origin.
- J. Taxicab Company. Any person that operates Taxicabs other than only as a Driver that either has its primary place of business within the city limits, or regularly conducts business within the City, regardless of whether the vehicles so operated are owned by the company, leased, or owned by individual members of the company.
- K. Taxicab Company Permit. A permit issued under this Ordinance to operate a Taxicab Company.
- L. Taxicab Driver Permit. A permit issued by the City that the Driver is authorized to operate a Taxicab under this Ordinance.
- M. Translink Provider. A business or company that has been approved as a provider of transportation services by the federal government by meeting federal standards and receipt of a certificate evidencing such compliance.
- N. Taximeter. A mechanical or electronic device which calculates and displays a fare based on an initial fee, distance traveled, waiting time, or any combination thereof.

## **Section 2. Taxicab Company Permit Required – Exemptions**

- A. No Person shall operate any Taxicab Company in the City of Woodburn without possessing, in addition to any license required by any other law, a valid Taxicab Company Permit issued pursuant to this Ordinance. A Taxicab Company Permit may not be sold, assigned, mortgaged or otherwise transferred.
- B. Exemptions to Taxicab Company Permit Requirement.
- 1. Public Transportation provided and funded in whole or in part by public organizations shall be exempt from the permit requirements of this Ordinance.
  - 2. Certified Translink Providers that show proof of such certification to the City.

### Section 3. Taxicab Company Permit Applications – Issuance

A. Application Requirements. An applicant for a Taxicab Company Permit must submit to the Finance Director:

1. Proof of registration with the Secretary of State for any corporate, LLC or LLP entity;
2. Proof of registration with the Secretary of State for any assumed business name, along with a listing of the registrant of such;
3. The business name, business address and residence address and telephone numbers of the applicant;
4. A list of any misdemeanor or felony convictions of the owner(s) and officers of the Taxicab Company;
5. The name of the person who will be responsible for and who will oversee the day-to-day operations of the Taxicab Company;
6. The make, type, year of manufacture, VIN number, and seating capacity of each vehicle that will be operated as a Taxicab under the Taxicab Company Permit;
7. A description of the proposed color scheme, name, monogram or insignia that will be used on the Taxicabs;
8. A nonrefundable application fee in the amount of \$120.

B. Insurance Certificate. No Taxicab Company Permit will be issued unless the Taxicab Company provides to the Finance Director a Certificate of Insurance indicating that the insurance requirements of Section 8 of this Ordinance have been satisfied.

C. Inspection Certificate. No Taxicab Company Permit will be issued unless the Taxicab Company provides to the Finance Director an Inspection Certificate from a Certified Mechanic as provided in Section 7 of this Ordinance.

D. Issuance of Permit. The Finance Director will issue a Taxicab Company Permit upon finding that the applicant has met the requirements of this Ordinance.

E. External display of permit. Each Taxicab operated by a Taxicab Company shall prominently display on the exterior of the Taxicab a sticker issued by the City indicating that the permit requirements of this Ordinance have been met.

**Section 4. Annual Taxicab Company Permit Renewal.** Taxicab Company Permits shall be renewed upon submission of an annual permit fee in the amount of \$100.



**Section 5. Equipment**

Every Taxicab is to be equipped with the following:

- A. Except for a Taxicab charging a flat rate, a Taximeter that meets the requirements of this Ordinance.
- B. A Taxicab charging a flat rate must be equipped with a sign that states "Flat Rate" and specifies the rate.
- C. A top light identifying it as a Taxicab.
- D. The company name and telephone number where service can be requested displayed on the exterior of the Taxicab.
- E. A cell phone or taxi radio dispatching calls for service.
- F. A current copy of the Taxicab Company Permit with the approved vehicle's Vehicle Identification Number (VIN).
- G. A notice providing information necessary to file a complaint under this Ordinance.

**Section 6. Taximeter Requirements.**

- A. Every Taxicab, except for a Taxicab charging a Flat Rate, must be equipped with a Taximeter in accurate operating condition, with a lighted face that can easily be read at all times by the passenger.
- B. Every Taximeter must be inspected by a certified taximeter installer and certified at installation, at change in rate, and within 1 year of the last inspection. A certificate of inspection must be issued by a qualified Taximeter repair service upon each inspection. A copy of the certificate of inspection must remain in the Taxicab.
- C. Certificates of inspection must include:
  - 1. The identifying number of the Taximeter;
  - 2. The make, model and license number of the Taxicab in which the Taximeter is installed;
  - 3. The name of the Taxicab Company;
  - 4. The date of inspection;
  - 5. A statement that the Taximeter has been inspected and approved and that its readings are accurate; and

---

6. The signature of the individual making the certification.

D. A Taxicab Company must keep on file copies of all certificates of inspection of Taximeters.

E. Taximeters must operate within the following limits of accuracy: Plus or minus 50 feet in 1 mile and 1 second in 1 minute of waiting time.

F. Certificates of inspection may be examined by the City at any time during normal business hours.

G. All Taximeters must be approved by the National Type Evaluation Program (NTEP) as evidenced by a "Certificate of Conformance" issued by an authorized inspector. All Taximeters must have an active NTEP Certificate of Conformance number.

### **Section 7. Inspection and Maintenance of Taxicabs**

A. Prior to the issuance of a Taxicab Company Permit, and annually thereafter, each Taxicab shall be examined and inspected by either a Certified Mechanic and shall be found to be in safe operating condition.

B. Every Taxicab must have proof of its annual inspection in the vehicle. Proof of the inspection shall be submitted to the Finance Director on an annual basis.

### **Section 8. Taxicab Insurance Requirements.**

A. Coverages and Limits: All Taxicab Company Permit holders must obtain, comply with, and maintain the minimum levels of insurance coverage outlined below during the entire term that the Taxicab Company Permit is valid:

1. Commercial Business Insurance. Taxicab Company Permit holders must secure and maintain a Commercial General Liability policy reflecting limits of no less than \$1,000,000 per Occurrence and \$2,000,000 Aggregate for covered claims arising out of, but not limited to, Bodily Injury, Property Damage, Personal Injury, and Contractual Liability in the course of the policy holder's work under the Taxicab Company Permit.

2. Vehicle Insurance. All Taxicab Company Permit holders, regardless of whether the company holds title to a vehicle or not, must provide the City with a copy of a valid Commercial Auto Liability policy reflecting a Combined Single Limit of not less than \$500,000 per occurrence for claims arising out of, but not limited to, bodily injury and property damage incurred in the course of the vehicle's use as a Taxicab. The Commercial Auto Liability policy must comply with the mandatory laws of the State of Oregon and/or other applicable governing bodies.

3. Worker's Compensation and Employers Liability Insurance. The Taxicab Company Permit holder must secure and maintain a Workers Compensation and Employers Liability policy where required by state law.
4. The Commercial General Liability and Commercial Auto Liability coverage must name the City and its officers, agents and employees as additional insureds as respects to claims, in the course of the policy holder's work as a Taxicab Company.
5. The insurance limits are subject to statutory changes as to maximum limits of liability imposed on municipalities of the State of Oregon during the permit's term.
6. The insurance policy must allow for written notice to the Finance Director 30 days before any policy is canceled, will expire, or be reduced in coverage.

### **Section 9. Taxicab Driver Permits Required – Application Process & Requirements.**

A. Permit Required. No person may drive a Taxicab that regularly conducts business in the City without a Taxicab Driver Permit issued under this Ordinance.

B. Application Documents Required. Applicants for a Taxicab Driver Permit must submit to the Finance Director the items listed below. The failure to submit any of the items listed will result in a denial of the permit:

1. A completed application on a form approved by the Finance Director;
2. A copy of the applicant's current driver's license;
3. A copy of the applicant's non-Oregon driving record for any year in which the applicant was not a resident of Oregon during the last 10 years, regardless of the jurisdiction; and
4. A copy of the applicant's criminal history; and
5. A set of the applicant's fingerprints; and
6. If necessary, any information that reasonably relates to the application or is a clarification of information provided to the Finance Director.

C. Photographs. Applicants will be photographed by the City upon submittal of the Taxicab Driver Permit application. The photograph then becomes a part of the applicant's submittal package.

D. Fees Required. Applicants must submit a nonrefundable application fee in the amount of \$105.

E. Age, Criminal History, Driving History and Insurability Requirements. Applicants for a Taxicab Permit may not be issued a permit if any of the following conditions exist:

1. The applicant has been convicted of any felony in the 10 years preceding the submission of the application;
2. The applicant has been convicted of any misdemeanor involving assault, sex crimes, drugs, prostitution or weapons in the 10 years preceding the submission of The application;
3. The applicant has a felony conviction involving physical harm or attempted physical harm to a person, regardless of when the conviction occurred;
4. During the 5-year period preceding the submission of the application, the applicant has been convicted of:
  - a. Any traffic crime, including but not limited to: Driving under the Influence of Intoxicants, Reckless Driving, Attempt to Elude a Police Officer, or Failure to Perform the Duties of a Driver; or
  - b. Misdemeanor theft.
5. During the 5-year period preceding the submission of the initial application, the applicant had greater than 10 traffic infractions as defined in ORS 801.557; greater than five serious traffic violations as defined in ORS 801.477; greater than five motor vehicle accidents that are required to be reported to the Oregon Department of Motor Vehicles pursuant to ORS 811.720; or, greater than five of any combination of serious traffic violations or motor vehicle accidents as provided above;
6. During the 10-year period preceding the filing of the initial application, the applicant's driving privileges were suspended or revoked by any governing jurisdiction as a result of a driving-related incident;
7. The applicant has more than three traffic violations of any kind within the previous 12 months from the date of the application;
8. The applicant does not have at least 2 years' worth of continuous driving experience in a United States jurisdiction immediately prior to the date of the application's submission;
9. The applicant is less than 21 years old; or
10. The applicant is unable to obtain car insurance for any reason.

**Section 10. Issuance of Taxicab Driver Permit; Term; Replacements.**

A. After an application for a Taxicab Driver Permit is submitted, the Police Chief will provide to the Finance Director a written investigation based upon the requirements of this Ordinance.

B. Issuance and Fees. If an applicant submits the required documents and otherwise satisfies all conditions and requirements of this Ordinance, the Finance Director will issue a Taxicab Driver Permit.

C. Permit Requirements: A Taxicab Driver Permit must:

1. Contain the permit number, permit expiration date, the driver's name and the driver's photograph;
2. Be posted in a prominent place within the Taxicab; and
3. Be inside the vehicle and available for inspection by any customer, passenger, police officer or designated City employee.

D. Term. A Taxicab Driver Permit is valid for a period of 12 months from the date of issuance and must be renewed upon expiration.

E. Replacements. If a driver's permit is lost, damaged or stolen, the Finance Director will issue a replacement permit for a fee in the amount of \$25.

**Section 11. Taxicab Driver Permit Renewals; Consequences of Failure to Renew.**

A. Taxicab Driver Permits must be renewed every 12 months from the date of issuance.

B. The following information and the renewal fee must be submitted to the Finance Director no less than 30 days prior to the renewal date:

1. Updated file information if any information in the original application has changed;
2. Payment of the renewal fee of \$55.

C. A Taxicab Driver Permit will not be renewed if the driver fails to satisfy any condition that would have been grounds to deny the initial permit, including any criminal activity or driving crimes/violations.

D. If a driver fails to timely pay the permit renewal fee or timely provide the renewal information required by this Ordinance, the Taxicab Driver Permit expires and becomes void. A voided Taxicab Driver Permit requires the former permittee to file an initial permit application and pay all necessary fees required by this Ordinance to obtain a valid Taxicab Driver Permit.

**Section 12. Operating Regulations of Taxicab Companies and Drivers**

A. Taxicab Companies. A Taxicab Company shall not:

1. Allow any Taxicab to be driven that has not been inspected and properly permitted, or
2. Allow a person to operate a Taxicab that does not have a valid Taxicab Driver Permit issued pursuant to this Ordinance.

B. Drivers. A Driver shall not:

1. Transport a passenger to his destination by any other than the most direct route, unless requested to do so by the passenger;
2. Fail to give a correct receipt upon payment of the correct fare if requested to do so by the passenger;
3. Permit additional persons to occupy or ride in the Taxicab without consent of the original passenger;
4. Unreasonably refuse to transport to a requested destination any passenger who requests services and is able to demonstrate the ability and willingness to pay the fare;
5. Charge a fare higher than the posted rates, or try to defraud a passenger in any way by manipulating devices to cause a registration to be made of a greater distance or more time; or
6. Operate a Taxicab in violation of any Oregon law.

**Section 13. Suspension or Revocation**

A. Any Permit under this Ordinance may be suspended or revoked by the Finance Director if after a reasonable investigation one or more of the following conditions exist:

1. The Taxicab Company ceases to operate any Taxicab for a period of 15 consecutive days without obtaining permission for the cessation of such operation from the City.
2. The Taxicab Company and/or Driver fails to operate the Taxicab in accordance with the provisions of this Ordinance.
3. The Taxicab Company and/or Driver fails to pay any of the fees or payments required to be paid by the provisions of this Ordinance.
4. The suspension or revocation is necessary to protect the public health, safety, and welfare.

5. The revocation or suspension is otherwise authorized by Ordinances of the city.
- B. Any suspension or revocation pursuant to this section shall be in writing, setting forth the reasons therefore and the right of appeal pursuant to this Ordinance.
- C. Except as provided below, any suspension or revocation shall be effective 10 days after mailing a copy thereof by first class United States mail addressed to the Taxicab Company and/or Driver at the business or residence address shown on the Permit application or renewal.
- D. Notwithstanding subsection (C) of this section, a suspension or revocation may be made effective immediately if the City finds reasonable grounds to believe that:
1. A person holding a Taxicab Driver's Permit is not covered by liability insurance as required by this Ordinance,
  2. A vehicle being operated as a Taxicab is not covered by liability insurance required by this Ordinance, or
  3. Continued operation by the Taxicab Company or Taxicab Driver would cause, or is likely to cause, imminent danger to the public health, safety, or welfare.

#### **Section 14. Surrender of Certificate or Permit**

Any Permit suspended or revoked by the City shall be surrendered to the Finance Director and the operation of any Taxicab covered by said permit shall cease.

#### **Section 15. Rates**

- A. Except for a Taxicab charging a Flat Rate, the rates to be charged to passengers are to be based on the factors of mileage from the point of origin to the point of destination by the most direct route, the time involved, and the number of passengers. No Taxicab may charge any fees or rates other than those that are posted.
- B. A clear and complete summary of a Taxicab Company's rate schedule shall be posted in a conspicuous place in the passenger compartment of every Taxicab. Every Taxicab Company shall provide the Finance Director with a copy this summary prior to posting them in the Taxicabs.
- C. Except for a Taxicab charging a Flat Rate, a summary of the meter rate in a form approved by the Finance Director shall be placed in a manner to be visible from the outside of every Taxicab.

#### **Section 16. Complaints**

A. Every Taxicab shall have posted in a prominent place within the passenger compartment a notice entitled "Complaints" providing the information necessary to file a complaint with the City and/or the Taxicab Company under this Ordinance.

B. Every Taxicab Company shall maintain an Annual Log of all complaints it receives either in writing or by telephone. Each Annual Log shall be kept by the Taxicab Company for a period of five years and shall be available to the City upon request.

### **Section 17. Appeals and Writ of Review**

A. Any Person aggrieved by a decision of the Finance Director under this Ordinance may appeal such action to the City Council by filing a written Notice of Appeal, accompanied by an appeal fee of \$65 with the City Recorder within 10 days of the Finance Director's decision.

B. Within 10 days of receiving the Notice of Appeal, the City Recorder will:

1. Set a time for the appeal to be heard by the City Council;
2. Place the hearing of the appeal upon the Council agenda; and
3. Notify the aggrieved Person and the Finance Director of the time set no less than 10 days prior to that time.

C. The aggrieved Person may appear personally, via a company representative, and/or by counsel and present such facts and arguments as may tend to support the appeal.

D. The Finance Director will provide the City Council with a staff report outlining the decision and the reasons therefore.

E. The City Council will uphold the Finance Director's decision, reverse it, or modify it with any conditions that the City Council deems appropriate. The City Council's final decision shall be in written and supported by findings.

F. All final decisions by the City Council under this Ordinance shall be subject only to Writ of Review in the Marion County Circuit Court pursuant to ORS Chapter 34.

### **Section 18. Violation – Penalty**

A. In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class 1 Civil Infraction and may be processed according to the procedures contained in the Woodburn Civil Infraction ordinance.

B. Each day that a violation of this Ordinance is committed or permitted to continue shall constitute a separate Civil Infraction.



C. The remedies provided for in this Section are cumulative and not mutually exclusive.

**Section 19. Severability.** The sections and subsections of this Ordinance are severable. The invalidity of any section or subsection shall not affect the validity of the remaining sections and subsections.

**Section 20. Savings.** The repeal of any ordinance by this Ordinance shall not preclude any action against any person who violated the ordinance prior to the effective date of this Ordinance.

**Section 21. Effective Date.** This Ordinance is effective on October 1, 2010.

Passed by the Council March 22, 2010 and approved by the Mayor March 24, 2010.

**ORDINANCE NO. 1766**

**AN ORDINANCE RELATING TO THE CONSTRUCTION, OPERATION, REGULATION AND CONTROL OF CABLE COMMUNICATIONS SYSTEMS WITHIN THE CITY'S TERRITORIAL LIMITS.**

**THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:**

[The substance of this ordinance is not reproduced here because of its great length. The full text of the ordinance is on file for public reference in the office of the City Recorder.]

*Passed by the Council September 21, 1981, and approved by the Mayor  
September 22, 1981.*

## ORDINANCE NO. 1925

## AN ORDINANCE PROVIDING FOR THE REGULATION OF PUBLIC DANCES; REPEALING ORDINANCE NO. 1299; AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Public Dance Defined.** A "public dance" is any dance not held in a private home or residence which is open to the general public.

**Section 2. Exclusions.** Provisions of this ordinance shall not apply to dances conducted as follows:

(a) Dances on premises regularly licensed by the Oregon Liquor Control Commission when such licenses are in effect.

(b) Dances or dancing instruction conducted by private dancing schools conducted exclusively for the purpose of giving instructions in dancing.

(c) Dances sponsored by public schools or church organizations on their property.

(d) Dances conducted by nonprofit clubs or fraternal, charitable or religious organizations to which admission is limited to members and to guests of a member.

**Section 3. Necessity for License.** No public dance shall be held until a license is obtained under this ordinance.

**Section 4. Application for Issuance of License.**

(a) Application for a license to hold a public dance shall be made in writing to the City Recorder at least 14 days prior to the date of the proposed dance. An application for an annual public dance license shall be accompanied by a fee of \$300.00, \$250.00 of which shall be refunded in the event such license is denied. An application for a license for a single public dance shall be accompanied by a license application fee of \$50.00, no part of which shall be refundable in the event such license is denied. An annual public dance license shall be effective for one year from the date of issue. However, individual application for each public dance to be held shall be required as provided above.

(b) The application shall be signed by the applicant and by not less than two residents of the City of Woodburn. The residents shall certify that the applicant is of good moral character and shall request that such a license be issued to the applicant.

(c) The application shall contain the names of persons employed by the applicant to be in charge of providing security and control of said public dance. There shall be a minimum of two (2) such persons employed by the applicant for each dance. The persons so employed shall be over the age of 21 years.

(d) The application shall contain all such information as may be relevant to the character and background of the applicant, his security personnel required by Subsection (c) above, and his associates and partners, if any.

(e) The City Recorder shall forward the application to the Police Chief for investigation and may withhold issuance of a dance license until the application has been investigated and approved by the Police Chief. Upon approval by the City Recorder and Police Chief, the City Recorder shall issue the dance license.

**Section 5. License Non-Transferable.** Public dance licenses issued pursuant to this ordinance shall not be transferable.

**Section 6. Hold Harmless Provision.** By applying for and accepting a public dance license the applicant shall be deemed to have agreed to indemnify and hold harmless the City of Woodburn, its officers, boards, commissions, agents, and employees against and from any and all claims, demands, causes of actions of any kind or nature whatsoever which arise as a result of the issuance of the public dance license.

**Section 7. License Denial, Cancellation and Revocation.**

(a) Approval of a dance license shall be denied if the required application is incomplete, false or fraudulent or if the applicant, his security personnel, or partners or associates have, in the previous two years, violated the terms of a public dance license or of this ordinance. Prior conviction of the applicant of a felony or misdemeanor involving moral turpitude may be grounds for denial of a license when considered in the light of an applicant's entire background. Denial of a dance license may be based upon previous disruptive behavior having occurred at a public dance promoted, sponsored or held by the applicant, within the previous two years. Disruptive behavior may also be grounds for revocation or suspension of a license by the City Administrator.

(b) The City Administrator may cancel or revoke any dance license after it has been issued, if it is learned that the same was procured by fraud or false representation of fact.

(c) The applicant may appeal to the City Council from the decision of the city administrator in refusing to issue a public dance license, or revoking or canceling a license previously issued.

(d) All appeals to the City Council shall be in writing and filed with the city recorder within three days from the date of notice of the city administrator's decision. All appeals shall be heard by the City Council at its next regular meeting.

(e) The decision of the City Administrator shall not be stayed during the pendency of the appeal to the City Council. The City Council shall review the denial, suspension or revocation appealed from, and the action of the City Council shall be final.

**Section 8. Use of Return Checks Prohibited.**

(a) No person shall give to any person leaving a dance hall a return check or other token whereby readmission to such dance hall can be obtained without the payment of a fee the same as on original admission.

(b) No person leaving a dance hall shall receive any such ticket or token or gain readmission without paying the same fee as upon original admission.

(c) The provisions of this section shall not affect in any way readmittance during or after a regularly scheduled intermission.

**Section 9. Closing Hours.** All public dances shall be discontinued and all dance halls shall be closed on or before 12:30 a.m.

**Section 10. Alcoholic Beverages Prohibited.**

(a) The use of alcoholic beverages is prohibited at a public dance except that a person granted a license under this ordinance may serve and dispense alcoholic beverages for use on the premises of the public dance if that person has a valid special events permit issued by the Oregon Liquor Control Commission.

(b) The necessity of obtaining a license under the ordinance in no way relieves a person from complying with the rules and regulations of the Oregon Liquor Control Commission and any other applicable law.

**Section 11. Authority to Terminate Dance.** The City Administrator or Chief of Police shall have the authority to terminate a public dance without notice for non-compliance with this ordinance or other applicable law.

**Section 12. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 2 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 12 as amended by Ordinance 2008 passed October 24, 1988.]

**Section 13. Severability.** Each portion of this ordinance shall be deemed severable from any other portion. The unconstitutionality or invalidity of any portion of this ordinance shall not invalidate the remainder of the ordinance.

**Section 14. Repeal and Saving Clause.**

(a) Ordinance No. 1299 is hereby specifically repealed.

(b) Notwithstanding Subsection (a) of this section, Ordinance No. 1299 shall remain valid and in force for the purpose of authorizing the arrest, prosecution, conviction and punishment of a person who violated Ordinance No. 1299 prior to the effective date of this ordinance.

---

**Section 15.** [Emergency clause.]

*Passed by the Council September 9, 1985, and approved by the Mayor  
September 11, 1985.*

## ORDINANCE NO. 2084

AN ORDINANCE PRESCRIBING THE METHODS AND PROCEDURE FOR REGULATING ALARM SYSTEMS IN THE CITY OF WOODBURN, PROVIDING FOR FEES, AND PENALTIES FOR VIOLATIONS THEREOF; AND REPEALING ORDINANCE NO. 1649.

THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Title.** This ordinance shall be known as "Alarm System Control Ordinance".

**Section 2. Purpose, Construction and Scope.**

(1) The occupants of numerous residential, commercial and industrial establishments within the corporate limits of the City of Woodburn have found it desirable to make provisions for the installation upon their premises, at their own cost and expense, of alarms systems for emergencies requiring police response.

(2) There is a growing number of private enterprises that have embarked upon the business of selling or leasing such alarm systems, entering into contract with such occupants for the installation, operation and maintenance of such alarm systems, and providing, either individually or in concert with other private business enterprises an alarm device or devices installed in various alarm monitoring centers. Likewise, there is a growing number of private enterprises that have embarked upon the business of selling such alarm systems where the installation is completed by the purchaser and/or the user.

(3) The proliferation of the number of private enterprises engaged in the distribution of alarm systems and the number of commercial and residential users of such systems has resulted in conditions that has led to an unnecessary drain on the personnel, time, space, facilities and finances of the City and its police services, and a deterioration of the quality of police service to the City's residents.

(4) The public interest, therefore, requires the enactment of rules, regulations, standards, and procedures to regulate and control the private alarm business within the corporate limits of the City of Woodburn for the following purposes:

(a) The Police Department may efficiently and economically coordinate their functions with the various alarm services to which the public within the City may subscribe;

(b) The quality of the alarms services rendered to the public may be improved and maintained at a high level;

(c) The excessive number of false alarms which require expenditure of police resources must be reduced so that those limited resources may be more efficiently utilized;

(d) Those private enterprises engaged in the alarm business and persons who utilize alarm systems should help support the administration of the alarm system and where alarm users are responsible for an excessive number of false alarms, they should pay additional charges, which relate to the additional responses by the police and motivate alarms users to reduce the number of false alarms;

(e) Those alarm users who are responsible for excessive false alarms, and who fail or refuse to remedy the cause of excessive false alarms demonstrate their indifference to limited police resources being devoted to unnecessary emergency responses, and such users should be treated by punitive measures. By the time an alarm user's system has generated three false alarms within a year, the police response by way of notices will have provided the user with ample warning of the consequences and therefore it is presumed the alarm user has failed to take adequate steps to remedy the problem(s) and maintain the alarm system.

(5) The purpose of this ordinance is to encourage alarm users and alarm businesses to assume increased responsibility for maintaining the mechanical reliability and the proper use of alarms systems to prevent unnecessary police emergency responses to false alarms and thereby protect the emergency response capability of the City from misuse.

(6) Except where otherwise expressly provided, this ordinance governs all alarm systems eliciting a police response, establishes fees and charges and provides for the enforcement of violations.

### **Section 3. Definitions.**

For the purpose of this ordinance, the following definitions apply:

(1) Alarm Business. A person, firm, partnership, corporation, association or other legal entity, engaged in the profit-oriented selling, leasing, maintaining, servicing, repairing, altering, replacing, moving or installing of any alarm system in or on any building, structure, facility or portion thereof.

(2) Alarm System. An assembly or equipment, mechanical or electrical, or both, designed and used to signal the occurrence of an illegal or unauthorized entry or attempted entry or other illegal activity on the premises of the alarm user, which requires or solicits urgent attention and to which the police are expected to respond.

(3) Alarm User. A person, firm, partnership, corporation, association or other legal entity in control of a building, structure, facility or portion thereof within the City of Woodburn wherein an alarm system is used.

(4) Automatic Dialing Device. A device which is interconnected to a telephone line and is programmed to select a predetermined telephone number and to transmit by voice message or code signal an emergency message indicating a need for emergency response. An automatic dialing device is an alarm system.



(5) Excessive False Alarm. A false alarm which occurs following three previous false alarms within one year.

(6) False Alarm. Signal or activation by an alarm system which elicits a response by the Police Department when a situation requiring a response by the police does not in fact exist. False alarms do not include an alarm signal by an alarm system, which is caused by violent and extraordinary conditions of nature or other extraordinary circumstances not reasonably anticipated or subject to control by the alarm business operator or the alarm user.

(7) Governmental Political Unit. Any tax supported public agency.

(8) Interconnect. To connect an alarm system including an automatic dialing device to a telephone line either directly or through a mechanical device that utilizes a telephone for the purpose of using the telephone line to transmit a message upon the activation of the alarm system.

(9) Municipal Court. The Woodburn Municipal Court.

(10) Monitoring Center. A facility used to receive emergency and general information from an alarm user and to direct an emergency response.

(11) Police Chief. The police chief of Woodburn, Oregon or his designee.

(12) Police Department. The Woodburn Police Department.

**Section 4. User Instructions.** Every alarm business, which operates as such on behalf of alarm users within the City shall furnish the user with instructions which enable the user to operate the alarm system properly without false alarms and to obtain service for the alarm system.

**Section 5. Automatic Dialing Device. Certain Interconnection Prohibited.**

(1) It is unlawful for any person to program an automatic dialing device to select a primary trunk line or any 911 trunk line, capable of signaling a need for police response; and it is unlawful for an alarms user to fail to disconnect or reprogram an automatic dialing device which is programmed to select a primary trunk line upon receipt of notice from the Police Chief, directing that such disconnection or reprogramming occur.

(2) It is unlawful for any person to program an automatic dialing device which selects any telephone line assigned to the City of Woodburn; and it is unlawful for an alarm user to fail to disconnect or reprogram such a device upon receipt of notice from the Police Chief that such automated dialing device should be disconnected or reprogrammed.

(3) The City of Woodburn and other governmental providers of emergency and critical municipal services, including but not limited to water, sewer, and streets are exempt from the provisions of this section.

**Section 6. False Alarms, Hearing, Determination.**

(1) An alarm user, whose alarm system has three or more false alarms within a year shall be subject to a charge for excessive false alarms in an amount of \$15.00. Excessive false alarm charges shall be paid by the alarm user notwithstanding an agreement or claim of liability which holds an alarm business responsible for such charges. Excessive false alarm charges shall be established in an amount designed to encourage correction in an alarm system or in the operation of an alarm system, to discourage false alarms and to reimburse the City for the use of its police resources.

(2) After each of the first three false alarms during a year, the Police Chief shall send by regular mail a notice of false alarm to the alarm user and the alarm business. The notice shall advise the alarm user and the alarm business of the date and time of the false alarm and the specific number of false alarms recorded by the coordinator for the alarm system during the current year. The notice shall also advise that upon the occurrence of a fourth false alarm during the year, the alarm user will be charged a fee for each excessive false alarm.

(3) If the Police Department responds to a third false alarm during the year, the Police Chief shall forward a notice by certified mail return receipt requested to the alarm business stating that the Police Department has responded to three (3) false alarms at the address where the alarm system is located. This notice shall also advise that the occurrence of any additional false alarms at the address where the alarm system is located during the year will result in a fee to the user for excessive false alarms.

(4) The Police Chief shall prescribe the form of the notices to be used in this section. For purposes of determining which form of mailing and notice to use, any alleged false alarm, which is disputed as provided in this section and for which a final determination has not been made, shall be treated as having occurred. The Police Chief shall insure that adequate records of notices being sent to alarm users and alarm businesses are maintained by the Police Department. Failure of a person to receive a notice shall not invalidate any proceeding in connection with a false alarm or in the imposition of additional charges.

(5) An alarm user or alarm business who is aggrieved by the determination that a particular false alarm has occurred may request a hearing. The request shall be made in writing and filed with the Police Chief and the Municipal Court within ten (10) days of the date on which the alarm user is sent the notification of false alarm for which a hearing is requested. Unless a request for a hearing is made in accordance with this section, an alarm user shall have waived any right to challenge the decision whether a particular false alarm occurred and the false alarm shall thereafter be treated as having occurred on the date and time alleged. If a hearing is requested in accordance with this subsection, the Municipal Court shall notify by regular mail the person requesting the hearing of the time and place of the hearing.

(6) Every hearing to determine whether a false alarm has occurred shall be held before the Municipal Court without a jury. The court may in the interest of justice consolidate hearings which involve the same alarm user or alarm system and false alarms within the same year. The person requesting the hearing may be represented by counsel, but counsel shall not be provided at public expense. If counsel is to appear, written notice shall be provided to the Municipal Court and Police Chief not less than five (5) business days prior to the hearing date. The Police Chief, or the City's designated representative and the person requesting the hearing shall have the right to present written and oral evidence. Oral testimony shall be taken only on oath or affirmation and shall be subject to the right of cross-examination. If the person requesting a hearing wishes that witnesses be ordered to testify, they must request the court to order the desired witness subpoenaed, which request shall be at least five (5) business days prior to the scheduled hearing. A deposit for each witness shall accompany the request and such deposit shall be refunded, if it is determined the alleged false alarm did not occur. The deposit for subpoenas shall be in an amount equal to witness fees provided by statute in other courts of this State. At the hearing, any relevant evidence shall be admitted if it is the type of evidence on which reasonable persons are accustomed to rely in the conduct of serious affairs. However, irrelevant and unduly repetitious evidence shall be excluded. The City shall have the burden of proving that a false alarm occurred by a preponderance of the evidence. Within thirty days after the hearing, the Municipal Court shall determine whether the alleged false alarm has occurred and shall so advise the parties. The decision of the Municipal Court is final.

**Section 7. Confidentiality, Statistics.**

(1) Except as otherwise required by law, if an alarm user requests that information submitted by the user as part of an application be kept in confidence, such information shall be held in confidence and shall be deemed a public record exempt from disclosure under Oregon law. The Police Department shall be responsible for maintenance of records created under this ordinance.

(2) Notwithstanding the requirements of subsection (1) the Police Department shall develop and maintain statistics for purposes of evaluating alarm systems.

**Section 8. Allocation of Revenues.** All fees and charges collected pursuant to this ordinance shall be deposited in the general fund in the City of Woodburn, and are nonrefundable.

**Section 9. Duty to Maintain Alarm System.**

(1) It shall be the duty of an alarm user to maintain its alarm system in good operating condition and free of false alarms.

(2) An alarm user whose alarm system generates four or more false alarms within a year violates this ordinance.

**Section 10. Civil Infraction in Addition to Fee.**

In addition to any fees assessed pursuant to this ordinance, a violation of the provisions of this ordinance constitutes a class 4 civil infraction, punishable in accordance with Ordinance 1988 of the City of Woodburn. Every date that a violation is found to exist constitutes a separate civil infraction.

**Section 11. Severability.** If any section, subsection, sentence, clause, phrase or portion of this ordinance or of any resolution adopted hereunder is, for any reason, held invalid or unconstitutional by a court of competent jurisdiction, such portion shall be deemed a separate, distinct and independent provision, and such holding shall not affect the validity of the remaining provisions of this ordinance or any resolution adopted hereunder.

**Section 12. Repeal.** Ordinance No. 1649 is hereby repealed.

*Passed by the Council May 26, 1992, approved by the Mayor May 27, 1992.*

## ORDINANCE NO. 2336

**AN ORDINANCE ESTABLISHING A FILMING PERMIT PROCESS; SETTING FEES; PROVIDING FOR PENALTIES; AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Permits for Filming Required.** All persons or legal entities shall obtain a filming permit prior to filming motion pictures, commercials or videotaped productions within the Woodburn City limits. This requirement shall not apply to films made by amateurs or to the filming of news events by accredited representatives of news agencies.

**Section 2. Issuance of Filming Permit.** Filming permits shall be issued by the City Administrator or the City Administrator's designee.

**Section 3. Application.** A written application for a filming permit shall be filed with the City Administrator or designee at least fourteen (14) days prior to filming, unless waived by the City Administrator. The application shall include:

1. The name and contact information of the person, firm, or corporation employing the person or persons who will perform the filming.
2. The name and contact information of a person who will be responsible for the filming crew on location in the City.
3. The specific date, location, time of arrival on the filming site and duration of filming (including site preparation, site restoration, and departure) for each scene to be filmed within the City limits.
4. The extent to which normal use of public property/right-of-way will or could be impaired or curtailed during filming.
5. The number and location of vehicle parking spaces that will be needed during filming and the anticipated hours of use of the spaces.
6. The number of police or other City personnel desired or needed for traffic and/or pedestrian control, security of equipment, or other purposes during filming.
7. Written authorization from the property owner if private property is to be used in conjunction with public property during filming.
8. The processing fee as set by this Ordinance.

**Section 4. Review of the Application.**

1. The City Administrator or designee shall review the application and may issue the permit if the City Administrator or designee finds that the filming permit will not:

- a. Adversely impact the public health, safety or welfare;
- b. Adversely impact the affected neighborhood(s) or business district(s);
- c. Result in a cost to the public due to the use of public property or facilities, potential loss of public revenue, or provision of City personnel, unless the City is compensated for such costs by the applicant;
- d. Substantially inconvenience residents or businesses; or
- e. Substantially interfere with the public peace or the quiet enjoyment of private residential property.

2. The City Administrator or designee may impose conditions on a permit in order to alleviate or mitigate any potential adverse impacts described in subsection 1 of this section.

3. The City Administrator or designee may deny the application if he or she determines that the permit will result in any of the potential adverse impacts described in subsection 1 of this section which cannot be alleviated or mitigated by the imposition of conditions.

4. An approved filming permit shall:

- a. Specify the location and time of use of any City property that will be affected by filming.
- b. Set forth any conditions or restrictions imposed by the City Administrator or designee pursuant to subsection 2 of this section.
- c. Require a deposit of funds prior to filming in an amount estimated by the City Administrator or designee to be sufficient to compensate the City for any public costs described in subsection (1)(c) of this section incurred as a result of the filming. In the event that filming is cancelled, the City shall refund the deposit minus an amount for any costs incurred by the City up to the date of cancellation.
- d. Require the delivery of a certificate of insurance prior to filming in an amount determined by the City Administrator or designee to be sufficient to protect the City from any and all liability arising out of the filming activity. The certificate of insurance shall name the City of Woodburn as an additional insured.

**Section 5.     Appeals.**

1.       Any decision regarding an application or the conditions of a permit may be appealed by the applicant to the City Council by filing a written notice of intent to appeal with the City Recorder. The notice shall be filed within seventy-two (72) hours of receipt of the decision by the applicant and shall include a statement of the reasons for the appeal and an appeal fee. The filing of an appeal shall stay the permit until the appeal is decided by the Council.

2.       In reviewing the appeal, the Council shall determine whether the decision complies with the criteria and requirements of Section 4 of this ordinance. The Council may affirm, reverse or modify the decision. The Council's decision shall be final.

**Section 6.     Compensation for Public Costs.** The applicant shall compensate the City for any and all public costs described in Section 4.1. If the deposit required pursuant to Section 4.4c is insufficient to cover such costs, the applicant shall remit the balance to the City upon receipt of written notice of such additional costs.

**Section 7.     Permit Application Fee.** An application for a filming permit shall be accompanied by a fee in the amount of \$1,000.00.

**Section 8.     Appeal Fee.** An appeal under Section 5 of this Ordinance shall be accompanied by an appeal fee in the amount of \$300.00.

**Section 9.     Violations.** A violation of any provision of this Ordinance or of any term or condition of an approved filming permit is a Class 1 civil infraction and shall be enforced pursuant to the Civil Infraction Ordinance.

**Section 10.    Severability Clause.** If a portion of this Ordinance is for any reason held to be invalid, such decision shall not affect validity of the remaining portions of this Ordinance.

**Section 11.**   [Emergency clause.]

*Passed by the Council May 12, 2003, and approved by the Mayor May 14, 2003.*

## ORDINANCE NO. 2399

AN ORDINANCE PROVIDING FOR THE REGISTRATION OF BUSINESS WITHIN THE CITY OF WOODBURN; ESTABLISHING A REGISTRATION PROCESS; AND PROVIDING A PENALTY FOR VIOLATION THEREOF; AND SETTING AN EFFECTIVE DATE.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Purpose.** The registration required and restrictions imposed by this ordinance are enacted primarily for the purpose of regulation of businesses. The public's interest is served by insuring that regulated businesses will be carried on in continuing compliance with applicable laws and ordinances and in a manner which does not detract from the public health, safety, or welfare. In addition, this ordinance is enacted to recoup the necessary expenses required to undertake the administration and enforcement of this ordinance and to provide revenue for law and code enforcement purposes. The payment of a registration fee required hereunder and the acceptance of such fee and issuance of a business registration certificate by the City shall not entitle the registrant to carry on any business not in compliance with all the requirements of City ordinances and all other applicable laws.

**Section 2. Definitions.** For the purpose of this ordinance, the following terms, phrases, and words are defined as follows:

A. "Business" means any vocation, occupation, profession, enterprise, establishment, or any activity, together with all devices, machines, vehicles and appurtenances used therein, any of which are conducted for private profit, or benefit, either directly or indirectly, on any premises in the City. This definition includes any transaction involving the rental of property, the manufacture or sale of goods, or the sale or rendering of services other than as an employee.

B. "The City" means the City of Woodburn, Oregon.

C. "City Council" means the City Council of the City of Woodburn, Oregon.

D. "City Administrator" means the City Administrator or any officer or employee designated by that person to perform duties described in this ordinance

E. "Garage Sale" means a commercial activity, open to the public, conducted at a private residence where personal property is sold or auctioned to others, provided the number of sale days at a particular residence does not exceed three (3) days per occurrence, and no more than two (2) occurrences per calendar year.

F. "Person" means and includes individual natural persons, partnerships, joint ventures, societies, associations, clubs, trustees, trusts or corporations or any officers, agents, employees or any kind of personal representatives thereof, in any capacity, either on that person's own behalf or for any other person, under either personal appointment or pursuant to law.



G. "Home occupations" means businesses that conform to the definition of Home Occupations under chapter 2.203.12 in Woodburn Development Ordinance as determined by the City Administrator.

H. "Residential Rental Unit" means separate living quarters, which are rented, leased, or let in exchange for full or partial monetary compensation.

I. "Government Entities" means the federal government, the State of Oregon, a county, a special district, or a municipality.

### **Section 3. Registration Required.**

A. No person shall engage in any business within the City or transact any business specified in this ordinance, without first obtaining a registration certificate and paying the fee prescribed. The provisions of this ordinance shall be in addition to any other fee or registration requirements imposed by the City of Woodburn, unless otherwise specified.

B. A person engaged in business in more than one location, or in more than one business registered under this ordinance at the same location, shall make a separate application for each business or location, provided however that the fee for second and subsequent businesses shall be twenty dollars (\$20.00). Warehouses and distributing plants used in connection with and incidental to a business shall not be deemed a separate place of business. Separately franchised operations shall be deemed separate businesses even if operated under the same name.

C. A person representing himself/herself, or exhibiting any sign or advertisement that he/she is engaged in a business within the City shall be deemed to be actually engaged in such business and shall be liable for the payment of such registration fee and subject to the penalties for failure to comply with the requirements of this ordinance.

D. No person shall maintain or operate two or more residential rental units without first obtaining a business registration certificate and paying the prescribed fees.

**Section 4. Exemptions.** The following entities and types of activities are exempt from regulation under this ordinance. The person asserting an exemption under this ordinance shall have the burden of establishing eligibility for the exemption.

A. Nothing in this ordinance shall be construed to apply to any person transacting or carrying on any business within the City of Woodburn, which is exempt from taxation, by the City by virtue of the Constitution of the United States or the Constitution of the State of Oregon.

B. No person whose income is based solely on a wage or salary shall, for the purpose of this ordinance, be deemed a person transacting or carrying on any business in the City, and it is the intention that all registration taxes and fees will be borne by the employer.

C. Any business paying a franchise tax or transient occupancy tax under City ordinances is exempt from the requirements of this ordinance.

D. Persons whose sole business activity is making deliveries or taking orders from duly registered businesses within the City are exempt from this ordinance.

E. Activities conducted pursuant to a special events permit issued by the City are exempt from the requirements of this ordinance.

F. Producers of farm products raised in Oregon, produced by themselves or their immediate families, who sell, vend, or dispose of such products within the City is exempt from this ordinance. [Section 4F is repealed by Ordinance No. 2426 passed November 26, 2007.]

G. Nonprofit organizations, religious organizations, civic organizations and clubs wishing to canvass for funds or sell door-to-door to raise funds, or conduct fund-raising events to be used solely for the purpose for which the organization was created, and from which no third party receives a profit are exempt from the requirements of this ordinance.

H. A builder who is registered under ORS 701.055 and is employed as a subcontractor working for a contractor possessing a valid business registration issued by the City of Woodburn is exempt from this ordinance.

I. Garage sales as defined in this ordinance are exempt from the requirements of this ordinance.

J. Any person required to be licensed through any other City ordinance including, but not limited to activities such as, peddlers and solicitors," "public dances," or other licensed activities is exempt from this ordinance.

K. Government entities are exempt from the requirement of this ordinance.

#### **Section 5. City Administrator Authority.**

A. The City Administrator may adopt reasonable rules and regulations in order to carry out the provisions of and for enforcement of the provision of this ordinance. The Administrator shall prescribe forms for business registration application. The Administrator shall review or cause to be reviewed application for and renewals for business registrations, and shall submit such applications to appropriate City departments for investigation to determine and comment on the applicant's compliance with City ordinance and other rules.

B. The City Administrator shall have the authority to approve, approve with conditions, or deny any application for or renewal of a business registration. If the Administrator determines that the application should be denied or approved with conditions, the Administrator shall notify the applicant in writing of the decision. The notice shall state the reason for the decision and inform the applicant of the provisions for appeal. If the Administrator's decision is to approve without conditions, issuance of

the registration is notification of the decision and it does not need to state any reason or appeal rights.

**Section 6. Application Requirements.**

A. Application for business registration shall be made to the City at least 30 days prior to the date the registration is requested to be effective. The application forms shall provide for information necessary to determine the identity and address of the applicant and of the owner of the business to be registered and shall provide for other information as may be requested by the City Administrator. The application shall be signed by the applicant and shall constitute the applicant's consent for the City to conduct an investigation of the applicant's request including permission to enter property to be used in conducting the business. The applicant shall submit information necessary to evaluate the applicant's request and to determine compliance with applicable City of Woodburn ordinances. If the applicant fails to supply information so required or submits false or misleading information, the registration may be denied and if issued, may be revoked.

B. Applications shall be accompanied by any required fee. Application fees shall be non-refundable.

**Section 7. Criteria for Approval or Denial.**

A. Approval or denial of an application for initial issue or renewal shall be based on consideration of all available evidence indicating whether or not the applicant meets the requirements of City ordinances. In the event no grounds exist for denial of a certificate, a certificate shall be issued.

B. Any of the following may be grounds for denial of the certificate:

1. Any false or incomplete statement made or acknowledged on the application form; provided, however, that in the event such statement is the result of excusable neglect, the applicant may resubmit an application with appropriate corrections.

2. The business activity would not comply with City ordinances and could not be made to comply through the imposition of appropriate conditions.

3. A previous history of unlawful business activity by the applicant, which, if continued would be grounds for revocation of the certificate.

4. The business activity would endanger persons or property.

**Section 8. Registrations and Renewals.**

A. Business registration is valid for one year.

B. Business registrations shall be renewed by the payment of the annual fee on or before the anniversary date of the original issuance of the business registration.

C. The renewal application will indicate any change in use, ownership, or location of the business.

**Section 9. Term, Transfers and Relocations.**

A. Term: A business registration issued under this ordinance shall be valid for one year from the date of issuance.

B. Transfer: In the event of the transfer of ownership of any business, the applicable registration certificate may be transferred by application to the City Administrator. An application shall be accompanied by a transfer fee.

C. Relocation of Existing Business: In the event a business relocates, the business shall reapply to the City Administrator to transfer the business registration.

**Section 10. Fee.**

A. As of the effective date of this ordinance fees shall be:

1. All businesses, excepting home occupation businesses, shall pay an annual fee of fifty dollars (\$50.00).

2. Home occupation businesses shall pay a reduced annual fee of twenty-five dollars (\$25.00).

3. The transfer of ownership fee shall be twenty dollars (\$20.00).

B. Future fees shall be set as part of the Master Fee ordinance.

**Section 11. Use of Revenue.** Revenue derived from Business Registration fees shall be used to recoup the cost of administering and enforcing the program. Any fees collected in excess of amounts necessary to recoup the costs of program administration and enforcement shall be dedicated to support the activities of the Police Department's Community Response Team. Elimination of that team or a permanent reduction of that team below FY 2005-06 staffing levels, by City Council policy choice, shall trigger a review of Sections 10 and 11 of this ordinance.

**Section 12. Revocation of Registration.** The City Administrator, upon determining that unlawful business activity is occurring or has occurred, or that a business would not qualify for a license pursuant to this ordinance, shall notify the licensee in writing that the license is to be revoked. The notice shall be sent at least thirty (30) days before the date of revocation. If the activity giving rise to the need for the revocation proceedings is discontinued, the City Administrator may terminate the proceedings. A notice of revocation shall state the reason for the revocation and inform the licensee of the provisions for appeal.

**Section 13. Appeal.**

A. A business whose registration has been denied renewal, or is to be revoked, may within thirty (30) days after the notice of denial, or revocation is mailed, appeal in writing to the City Council. The appeal shall state:

1. The name and address of the appellant;
2. The nature of the determination being appealed;
3. The reason the determination is incorrect; and
4. What the proposed determination of the appeal should be.

B. An appellant who fails to file such a statement within the time permitted waives his/her objections, and the appeal shall be dismissed. If a notice of revocation is appealed, the revocation does not take effect until final determination of the appeal. The City Council shall hear and determine the appeal on the basis of the written statement and such additional evidence as it considers appropriate.

C. At the hearing, the appellant may present testimony and oral argument, personally or by counsel, and any additional evidence. The rules of evidence as used by courts of law do not apply, and the decision of the City Council after the hearing is final.

**Section 14. Display Required.** All registration certificates issued in accordance with this ordinance shall be openly displayed in the place of business or kept on the person or on the vehicle of the person registered. Failure to display or carry such registration shall be deemed a violation of this ordinance.

**Section 15. Violation – Penalty.**

A. A violation of any provision of this ordinance constitutes a Class 2 civil infraction and shall be processed according to the procedures contained in the Woodburn Civil Infractions ordinance.

B. A finding that a person has committed a violation of this ordinance shall not act to relieve the person from payment of any unpaid business fee, including delinquent charges, for which the person is liable. The penalties imposed by this section are in addition to and not in lieu of any remedies available to the City.

**Section 16. Delinquency Charge.** In addition to the business registration fee required by this ordinance, a delinquency charge in the amount of 50% of the applicable fee shall be assessed if the annual renewal fee is not paid within 15 days after the anniversary date of the original issuance of the business registration.

**Section 17. Severability.** Each portion of this ordinance shall be deemed severable from any other portion. The unconstitutionality or invalidity of any portion of this ordinance shall not invalidate the remainder of this ordinance.

**Section 18. Effective Date.** This ordinance shall be in full force and effect on April 17, 2006.

*Passed by the Council March 13, 2006, and approved by the Mayor March 15, 2006.*

## ORDINANCE NO. 2425

## AN ORDINANCE REGULATING THE PLACEMENT AND PERMITTING OF NEWSRACKS AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. General Findings.** The City Council of the City of Woodburn finds and declares that:

A. It is in the public interest to establish regulations that balance the right to distribute information through newsracks with the right of persons to reasonably access and use public property. The City Council wishes to provide for the placement of newsracks, stands, containers and similar newspaper and publication vending machines to provide a forum for communication while preserving the convenience of those using the public rights of way. Newsracks placed and maintained on public property, absent some reasonable regulation, may unreasonably interfere with the use of such property, and may present hazards to persons or property.

B. The public health, safety, welfare, and convenience require that: interference with vehicular, bicycle, wheelchair or pedestrian traffic be avoided; obstruction of sight distance and views of traffic signs and street-crossing pedestrians be eliminated; damage done to sidewalks or streets be minimized and repaired; the good appearance of public property be maintained; trees and other landscaping be allowed to grow without disturbance; access to emergency and other public facilities be maintained; and ingress and egress from, and the enjoyment of store window displays on, properties adjoining public property be protected.

C. The regulations on the time, place and manner of the placement, location and maintenance of newsracks set forth in this Ordinance are carefully tailored to ensure that the purposes stated in this section are implemented while still providing ample opportunities for the distribution of information to the public.

D. The City Council finds that newsracks have proliferated and increased in the City to the extent that they must be addressed by this Ordinance. Exhibit "A" describes examples of the proliferation of newsracks in the city.

**Section 2. Special Findings for the Urban Renewal Core Area.** The City Council of the City of Woodburn finds and declares that:

A. The City has made a substantial monetary and policy commitment to revitalize its Urban Renewal Core Area, that area described in Exhibit "B" of this Ordinance.

B. The City Council passed Ordinance 2298 on August 13, 2001, which adopted the Woodburn Urban Renewal Plan. The Woodburn Urban Renewal Plan is incorporated into these findings by this reference.

C. The purpose of the Woodburn Urban Renewal Plan is to rehabilitate and redevelop blighted areas consistent with the Woodburn Comprehensive Plan.

D. A key component of the Woodburn Urban Renewal Plan is to enhance livability by making improvements in the Urban Renewal Core Area. This area encompasses Woodburn's downtown. It is pedestrian and bicycle friendly. Under the Woodburn Urban Renewal Plan, planned improvements in this area include street, sidewalk, landscape and lighting improvements, street furnishings and public art, building renovations and façade improvements, creation of public spaces, business incubation and small businesses assistance.

E. On August 21, 2005, the Woodburn Downtown Plaza was dedicated as part of the first phase of the improvements made through the Woodburn Urban Renewal Plan. The Plaza is in the center of the Urban Renewal Core Area and contains a water fountain, lawn, 8 benches, and the future location of a gazebo. Pedestrians regularly walk through the Plaza and sit on the benches.

F. The Urban Renewal Core Area is also a historic area, containing the oldest existing structures in Woodburn. Much of the construction is of un-reinforced masonry dating from the late Nineteenth Century.

G. The City Council passed Ordinance 2313 on April 9, 2002, which adopted the Woodburn Development Ordinance. The Woodburn Development Ordinance is incorporated into these findings by this reference.

H. The Woodburn Development Ordinance was also intended to enhance livability in the Urban Renewal Core Area through special zoning regulations in the form of a Downtown Development and Conservation District. Under the Woodburn Development Ordinance, Architectural Design Guidelines apply to exterior alterations to existing buildings and require that "materials, colors, and textures used in the alteration or addition should be fully compatible with the traditional architectural character of the historic building."

I. The Urban Renewal Core Area also has a higher crime rate than other areas of Woodburn. Street crimes, gang activity, vandalism, and the application of graffiti are ongoing problems that the City continues to address in this area. Exhibit "C" describes the concentration of graffiti and other property crimes in this area as compared to the rest of the city.

### **Section 3. Purpose.**

A. The general purpose of this Ordinance is to promote the public health, safety, and welfare through the regulation of placement, appearance, number, size, and servicing of newsracks on public rights of way so as to:



1. Provide for pedestrian and driving safety and convenience;
2. Prevent unreasonable interference with the flow of pedestrian or vehicular traffic including ingress into, or egress from, any residence, place of business, or from the street to the sidewalk, by persons exiting or entering parked or standing vehicles;
3. Provide reasonable access for the use and maintenance of sidewalks, poles, posts, traffic signs or signals, hydrants and mailboxes, and access to locations used for public transportation services;
4. Reduce visual blight on the public rights of way and protect the aesthetics of store window displays, public landscaping and other improvements;
5. Reduce exposure of the City to personal injury or property damage claims and litigation; and
6. Protect the right to distribute information that is protected by state and federal constitutions through the use of newsracks.

B. The purpose of the Additional Standards for newsracks in the Urban Renewal Core Area is to:

1. Require newsracks to be constructed of steel, a material more resistant to acts of vandalism (i.e., cutting and burning the newsrack) than lighter and weaker construction materials.
2. Require newsracks to be constructed of steel so that they are uniform in appearance and compatible with the architectural character of the historic buildings in this area.
3. Require that newsracks weigh at least 80 pounds. This weight requirement ensures that they are not easily vandalized, stolen or thrown into the public right-of-way. Newsracks made of lighter materials are not appropriate for installation in the Urban Renewal Core Area because the larger number of pedestrians and higher rate of crime in this area make it more likely that the newsracks could be thrown into the right-of-way and cause damage to persons and property.
4. Require newsracks to have coin mechanisms housed in the body of a newsrack or in armored heads welded or bolted to the body of a newsrack so that the newsracks are not subject to vandalism or theft.
5. Require newsracks to be painted or covered with a protective coating to make them graffiti resistant. This facilitates quick removal of graffiti so that criminal conduct and gang activity is discouraged.

**Section 4. Definitions.** For the purpose of this Ordinance, these words and phrases are defined as follows:

A. *Business day* means Monday through Friday, inclusive, of every week excepting holidays for which the city is closed to official business.

B. *City Administrator* means the Woodburn City Administrator or designee.

C. *Newsrack* means any self-service or coin-operated box, container, storage unit, or other dispenser installed, used, or maintained for the display and sale or distribution without charge of newspapers, periodicals, magazines or other publications.

D. *Owner* means the person or its duly authorized representative who owns a newsrack placed in the City.

E. *Parkway* means the area between the public sidewalk and the curb of any public street and where there is no public sidewalk, the area between the property line/right of way line and the curb.

F. *Permit* means a permit issued pursuant to this Ordinance which allows for the placement of a newsrack within a specifically designated portion of a sidewalk or parkway.

G. *Person* means any individual, firm, company, corporation or other organization.

H. *Roadway* means that portion of a public street improved, designed or ordinarily used for vehicular travel.

I. *Sidewalk* means any surface dedicated to the use of pedestrians by license, easement, and operation of law or by grant to the city.

J. *Street* means all of that area dedicated to public use for public street and sidewalk purposes and includes, but is not limited to, roadways, parkways, alleys, service drives and sidewalks.

K. *Urban Renewal Core Area* is that area located close to downtown Woodburn and described specifically in Exhibit "A" to this Ordinance.

L. *Vision Clearance Area* is that area defined by Section 3.103.10 of the Woodburn Development Ordinance.

**Section 5. Permit and Decal Required.** It shall be unlawful for any person to place, maintain, or cause to be placed, or maintained a newsrack on, or projecting on, any public right-of-way without first receiving a permit from the City for the newsrack and affixing a decal evidencing such permit on the newsrack.

**Section 6. Permit.**

A. An application for a newsrack permit shall be made to the City Administrator on a form which shall include:

1. The name, street and mailing address, email address, and telephone number of the applicant, which shall be the duly authorized representative of the newsrack owner.

2. The name, street and mailing address, email address, and telephone number of both the publisher, if different from the applicant, and, the independent distributor(s), if any, authorized to service the owner's newsrack(s) for which the permit is sought.

3. The name, street and mailing address, email address, and telephone number of the applicant's designated representative, if different than applicant, whom the City shall give notice under this ordinance or contact at any time concerning the applicant(s) newsrack(s).

4. A description of each proposed newsrack, including its dimensions and signage, and whether it contains a coin-operated mechanism.

5. The name and frequency of the publication proposed to be contained in each newsrack.

B. A separate application shall be required for each publication.

C. If the application is properly completed and the type of newsrack and location proposed for each newsrack meets the standards set forth in this Ordinance, the City Administrator shall issue a permit within 5 business days from the date the applicant files the application. A single permit shall be issued for all newsracks applied for by an applicant that meet the standards of this Ordinance. A permit shall not be transferable.

D. A permit shall be valid for 1 year.

E. The permit application fee shall be \$50.00, and the decal fee shall be \$10.00 per newsrack. All fees imposed under this Ordinance shall be paid to the City Administrator at the time the application is filed and may be adjusted from time to time.

F. Each permittee shall be issued a pre-printed decal for each permitted newsrack, which shall be affixed to the lower right or left corner inside the window opening on the front of each newsrack.

**Section 7. Denial of Permit.** If the application is incomplete or the type of newsrack and location proposed for a newsrack does not meet the standards set forth in this Ordinance, the City Administrator shall deny the permit application. If the newsrack permit is denied, in whole or in part, the City Administrator shall, by certified mail, notify the applicant within 5 business days from the date of filing a completed application, explaining the reasons for the denial of the permit. The applicant shall have 10 business days from the date the certified letter is mailed to correct and resubmit the application or to appeal the decision, in writing, to the Woodburn Municipal Court.

**Section 8. Appeal.** The Woodburn Municipal Court shall conduct a hearing within 30 days of receipt of the applicant's written appeal request. Written notice of the time and place of the hearing shall be provided to the applicant at least 10 business days prior to the date of the hearing. The Woodburn Municipal Court shall render a written decision within 15 business days after the date of the hearing.

**Section 9. General Placement and Location Standards for Newsracks.**

A. A person may not install, use or maintain a newsrack on any public right-of-way if the newsrack:

1. Endangers public safety;
2. Interferes with public utility, public transportation, or other governmental use; or
3. Interferes with or impedes:
  - a. Pedestrian or vehicular traffic;
  - b. Entry or exit from a residence or business;
  - c. Access to a legally parked or stopped vehicle;
  - d. Use of a traffic sign or signal, emergency call box, transit shelter, bus stop, elevator, mailbox, or other public service; or
  - e. Access to use of a delivery area or loading zone.

B. A newsrack shall not be placed upon any portion of the public right-of-way that abuts the Vision Clearance Area.

C. Except as otherwise provided in this Ordinance, a newsrack requiring a permit under this Ordinance shall be placed or maintained on any public right-of-way in compliance with the following standards:

1. Every newsrack shall be placed so as to open toward the street.
2. If multiple newsracks are permitted at the same location, all such newsracks must be placed together in a straight line and abutting adjoining newsracks and no group of newsracks shall extend for a distance of more than 10 feet.
3. No newsrack shall be chained or otherwise attached to any parking meter, kiosk, trash receptacle, street light, utility pole or device, sign pole, stand pipe, transit shelter, bus bench, bus stop, or to any tree, shrub or other plant, or other structure.
4. No newsrack shall be placed, installed or maintained:

- 
- a. Within 5 feet of any fire hydrant, emergency call box, or other emergency facility.
  - b. Within 5 feet of any parking meter, bench, kiosk, trash receptacle, tree well, utility pole, signal pole, sign pole, stand pipe, or control cabinet.
  - c. Within 10 feet of any transit shelter, bus bench or designated bus stop. The distance requirement shall be measured from the roof of any transit shelter, the edge of any bus bench, or the pole sign for any designated bus stop.
  - d. Within 10 feet of any alley, loading zone, disabled ramp or curb cut.
  - e. At any location where the clear space for the passage of pedestrians after placement or installation is less than 4 feet, or as required by ADA Accessibility Guidelines, whichever is greater.
  - f. Within 3 feet of or on any area of flowers or shrubs or similar landscaping, or in such a manner where ordinary use of the newsrack will cause damage to such landscaping.
  - g. Within 3 feet of any commercial window display.
  - h. Within 3 feet of or in such a manner as to block or cover any portion of an underground utility vault, manhole, or other sidewalk underground access location.
  - i. In such a manner as to be permanently affixed to any sidewalk, street or other property of the City.
  - j. Within 20 feet of any crosswalk.

D. Subject to the other provisions of this section, a newsrack requiring a permit under this Ordinance may be placed on the parkway adjacent to a sidewalk when placement of the newsrack on the sidewalk would reduce clear passage for pedestrians as provided in this Ordinance. In this case, the newsrack should open toward the sidewalk.

E. In the event the City must expand or otherwise reconfigure public right-of-way or make improvements thereto to improve the adjacent street, sidewalk, or for other public purpose, any and all newsracks displaced by such improvements shall be removed by the permittee at the permittee's sole cost and expense and in accordance with the instructions of the City. Wherever possible, and only in accordance with the requirements of this ordinance, the City shall attempt to allow the relocation of any newsracks displaced as provided herein to the newly reconfigured right-of-way without additional permit fee; provided, however, where such right-of-way will no longer accommodate newsracks in accordance with the requirements of this ordinance, the City shall not be obligated to provide alternative or other sites for such displaced newsracks.

**Section 10. General Construction and Maintenance Standards for Newsracks.**

Any newsrack requiring a permit under this Ordinance shall:

- A. Be in a clean condition and in good repair.
- B. Be constructed, installed, and maintained in a safe and secure condition.
- C. Be made of solid material on all sides; no wire or other open form of newsrack will be permitted.
- D. Be maintained so that it is free of graffiti.
- E. Be affixed with a decal, issued by the City, evidencing the issuance of a permit under this Ordinance.
- F. Be affixed with identifying information, which shall contain the name, address and telephone number of the newsrack owner and of the distributor of the publication contained therein. Such information shall be placed in a visible location on the front of the newsrack, and shall be legible.

**Section 11. Additional Construction and Maintenance Standards for Newsracks in Urban Renewal Core Area.** In addition to complying with the standards contained in Sections 9 and 10 of this Ordinance, any newsrack requiring a permit under this Ordinance that is located in the Urban Renewal Core Area shall meet the following additional standards:

- A. A newsrack shall be manufactured from 20-gauge or thicker zinc coated steel.
- B. A newsrack shall have a net weight of at least 80 pounds when not filled with newspapers, periodicals, magazines or other publications.
- C. Coin mechanisms, if any, shall be housed in the body of a newsrack or in armored heads welded or bolted to the body of a newsrack.
- D. A newsrack shall be painted or covered with a protective coating to make it graffiti resistant and promote the easy removal of any graffiti.

**Section 12. Abandoned Newsracks.** In the event any newsrack is severely damaged, or remains empty for more than 30 days, the newsrack shall be deemed abandoned, and may be seized and removed in the manner provided by this Ordinance.

**Section 13. Seizure of Newsracks.**

A. The City may seize and remove a newsrack if the person responsible for the newsrack has failed to obtain a permit under this Ordinance or where the newsrack creates an immediate danger to the public health, safety or welfare. The City Administrator shall provide notice to the owner, if known, by mailing a "Notice of Removal" to the last known address of the person.

B. Except for the instances specified in subsection "A" of this section, before any newsrack is seized, the designated representative shall be notified and provided 5 business days from notification in which to remedy the violation or to request a hearing to contest the seizure. A person notified under this subsection may make a written request for a hearing before the Woodburn Municipal Court.

C. If no hearing is requested after notice is given, the Woodburn Municipal Court may order the newsrack seized and disposed of. If a request for hearing is received, the Woodburn Municipal Court shall conduct a hearing within 30 days of receipt of the applicant's written request. Written notice of the time and place of the hearing shall be provided to the applicant.

D. The Woodburn Municipal Court shall render a written decision within 15 days after the date of the hearing.

E. The City shall hold any newsrack(s) seized under this section for 30 days from the date of seizure. The owner or designated representative may retrieve any seized newsrack(s) subject to a \$25 seizure and impound fee for each newsrack retrieved, to be paid at the time of retrieval. If a hearing has been requested, the City shall hold any seized newsrack(s) until the conclusion of all proceedings involving the newsrack(s), but not less than 30 days. At the conclusion of the appropriate time under this subsection, the City shall become owner of the seized newsrack(s) and may dispose of them as appropriate.

F. The owner of any newsrack(s) retrieved after seizure under this section, shall re-apply for a newsrack permit, pursuant to the requirements of this ordinance, prior to placing the formerly seized newsrack(s) back in the city.

**Section 14. Enforcement.**

A. A newsrack placed in violation of this Ordinance constitutes a public nuisance, and may be abated.

B. The City Attorney, after obtaining authorization from the City Council, may initiate a civil proceeding on behalf of the City to enforce the provisions of this Ordinance.

C. In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class 1 Civil Infraction and may be processed according to the procedures contained in the Woodburn Civil Infraction ordinance.

D. Each day that a violation of this Ordinance is committed or permitted to continue shall constitute a separate Civil Infraction.

E. The remedies provided for in this Section are cumulative and not mutually exclusive.

**Section 15. Severability.** If any section, subsection, sentence, clause, or phrase of this Ordinance is for any reason held to be invalid or unconstitutional by the decision of any court of competent jurisdiction, such decision shall not affect the validity of the remaining portions of this Ordinance.

**Section 16.** [Emergency clause.]

*Passed by the Council October 8, 2007, and approved by the Mayor  
October 10, 2007.*



**ORDINANCE NO. 2468****AN ORDINANCE IMPLEMENTING CERTAIN LOCAL INCENTIVES FOR BUSINESSES LOCATED WITHIN THE WOODBURN ENTERPRISE ZONE**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** All businesses located within the Woodburn Enterprise Zone that obtain authorization from the State of Oregon pursuant to ORS 285C.140 shall be subject to the Expedited Land Use Review process under Ordinance 2460, the Woodburn Development Ordinance.

**Section 2.** The Enterprise Zone filing fee referenced in ORS 285C.140(1)(c) is waived for businesses within the Woodburn Enterprise Zone that obtain authorization from the State of Oregon pursuant to 285C.140.

**Section 3.** All businesses within the Woodburn Enterprise Zone that obtain authorization from the State of Oregon pursuant to ORS 285C.140 shall also be entitled to the following:

- A. Waiver of 100% of the following planning fees adopted by Ordinance 2433 as part of the Master Fee Schedule;
  - 1. Sign Permit Fees
  - 2. Pre-Application Fees
  - 3. Expedited Land Use Review Fees

**Section 4.** All businesses within the Woodburn Enterprise Zone that obtain authorization from the State of Oregon pursuant to ORS 285C.140 shall have 100% of their business registration fees under Ordinance 2399 waived during the period of their authorization.

**Section 5.** All businesses within the Woodburn Enterprise Zone that obtain authorization from the State of Oregon pursuant to ORS 285C.140 shall have the water installation charges and sewer tap fees adopted by Ordinance 2433 as part of the Master Fee Schedule waived up to a maximum amount of \$2,000.

**Section 6.** In addition to the foregoing incentives, all businesses within the Woodburn Enterprise Zone that obtain extended authorization from the State of Oregon pursuant to ORS 285C.160 shall have 100% of their planning fees adopted by Ordinance 2433 as part of the Master Fee Schedule waived.

**Section 7.** Nothing in this Ordinance waives or is intended to waive any Systems Development Charges that are due to the City pursuant to Ordinances 2070, 2111, 2250, 2438 or any other applicable City Ordinance.

**Section 8.** Enterprise Zone data will be reported to the City Council on an annual basis and will include information on new investments, tax exemptions granted, job creation, and public benefit criteria.

**Passed by the Council July 26, 2010, and approved by the Mayor July 28, 2010.**

## ORDINANCE NO. 583

A BILL FOR AN ORDINANCE PROVIDING FOR THE NUMBERING OF HOUSES, STORES, AND OTHER BUILDINGS ERECTED WITHIN THE CITY OF WOODBURN; COMPELLING THE OWNERS THEREOF TO NUMBER SUCH BUILDINGS; AND PROVIDING A PENALTY FOR THE VIOLATION OF THIS ORDINANCE.

THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1. Buildings, How Numbered.** There shall be a uniform system of numbering all houses, stores and other buildings, except sheds and outbuildings erected or to be hereafter erected within the city limits of the city of Woodburn, by placing on the door or door frame of the main entrance of said building, or as near thereto as practicable, the number assigned thereto as hereinafter provided; said number to be painted on the building or on metal or glass, or a metallic figure used, at the option of the owner, and so placed as to be readily seen from the street. The figures designating the numbers when painted or otherwise shall be not less than three inches in height.

**Section 2. Time for Numbering.** All houses or buildings now erected shall be numbered within 90 days from the passage and approval of this ordinance, and all houses or buildings hereafter erected shall be numbered before being occupied.

**Section 3. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 4 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 3 as amended by Ordinance 2008 passed October 24, 1988.]

**Section 4. Public Buildings.** The committee on streets is hereby authorized to cause proper numbers to be placed on public buildings as required.

**Section 5. Houses, How Numbered.** That houses or buildings erected upon streets running northerly and southerly shall be numbered as follows: that part of each of said streets lying south of Cleveland Street shall be numbered southerly from the south side of said Cleveland Street, beginning with the number 100, and allow 100 numbers to each block; both sides of a street being considered a block. The even numbers to be used for numbering houses and buildings on the east side of said streets, and the odd numbers to be used for numbering on the west side of said streets. The first tier of blocks south of Cleveland Street shall be numbered southerly beginning such numbering with the figure 100, and continuing with successive numbers thereafter to and inclusive of the figure 199. The second tier of blocks shall be numbered beginning with the number 200 and continuing with the successive numbers thereafter, to and inclusive of the number 299, and continuing in like manner the numbering of each successive tier of blocks, giving 100 numbers to each tier of blocks, and ending such numbering at the southern boundary of the city. That part of said streets north of Cleveland Street shall be numbered in the same manner, but northerly from Cleveland

Street, beginning with the number 100 and giving 100 numbers to each tier of blocks northerly, and numbering in the same manner as numbering of said buildings southerly of Cleveland Street. Buildings or houses erected on lots which abut upon streets running easterly and westerly shall be numbered as follows: that part of each of said streets lying east of Front Street shall be numbered easterly from the east side of said Front Street, beginning with the number 100 and allowing 100 numbers to each block, both sides of the street being considered a block. The even numbers to be used for numbering houses and buildings on the south side of said streets, and the odd numbers to be used for such numbering on the north sides of said streets. The first tier of blocks east of Front Street shall be numbered easterly, beginning such numbering with the figure 100 and continuing with successive numbers thereafter to and inclusive of the figure 199. The second tier of blocks shall be numbered beginning with the number 200 and continuing with successive numbers thereafter to and inclusive of the number 299, and continuing in a like manner the numbering of each successive tier of blocks, giving 100 numbers to each tier of blocks, and ending such numbering at the eastern boundary of the city. That part of said streets lying west of Front Street shall be numbered in the same manner, but westerly from Front Street, beginning with the number 100 and giving 100 numbers to each tier of blocks westerly, numbering in the same manner as the numbering of said buildings easterly of Front Street.

All buildings or houses which are located upon short or otherwise irregular streets which are not covered by the foregoing provisions shall be numbered as near like as possible that of the nearest adjoining blocks of regular streets running relatively in the same direction. In order to ascertain the proper position of a number in a block, the length of the block shall be divided by 50 and this will give the relative distance apart of each number.

**Section 6.** All ordinances or part of ordinances in conflict herewith are hereby repealed.

***Passed by the Council and approved by the Mayor April 1, 1924.***

**ORDINANCE NO. 1015****AN ORDINANCE RELATING TO STREET DECORATIONS, ADVERTISING BANNERS, AND SIMILAR DISPLAYS; AND DECLARING AN EMERGENCY.****THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:**

**Section 1.** No persons shall install seasonal decorations or advertising banners, or similar displays upon, along or across streets of the city of Woodburn except as provided in this ordinance.

**Section 2.** All persons or organizations desiring to temporarily install seasonal decorations, advertising banners, or similar displays on poles owned by a public utility in the city of Woodburn upon, along or across the city streets shall file a written request with the city recorder that the street commissioner of the city of Woodburn install, maintain and remove or supervise the installation, maintenance and removal of the decorations, banners or displays.

**Section 3.** Upon approval of such request by the common council or by a city officer authorized by the council to approve such requests, the street commissioner shall install, maintain and remove, or supervise the installation, maintenance and removal of such decorations, banners and displays in conformity with the requirements of the owner of any public utility poles and all other buildings, poles or other objects to which the decorations, banners or displays are attached.

**Section 4.** The public utility company which owns the poles, and the owners of all buildings and objects to which such decorations or advertising banners are attached, shall not be liable for any damages to persons or property resulting from the installation, maintenance, and removal thereof by or under the supervision of the street commissioner of the city of Woodburn.

**Section 4A. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 4 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 4A as amended by Ordinance 2008, passed October 24, 1988.]

**Section 5.** [Emergency clause.]

***Passed by the council and approved by the mayor November 18, 1958.***

## ORDINANCE NO. 1358

AN ORDINANCE REGULATING THE MOVING OF BUILDINGS; PROVIDING FOR PROTECTION TO THE CITY FROM DAMAGES ARISING FROM SUCH MOVING; REQUIRING PERMITS AND FEES; PRESCRIBING PENALTIES FOR VIOLATION; AND DECLARING AN EMERGENCY.

THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1. Definitions.**

(a) Building. Any structure designed, built or occupied as a shelter or covered enclosure for persons, animals or property and used for residential, business, mercantile, storage, commercial, industrial, institutional, assembly, educational or recreational purposes. The following structures shall not fall within this definition:

- (1) Trailers, mobile homes.
- (2) Portable structures on skids.
- (3) Prefabricated utility or construction sheds with floor space less than 225 square feet.
- (4) Other structures with floor space less than 100 square feet and height less than 15 feet.

(b) City. City of Woodburn, Oregon.

(c) Person. Any individual person, firm, partnership, association, corporation, company or organization of any kind.

**Section 2. Permits.** No person shall move any building over, along or across any highway, street, alley, sidewalk or public right-of-way in the city without first obtaining a permit from the city. A person seeking such a permit shall file an application for such permit with the city. The application shall be in writing on a form provided by the city for such purpose. The application shall contain the following:

(a) A description of the building proposed to be moved, including address, construction materials, dimensions, number of rooms and general condition.

(b) Legal descriptions of the lots from and to which the building is to be moved, including lot, block and tract numbers if within the city.

(c) The portion of the lot to be occupied by the building where moved, if within the city.

(d) The specific highways, streets, alleys, sidewalks and rights-of-way over, along or across which the building is to be moved.

(e) Date and hours of movement.

(f) Any additional information which the city engineer shall find necessary for a fair determination of whether a permit should [be issued].

**Section 3. Tax Certificate.** The owner of the building to be moved shall file with the application sufficient evidence that the building and lot from which it is to be moved are free of all city taxes and city charges and assessments against the same are paid in full.

**Section 4. Certificate of Ownership or Entitlement.** The applicant, if other than the owner, shall file with the application a written statement or document of sale signed by the owner, or other sufficient evidence that he is entitled to move the building.

**Section 5. Permit Fee.** The fee to be paid for each permit under this ordinance shall be \$0.05 per square foot of floor space for one-story structures. Fees for structures in excess of one story shall be \$0.05 per square foot of floor space for the lowermost story, and \$0.03 per square foot of floor space of each additional story.

**Section 6. Deposit for Expense to City.** Upon receipt of an application, it shall be the responsibility of the city to estimate the expense that will be incurred in removing and replacing any electric wires, street lamps or pole lines belonging to the city, or any other property of the city, the removal and replacement of which will be required by reason of the moving of the building through the city, together with the cost of materials necessary to be used in making such removals and replacements. Prior to issuance of the permit, applicant shall deposit with the city a sum of money equal to twice the amount of the estimated expense.

**Section 7. Insurance.** An application hereunder shall be accompanied by a certificate of insurance certifying that the applicant has obtained a general liability insurance policy, issued by an insurance company authorized to do business in the state of Oregon, and approved as to form by the city attorney, which policy shall provide no less than the following coverage amounts:

- (a) \$100,000.00 bodily injury to one person.
- (b) \$300,000.00 per occurrence.
- (c) \$50,000.00 property damage.

**Section 8. Duties of the City.**

(a) Inspection. The city engineer shall inspect the building and the applicant's equipment to determine whether the standards for issuance of a permit are met.

- (b) Standards for Issuance. The city shall refuse to issue a permit if it finds:

(1) That any application requirement or any fee or deposit requirement has not been complied with;

(2) That the building is too large to move without endangering persons or property in the city;

(3) That the building is in such a state of deterioration or disrepair or is otherwise so structurally unsafe that it could not be moved without endangering persons and property in the city;

(4) That the building is structurally unsafe or unfit for the purpose for which moved, if the removal location is in the city;

(5) That the applicant's equipment is unsafe and that persons and property would be endangered by its use;

(6) That zoning or other ordinances would be violated by the building in its new location; [or]

(7) That for any other reason persons or property in the city would be endangered by the moving of the building.

**Section 9. Return of Deposits.**

(a) Return upon nonissuance. Upon refusal to issue a permit, the city shall return to the applicant all deposits and insurance policies. Permit fees filed with the application shall not be returned.

(b) Return upon allowance for expense. After the building has been removed, the city engineer shall furnish the city administrator with a written statement of all expenses incurred in removing and replacing all property belonging to the city, and of all material used in the making of the removal and replacement, together with a statement of all damage caused to or inflicted upon property belonging to the city. If any wires, poles, lamps or other property are not located in conformity with governing ordinances, the permittee shall not be liable for the costs of removing the same. The city administrator shall authorize the city engineer to return to the applicant all deposits after deducting the sum sufficient to pay for all of the costs and expenses and for all damage done to property of the city by reason of the removal of the building. Permit fees deposited with the application shall not be returned. [Section 9 as amended by Ordinance No. 1464, passed February 24, 1975.]

**Section 10. Routes.** The city engineer shall prepare a route over which the building may be moved. In doing so, he shall take into consideration maximum safety to all relevant engineering consequences. The route shall be stated in the permit, and any building shall be moved only over said route.

**Section 11. Responsibilities of Permittee.** Permittee shall:



(a) Notify the city in writing of any and all damage done to property belonging to the city within 24 hours after such damage has occurred.

(b) Cause red lights to be displayed during the nighttime on every side of the building, while standing on a street, in such manner as to warn the public of the obstruction, and shall at all times erect and maintain barricades across the streets in such manner as to protect the public from damage or injury by reason of the removal of the building.

(c) Remove the building from the city streets after a reasonable period of time to be determined by the city engineer.

(d) Comply with the building code, the fire zone, the zoning ordinance, and all other applicable ordinances and laws, upon relocating the building in the city.

(e) Pay the expense of a traffic officer ordered by the city to accompany the movement of the building to protect the public from injury.

(f) Remove all rubbish and materials and fill all excavations to existing grade at the original building site so that the premises are left in a safe and sanitary condition.

(g) Insure that the sewer line is plugged with a concrete stopper, the water shot off, and the meter returned to the city. Permittee shall notify the gas and electric service companies to remove their services.

#### **Section 12. Enforcement.**

(a) Permittee liable for expense above deposit. The permittee shall be liable for any expense, damages or costs in excess of deposited amounts or securities, and the city attorney shall prosecute an action against the permittee in a court of competent jurisdiction for the recovery of such excessive amounts.

(b) Original premises left unsafe. The city shall proceed to do the work necessary to leave the original premises in a safe and sanitary condition, where permittee does not comply with the requirements of this ordinance, and the cost thereof shall be charged against the general deposit.

**Section 13. Severability.** Each section, subsection or other portion of this ordinance shall be severable; the invalidity of any section, subsection or other portion shall not invalidate the remainder.

**Section 14. Civil Infraction Assessment.** A violation of any provision of this ordinance constitutes a class 2 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 14 as amended by Ordinance 2008, passed October 24, 1988.]

***Passed by the Council and approved by the Mayor June 11, 1993.***

## ORDINANCE NO. 1652

## AN ORDINANCE ASSESSING A TECHNICAL AND ENVIRONMENTAL SERVICES CHARGE AND PROVIDING FOR ITS EXPENDITURE.

[Whereas clauses.]

## THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1. Construction Fee.** That a fee of one dollar (\$1.50) per one thousand dollars (\$1,000) of construction value shall be charged to all new construction in the City of Woodburn.

[Section 1 as amended by Ordinance 2370, passed August 23, 2004.]

**Section 2. Fee Collection.** This fee shall be collected by the Building Official prior to issuance of a building permit.

**Section 3. Technical and Environmental Services Fund.** The monies collected shall be placed in two funds: two-thirds of the monies shall be placed in the General Fund for planning services, and one-third of the monies shall be placed in the Technical and Environmental Fund for engineering services. These monies shall be used to meet the expenses necessary in providing planning and engineering services associated with reviewing building permit applications.

[Section 3 as amended by Ordinance 2370, passed August 23, 2004.]

*Passed by the Council January 22, 1979, and approved by the Mayor  
January 23, 1979.*

## ORDINANCE NO. 1762

## AN ORDINANCE PROVIDING FOR INSPECTION AND ISSUANCE OF PERMITS FOR MOBILE HOME INSTALLATION AND DECLARING AN EMERGENCY.

[Whereas clause.]

## THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:

**Section 1.   Inspections.** Under authority of ORS 446.250, the City of Woodburn shall cause inspections to be made, approve plans and specifications, provide technical services and issue permits for installation of mobile homes and mobile home accessory buildings and structures on a lot.

**Section 2.   Fees.** The City of Woodburn shall collect, retain and have use of any fees required by state law to be paid in connection with the inspections listed in Section 1.

**Section 3.**   [Emergency clause.]

*Passed by the Council August 10, 1981, and approved by the Mayor  
August 12, 1981.*

## ORDINANCE NO. 1999

## AN ORDINANCE PROVIDING FOR THE ABATEMENT OF BUILDING NUISANCES; REPEALING ORDINANCE 1620; AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.** For the purposes of this ordinance, the following mean:

**Dangerous Building.**

(a) A structure that, for lack of proper repairs or because of age and dilapidated condition or of poorly installed electrical wiring or equipment, defective chimney, gas connection or heating apparatus, or for any other reason, is liable to cause fire, and which is situated or occupied in a manner that endangers other property or human life.

(b) A structure containing combustible or explosive materials or inflammable substances liable to cause fire or danger to the safety of the building, premises or to human life.

(c) A structure that is in a filthy or unsanitary condition liable to cause the spread of contagious or infectious disease.

(d) A structure in such a weak, dilapidated or deteriorated condition that it endangers a person or property because of the probability of partial or entire collapse.

**Person.** Every natural person, firm, partnership, association or corporation.

**Section 2. Nuisance Declared.** Every building found by the Council to be a dangerous building is declared to be a public nuisance and may be abated by the procedures specified in this ordinance or by a suit for abatement brought by the city.

**Section 3. Initial Action.** When a city official determines that there is a dangerous building, the official shall report it to the Council. The Council shall, within a reasonable time, fix a time and place for a public hearing.

**Section 4. Mailed Notice.**

(a) The City Recorder shall notify the owner of the building and, if not the same person, the owner of the property on which the building is situated. The notice shall state:

(1) That a hearing will be held concerning the nuisance character of the property, and

(2) The time and place of the hearing.

(b) A copy of this notice shall be posted on the property.

**Section 5. Published Notices.** Ten days' notice of the hearing shall be published in a newspaper of general circulation in the city or by posting notices in three public places in the city.

**Section 6. Hearing.**

(a) At the hearing, the owner or other persons interested in the dangerous building shall have a right to be heard.

(b) The Council may inspect the building and may consider the facts observed by it in determining if the building is dangerous.

(c) If the Council determines that the building is dangerous, the Council may by resolution:

(1) Order the building to be abated; or

(2) Order the building to be made safe and prescribe what must be done to make it safe.

**Section 7. Council Order; Notice.** Five day's notice of the Council's findings and any order made by the Council shall be given to the owner of the building, the owner's agent or other person controlling it. If the orders are not obeyed and the building not made safe within the time specified by the order (being not less than five days), the Council may order the building demolished or made safe at the expense of the property on which it is situated.

**Section 8. Abatement by the City.**

(a) If the Council orders are not complied with, the Council may:

(1) Specify the work to be done;

(2) Advertise for bids for doing the work in the manner provided for advertising for bids for street improvements.

**Section 9. Assessment.**

(a) The Council shall determine the probable cost of the work and assess the costs against the property upon which the building is situated. The assessment shall be declared by resolution, and it shall be entered in the docket of city liens and become a lien against the property.

(b) The creation of the lien and the collection and enforcement of the cost shall be performed in substantially the same manner as assessments for street improvements.

**Section 10. Summary Abatement.** The procedures of this ordinance need not be followed if a building is unmistakably dangerous and imminently endangers human life or property. In this instance, the city may summarily demolish the building.

**Section 11. Errors in Procedure.** Failure to conform to the requirements of this ordinance that does not substantially affect a legal right of a person does not invalidate a proceeding under this ordinance.

**Section 12. Civil Infraction.**

(a) A violation of any provision of this ordinance constitutes a class 1 civil infraction and shall be dealt with according to the procedures established by Ordinance 1998. [Section 12(a) as amended by Ordinance 2008 passed October 24, 1988.]

(b) Subsection (a) of this section provides an alternative remedy to the abatement provisions contained elsewhere in this ordinance and shall not be read to prohibit abatement of building nuisances as so provided.

**Section 13. Repeal.** Ordinance 1620 is hereby repealed.

**Section 14.** [Emergency clause.]

*Passed by the Council May 23, 1988, and approved by the Mayor May 23, 1988.*

## ORDINANCE NO. 2018

**AN ORDINANCE REGULATING AND CONSTRAINING DEVELOPMENT AND CONSTRUCTION WITHIN THE FLOOD PLAIN AREAS OF WOODBURN, REPEALING ORDINANCE NO. 1967, AND DECLARING AND EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Purpose and Intent.** It is the purpose and intent of this ordinance to promote the public health, safety and welfare, and to minimize public and private losses due to flood conditions by regulating and constraining development and construction within the flood plain areas of Woodburn.

**Section 2. Definitions.**

(A) "Area of Special Flood Hazard" means the land in the flood plain within a community subject to a one percent or greater chance of flooding in any given year. The area may be designated as Zone A on the FIRM. Zone A is usually refined into Zones A, AO, AH, A1-30, AE, A99, AR, AR/A1-30, AR/AE, AR/AO, AR/AH or AR/A. (Amended by Ordinance 2253, January 10, 2000)

(B) "Base Flood" means the flood having a one percent chance of being equaled or exceeded in any given year. Also referred to as the "100-year flood." (Amended by Ordinance 2253, January 10, 2000)

(C) "Development" means any man-made changes to improved or unimproved real estate including, but not limited to, buildings or other structures, mining, dredging, filling, grading, paving, excavation, or drilling operations located within the area of special flood hazard.

(D) "FIRM". An acronym for Flood Insurance Rate Map. This is the official map of the community, on which has been delineated both the special hazard areas and the risk premium zones applicable to the City of Woodburn. (Amended by Ordinance 2253, January 10, 2000)

(E) "Flood or Flooding" means a general and temporary condition of partial or complete inundation of normally dry land areas.

(F) "Flood Insurance Study" means the official report provided by the Federal Emergency Management Agency that is an examination, evaluation and determination of flood hazards and, if appropriate, corresponding water surface elevations. (Amended by Ordinance 2253, January 10, 2000)

(G) "Floodway" means the channel of a stream or other water course and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing water surface elevations more than one(1) foot.

(H) "Lowest Floor" means the lowest floor of the lowest enclosed area (including a basement). An unfinished or flood resistant enclosure, usable solely for parking of vehicles, building access or storage, in an area other than a basement area, is not considered a building's lowest floor, provided that such enclosure is not built so as to render the structure in violation of the applicable nonelevation design requirements of this ordinance found at Section 5(A)(2). (Amended by Ordinance 2253, January 10, 2000)

(I) "Manufactured Home" means a structure, transportable in one or more sections, which is built on a permanent chassis and is designed for use with or without a permanent foundation when connected to the required utilities. For insurance purposes the term "manufactured home" does not include a "recreational vehicle" which is: built on a single chassis, 400 square feet or less when measured at the largest horizontal projection, designed to be self propelled or permanently towable by a light duty truck, and designed primarily not for use as a permanent dwelling but as temporary living quarters for recreational, camping, travel or seasonal use. (Amended by Ordinance 2253, January 10, 2000)

(J) "Mean Sea Level" means the National Geodetic Vertical Datum (NGVD) of 1929 or other datum, to which base flood elevations on the city's FIRM are referenced. (Amended by Ordinance 2253, January 10, 2000)

(K) "New Construction" means structures for which the start of construction commenced on or after the effective date of this ordinance.

(L) "Start of Construction" includes substantial improvement, and means the date the building permit was issued, provided the actual start of construction, repair, reconstruction, placement or other improvement was within 180 days of the permit date. The actual start means either the first placement of permanent construction of a structure on a site, such as the pouring of slab or footings, the installation of piles, the construction of columns, or any work beyond the stage of excavation; or the placement of a manufactured home on a foundation. Permanent construction does not include land preparation, such as clearing, grading and filling; nor does it include the excavation for a basement, footings, piers, or foundation or the erection of temporary forms, nor does it include the installation on the property of accessory buildings, such as garages or sheds not occupied as dwelling units or not part of the main structure. (Amended by Ordinance 2253, January 10, 2000.)

(M) "Storm Water Management Plan" means the section of the City's officially adopted Comprehensive Plan which deals with storm water and flood water management. (Amended by Ordinance 2253, January 10, 2000)

(N) "Structure" means a walled and roofed building including a gas or liquid storage tank that is principally above ground, as well as a manufactured home. (Amended by Ordinance 2253, January 10, 2000)



(O) Substantial Improvement" means any reconstruction, rehabilitation, addition or other improvement of the structure, the cost of which equals or exceeds fifty percent (50%) of the market value of the structure before the "start of construction" of the improvement. This term includes structures which have incurred damage of any origin sustained by a structure whereby the cost of restoring the structure to its before damaged condition would equal or exceed 50 percent of the market value of the structure before the damage occurred regardless of the actual repair work performed. The term does not, however, include either:

(1) Any project for improvement of a structure to correct existing violations of state or local health, sanitary, or safety code specifications which have been identified by the city code enforcement official and which are the minimum necessary to assure safe living conditions or,

(2) Any alteration of a "historic structure", provided that the alteration will not preclude the structure's continued designation as a "historic structure".

(Amended by Ordinance 2253, January 10, 2000.)

### **Section 3. General Provisions.**

(A) Land to which this ordinance applies. This ordinance shall apply to all areas of special flood hazard within the jurisdiction of the City of Woodburn.

(B) Subdivision Proposals:

(1) All subdivision proposals shall be consistent with the need to minimize flood damage;

(2) All subdivision proposals shall have public utilities and facilities such as sewer, gas, electrical, and water systems located and constructed to minimize flood damage;

(3) All subdivision proposals shall have adequate drainage provided to reduce exposure to flood damage; and

(4) Where base flood elevation data has not been provided or is not available from another authoritative source, it shall be generated for subdivision proposals and other proposed developments which contain at least 50 lots or 5 acres (which ever is less).

(C) Review of Building Permits: Where elevation data is not available either through the Flood Insurance Study or from another authoritative source, applications for building permits shall be reviewed to assure that proposed construction will be reasonably safe from flooding. The test of reasonableness is a local judgment and includes use of historical data, high-water marks, photographs of past flooding, etc, where available. Failure to elevate at least two feet above grade in these zones may result in higher insurance rates.

(D) Basis for establishing the areas of special flood hazard. The area of special flood hazard identified by the Federal Emergency Management Agency in a scientific and engineering report entitled "The Flood Insurance Study for Marion County and Incorporated Areas" dated January 19, 2000, with accompanying flood insurance maps is hereby adopted by reference and declared to be a part of this ordinance. In addition, the City's Storm Water Management Plan is also adopted by this ordinance and included as a part thereof. (Amended by Ordinance 2253, January 10, 2000)

(E) Minimum floor elevations for structures in the flood hazard area. THE MINIMUM FLOOR ELEVATIONS FOR STRUCTURES IN THE FLOOD HAZARD AREAS SHALL BE DETERMINED ON A SITE SPECIFIC BASIS USING SURVEYS AND SURVEY DATA OR DATA FOUND TO BE ACCEPTABLE UNDER THE SECTIONS OF THIS ORDINANCE OR THE NATIONAL FLOOD INSURANCE STANDARDS.

(F) Floodways defined. The following floodways are hereby defined by this ordinance:

(1) For Mill Creek main drainage channel A MAXIMUM FLOODWAY WIDTH OF 150 FEET AS DEFINED ON DATA TABLE #6 OF THE MARION COUNTY AND INCORPORATED AREA FLOOD INSURANCE STUDY. (Amended by Ordinance 2253, January 10, 2000)

(2) For Senecal Creek main channel, a MAXIMUM FLOODWAY WIDTH OF 145 FEET AS DEFINED ON DATA TABLE #2 OF THE MARION COUNTY AND INCORPORATED AREA FLOOD INSURANCE STUDY. (Amended by Ordinance 2253, January 10, 2000)

(3) For the tributary in drainage basin no. 2 as defined on the Storm Water Management Plan, a floodway of 80 feet from the confluence with tributary no. 2 with Mill Creek upstream 1,600 feet.

(4) For the tributary in drainage basin no. 3, a floodway channel of 60 feet from the confluence of tributary no. 3 with the main Mill Creek channel upstream 1,000 feet.

(5) For the tributary in drainage basin no. 5, a floodway of 80 feet from the confluence of tributary No. 5 with the Mill Creek channel upstream 1,600 feet.

(6) For the tributary in drainage basin no. 6, a floodway of 100 feet from the confluence of tributary no. 6 with the Mill Creek channel upstream 1,000 feet, a floodway of 80 feet from 1,000 to 1,500 feet, and a floodway of 60 feet from 1,500 feet to 2,000 feet above the confluence of Mill Creek.

(7) For the tributary in drainage basin no. 7, a floodway of 80 feet from the confluence of tributary no. 7 with Mill Creek upstream 1,800 feet.

(8) For the Senecal Creek tributary which is unnumbered on the Storm Water Management Plan but which drains the area from Interstate 5 to Woodland Avenue, a floodway of 80 feet from the point of its confluence with Senecal Creek upstream to the point at which it crosses underneath State Highway 214.

(G) In addition to the above mentioned floodways, a floodway of 40 feet shall be maintained on all open existing drainage channels within the City of Woodburn.

#### **Section 4. Administration.**

(A) Establishment of development permit. A development permit shall be obtained before construction or development begins within any area of special flood hazard established in Section 3 (F). The permits shall be for all structures including manufactured homes as set forth in the definitions and for all other developments including fill and other activities as also set forth in the definitions. (Amended by Ordinance 2253, January 10, 2000)

(B) Designation of the City Engineer. The City Engineer, or his designate, is hereby appointed to administer and implement this ordinance by granting or denying development applications in accordance with its provisions.

(C) Duties and responsibilities of the City Engineer. Duties of the City Engineer shall include, but are not limited to:

(1) Permit review. Review all development permits to determine whether the permit requirements of this ordinance have been satisfied.

(2) Review all development permits to determine that all necessary permits have been obtained from those federal, state or local governmental agencies from which prior approval is required.

(3) Review all development permits to determine if the proposed development is located in the floodway.

(4) Review all requests to fill in the flood hazard area to determine if the requests are in conformance with the criteria set forth in this ordinance.

(D) Use of other base flood data. When base flood elevation data has not been provided in accordance with Section 3(B), (C), basis for establishing the areas of special flood hazard, the City Engineer shall obtain, review, and reasonably utilize any base flood elevation and floodway data available from federal, state, or other sources in order to administer the provisions of this ordinance.

(E) Information to be obtained and maintained.

(1) Where base flood elevation data is provided through the Flood Insurance Study or required as in Section 4(D), obtain and record the actual elevation in relation to mean sea level of the lowest floor (including basement) of all new or substantially improved structures and whether or nor the structure contains a basement.

(2) For all new or substantially improved flood-proof structures:

(i) Obtain and record the actual elevation (in relation to mean sea level) and,

(ii) Maintain the flood proofing certifications required in Section 6(B)(3).

(iii) Elevations required above shall be provided by the owner along with a certification by an engineer or registered land surveyor of the actual elevation above mean sea level of the lowest floor of the structure.

(F) Alteration of water courses.

(1) Notify adjacent communities and the state agency responsible prior to any alteration or relocation of a water course, and submit evidence of such notification to the Federal Emergency Management Agency.

(2) Require that maintenance is provided within the altered and relocated portion of said water course so that the flood carrying capacity is not diminished.

(Amended by Ordinance 2253, January 10, 2000)

**Section 5. General Standards.** In all areas of special flood hazards the following standards are required.

(A) Anchoring.

(1) All new construction and substantial improvements to existing structures shall be anchored to prevent flotation, collapse, or lateral movement of the structure.

(2) All manufactured homes in a special flood hazard area shall be placed on fill AND elevated to the minimum elevations established in Section 3(C) or 1.5 feet above the elevation of the base flood.

(3) All manufactured homes must likewise be anchored to prevent flotation, collapse or lateral movement, and shall be installed using methods and practices that minimize flood damage. Anchoring methods may include, but are not limited to, use of over-the-top or frame ties to ground anchors.

(B) Utilities.

(1) All new and replacement water supply systems shall be designed and constructed to minimize or eliminate infiltration of flood waters into the system.

(2) New and replacement sanitary sewer systems shall be designed and constructed to minimize or eliminate infiltration of flood waters into the systems and discharge of the systems into the flood waters.

(3) On-site waste disposal systems shall be located to avoid impairment to them or contamination from them during flooding.

(C) Storage of materials and equipment. Materials that are buoyant, flammable, obnoxious, toxic or otherwise injurious to persons or property, if transported by flood-waters, are prohibited in the flood hazard area. Storage of materials and equipment not having these characteristics is permissible only if the materials and equipment have low-damage potential and are anchored or are readily removable from the area within the time available after forecasting and warning, however, no storage is allowed in the floodway.

**Section 6. Specific Standards.** In all areas of special flood hazards where base flood elevation data has been provided in this ordinance under Section 3(C) or Section 4(D), the following provisions are required.

(A) Electrical, heating, ventilation, plumbing, and air conditioning equipment and other service facilities shall be designed and/or otherwise elevated or located so as to prevent water from entering or accumulating within the components during conditions of flooding.

(B) All manufactured homes to be placed or substantially improved within Zones A1-30, AH, and AE shall be elevated on a permanent foundation such that the lowest floor of the manufactured homes is ABOVE the base flood elevation and be securely anchored or an adequately anchored foundation system in accordance with the provisions of Section 5(A)(2) and 5(A)(3).

(C) Residential Construction. New construction and substantial improvement of any residential structures shall have the lowest floor, including basement, elevated to or above the elevation established in Section 3(C), or 1.5 feet above the elevation established in Section 3(D) and 4(D).

(D) Fully enclosed areas below the lowest floor that are subject to flooding are prohibited, or shall be designed to automatically equalize hydrostatic flood forces on exterior walls by allowing for the entry and exit of floodwaters. Designs for meeting this requirement must either be certified by a registered professional engineer or architect or must meet or exceed the following minimum criteria:

(1) A minimum of two openings having a total of not less than one square inch for every square foot of enclosed area subject to flooding shall be provided.

(2) The bottom of all openings shall be no higher than one foot above grade.

(3) Openings may be equipped with screens, louvers, or other coverings or devices provided that they permit the automatic entry and exit of flood waters.

(E) Non-Residential Construction. New construction and substantial improvement of any commercial, industrial or other non-residential structure shall either have the lowest floor, including basement, elevated to the level of the elevation established in Section 3(C), or 1.5 feet above the elevation of the base flood established in Section 3(D) and 4(D) or, together with the attendant utility and sanitary facilities shall:

(1) Be flood proofed so that below the base flood level of the structure is water-tight with walls substantially impermeable to the passage of water.

(2) Have structural components capable of resisting hydrostatic loads and effect of buoyancy in a base flood.

(3) Be certified by a registered professional engineer or architect that the design and methods of construction are in accordance with accepted standards of practice of meeting provisions of this subsection based on their development and/or review of the structural design, specifications and plans. Such certifications shall be provided to the City Engineer.

(4) Nonresidential structures that are elevated, not floodproofed, must meet the same standards for space below the lowest floor as described in Section 6(A).

(5) Applicants floodproofing nonresidential buildings shall be notified that flood insurance premiums will be based on rates that are one foot below the flood-proofed level (e.g., a building constructed to the base flood level will be rated as one foot below that level).

## **Section 7. Floodways.**

(A) IN THE FLOODWAYS AS DEFINED UNDER SECTION 3(F), NO ENCROACHMENTS INCLUDING FILL, NEW CONSTRUCTION, SUBSTANTIAL IMPROVEMENTS, AND OTHER DEVELOPMENT, WITHIN THE ADOPTED REGULATORY FLOODWAY THAT WOULD RESULT IN ANY INCREASE IN FLOOD LEVELS, IS PERMITTED.

(B) THE NORMAL AND ROUTINE MAINTENANCE OF STREAM CHANNELS IS NOT PRECLUDED BY THIS ORDINANCE PROVIDED SUCH MAINTENANCE COMPLIES WITH THE NO RISE STANDARD IN FLOOD LEVELS AS OUTLINED IN SECTION 7(A).

**Section 8. Fill Standards**

(A) All structures built in the special flood area shall be constructed on engineered fill or shall have designed footings at suitable depth, both as required by the Uniform Building Code, or in conformance with other additional standards as required by the City Engineer in accordance with good engineering practices.

(B) The slope on a fill in the special flood hazard area shall not exceed 33%. Toe of such fill shall be outside the floodways defined in Section 3(D).

(C) The amount of fill in the special flood hazard area shall be kept to a minimum. The following standards shall apply.

(1) Only one structure per existing lot at the time of passage of this ordinance shall be allowed for areas within the special flood hazard area. The structure shall be located so that a minimum amount of fill will be necessary for the elevation of the structure above the flood level.

(2) All subdivision, partition, and planned unit developments which envision development of any special flood hazard area shall indicate on the preliminary plan the location of all structures proposed to be located in the flood hazard area. These structures shall be located so that a minimum amount of fill is required to develop the land.

(3) Development proposals, whether nonresidential or residential, together with public utilities and facilities attendant to them, shall be constructed to minimize flood damage, and adequate drainage shall be provided. In areas not covered by Section 3(B), flood elevation data shall be provided by the developer.

(4) Multiple family residential or nonresidential structures shall be located as far as practical on the existing contiguous property from the floodway.

**Section 9. Density Transfer.** The Planning Commission may, upon application under the variance procedure, allow a higher density of dwelling units or structures on a parcel of property which contains areas of special flood hazard if the areas of special flood hazard are left substantially without fill. The Commission shall determine the amount of fill which would practicably be allowed in the flood hazard, and the additional amount of density on land outside the special flood hazard area which should be allowed due to the loss of the developable land in the flood hazard area.

**Section 10. Variances.** Variances to this ordinance shall comply with the same standards and follow the same procedures for variances to the Zoning Code of the City of Woodburn.

**Section 11. Enforcement.**

(A) Violation of this ordinance is a CLASS I CIVIL INFRACTION and shall be punishable by a fine of up to \$500 for the first offense (finding of violation), and by a fine of up to \$500 for the second and succeeding offenses (finding of violation). A separate offense will be deemed to occur on each calendar day that the infraction continues to exist, and a separate citation may be filed for each such offense.

(B) Alternate Remedy. If a parcel of land is, or is proposed to be used, developed, or maintained in violation of this ordinance, the aforesaid use shall constitute a nuisance, and the City may, as an addition to other remedies that are legally available for enforcing this ordinance institute injunction, mandamus, abatement, or other appropriate proceedings to prevent, enjoin temporarily or permanently, abate or remove the unlawful use, development, or maintenance of the land.

**Section 12. Violation as Nuisance.** Violation of any provision of this ordinance is hereby declared to be a nuisance, for which remedy may be pursued by the City to the full extent of law, notwithstanding any limitation in this or any other ordinance.

**Section 13. Severability.** If any word, clause, phrase, section, subsection, or other portion of this ordinance is found invalid by a court of competent jurisdiction, then the remainder of the ordinance shall be given full effect.

**Section 14. Ordinance Repealed.** Ordinance No 1967 is hereby repealed and Ordinance No. 1664 is not thereby resurrected.

**Section 15.** [Emergency clause.]

*Passed by the Council and approved by the Mayor March 27, 1989*



## ORDINANCE NO. 2415

AN ORDINANCE ADOPTING CERTAIN STATE SPECIALTY CODES; SETTING FORTH THE POWERS AND DUTIES OF THE BUILDING OFFICIAL; PROVIDING FOR PROCEDURES AND FEES; ESTABLISHING PENALTY PROVISIONS; REPEALING ORDINANCE 2293 AND DECLARING AN EMERGENCY.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.** For the purpose of this Ordinance, the following terms shall mean:

- A. Building Official - means the City of Woodburn Building Official who is responsible for building inspections and with the administration and enforcement of this ordinance.
- B. State Building Code - or "the code" means the combined specialty codes adopted by this ordinance.

**Section 2. State Codes Adopted.** The following codes, standards and rules are adopted and are by this reference incorporated herein and shall be in force and effect within the corporate boundaries of the City of Woodburn:

A. The Oregon Structural Specialty Code, as adopted by the State of Oregon, including the following administrative provisions:

- 1. Section 104.2 (Applications and permits).
- 2. Section 104.4 (Inspections).
- 3. Section 104.7 (Department Records).
- 4. Section 104.8 (Liability).
- 5. Section 104.9 (Approved materials and equipment).
- 6. Section 104.10 (Modifications).
- 7. Section 104.11 (Alternate materials, design and methods of construction and equipment).
- 8. Section 104.12 (Requests for rulings).
- 9. Section 105.3.2. (Time limit of application). "An application for a permit for any proposed work shall be deemed to have been abandoned 180 days

after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one extensions of time for an additional period not exceeding 180 days. The extension shall be requested in writing and justifiable cause demonstrated."

10. AN109.4 (Alternative fire sprinkler system requirements).

(Section 2A as amended by Ordinance 2420 dated May 29, 2007)

B. The Oregon Mechanical Speciality Code, as adopted by the State of Oregon, including the following administrative provision:

1. Section 106.4.3. (Time limit of application). "An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one extensions of time for an additional period not exceeding 180 days. The extension shall be requested in writing and justifiable cause demonstrated."

C. The Oregon Residential Specialty Code, as adopted by the State of Oregon, including the following administrative and automatic fire sprinkler system provisions:

1. Section 105.3.2 (Time limit of application). "An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one extension of time for an additional period not exceeding 180 days. The extension shall be requested in writing and justifiable cause demonstrated."

2. Sections AN109.4.2 through AN109.4.3 (Fire sprinkler system requirements).

3. Section AN109.4.3 (Definition: Substantially altered or damaged). "The valuation to repair or alter the building or structure exceeds 60 percent of the value of that portion of the building or structure as defined in the building code and determined by the Building Official."

D. The Oregon Plumbing Specialty Code as adopted by the State of Oregon.

E. The Electrical Safety Law as contained in ORS 479.510 to 479.995.

F. The Oregon Fire Code Amendments, as adopted by the State of Oregon;

G. Manufactured structure installation requirements under ORS 446.155, 446.185 (1) and 446.230;

H. Manufactured dwelling park and mobile home park requirements under ORS Chapter 446;

I. Park and camp program requirements under ORS 455.680;

- J. Tourist facility requirements under ORS 446.310 to 446.350;
- K. Manufactured dwelling alterations under ORS 446.155; and
- L. Manufactured structure accessory buildings and structures under ORS 446.253.

**Section 3. Powers and Duties of the Building Official.** The Building Department shall be under the administrative and operational control of the building official. The building official shall have the power to render written and oral interpretations of the code and to adopt and enforce administrative procedures in order to clarify the application of its provisions. Such interpretations, rules, and regulations shall be in conformance with the intent and purpose of the code. The building official is authorized to enforce all the provisions of the code.

**Section 4. Right of Entry.** When it is necessary to make an inspection to enforce the state building code, or when the building official has reasonable cause to believe that there exists in a building or upon a premises a condition which is contrary to or in violation of the code which makes the building or premises unsafe, dangerous or hazardous, the building official may enter the building or premises at reasonable times to inspect or to perform the duties imposed by the code, provided that if such building or premises be occupied that credentials be presented to the occupant and entry requested. If such building or premises be unoccupied, the building official shall first make a reasonable effort to locate the owner or other person having charge or control of the building or premises and request entry. If entry is refused, the building official shall have recourse to the remedies provided by law to secure entry.

**Section 5. Stop Work Orders.** Whenever any work is being done contrary to the provisions of the code, or other pertinent laws or ordinances implemented through the enforcement of the code, the building official may order the work stopped by notice in writing served on any person(s) engaged in the doing or causing such work to be done. Such person(s) shall forthwith stop such work until specifically authorized by the building official to proceed with the work. Notwithstanding the other remedies, if the building official determines that any building under construction, mechanical work, electrical work, or plumbing work on any building or structure poses an immediate threat to the public health, safety or welfare, the building official may order the work halted and the building or structure vacated pending further action by the city and its legal counsel.

**Section 6. Authority to Disconnect Utilities in Emergencies.** The building official or the building official's authorized representative shall have the authority to disconnect fuel-gas utility service, or energy supplies to a building, structure, premises or equipment regulated by the code in case of emergency when necessary to eliminate an immediate hazard to life or property. The building official shall, whenever possible, notify the serving utility, the owner and occupant of the building, structure or premises of the decision to disconnect prior to taking such action, and shall notify such serving utility, owner and occupant of the building, structure or premises in writing of such disconnection immediately thereafter.

**Section 7. Connection After Order to Disconnect.** Persons shall not make connections from an energy, fuel or power supply nor supply energy or fuel to any equipment regulated by the code which has been disconnected or ordered to be disconnected by the building official, or the use of which has been ordered to be discontinued by the building official, until the building official authorizes the reconnecting and use of such equipment.

**Section 8. Occupancy Violations.** Whenever any building or structure or equipment is being used contrary to the provisions of the code, the building official may order such use discontinued and the structure, or portion thereof, vacated by notice served on any person causing such use. Such person shall discontinue the use within the time prescribed by the building official after receipt of such notice to make the structure, or portion thereof, comply with the requirements of the code.

**Section 9. Appeals Process.** When there is an appeal of a staff interpretation of the code during plan review or inspection, the aggrieved persons shall be notified of the provisions of ORS 455.475 and the following procedures:

A. **Plan Review.** In an informal appeal of a plans examiner's decision, the plans examiner shall refer the request and any related information to the building official who, in consultation with appropriate technical staff, shall review the request and make a final determination in writing to the applicant within 15 days.

In an informal appeal of the building official's decision, the request shall be forwarded to the State of Oregon, Building Codes Division staff person responsible for interpretations. Formal appeals shall be forwarded to the appropriate state board at the Building Codes Division for final action. The appeal shall be sent to the Department of Consumer Business Services, Building Codes Division accompanied by the required fee, a completed appeal form of the department, and justification for the request along with any supporting information. (ORS 455.690)

B. **Inspection.** When there is an appeal of a field inspector's interpretation of a particular code, the following process shall be used:

1. The field inspector shall refer the customer and related information to the building official. The building official, in consultation with appropriate technical staff, shall review the request and make a final decision in writing to the customer within 15 days.

2. Formal appeals of the building official shall be forwarded to the appropriate state board for final action. The appeals shall be sent to the Department of Consumer Business Services, accompanied by the required fee, a completed appeal form of the department, and justification for the request along with any supporting information. (ORS 455.690)

3. In accordance with ORS 455.690, any person aggrieved by a final decision may, within 30 days after the date of the decision, appeal to the appropriate state advisory board as listed below:

- Structural Code - Building Codes Structures Board
- Mechanical Code - Mechanical Board
- Residential Code - Residential Structures Board
- Plumbing Code – Oregon State Plumbing Board
- Electrical Code – Electrical & Elevator Board
- **Manufactured Home Installation Standard - Manufactured Structures & Parks Board.**
- Park & Camp Rules - Manufactured Structures & Parks Board

C. Appeals of Board Decisions. Judicial review of the decision of advisory boards shall be available as provided in Oregon Revised Statutes Chapter 183.

**Section 10. Permits Not Transferable.** A permit issued to one person or firm is not transferable and shall not permit any other person or firm to perform any work thereunder.

**Section 11. Suspension/Revocation.** The building official may, in writing, suspend or revoke a permit issued under the provisions of the state building code whenever the permit is issued in error or on the bases of incorrect information supplied, or in violation of any ordinance or regulation or any of the provisions of the code.

**Section 12. Inspections.** It shall be the duty of the permit holder or his agent to request all necessary inspections in a timely manner, provide access to the site, and provide all necessary equipment as determined by the building official. The permit holder shall not proceed with the building construction until authorized by the building official. It shall be the duty of the permit holder to cause the work to remain accessible and exposed for inspection purposes. Any expense incurred by the permit holder to remove or replace any material required for proper inspection shall be the responsibility of the permit holder or his agent.

**Section 13. Fees.**

A. Fees for permits, inspections, plan checks, site plan review, copy costs, and such other fees that the City Council deems reasonable in order to administer this ordinance shall be set by ordinance or resolution.

B. The building official may authorize the refunding of fees paid in accordance with the refund policy in effect.

C. The determination of value or valuation under any provisions of the state building code shall be made by the building official. The value to be used in computing the building permit and plan review fees shall be the total value of all construction work for which the permit is issued as well as all finish work, painting, roofing, electrical, plumbing, heating, air conditioning, elevators, fire-extinguishing systems and any other permanent or attached equipment.

**Section 14. Savings Clause.** If any section, paragraph, subdivision, clause, sentence, or provisions of the ordinance shall be adjudged by any court of competent jurisdiction to be unconstitutional or invalid, such judgment shall not affect, impair, invalidate, or nullify the remainder of the ordinance.

**Section 15 Violations; Penalties; Remedies.**

A. No person shall erect, construct, enlarge, alter, repair, move, improve, remove, convert or demolish, equip, use, occupy or maintain a building or structure in the City, or cause the same to be done, contrary to or in violation of this Ordinance.

B. No person shall install, alter, replace, improve, convert, equip or maintain any mechanical equipment or system in the City, or cause the same to be done contrary to or in violation of this Ordinance.

C. No person shall install, alter, replace, improve, convert, equip or maintain any plumbing or drainage piping work or any fixture or water heating or treating equipment in the City, or cause the same to be done contrary to or in violation of this Ordinance.

D. No person shall install, alter, replace, improve, convert, equip or maintain any electrical equipment or system in the City, or cause the same to be done contrary to or in violation of this Ordinance.

E. Violation of a provision of this Ordinance shall be subject to a Civil Penalty not exceeding \$5,000.00 for a single violation of \$1,000.00 for continuing violations and shall be processed in accordance with the procedures set forth in this Ordinance.

F. Each day that a violation of a provision of this Ordinance exists constitutes a separate violation.

G. The penalties and remedies provided in this section are not exclusive and are in addition to all other penalties and remedies available to the City.

H. Notwithstanding the other remedies in this Ordinance, if the Building Official determines that any building under construction, mechanical work, electrical work, or plumbing work on any building or any structure poses an immediate threat to the public health, safety or welfare, the Building Official may order the work halted and the building or structure vacated pending further action by the City and its legal counsel. (Section 15 as amended by Ordinance 2461 and adopted December 15, 2009)

---

**Section 15A Building Official • Authority to Impose Administrative Civil Penalty.**

A. In addition to, and not in lieu of, any other enforcement mechanism authorized by this Ordinance, upon a determination by the Building Official that a person has violated a provision of this Ordinance, the Building Official may impose upon the violator and/or any other responsible person an administrative civil penalty as provided by this section. For purposes of this subsection, a responsible person includes the violator, and if the violator is not the owner of the building or property at which the violation occurs, may include the owner as well.

B. Prior to imposing an administrative civil penalty under this section, the Building Official shall pursue reasonable attempts to secure voluntary correction, failing which the Building Official may issue a notice of civil violation to one or more of the responsible persons to correct the violation. Except where the Building Official determines that the violation poses an immediate threat to health, safety, environment, or public welfare, the time for correction shall be not less than five calendar days.

C. Following the date or time by which the correction must be completed as required by an order to correct a violation, the Building Official shall determine whether such correction has been completed. If the required correction has not been completed by the date or time specified in the order, the Building Official may impose a civil penalty on each person to whom an order to correct was issued.

D. Notwithstanding subsection (B) above, the Building Official may impose a civil penalty without having issued an order to correct violation or made attempts to secure voluntary correction where the Building Official determines that the violation was knowing or intentional or a repeat of a similar violation.

E. In imposing a penalty authorized by this section, the Building Official shall consider:

1. The person's past history in taking all feasible steps or procedures necessary or appropriate to correct the violation;
2. Any prior violations of statutes, rules, orders, and permits;
3. The gravity and magnitude of the violation;
4. Whether the violation was repeated or continuous;
5. Whether the cause of the violation was an unavoidable accident, negligence, or an intentional act;
6. The violator's cooperativeness and efforts to correct the violation; and
7. Any relevant provision of the Building Code or City Ordinance.

F. The notice of civil penalty shall either be served by personal service or shall be sent by registered or certified mail and by first class mail. Any such notice served by mail shall be deemed received for purposes of any time computations hereunder three days

after the date mailed if to an address within this state, and seven days after the date mailed if to an address outside this state. A notice of civil penalty shall include:

1. Reference to the particular code provision or rule involved;
2. A short and plain statement of the matters asserted or charged;
3. A statement of the amount of the penalty or penalties imposed;
4. The date on which the order to correct was issued and time by which correction was to be made, or if the penalty is imposed pursuant to subsection (D), a short and plain statement of the basis for concluding that the violation was knowing, intentional, or repeated; and
5. A statement of the party's right to appeal the civil penalty to the City Administrator or City Administrator's designee.

G. Any person who is issued a notice of civil penalty may appeal the penalty to the City Administrator or City Administrator's designee. The City Administrator's designee shall not be the Building Official or Building Inspector.

H. A civil penalty imposed hereunder shall become final upon expiration of the time for filing an appeal, unless the responsible person appeals the penalty to the City Administrator or City Administrator's designee pursuant to, and within the time limits established by this Ordinance. If the responsible person appeals the civil penalty to the City Administrator or City Administrator's designee, the penalty shall become final, if at all; upon issuance of the City Administrator or City Administrator's designee's decision affirming the imposition of the administrative civil penalty.

I. Each day the violator fails to remedy the violation shall constitute a separate violation.

J. Failure to pay a penalty imposed hereunder within ten days after the penalty becomes final as provided in subsection (H) shall constitute a violation of this Ordinance. Each day the penalty is not paid shall constitute a separate violation. The Building Official also is authorized to collect the penalty by any administrative or judicial action. The civil administrative penalty authorized by this section shall be in addition to:

1. Assessments or fees for any costs incurred by the City in remediation, cleanup, or abatement, and
2. Any other actions authorized by law.



K. If an administrative civil penalty is imposed on a responsible person because of a violation of any provision of this Ordinance resulting from prohibited use or activity on real property, and the penalty remains unpaid 30 days after such penalty become final, the Building Official shall assess the property the full amount of the unpaid fine and

shall enter such an assessment as a lien in the docket of City liens. At the time such an assessment is made, the Building Official shall notify the responsible person that the

penalty has been assessed against the real property upon which the violation occurred and has been entered in the docket of City liens.

L. In addition to enforcement mechanisms authorized elsewhere in this Ordinance, failure to pay an administrative civil penalty imposed pursuant to subsection (A) of this section shall be grounds for withholding issuance of requested permits or licenses, or revocation or suspension of any issued permits or certificates of occupancy.

M. This Ordinance does not prohibit the City from charging an increased permit fee or investigation fee, seeking injunctive relief from a violation or taking any enforcement action that does not include a monetary penalty. (Section 15A as amended by Ordinance 2461 and adopted December 15, 2009)

### **Section 15B Appeal Procedures.**

A. A person aggrieved by an administrative action of the Building Official taken pursuant to a section of this Ordinance authorizing an appeal under this section may, within 15 days after the date of notice of the action, appeal in writing to the City Administrator or City Administrator's designee. The appeal shall state:

1. The name and address of the appellant;
2. The nature of the determination being appealed;
3. The reason the determination is incorrect; and
4. What the correct determination of the appeal should be.

An appellant who fails to file such a statement within the time permitted waives the objections, and the appeal shall be dismissed.

B. If a notice of revocation of a license or permit is the subject of the appeal, the revocation does not take effect until final determination of the appeal. Notwithstanding this paragraph, an emergency suspension shall take effect upon issuance of, or such other time stated in, the notice of suspension.

C. Unless the appellant and the City agree to a longer period, an appeal shall be heard by the City Administrator or City Administrator's designee within 30

days of the receipt of the notice of intent to appeal. At least 10 days prior to the hearing, the City shall mail notice of the time and location thereof to the appellant.

D. The City Administrator or City Administrator's designee shall hear and determine the appeal on the basis of the appellant's written statement and any additional evidence the City Administrator or City Administrator's designee deems

appropriate. At the hearing, the appellant may present testimony and oral argument personally or by counsel.

E. The City Administrator or City Administrator's designee shall issue a written decision within 10 days of the hearing date. The decision of the City Administrator or City Administrator's designee after the hearing is final. (Section 15B as amended by Ordinance 2461 and adopted December 15, 2009)

**Section 16.** Repeal. Ordinance No. 2293 is hereby repealed.

**Section 17.** [Emergency clause.]

**Passed by the Council December 11, 2006, and approved by the Mayor December 13, 2006.**

## ORDINANCE NO. 2445

## AN ORDINANCE REQUIRING HABITABLE RENTAL HOUSING AND PROVIDING FOR ADMINISTRATION AND ENFORCEMENT.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Title.** This Ordinance shall be known as the "Habitable Rental Housing Ordinance."

**Section 2. Legislative Findings.**

A. The City Council finds that a safe, decent place to live is a basic necessity that enables families to meet other basic necessities and save for their future.

B. The City Council further finds there are a growing number of residential rental properties within the City, and that many of these properties are in a declining state of maintenance.

C. The City Council further finds that inadequate maintenance directly affects the health, life, safety and welfare of the residents of the City of Woodburn and impacts the health and vitality of the surrounding neighborhood and the City as a whole.

D. The City Council further finds that it is necessary to adopt this Ordinance so that Rental Housing in the City is maintained in a good, safe, and sanitary condition and does not create a nuisance or blighted conditions to its surroundings.

E. The City Council further finds that the adoption of this Ordinance is a reasonable method of insuring suitable housing, safe and viable neighborhoods and a healthy City.

**Section 3. Purpose.** The purpose of this Ordinance is to provide minimum habitability criteria to safeguard health, property and public welfare of the Owners, occupants and users of residential rental buildings.

**Section 4. State of Oregon Residential Landlord and Tenant Act.** This Ordinance is intended to supplement and not conflict with the habitability standards of the Oregon Residential Landlord and Tenant Act.

**Section 5. Scope.**

A. Except as described below, these standards shall apply to Rental Housing located within the City.

B. Notwithstanding subsection 5A and consistent with the Oregon Residential Landlord and Tenant Act, the following are exempted from the application of this Ordinance:

1. Hotels, motels and lodging houses;
2. Hospitals and other medical facilities;
3. Nursing care facilities as defined in the Woodburn Development Ordinance; and
4. Group homes and group care facilities as defined in ORS Chapter 443.

**Section 6. Complaints.** Complaints under this Ordinance will be initiated on a form provided by the City containing the following information:

- A. The name of the Person filing the complaint.
- B. The name of the Landlord.
- C. The address of the alleged violation.
- D. A description of the alleged violation.
- E. Where the Tenant is the Complainant, a certification that reasonable efforts were made to provide the Landlord with notice of the alleged violation.

**Section 7. Definitions.** For purposes of this Ordinance, the following definitions shall apply:

**Dwelling Unit.** A single unit providing complete independent living facilities for one or more Persons including provisions for living, sleeping, eating, cooking, and sanitation. For purposes of this Ordinance, where portions of a residential building are occupied under separate Rental Agreements, but tenants share eating, cooking, and/or sanitation facilities, each portion under a separate Rental Agreement shall be considered a Dwelling Unit.

**Enforcement Officer.** A police officer, code enforcement officer or other city official authorized by the City Administrator to enforce this Ordinance.

**Landlord.** The Owner, lessor, or sublessor of a Dwelling Unit or a party acting as an authorized agent of the Owner, lessor or sublessor.

**Owner** includes a mortgagee in possession and means one or more Persons, jointly or severally, in whom is vested: (a) all or part of the legal title to property; or (b) all or part of the beneficial ownership and a right to present use and enjoyment of the premises.

**Person.** Any natural Person, firm, partnership, association or corporation.

**Rental Agreement.** All agreements, written or oral, concerning the use and occupancy of a Dwelling Unit and premises.

**Rental Housing.** A Dwelling Unit which is the subject of a Rental Agreement.

**Section 8. Maintenance of Dwelling Unit in Habitable Condition.**

A. A Landlord shall at all times during the tenancy maintain the Dwelling Unit in a habitable condition. For purposes of this section, a Dwelling Unit shall be considered uninhabitable if it substantially lacks:

1. Effective waterproofing and weather protection of roof and exterior walls, including windows and doors;
2. Plumbing facilities which conform to applicable law in effect at the time of installation, and maintained in good working order;
3. A water supply approved under applicable law, which is:
  - a. Under the control of the Tenant or Landlord and is capable of producing hot and cold running water;
  - b. Furnished to appropriate fixtures;
  - c. Connected to a sewage disposal system approved under applicable law; and
  - d. Maintained so as to provide safe drinking water and to be in good working order to the extent that the system can be controlled by the Landlord;
4. Adequate heating facilities which conform to applicable law at the time of installation and maintained in good working order;
5. Electrical lighting with wiring and electrical equipment which conform to applicable law at the time of installation and maintained in good working order;
6. Buildings, grounds and appurtenances at the time of the commencement of the Rental Agreement in every part safe for normal and reasonably foreseeable uses, clean, sanitary and free from all accumulations of debris, filth, rubbish, garbage, rodents and vermin, and all areas under control of the Landlord kept in every part safe for normal and reasonably foreseeable uses, clean, sanitary and free from all accumulations of debris, filth, rubbish, garbage, rodents and vermin;
7. Except as otherwise provided by local ordinance or by written agreement between the Landlord and the Tenant, an adequate number of appropriate receptacles for garbage and rubbish in clean condition and good repair at the time of the commencement of the Rental Agreement, and the Landlord shall provide and maintain appropriate serviceable receptacles thereafter and arrange for their removal;

8. Floors, walls, ceilings, stairways and railings maintained in good repair;

9. Ventilating, air conditioning and other facilities and appliances, including elevators, maintained in good repair if supplied or required to be supplied by the Landlord;

10. Safety from fire hazards, including a working smoke alarm or smoke detector, with working batteries if solely battery-operated, provided only at the beginning of any new tenancy when the Tenant first takes possession of the premises, as provided in ORS 479.270, but not to include the Tenant's testing of the smoke alarm or smoke detector as provided in ORS 90.325 (6); or

11. Working locks for all dwelling entrance doors, and, unless contrary to applicable law, latches for all windows, by which access may be had to that portion of the premises which the Tenant is entitled under the Rental Agreement to occupy to the exclusion of others and keys for such locks which require keys.

**Section 9. Abatement Notice.** Whenever a violation of this Ordinance is found to exist within the corporate limits of the city and the Enforcement Officer elects to proceed by abatement, the Enforcement Officer shall give written notice, by a type of mail that requires a signed receipt, to the Landlord of the property upon which the violation exists.

**Section 10. Abatement.** Upon receipt of the notice that a violation exists, the Landlord shall have thirty (30) days to abate the violation.

**Section 11. Notice Requirements.** The notice to abate the violation shall contain the following:

- A. An order to abate the violation within thirty (30) days;
- B. The location of the violation;
- C. A description of what constitutes the violation;
- D. A statement that if the violation is not abated within the prescribed time, the City will seek civil penalties under this Ordinance; and
- E. A statement that a Person who is dissatisfied with the abatement notice has the right to judicial review under this Ordinance.

**Section 12. Request for Judicial Review.** The Landlord may file a written request for judicial review in the Woodburn Municipal Court within ten (10) days of the date that the notice to abate was mailed.

**Section 13. Requirements for Request.** The request for judicial review need not be in any particular form, but should substantially comply with the following requirements:

- A. Be in writing;
- B. Identify the place and nature of the alleged violation;
- C. Specify the name and address of the Landlord seeking judicial review;  
and
- D. Identify the Enforcement Officer alleging that a violation exists.

A copy of the request for judicial review shall be served on the Woodburn City Attorney's office.

**Section 14. Scheduling of Judicial Review.**

A. The judicial review hearing shall be held within ten (10) days after the request for judicial review is made. The day may be postponed by:

- 1. Agreement of the parties; or
- 2. Order of the court for good cause.

B. After a hearing is scheduled, the court shall promptly notify the parties as to the time and location of the hearing.

**Section 15. Judicial Review Hearing.** At the judicial review hearing the City and the Landlord shall have the right to present evidence and witnesses and to be represented by legal counsel at their own expense. After due consideration of pertinent information and testimony, the court shall make its findings. The findings shall be based on substantial evidence and shall be final.

**Section 16. Notification of Violation.** The Landlord shall be notified by a type of mail that requires a signed receipt postmarked no later than five days after the findings are entered by the court or by personal delivery by a representative of the City. Upon notification of violation, the Landlord shall have 30 days to abate the violation.

**Section 17. Enforcement.**

A. Inspection and Right of Entry. Whenever the Enforcement Officer has reasonable cause to suspect a violation of any provision of this Ordinance, the Enforcement Officer may enter on any site or into any structure for the purposes of investigation provided that no premises shall be entered without first attempting to obtain the consent of the Owner or person in control of the premises if other than the Owner. If consent cannot be obtained, the Enforcement Officer shall secure a search warrant before further attempts to gain entry, and shall have recourse to every other remedy provided by law to secure entry.

B. Civil Infraction. In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of this Ordinance constitutes a Class I Civil

Infraction which shall be processed according to the procedures contained in the Woodburn Civil Infraction Ordinance.

C. Civil Proceeding Initiated by City Attorney. The City Attorney, after obtaining authorization from the City Council, may initiate a civil proceeding on behalf of the city to enforce the provisions of this Ordinance. This civil proceeding may include, but is not limited to, injunction, mandamus, abatement, or other appropriate proceedings to prevent, temporarily or permanently enjoin or abate any violations of this Ordinance.

**Section 18. Prohibition on Retaliatory Conduct by Landlord.** No Landlord may terminate a tenancy, increase rent, decrease services or refuse to renew a lease or tenancy because a Tenant has in good faith:

- A. Filed a complaint under this Ordinance; or
- B. Requested the Landlord to make repairs to a premises as required by this Ordinance; or
- C. Provided information or testified in any proceeding involving the enforcement of this Ordinance.

**Section 19. Separate Offenses.** Each day during which a violation of this Ordinance continues shall constitute a separate offense for which a separate penalty may be imposed.

**Section 20. Severability.** If any section, paragraph, subdivision, clause, sentence, or provisions of this Ordinance shall be adjudged by any court of competent jurisdiction to be unconstitutional or invalid, such judgment shall not affect, impair, invalidate, or nullify the remainder of the title, but the effect thereof shall be confined to the section, paragraph, subdivision, clause, sentence or provision immediately involved in the controversy in which such judgment or decree shall be rendered, it being the intent of the governing body to enact the remainder of this Ordinance notwithstanding the parts to be declared unconstitutional and invalid.

**Passed by the Council September 8, 2008 and approved by the Mayor September 10, 1008.**



## ORDINANCE NO. 1101

**AN ORDINANCE GRANTING A REVOCABLE PERMIT TO PACIFIC NORTHWEST BELL TELEPHONE COMPANY TO INSTALL, MAINTAIN, AND OPERATE PUBLIC TELEPHONE BOOTHS AT VARIOUS LOCATIONS ON CITY PROPERTY AND CITY STREETS.**

**THE PEOPLE OF THE CITY OF WOODBURN DO ORDAIN:**

**Section 1.** A revocable permit is hereby granted to the Pacific Northwest Bell Telephone Company, its successors and assigns, to install, maintain, and operate public telephone booths at various locations on city property and city streets in the city of Woodburn on the following terms:

(A) **Location of booths.** Sites for the location or relocation of telephone booths shall be selected by the permittee, subject to the approval of the common council of the city of Woodburn.

(B) **Installation and maintenance.** The permittee shall bear the entire cost of installation, maintenance, relocation, and removal of every telephone booth installed under this permit.

(C) **Commissions.** The permittee shall pay to the City of Woodburn a commission equal to 15 per cent of the net contents of the coin box of each public telephone installed hereunder, after deduction for applicable excise taxes. After this permit becomes effective, such commissions shall be paid to the city semiannually.

(D) **Electricity.** With approval of the common council of the city of Woodburn and Portland General Electric Company, its successors and assigns, the permittee, where feasible, may interconnect with electric service furnished to the city.

(E) **Removal of booth.** Upon 30 days' notice, the city, for cause, may require the permittee to remove or relocate any telephone booth installed hereunder. The permittee on its own initiative may remove any telephone booth any time, but shall restore the surface to good condition and safe for public use, considering the nature and location of the property.

(F) **Termination of permit.** This permit may be revoked by the council, or operations hereunder may be discontinued voluntarily by the permittee, only after 30 days' notice. In event of such termination, the permittee shall remove all installations hereunder within 90 days and in compliance with provisions of subsection (E) hereof.

**Section 2.** The permit granted by this ordinance is subject to the condition that permittee, its successors and assign, forever will indemnify and save the city of Woodburn, its officers, agents, and employees harmless from and against any and all liability, loss, cost, damage, and expense, and any and all claims for injury or death to persons and damage to property, directly or indirectly arising from the installation, maintenance, or operation of telephone booths under this permit. The city shall

promptly notify the permittee upon receipt of any claim or demand against which it is, or may be, held harmless by the permittee under this indemnification. As evidenced by its written acceptance of the terms and conditions and agrees that the within permit is granted only upon, and constitutes consideration for, this indemnification.

**Section 3.** This ordinance is not operative until permittee has filed with the city recorder a written acceptance of all terms and conditions contained herein, signed by an authorized official of said corporation, and approved as to form by the city attorney.

*Passed by the Council and approved by the Mayor July 21, 1964.*

**ORDINANCE NO. 1885****AN ORDINANCE ESTABLISHING A CABLE TELEVISION RATE SCHEDULE PURSUANT TO ORDINANCES NO. 1766 AND 1784, AND DECLARING AN EMERGENCY.**

[Whereas clause.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** That after the conclusion of a public hearing, having duly considered the information and testimony presented, the Woodburn City Council hereby adopts the rate proposed by the franchisee, Northland Communications Corporation, Inc., as set out in its petition dated June 4, 1984, which is attached hereto as Exhibit "A" and by this reference incorporated herein.\*

**Section 2.** That pursuant to the applicable ordinances this rate change is effective 90 days from the date of said petition.

**Section 3.** [Amends Section 15 of Ord. No. 1784, Comp. 11-12.]

**Section 4.** [Emergency clause.]

***Passed by the Council and approved by the Mayor August 17, 1984.***

---

\* Exhibit "A" is on file with the original ordinance and is available for inspection at City Hall.

## ORDINANCE NO. 2028

AN ORDINANCE IMPOSING A MOTOR VEHICLE FUEL TAX ON MOTOR VEHICLE FUEL DEALERS, PROVIDING FOR ADMINISTRATION, ENFORCEMENT AND COLLECTION OF THE TAX, AND IMMEDIATELY REFERRING SAID ORDINANCE TO THE ELECTORS OF THE CITY OF WOODBURN.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Title:** This ordinance shall be known as the "City of Woodburn Motor Vehicle Fuel Tax Ordinance.

**Section 2. Definitions.** As used in this ordinance, unless the context requires otherwise:

(A) "Aircraft Fuel" means any gasoline and other inflammable or combustible gas or liquid by whatever name such as gasoline, gas or liquid is known or sold, usable as fuel for the operation of aircraft, except gas or liquid, the chief use of which, as determined by the City is for purposed other than the propulsion of aircraft.

(B) "Authorized Agent" any person or agency that has been given authority to implement a portion of this ordinance.

(C) "City" means City of Woodburn, a municipal corporation of the State of Oregon.

(D) "Dealer" means any person who:

(1) Supplies or imports motor vehicle fuel for sale, use or distribution in, and after the same reaches the City, but "dealer" does not include any person who imports into the City motor vehicle fuel in quantities of 500 gallons or less purchased from a supplier who is permitted as a dealer hereunder and who assumes liability for the payment of the applicable motor vehicle fuel tax to the City; or

(2) Produces, refines, manufactures or compounds motor vehicle fuels in the City for use, distribution or sale in the City; or

(3) Acquires in the City for sale, use or distribution in the City motor vehicle fuels with respect to which there has been no motor vehicle fuel tax previously incurred.

(E) "Motor Vehicle Fuel-Handler" means any person who acquires or handles motor vehicle fuel within the City through a storage tank facility with storage tank capacity that exceeds 500 gallons of motor vehicle fuel.

(F) "Distributor" means, in addition to its ordinary meaning, the deliverer of motor vehicle fuel by a dealer to any service station or into any tank, storage facility or series of tanks or storage facilities connected by pipelines, from which motor vehicle fuel is withdrawn directly for sale or for delivery into the fuel tanks or motor vehicles whether or not the service station, tank or storage facility is owned, operated or controlled by the dealer.

(G) "Highway" means every way, thoroughfare and place of whatever nature, open for use of the public for the purpose of vehicular travel.

(H) "Motor Vehicle" means all vehicles, engines or machines, moveable or immovable, operated or propelled by the use of motor vehicle fuel.

(I) "Motor Vehicle Fuel" means and includes gasoline, diesel, mogas, methanol, and any other flammable or combustible gas or liquid, by whatever name such gasoline, diesel, mogas, methanol, gas or liquid is known or sold, usable as fuel for the operation of motor vehicles, except gas, diesel, mogas, methanol, or liquid, the chief use of which, as determined by the City, is for purposes other than the propulsion of motor vehicles upon the highways. Propane fuel and motor vehicle fuel used exclusively as a structural heating source are excluded as a taxable motor vehicle fuel.

(J) "Person" includes every natural person, association, firm, partnership, or corporation.

(K) "Service Station" means and includes any place operated for the purpose of retailing and delivering motor vehicle fuel into the fuel tanks of motor vehicles.

(L) "State" means State of Oregon.

**Section 3. Tax Imposed.** A motor vehicle fuel tax is hereby imposed on every dealer operating within the corporate limits of Woodburn. The City of Woodburn motor vehicle fuel tax imposed shall be paid monthly to the City or to its authorized agent.

(A) A person who is not a permitted dealer or permitted motor vehicle fuel-handler shall not accept or receive motor vehicle fuel in this City from a person who supplies or imports motor vehicle fuel who does not hold a valid motor vehicle fuel dealers permit in this City. If a person is not a permitted dealer or permitted motor vehicle fuel-handler in this City and accepts or receives motor vehicle fuel, the purchaser or receiver shall be responsible for all taxes, interests and penalties prescribed herein.

(B) A permitted dealer or fuel-handler who accepts or receives motor vehicle fuel from a person who does not hold a valid dealer or fuel-handler permit in this City, shall pay the tax imposed by this Ordinance to the City or its authorized agent, upon the sale, use or distribution of the motor vehicle fuel.

**Section 4. Amount and Payment.**

(A) Subject to subsections (B) and (C) of this section, by law, every dealer engaging in his own name, or in the name of others, or in the name of his representatives or agents in the City, in the sale, use or distribution of motor vehicle fuel, shall:

(1) Not later than the 25th day of each calendar month, render a statement to the City or to its authorized agent, of all motor vehicle fuel sold, used or distributed by him in the City as well as all such fuel sold, used or distributed in the City by a purchaser thereof upon which sale, use or distribution the dealer has assumed liability for the applicable motor vehicle fuel tax during the preceding calendar month.

(2) Pay a motor vehicle fuel tax computed on the basis of one (1.0) cent per gallon of such motor vehicle fuel so sold, used or distributed as shown by such statement in the manner and within the time provided in this ordinance.

(B) In lieu of claiming refund of the tax as provided in Section 20, or of any prior erroneous payment of motor vehicle fuel tax made to the City by the dealer, the dealer may show such motor vehicle fuel as a credit or deduction on the monthly statement and payment of tax.

(C) The motor vehicle fuel tax shall not be imposed wherever it is prohibited by the Constitution or laws of the United States or of the State of Oregon.

**Section 5. Permit Requirements.** No dealer or fuel handler, shall sell, use or distribute any motor vehicle fuel until he has secured a dealer or fuel-handler permit as required herein.

**Section 6. Permit Applications and Issuance.**

(A) Every person, before becoming a dealer or fuel handler in motor vehicle fuel in this City shall make an application to the City or its duly authorized agent, for a permit authorizing such person to engage in business as a dealer or fuel-handler.

(B) Applications for the permit must be made on forms prescribed, prepared and furnished by the City or its duly authorized agent.

(C) The applications shall be accompanied by a duly acknowledged certificate containing:

(1) The business name under which the dealer or fuel-handler is transacting business.

(2) The place of business and location of distributing stations in the City and in areas adjacent to the City limits in the State of Oregon.

(3) The name and address of the managing agent, the names and addresses of the several persons constituting the firm or partnership and, if a corporation, the corporate name under which it is authorized to transact business and the names and addresses of its principal officers and registered agent, as well as primary transport carrier.

(D) The application for a motor vehicle fuel dealer or fuel-handler permit having been accepted for filing, the City or its authorized agent, shall issue to the dealer or fuel-handler a permit in such form as the City or its duly authorized agent may prescribe to transact business in the City. The permit so issued is not assignable, and is valid only for the dealer or fuel handler in whose name issued.

(E) The City Recorder's Office shall keep on file a copy of all applications and/or permits.

(F) No fee(s) shall be charged by the City for securing said permit as described herein.

**Section 7. Failure to Secure Permit.**

(A) If any dealer sells, distributes or uses any motor vehicle fuel without first filing the certificate and securing the permit required by Section 6, the motor vehicle fuel tax shall immediately be due and payable on account of all motor vehicle fuel so sold, distributed or used.

(B) The City shall proceed forthwith to determine, from the best available sources, the amount of such tax, and it shall assess the tax in the amount found due, together with a penalty of 200 percent of the tax, and shall make its certificate of such assessment and penalty, determined by City Administrator or the City's duly authorized agent. In any suit or proceeding to collect such tax or penalty or both, the certificate is prima facie evidence that the dealer therein named is indebted to the City in the amount of the tax and penalty therein stated.

(C) Any fuel-handler who sells, handles, stores, distributes, or uses any motor vehicle fuel without first filing the certificate and securing the permit required by Section 6, shall be assessed a penalty of \$250.00 unless modified by Section 27, Subsection "a", determined by the City Administrator or the City's duly authorized agent. In any suit or proceeding to collect such penalty, the certificate is prima facie evidence that the fuel-handler therein named is indebted to the City in the amount of the penalty therein stated.

(D) Any tax or penalty so assessed may be collected in the manner prescribed in Section 11 with reference to delinquency in payment of the tax or by Court action.

**Section 8. Revocation of Permit.** The City or its authorized agent shall revoke the permit of any dealer or fuel-handler refusing or neglecting to comply with any provision of this Ordinance. The City or its authorized agent shall mail by certified mail addressed to such dealer or fuel-handler at his last known address appearing on the files, a notice of intention to cancel. The notice shall give the reason for the cancellation. The cancellation shall become effective without further notice if within 10 days from the mailing of the notice the dealer or fuel-handler has not made good its default or delinquency.

**Section 9. Cancellation of Permit.**

(A) The City or its authorized agent may, upon written request of a dealer or fuel-handler cancel any permit issued to such dealer or fuel-handler, the cancellation to become effective 30 days from the date of receipt of the written request.

(B) If the City or its authorized agent ascertains and finds that the person to whom a permit has been issued is no longer engaged in the business of a dealer or fuel-handler, the City or its authorized agent may cancel the permit of such dealer or fuel-handler upon investigation after 30 days' notice has been mailed to the last known address of the dealer or fuel handler.

**Section 10. Remedies Cumulative.** Except as otherwise provided in Sections 11 and 13, the remedies provided in Sections 7, 8, and 9 are cumulative. No action taken pursuant to those sections shall relieve any person from the penalty provisions of this Ordinance.

**Section 11. Payment of Tax and Delinquency.**

(A) The motor vehicle fuel tax imposed by Sections 3 and 4 shall be paid on or before the 25th day of each month to the City or its authorized agent which, upon request, shall receipt the dealer or fuel-handler therefor.

(B) Except as provided in subsection (D) of this Section, to any motor vehicle fuel tax not paid as required by subsection (A) of this Section, there shall be added a penalty of one percent (1.0%) of such motor vehicle fuel tax.

(C) Except as provided in subsection (D) of this Section, if the tax and penalty required by subsection (B) of this section are not received on or before the close of business on the last day of the month in which the payment is due, a further penalty of ten percent (10.0%) shall be paid in addition to the penalty provided for in subsection (B) of this Section.

(D) If the City or its authorized agent, determines that the delinquency was due to reasonable cause and without any intent to avoid payment, the penalties provided by subsections (B) and (C) of this Section may be waived. Penalties imposed by this Section shall not apply when the penalty provided in Section 7 has been assessed and paid.



(E) If any person fails to pay the motor vehicle fuel tax or any penalty provided for by this Ordinance, the amount thereof shall be collected from such person for the use of the City. The City shall commence and prosecute to final determination in any court of competent jurisdiction an action to collect the same.

(F) In the event any suit or action is instituted to collect the motor vehicle fuel tax or any penalty provided for by this ordinance, the City shall be entitled to recover from the person sued reasonable attorney's fees at trial or upon appeal of such suit or action, in addition to all other sums provided by law.

(G) No dealer who collects from any person the tax provided for herein, shall knowingly and willfully fail to report and pay the same to the City or its authorized agent, as required herein.

**Section 12. Monthly Statement of Dealer and Fuel-Handler.** Unless modified by Section 27 Subsection "b" every dealer and fuel-handler in motor vehicle fuel shall render to the City or its authorized agent, on or before the 25th day of each month, on forms prescribed, prepared and furnished by the City or its authorized agent, a signed statement of the number of gallons of motor vehicle fuel sold, distributed, used or stored by him during the preceding calendar month. The statement shall be signed by the permit holder. All statements as required in this section are public records.

**Section 13. Failure to File Monthly Statement.** If any dealer or fuel-handler fails to file the report required by Section 12, the City or its authorized agent, shall proceed forthwith to determine from the best available sources the amount of motor vehicle fuel sold, distributed, used or stored by such dealer or fuel-handler for the period unreported, and such determination shall be prima facie evidence of the amount of such fuel sold, distributed, used or stored. The City or its authorized agent, immediately shall assess the motor vehicle fuel tax in the amount so determined, as pertaining to the reportable dealer, adding thereto a penalty of 10 percent for failure to report. Fuel-handlers failing to file a monthly statement of motor vehicle fuel shall be assessed a penalty of \$50.00. The penalty shall be cumulative to other penalties provided in this Ordinance. In any suit brought to enforce the rights of the City under this section, the above determination showing the amount of tax, penalties and costs unpaid by any dealer or fuel-handler and that the same are due and unpaid to the City or its authorized agent is prima facie evidence of the facts as shown.

**Section 14. Billing Purchasers.** Bills shall be rendered to all purchasers of motor vehicle fuel by dealers in motor vehicle fuel. The bills shall separately state and describe to the satisfaction of the City or its authorized agent the different products shipped thereunder and shall be serially numbered except where other sales invoice controls acceptable to the City or its authorized agent are maintained. The bills required hereunder may be the same as those required under ORS 319.210.

**Section 15. Failure to Provide Invoice or Delivery Tag.** No person shall receive and accept any shipment of motor vehicle fuel from any dealer, or pay for the same, or sell or offer the shipment for sale, unless the shipment is accompanied by an invoice or delivery tag showing the date upon which shipment was delivered and the name of the dealer in motor vehicle fuel.

**Section 16. Transporting Motor Vehicle Fuel in Bulk.** Every person operating any conveyance for the purpose of hauling, transporting or delivering motor vehicle fuel in bulk shall, before entering upon the public highways of the City with such conveyance, have and possess during the entire time of his hauling or transporting such motor vehicle fuel an invoice, bill of sale or other written statement showing the number of gallons, the true name and address of the seller or consignor, and the true name and address of the buyer or consignee, if any, of the same. The person hauling such motor vehicle fuel shall at the request of any officer authorized by the City to inquire into or investigate such matters, produce and offer for inspection the invoice, bill of sale or other statement.

**Section 17. Exemption of Export Fuel.**

(A) The license tax imposed by Sections 3 and 4 shall not be imposed on motor vehicle fuel:

(1) Exported from the City by a dealer; or

(2) Sold by a dealer in individual quantities of 500 gallons or less for export by the purchaser to an area or areas outside the City in containers other than the fuel tank of a motor vehicle, but every dealer shall be required to report such exports and sales to the City or its authorized agent in such detail as may be required.

(B) In support of any exemption from motor vehicle fuel taxes claimed under this section other than in the case of stock transfers or deliveries in his own equipment, every dealer must execute and file with the City or its authorized agent an export certificate in such form as shall be prescribed, prepared and furnished by the City or its authorized agent, containing a statement, made by some person having actual knowledge of the fact of such exportation, that the motor vehicle fuel has been exported from the City, and giving such details with reference to such shipment as may be required. The City or its authorized agent may demand of any dealer such additional data as is deemed necessary in support of any such certificate, and failure to supply such data will constitute a waiver of all right to exemption claimed by virtue of such certificate. The City or its authorized agent may, in a case where it believes no useful purpose would be served by filing of an export certificate, waive the certificate.

(C) Any motor vehicle fuel carried from the City in the fuel tank of a motor vehicle shall not be considered as exported from the City.

(D) No person shall, through false statement, trick or device, or otherwise, obtain motor vehicle fuel for export as to which the City motor vehicle fuel tax has not been paid and fail to export the same, or any portion thereof, or cause the motor vehicle fuel or any portion thereof not to be exported, or divert or cause to be diverted the motor vehicle fuel or any portion thereof to be used, distributed or sold in the City and fail to notify the City or its authorized agent and the dealer from whom the motor vehicle fuel was originally purchased of his act.

(E) No dealer or other person shall conspire with any person to withhold from export, or divert from export or to return motor vehicle fuel to the City for sale or use so as to avoid any of the fees imposed herein.

(F) In support of any exemption from taxes on account of sales of motor vehicle fuel in individual quantities of 500 gallons or less for export by the purchaser, the dealer shall retain in his files for at least three years an export certificate executed by the purchaser in such form and containing such information as is prescribed by the City or its authorized agent. This certificate shall be prima facie evidence of the exportation of the motor vehicle fuel to which it applies only if accepted by the dealer in good faith.

**Section 18. Sales to Armed Forces Exempted.** The motor vehicle fuel tax imposed by Sections 3 and 4 shall not be imposed on any motor vehicle fuel sold to the Armed Forces of the United States for use in ships, aircraft or for export from the City; but every dealer shall be required to report such sales to the City or its authorized agent, in such detail as may be required. A certificate by an authorized officer of such Armed Forces shall be accepted by the dealer as sufficient proof that the sale is for the purpose specified in the certificate.

**Section 19. Fuel in Vehicles Coming Into City Not Taxed.** Any person coming into the City in a motor vehicle may transport in the fuel tank of such vehicle motor vehicle fuel for his own use only and for the purpose of operating such motor vehicle without securing a license or paying the tax provided in Sections 3 and 4, or complying with any of the provisions imposed upon dealers herein, but if the motor vehicle fuel so brought into the City is removed from the fuel tank of the vehicle or used for any purpose other than the propulsion of the vehicle, the person so importing the fuel into the City shall be subject to all provisions herein applying to dealers.

**Section 20. Refunds.** Refunds will be made pursuant to ORS. 319.280 to 319.320.

**Section 21. Examination and Investigations.** The City, or its duly authorized agent, may make any examination of accounts, records, stocks, facilities and equipment of dealers, fuel-handlers, service stations and other persons engaged in storing, selling or distributing motor vehicle fuel or other petroleum products within this City, and such other investigations as it considers necessary in carrying out the provisions of this ordinance. If the examinations or investigations disclose that any reports of dealers or other persons theretofore filed with the City or its authorized agent pursuant to the requirements herein, have shown incorrectly the amount of gallons of motor vehicle fuel distributed or the tax accruing thereon, the City or its authorized

agent may make such changes in subsequent reports and payments of such dealers or other persons, or may make such refunds, as may be necessary to correct the errors by its examinations or investigations.

**Section 22. Limitation on Credit for or Refund of Overpayment and on Assessment of Additional Tax.**

(A) Except as otherwise provided in this ordinance, any credit for erroneous overpayment of tax made by a dealer taken on a subsequent return or any claim for refund of tax erroneously overpaid filed by a dealer must be so taken or filed within three years after the date on which the overpayment was made to the City or to its authorized agent.

(B) Except in the case of a fraudulent report or neglect to make a report, every notice of additional tax proposed to be assessed under this ordinance shall be served on dealers within three years from the date upon which such additional taxes become due.

**Section 23. Examining Books and Accounts of Carrier Motor Vehicle Fuel.** The City or its duly authorized agent may at any time during normal business hours examine the books and accounts of any carrier of motor vehicle fuel operating within the City for the purpose of checking shipments or use of motor vehicle fuel, detecting diversions thereof or evasion of taxes in enforcing the provisions of this ordinance.

**Section 24. Records to be Kept by Dealers and Fuel Handler.** Every dealer and fuel-handler in motor vehicle fuel shall keep a record in such form as may be prescribed by the City or its authorized agent of all purchases, receipts, sales and distribution of motor vehicle fuel. The records shall include copies of all invoices or bills of all such sales and purchases, and shall at all times during the business hours of the day be subject to inspection by the City or its authorized officers or agents.

**Section 25. Records to be Kept Three Years.** Every dealer and fuel-handler shall maintain and keep, for a period of three years, all records of motor vehicle fuel used, sold and distributed within the City by such dealer or fuel handler, together with stock records, invoices, bills of lading and other pertinent papers as may be required by the City or its authorized agent. In the event such records are not kept within the State of Oregon, the dealer shall reimburse the City or its duly authorized agents for all travel, lodging, and related expenses incurred in examining such records. The amount of such expenses shall be an additional tax imposed hereunder.

**Section 26. Use of Tax Revenues.**

(A) The City Administrator shall be responsible for the disposition of the revenue from the tax imposed by this ordinance in the manner provided by this section.

(B) For the purposes of this section, net revenue shall mean the revenue from the tax imposed by this ordinance remaining after providing for the cost of administering the motor vehicle fuel tax to motor vehicle fuel dealers and any refunds and credits authorized herein. The program administration costs of revenue collection and accounting activities shall not exceed 10.5% for the first year, and 10% thereafter, of annual tax revenues.

(C) The net revenue shall be used only for the activities related to the construction, reconstruction, improvement, repair, maintenance of public highways, roads and streets within the City of Woodburn.

**Section 27. Administration.** The City Administrator or his designate is responsible for administering this ordinance. In addition, the City Administrator may enter into an agreement with the Motor Vehicle Division of the Department of Transportation as an authorized agent for the implementation of certain sections of this ordinance. If the Motor Vehicles Division is chosen as an authorized agent of the City, then the modifications outlined below shall apply:

(a) The fuel handler's penalty of Section 7 Subsection "c" shall be reduced to \$100.00. And if the Division determines that the failure to obtain the permit was due to reasonable cause and without any intent to avoid obtaining a permit, then the penalty provided in Section 7 and this Subsection may be waived.

(b) The fuel handler's monthly reporting requirements of Section 12 and 13 shall be waived.

**Section 28. Separability.** If any portion of this ordinance is for any reason held invalid or unconstitutional by a court of competent jurisdiction, such portion shall be deemed a separate, distinct and independent provision and such holding shall not affect the validity of the remaining portions of this ordinance.

**Section 29. Voter Referral.** This ordinance shall be referred to the electors of the City of Woodburn at the September 19, 1989, special election. A copy of the ballot measure for this referral is attached hereto and by this reference incorporated herein.

**Section 30. Emergency Clause for Voter Referral.** An emergency is declared to exist in regard to the referral of this matter to the voters and Section 29 of this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor.

**Section 31. Effective Date for Remainder of Ordinance.** Excepting Section 29 regarding voter referral, the taxation imposed by this ordinance shall commence November 1, 1989, upon approval of a majority of the electors of the City of Woodburn at the special election of September 19, 1989.

***Passed by the Council and approved by the Mayor August 14, 1989.***

## ORDINANCE NO. 2057

## AN ORDINANCE PROVIDING FOR A TRANSIENT OCCUPANCY TAX AND PROVIDING ADMINISTRATIVE PROCEDURES FOR COLLECTING SAID TAX.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Definitions.** For purposes of this ordinance, the following mean:

(1) Accrual Accounting. A system of accounting in which the operator enters the rent due from a transient into the record when the rent is earned, whether or not it is paid.

(2) Cash Accounting. A system of accounting in which the operator does not enter the rent due from a transient into the record until the rent is paid.

(3) Hotel. A structure, any portion of a structure, or any space that is occupied or intended or designed for transient occupancy for thirty (30) days or less for dwelling, lodging or sleeping purposes; and including, but not limited to, any hotel, inn, tourist home or house, motel, studio hotel, bachelor hotel, lodging house, public or private dormitory, fraternity, sorority, rooming house, public or private club, space in a mobile home or trailer park, space in a recreational vehicle park, or other similar structure if the occupancy is for less than a 30-day period.

(4) Occupancy. The use or possession or right to the use or possession of a room or space in a "hotel" for lodging or sleeping purposes.

(5) Operator. A person who is a proprietor of a hotel in any capacity. When the operator performs his functions through a managing agent of a type or character other than an employee, the managing agent shall also be considered an operator and shall have the same duties and liabilities as his principal. Compliance with the provisions of this ordinance be either the principal or the managing agent shall be considered compliance by both.

(6) Person. "Person" means any individual, firm, partnership, joint venture, association, social club, fraternal organization, fraternity, sorority, public or private dormitory, joint stock company, corporation, estate, trust, business trust, receiver, trustee, syndicate, or any other group or combination acting as a unity.

(7) Rent. The consideration charged for the occupancy of space in a hotel as that term is defined by this Ordinance. (Section 1(7) as amended by Ordinance 2419 dated May 14, 2007.)

(8) Rent Package Plan. The consideration charged for both food and rent when a single rate is made for the total of both. The amount applicable to rent for determination of the transient occupancy tax shall be the same charge made for rent when it is not a part of a package plan.

(9) Tax. The tax payable by the transient or the aggregate amount of taxes due from an operator during the period for which he is required to report his collections.

(10) Tax Administrator. The Finance Director or designee.

(11) Transient. An individual who exercises occupancy for a period of 30 consecutive calendar days or less, counting portions of calendar days as full days. The day a transient checks out of the hotel shall not be included in determining the 30-day period if the transient is not charged rent for that day by the operator. An individual occupying space in a hotel shall be transient until the period of 30 days has expired unless there is an agreement in writing between the operator and the occupant providing for a longer period of occupancy. A person who pays for lodging on a monthly basis, irrespective of the number of days in such month, shall not be deemed a transient.

**Section 2. Imposition of Tax**. For the privilege of occupancy in a hotel, a transient shall pay a tax in the amount of nine percent (9%) of the rent charged by the operator. The tax constitutes a debt owned by the transient to the City, and the debt is extinguished only when the tax is remitted by the operator to the City. The transient shall pay the tax to the operator of the hotel at the time the rent is paid. The operator shall enter the tax into the records when rent is collected if the operator keeps his records on the accrual accounting basis. If rent is paid in installments, a proportionate share of the tax shall be paid by the transient to the operator with each installment. If for any reason the tax due is not paid to the operator of the hotel, the tax administrator may require that the tax be paid directly to the City. In all cases, the rent paid or charged for occupancy shall exclude the sale of any goods, services and commodities other than the furnishing of rooms, accommodations, and parking space in mobile home parks, trailer parks or recreation vehicle parks. (Section 2 as amended by Ordinance 2290 dated June 11, 2001.)

**Section 3. Rules for Collection of Tax by Operator**.

(1) Every operator renting space for lodging or sleeping, the occupancy of which is not exempted under terms of this ordinance, shall collect a tax from the occupant. The tax collected or accrued constitutes a debt owned by the operator to the City.

(2) In cases of credit or deferred payment of rent, the payment of tax to the operator may be deferred until the rent is paid, and the operator shall not be liable for the tax until credits are paid or deferred payments are made. Adjustments may be made for uncollectible accounts.

(3) The tax administrator shall enforce this ordinance and may adopt rules and regulations necessary for enforcement.

(4) For rent collected on portions of a dollar, fractions of a penny of tax shall not be remitted.

**Section 4. Operator's Duties.** An operator shall collect the tax when the rent is collected from the transient. The amount of tax shall be stated separately in the operator's records and on the receipt given by the operator. An operator shall not advertise that the tax will not be added to the rent, that portion of it will be assumed or absorbed by the operator, or that a portion will be refunded, except in the manner provided by this ordinance. The operator shall pay the tax to this city as imposed by this ordinance as provided for in Section 8 of this ordinance.

**Section 5. Exemptions.** The tax shall not be imposed on:

- (1) An occupant staying for more than 30 consecutive days.
- (2) A person who rents a private home, vacation cabin or similar facility from an owner who personally rents the facility incidentally to the owner's personal use.
- (3) Any occupant whose rent is paid for a hospital room or stay in a medical clinic, convalescent home or home for aged people.
- (4) Any occupant whose rent is of a value less than \$2.00 per day.
- (5) Employees, officials or agents of the U.S. Government occupying a hotel in the course of official business. (Section 5(5) as amended by Ordinance 2419 dated May 14, 2007.)

**Section 6. Operator's Registration.**

- (1) An operator of a hotel shall possess a valid business registration in accordance with the requirements of Ordinance 2399.
- (2) Failure to register does not relieve the operator from collecting the tax imposed by this ordinance, or a person from paying said tax.

**Section 7. Certificate of Authority.**

- (1) The tax administrator shall, within 10 days after registration, issue without charge a certificate of authority to each registrant to collect the tax from the occupant, together with a duplicate for each additional place of business of each registrant. Certificates are nonassignable and nontransferable and shall be surrendered immediately to the tax administrator on the cessation of business at the location named or on the sale or transfer of the business. Each certificate and duplicate shall state the place of business to which it is applicable and shall be



prominently displayed so as to be seen by all occupants and persons seeking occupancy.

- (2) The certificate shall state:
  - (a) The name of the operator.
  - (b) The address of the hotel.
  - (c) The date on which the certificate was issued.

(d) This Transient Occupancy Registration Certificate signifies that the person named has fulfilled the requirements of the Transient Occupancy Tax Ordinance of the City of Woodburn by registering with the tax administrator for the purpose of collecting from transients the occupancy tax imposed by the City and remitting the tax to the tax administrator. This certificate does not authorize any person to operate a hotel without strictly complying with all local applicable laws including, but not limited to, those requiring a permit from any board, commission, department or office of the City of Woodburn. This certificate does not constitute a permit. This certificate does not authorize any person to conduct any unlawful business or to conduct any lawful business in an unlawful manner.

#### **Section 8. Collections, Returns and Payments.**

(1) The tax shall be paid by the transient to the operator at the time that rent is paid. The taxes collected by the operator are due and payable to the tax administrator on a calendar basis on the 15th day of the month for the preceding month and are delinquent on the last day of the month in which they are due.

(2) On or before the 15th day of the month following each month of collection, a return for the preceding month's tax collections shall be filed with the tax administrator. The return shall be filed on a form prescribed by the tax administrator.

(3) Returns shall show the amount of tax collected or otherwise due for the related period. The tax administrator may require returns to show the total rentals on which tax was collected or is due, gross receipts of the operator for the period, an explanation in detail of any discrepancy between the amounts, and the amounts of rents exempt.

(4) The operator is entitled to withhold ten percent (10.0%) of the tax due to cover the administrative expense of collecting and remitting the tax. This deduction shall be so noted in the appropriate place on the return form.

(5) The operator shall deliver the return and the tax due the City to the tax administrator's office either by personal delivery or by mail. If the return is by mail, the postmark shall be considered the date of delivery for determining delinquencies.

(6) For good cause, the tax administrator may extend the time for filing a return or paying the tax for not more than one month. No further extensions shall be granted except by the Council. An operator to whom an extension is granted shall pay interest at the rate of one percent (1%) per month on the amount of tax due, without proration for a fraction of a month. If a return is not filed, the tax and interest due are not paid by the end of the extension, the interest shall become part of the tax computation of penalties described in Section 9.

(7) The tax administrator may require returns and payment of the amount of taxes for other than monthly period in individual cases to ensure payment or to facilitate collection by the City.

#### **Section 9. Delinquency Penalty.**

(1) An operator who has not been granted an extension of time for remittance of tax due and who fails to remit the tax prior to delinquency shall pay a penalty of ten percent (10%) of the tax due in addition to the tax.

(2) An operator who has not been granted an extension of time for remittance of tax due and who fails to pay a delinquent remittance before the expiration of 31 days following the date on which the remittance became delinquent shall pay a second delinquency penalty of fifteen percent (15%) of the tax due, the amount of the tax, and the ten percent (10%) penalty first imposed.

(3) If the tax administrator determines that non payment of a remittance is due to fraud or intent to evade the tax, a penalty of twenty-five percent (25%) of the tax shall be added to the penalties state in subsections (1) and (2).

(4) In addition to the penalties imposed by this section, an operator who fails to remit the required tax shall pay interest at the rate of one percent (1.0%) per month, without proration for portions of a month, on the tax due, exclusive of penalties, from the date on which the tax first became delinquent until paid.

(5) Each penalty imposed and the interest accrued under provisions of this section shall be merged with and become part of the tax required to be paid.

(6) An operator who fails to remit the tax within the required time may petition the tax administrator for waiver and refund of the penalty or a portion of it. The tax administrator may, if good cause is shown, direct a refund of the penalty or a portion of it.

#### **Section 10. Deficiency Determinations.**

(1) In making a determination that the returns are incorrect, the tax administrator may determine the amount required to be paid on the basis of the facts contained in the return or on the basis of any other information.

(2) Deficiency determination may be made on the amount due for one or more than one period. The determined amount shall be payable immediately on service of notice, after which the determined amount is delinquent. Penalties on deficiencies shall be applied as provided in Section 9.

(3) In making a determination, the tax administrator may offset overpayments that have been made against a deficiency for a subsequent period or against penalties and interest on the deficiency. The interest on the deficiency shall be computed as provided in Section 9.

**Section 11. Redemption Petition.** A determination becomes payable immediately on receipt of notice and becomes final within 10 days after the tax administrator has given notice. However, the operator may petition for redemption and refund by filing a petition before the determination becomes final.

**Section 12. Fraud, Refusal to Collect, Evasion.**

(1) If an operator fails or refuses to collect the tax, make the report, or remit the tax, or makes a fraudulent return or otherwise willfully attempts to evade the tax payment, the tax administrator shall obtain facts and information on which to base an estimate of the tax due. After determining the tax due and the interest and penalties, the tax administrator shall give notice of the total amount due.

(2) Determination and notice shall be made and mailed within three years after discovery of fraud, intent to evade, failure or refusal to collect the taxes, or failure to file a return. The determination becomes payable immediately on receipt of notice and becomes final 10 days after the tax administrator has given notice.

(3) The operator may petition for redemption and refund if the petition is filed before the determination becomes final.

**Section 13. Notice of Determination.**

(1) The tax administrator shall give the operator a written notice of the determination. If notice is mailed it shall be addressed to the operator at the address that appears on the records of the tax administrator, and service is complete when the notice is deposited in the post office.

(2) Except in the case of fraud or intent to evade the tax, a deficiency determination shall be made and notice mailed within three years after the last day of the month following the close of the monthly period for which the determination has been made or within three years after the return is filed, whichever is later.

**Section 14. Operator Delay** If the tax administrator believes that collection of the tax will be jeopardized by delay, the tax administrator shall determine the tax to be collected and note facts concerning the delay on the determination. The determined amount is payable immediately after service of notice. After payment has been made,

the operator may petition for redemption and refund of the determination if the petition is filed within 10 days from the date of service of notice by the tax administrator.

#### **Section 15. Redetermination.**

(1) An operator against whom a determination is made under Section 10, or a person directly interested, may petition for a redetermination, redemption and refund within the time required in Section 14. If a petition for redetermination refund is not filed within the time required, the determination is final on expiration of the allowable time.

(2) If a petition for redetermination and refund is filed within the allowable period, the tax administrator shall reconsider the determination and, if the operator requested a hearing in the petition, shall grant the hearing and give the operator 10 days notice of the time and place of the hearing. The tax administrator may continue the hearing if necessary.

(3) The tax administrator may change the amount of the determination as a result of the hearing. If an increase is determined, the increase is payable immediately after the hearing.

(4) The decision of the tax administrator on a petition for redetermination becomes final 10 days after service of notice on the petitioner unless appeal of the decision is filed with the City Council within 10 days after notice is served.

(5) A petition for redetermination or an appeal is not effective unless the operator has complied with the payment provisions.

#### **Section 16. Security for Collection of Tax.**

(1) The tax administrator may require an operator to deposit security in the form of cash, bond or other security. The amount of security shall be fixed by the tax administrator, but shall not be greater than twice the operator's estimated average monthly liability for the period for which the operator files returns or \$5,000, whichever amount is less. The amount of the security may be increased or decreased by the tax administrator, subject to the limitations of this subsection.

(2) Within three years after any amount of the tax becomes due and payable or within three years after any determination becomes final, the tax administrator may bring an action in the courts of this state, or any other state, or of the United States in the name of the city to collect the amount delinquent, together with penalties and interest.

#### **Section 17. Liens**

(1) The tax, interest, penalty, and filing fees paid to the tax administrator any advertising costs incurred when the tax becomes delinquent shall be a lien from the date of its recording with the County Clerk of Marion County, Oregon until the tax is

paid. The lien shall be superior to all subsequently recorded liens on all tangible personal property in the operator's hotel. The lien may be foreclosed and the necessary property may be sold to discharge the lien.

(2) Notice of the lien shall be issued by the tax administrator when the operator has defaulted in payment of the tax, interest and penalty. A copy of the notice shall be sent by certified mail to the operator.

(3) Personal property subject to the lien may be sold at public auction after 10 days notice in a newspaper of general circulation in the city.

(4) A lien for the tax, interest and penalty shall be released by the tax administrator when the full amount has been paid to the city. The operator or person making the payment shall receive a receipt stating that the full amount of the tax, interest and penalty has been paid, that the lien is released and that the record of the lien is satisfied.

**Section 18. Refunds by City to Operator.** When the tax, penalty or interest has been paid more than once or has been erroneously or illegally collected or received by the tax administrator, it may be refunded if a written verified claim stating the specific reason for the claim is filed within three years from the date of payment. The claim shall be submitted on forms provided by the tax administrator. If the claim is approved, the excess amount may be refunded to the operator or it may be credited to an amount payable by the operator and any balance refunded.

**Section 19. Refunds by City to Transient.** If the tax has been collected by the operator and deposited with the tax administrator and it is later determined that the tax was erroneously or illegally collected or received by the tax administrator, it may be refunded to the transient if a written verified claim stating the specific reason for the claim is filed with the tax administrator within three years from the date of payment.

**Section 20. Records Required from Operators.** Every operator shall keep guest records, accounting books, and records of room rentals for a period of three years and six months.

**Section 21. Examination of Records.** During normal business hours and after notifying the operator, the tax administrator may examine books, papers, and accounting records related to room rentals to verify the accuracy of a return or, if no return is made, to determine the amount to be paid. To assist in this process, the tax administrator may request certified copies of the annual income tax return covering the hotel operator.

**Section 22. Confidentiality.** The tax administrator or a person having an administrative or clerical duty under the provisions of this ordinance shall not make known in any manner the business affairs, operations, or information obtained by an investigation of records and equipment of a person required to file a return or pay a transient occupancy tax or a person visited or examined in the discharge of official

duty; or the amount or source of income, profits, losses or expenditures contained in a statement or application; or permit a statement or application, or a copy of either, or a book containing an abstract or particulars to be seen or examined by any person. However, nothing in this section shall be construed to prevent:

(1) Disclosure to or examination of records and equipment by a city official, employee or agent for collecting taxes for the purpose of administering or enforcing the provisions or collecting the taxes imposed by this ordinance.

(2) Disclosure, after filing a written request, to the taxpayer, receivers, trustees, executors, administrators, assignees, and guarantors, if directly interested, of information concerning tax paid, unpaid tax, amount of tax required to be collected, or interest and penalties. However, the City Attorney shall approve each disclosure, and the tax administrator may refuse to make a disclosure referred to in this subsection when, in the tax administrator's opinion, the public interest would suffer.

(3) Disclosure of names and address of persons making the returns.

(4) Disclosure of general statistics regarding taxes collected or business done in the City.

**Section 23. Disposition of Tax Funds.** All revenue received from the transient occupancy tax shall be accounted for by a separate revenue line item contained in the General Fund. Sixty-six and two-thirds percent (66 2/3%) of all revenues received from the transient occupancy tax shall be used at the Council's discretion. Thirty-three and one-third percent (33 1/3%) of all revenues received from the transient occupancy tax shall be dedicated to uses that promote and support tourism and economic development activities. Of the monies set aside for tourism and economic development the Council may, at its discretion, expend some or all of those monies on activities conducted by the City or other agencies that advance the Council's tourism and economic development goals. Monies distributed to agencies and organizations other than the City shall be dispersed pursuant to a tourism and economic development grant program. Policies and procedures governing that program shall be established by City Council resolution. (Section 23 as amended by Ordinance 2444 adopted August 11, 2008.)

**Section 24. Appeals to Council.** A person aggrieved by a decision of the tax administrator may appeal to the City Council by filing a notice of appeal with the tax administrator within ten days of notice of the decision. The tax administrator shall transmit the notice, together with the file of the appealed matter, to the Council. The Council shall fix a time and place for hearing the appeal and shall give the appellant not less than ten days written notice of the time and place of hearing.

**Section 25. Severability.** The provisions of this ordinance are severable. If a portion of this ordinance is for any reason held by a court of competent jurisdiction to be invalid, such decision shall not affect the validity of the remaining portions of this ordinance.

**Section 26. Violations.**

(1) It is unlawful for any operator or other person so required to fail or refuse to register as required herein, or to furnish any return required to be made, or to fail to pay the tax collected, or fail or refuse to furnish a supplemental return or other data required by the tax administrator, or to render a false or fraudulent return. No person required to make, render, sign, or verify any report shall make any false or fraudulent report, with intent to defeat or evade the determination of any amount due required by this ordinance.

(2) Notwithstanding paragraph (1) of this section, the City Attorney, in addition to other remedies permitted by law, may commence and prosecute to final determination in any court of competent jurisdiction an action at law to collect the tax imposed.

**Section 27. Civil Infraction.** A violation of any provision of this ordinance shall constitute a Class 2 civil infraction and shall be dealt with according to the procedures established by Ordinance No. 1998. Each day of noncompliance with this ordinance shall constitute a separate violation.

**Section 28. Effective Date.** This ordinance shall be in full force and effect effective June 1, 1991.

***Passed by the Council April 8, 1991 and approved by the Mayor April 9, 1991.***

**ORDINANCE NO. 2328**

**AN ORDINANCE GRANTING PORTLAND GENERAL ELECTRIC COMPANY, AN OREGON CORPORATION, A NONEXCLUSIVE FRANCHISE FOR TEN YEARS TO OPERATE AN ELECTRIC LIGHT AND POWER SYSTEM WITHIN THE CORPORATE LIMITS OF THE CITY OF WOODBURN, FIXING THE TERMS AND CONDITIONS; PROVIDING AN EFFECTIVE DATE; AND REPEALING ORDINANCE NO. 2109**

**Section 1 – Franchise Granted**

Portland General Electric Company, an Oregon Corporation ("Company"), is hereby granted a non-exclusive Franchise to operate an electric light and power system within the corporate limits of the City of Woodburn ("City"), subject to the terms and conditions of this ordinance,

A. Definitions. As used in this ordinance:

"City" means the City of Woodburn, a municipal corporation of the State of Oregon, and its duly authorized officers, employees, agents or assigns.

"City Engineer" means the duly appointed City Engineer of Woodburn, Oregon.

"City Recorder" means the duly appointed City Recorder of Woodburn, Oregon.

"Company" means Portland General Electric Company.

"Company facilities" means all poles, wires, fixtures, equipment, underground circuits, conduit, and other property necessary or convenient to the supply of electric energy owned or operated by the Company within the corporate limits of the City.

"Corporate limits of the City of Woodburn" means the City boundary as it now exists or may be amended during the term of this Franchise.

"Franchise to operate an electric light and power system" includes the right and privilege to erect, construct, repair, maintain and operate poles, wires, fixtures, conduit, equipment, underground circuits and other property necessary or convenient to supply the City, its inhabitants and other persons and territory with electric energy for light, power and other purposes, upon, over, along, under and across the streets, alleys, roads and any public right-of-way, property or place.

"Gross revenue" includes any revenue earned by the Company within the City from the sale of electric energy after adjustment for the net write-off of uncollectible accounts computed on the average annual rate for the



entire Company, excluding existing sales of electric energy sold by the Company to any public utility when the public utility purchasing such electric energy is not the ultimate consumer. Gross revenue shall include revenues from the use, rental or lease of the Company's operating facilities of the utility other than residential-type space and water heating equipment under tariffs filed with and approved by the Oregon Public Utility Commission (OPUC). Gross revenue shall not include proceeds from the sale of bonds, mortgages or other evidence of indebtedness, securities or stocks, revenue from joint pole use, or revenue paid directly by the United States of America or any of its agencies. The meaning of "gross revenue" as used in this ordinance shall be amended and interpreted consistently with regulations prescribed by OPUC for determining the amount of franchise fees allowed as operating expenses of a utility for ratemaking purposes.

"Person" includes any individual, group of individuals, or legal entity.

"OPUC" means the Oregon Public Utility Commission, and any successor or additional agency empowered by the State of Oregon to regulate public utilities.

"Public project" means any project for work in the right of way that is not undertaken to benefit a specific development or redevelopment project on private property and that is not undertaken to benefit a public utility or service provider other than the City.

"Public right-of-way" includes the public streets, alleys, roads, dedicated rights-of-way, easements, and other public property, way or place within the corporate limits of the City, and further includes that portion of private property upon which a preliminary subdivision or partition plat has been approved by the City for provision of public utilities within the corporate limit of the City, which is expected to be dedicated to the City and over which the City shall have administration, ownership and control.

"Public utility" means any individual, partnership, cooperative, corporation or government agency buying electric energy and distributing such electric energy to other customers or users.

- B. Facilities Subject to Ordinance. All Company facilities within the City limits shall be deemed to be covered by the terms of this ordinance.
- C. Compliance with Laws. The Company shall at all times be subject to all laws, statutes, ordinances, codes, rules, regulations, standards, and procedures regarding the Company's facilities, whether Federal, State or local, now in force or which , hereinafter, may be promulgated (including but not limited to zoning, land use, historic preservation ordinances, safety standards, and other application requirements) ), unless specifically exempted.

- D. Unless otherwise specified in this ordinance, any action authorized or required to be taken by the City may be taken by the Woodburn City Council or its designee.

## **Section 2 – Term of Franchise and Effective Date**

This ordinance shall become effective March 1, 2003, and shall terminate on December 31, 2012.

## **Section 3 – Revocation**

- A. General. In addition to any rights set out elsewhere in this document, the City reserves the right to declare a forfeiture or otherwise revoke this Franchise, and all rights and privileges pertaining thereto, under certain circumstances.
- B. Conditions of Revocation. The grounds for which the City may declare forfeiture or revoke the Franchise are the following:
1. If the Company is in substantial violation of any material provision of the Franchise agreement and fails to correct the violation after written notice of the violation and proposed forfeiture and a reasonable opportunity thereafter to correct the violation;
  2. The Company becomes insolvent, unable or unwilling to pay its debts, or is adjudged bankrupt;
  3. The Company is found by a court of competent jurisdiction to have engaged in fraud or deceit upon the City; or
  4. The Company fails to obtain and maintain any right granted by any state regulatory body, required in order to provide electric service to customers within the City or to construct, maintain and operate the system; provided, however, that the Company shall be allowed a reasonable time to cure failure to obtain any permit.
- C. Due Process. Upon the occurrence of one of the events set out above, following 30 days written notice to Company of the occurrence and the proposed forfeiture and an opportunity for Company be heard, the City may by ordinance declare a forfeiture. In a hearing, the Company shall be afforded due process rights. Findings from the hearing shall be written, and shall stipulate the reasons for the City's decision. In the event the Company believes the City improperly has declared a forfeiture, the Company may file such proceeding as is appropriate in a court of competent jurisdiction.

- D. The City reserves the right to cancel this Franchise at any time upon one year's written notice to the Company in the event that the City decides to engage in public ownership of light and power facilities and the public distribution of electric energy to customers throughout the City.

#### **Section 4 – Construction to be Approved by City**

- A. Before the Company may conduct underground work involving excavation, new construction or major relocation work in any public right-of-way, the Company shall first notify the City, furnish appropriate maps and drawings, and provide not less than forty-eight (48) business day hours notice, except in the case of an emergency. The City will not sell or transmit Company maps or data to third parties unless permitted by the Company. The City shall upon request make available to the Company any City prepared maps or data which are a matter of public record, to facilitate permitting or the Company's capital planning. These maps or data shall be made available to Company upon payment of the applicable public records fees.
- B. In the case of an emergency the Company shall file maps and drawings with the City Engineer showing any construction work done by the Company within the corporate limits of the City, within thirty (30) days after completion of the work.
- C. Such construction work shall be done in a reasonably safe manner in accordance with requirements of applicable ordinances, State laws, and rules. In all circumstances pertinent to this Franchise, any actions by the Company's contractors shall be the responsibility of the Company. Any contractor of the Company shall be bound by all terms and conditions of this Franchise.

#### **Section 5 – Location and Relocation of Company Facilities**

- A. City Approval Required for Company Installations, Excavations and Restorations. Subject to City approval, the Company may make all necessary excavations in any public right-of-way for the purpose of erecting, locating, installing, constructing, repairing, maintaining, removing and relocating Company facilities. The location of Company facilities in the public right-of-way shall be at places approved by the City. Except in emergencies, the City may require the Company to obtain a permit prior to commencing any work pursuant to this section pursuant to the City's ordinances or regulations. In emergencies, the Company shall take reasonable measures to notify the City Engineer prior to commencing work.

- B. Removal or Relocation – Temporary or Permanent. In accordance with ORS 221.420, the City may require the Company to remove and relocate transmission and distribution facilities maintained by the Company in any public rights of way, property or place of the City by giving notice to the Company. The Company shall, upon ten (10) days written notice from the City, respond and begin the design process to relocate such facilities. Both parties will, to the greatest possible extent, agree on a relocation plan that provides for a suitable location for both ground and aerial transmission. In the event of a disagreement regarding suitable location, the City's determination shall be final subject to state law and regulations including, but not limited to, the National Electrical Safety Code. If the City's determination of a location requires the acquisition of easements or right-of way, the required easements or right-of way from private property owners for such relocated facilities sufficient to maintain service will be obtained by the City. If acquisition of easements or right-of-way is required to satisfy Company's location requirements, the required easements or rights-of-way will be obtained by the Company from private property owners. The cost of removal or relocation of its facilities for public projects shall be paid by the Company. When the City requires the Company to relocate the same facilities that were previously relocated on another public works project that was completed within the past two years, the cost will be borne by the City. This provision shall apply only to fully completed projects, and shall not apply to phases of the same project and minor relocation work.
- C. Overhead to Underground Conversion. As permitted by law, administrative rule, or regulation, the City may require the Company to remove any overhead facilities and replace those facilities within underground facilities at the same or different locations. Both parties will, to the greatest possible extent, agree on a relocation plan that provides for a suitable location. In the event of a disagreement regarding suitable location, the City's determination shall be final subject to state law and regulations including, but not limited to, the National Electrical Safety Code. If the City's determination of a location requires the acquisition of easements or right-of way, the required easements or right-of way from private property will be obtained by the City. If acquisition of easements or right-of-way is required to satisfy Company's location requirements, the required easements or rights-of-way will be obtained by the Company from private property owners. The expense of such a conversion shall be paid by the Company subject to OAR 860-022-0046 and the conversion itself shall be accomplished in the manner described by the rules of the OPUC. The Company shall collect conversion costs in accordance with OPUC rules. Nothing in this paragraph prevents the City and the Company from agreeing to a different form of cost recovery on a case-by-case basis.

- D. Notice Required. Except in an emergency, the Company shall provide not less than forty-eight (48) business day hours notice to the City Engineer prior to any work by the Company which involves excavation in the public right-of-way or relocation of Company facilities. The Company shall exercise all reasonable efforts to provide advance notice of such work so as not to disrupt City services or any other person using the right-of-way and to enable the City to inspect the work.
- E. Company to Minimize Disruptions. Whenever work is performed in any public right-of-way, the Company shall take all reasonable precautions to minimize interruption to traffic flow, damage to property or creation of a hazardous condition.
- F. Restoration Required. When the Company makes any excavation or installation pursuant to this ordinance, the Company or its contractors shall restore the affected public right-of-way to the same condition which it was in prior to the excavation. All work done shall be subject to the reasonable rejection or correction requirements of the City Engineer and subject to the City Engineer's approval. If the Company fails to promptly restore the affected portion of the public right-of-way, the City may restore the right-of-way and charge all costs to the Company. If the Company inadequately restores the right-of-way, the City may repair the restored area to correct the defect and charge the cost to the Company, provided that the City gives the Company notice of the defect and ten (10) days opportunity to correct the defect. All excavation and restoration work shall be done in strict compliance with applicable rules, permits issued, regulations, ordinances or orders of the City and other applicable laws and regulations which may be adopted from time to time during the continuance of this Franchise by the City Council or as may otherwise be provided by law.

## **Section 6 – Public Facilities and Improvements**

- A. All Company facilities shall be placed so that they do not interfere with the use by the City or the public of any public right-of-way and in accordance with any requirements adopted by the City Council. Nothing in this ordinance shall be construed to prevent the City from severing, grading, paving, planking, repairing, widening, altering or doing any work that may be desirable on or in any public right-of-way. If possible, all such work shall be done so as not to obstruct, injure or prevent free use and operation of the electric light and power system of the Company.
- B. Whenever the City performs or contracts for work in the right-of-way that may disturb but does not require the relocation of Company facilities, the City shall take reasonable measures to notify the Company in advance to enable Company to take measures to protect its facilities from damage

or injury to the public. In such case, the Company shall furnish field marking to the City or contractor showing the approximate location of all of its facilities in the area involved in the construction.

- C. If space is available, the Company shall permit the City to run wires on Company poles or conduit for municipal purposes and to attach city alarms and police signals to Company poles, subject to the following conditions:
1. Such wires and signals shall be strung so as not to interfere with the wires of the Company and to conform to the provisions of the National Electrical Safety Code and any other applicable building code. City shall submit applications for permits for such attachments;
  2. The City shall not lease or sell space on Company poles or conduit to third parties, or in its facilities attached to Company poles or in conduit. The City may provide space in its facilities at no charge to entities using such space for a public purpose as long as such entities' use will cause no additional burden to Company poles or conduit or require any separate attachment on or space in Company poles or conduit ; and
  3. To the degree permitted by Oregon Law, the City shall defend, indemnify and hold the Company harmless from loss or damage resulting from damage to persons or property or injury or death to City employees, Company employees, or the public arising from the use of said poles by the City.
- D. The Company shall by permit allow the City to attach banners or other civic beautification or information items to poles of the Company subject to the following:
1. The attachments shall not interfere with the wires of the Company and shall conform to the provisions of the National Electric Safety Code and any other applicable Federal, State or PUC regulation. The Company may regulate the location of such attachment or may deny requests for such attachments on a case-by-case basis if the attachment would violate the requirement of this subsection. In addition, all such attachments shall be in accordance with PGE's banners and attachments policy; and
  2. To the degree permitted by Oregon Law, the City shall defend, indemnify and hold the Company harmless from loss or damage resulting from damage to persons or property or injury or death to City employees, Company employees, or the public arising from the use of said poles by the City. The City shall maintain general liability insurance in the amount of at least \$1,000,000; which shall

name the Company as an additional insured, during use of the poles by the City pursuant to Sections 6 (c) and (d).

### **Section 7 – Continuous Service: Safety Standards**

- A. The Company shall furnish adequate and safe service for the distribution of electrical energy in the City. The Company shall use due diligence to maintain continuous 24-hour a day service which shall at all times conform at least to the standards common in the business and to the standards adopted by the State. Under no circumstances shall the Company be liable for an interruption or failure of service caused by an act of God, unavoidable accident, or other circumstances beyond the control of the Company.
- B. The Company shall comply with all the applicable rules and regulations of the OPUC.

### **Section 8 – Acceptance of Franchise Fees**

The rights and privileges granted by this Franchise are granted upon the conditions herein contained and also upon the following conditions:

- A. PGE shall, within thirty (30) days from the effective date of this ordinance, file with the City Recorder its written acceptance of this Franchise (Exhibit "A". Acceptance of Franchise), subject to all the terms and conditions of this Franchise. If Company has not unconditionally accepted this ordinance within the above noted acceptance period, this ordinance shall become void.
- B. In consideration of the rights and privileges granted by this Franchise, the Company shall pay to the City a franchise fee each calendar year during the life of this Franchise of three and one-half (3-1/2) percent of the gross revenue as defined herein for the immediately preceding calendar year. If the Company pays a franchise fee of more than 3.5% to another municipal corporation or the OPUC permits the Company to pay any municipality a percentage rate of compensation exceeding that provided for herein as an operating expense of the Company, the Company shall inform the City. The City shall have the right to immediately require and receive the same percentage fee permitted by the OPUC or paid by the Company to another municipal corporation.
- C. In consideration of the agreement of the Company to make such payments, the City agrees that no license, permit fee, tax or charge on the business or occupation of the Company shall be imposed upon the Company by the City during the term of this ordinance, except:
  - 1. This provision shall not exempt the property of the Company from lawful ad valorem taxes, local improvement district assessments, or

conditions, exactions, fees and charges which are generally applicable to the Company's real property, use or development as required by the City's ordinances and regulations.

2. The City shall retain the power to impose a privilege tax on the Company as permitted by Oregon law, so long as the combined franchise fee and privilege tax assessed against the Company does not exceed five (5) percent of the Company's gross revenue from within the City as defined in this ordinance. If the City decides to enact a privilege tax, the City shall provide the Company with sixty (60) days notice prior to the effective date of the ordinance enacting the tax.
- D. On or before the first day of March of each year during the term of this Franchise, beginning in 2003, the Company shall file with the City Recorder a statement under oath showing the amount of gross revenue of the Company within the City on the basis outlined in paragraph (B) for the calendar year immediately preceding the year in which the statement is filed. The annual franchise fee (and any privilege tax that may be assessed) for the year in which the statement is filed shall be computed on the gross revenue so reported. Such franchise fee (and any privilege tax that may be assessed) shall be payable annually on or before the first day of April, beginning in 2003. Any privilege tax enacted by the City shall be paid by the Company to the City beginning with the annual payment following enactment of the tax. The City Recorder shall issue a receipt for such annual payment, which shall be the full acquittance of the Company for the payment. Any dispute as to the amount of the Company's gross revenue within the meaning of this ordinance shall be resolved by the Public Utility Commission of Oregon after examination of the Company's records. Any difference of payment due the City through error or otherwise shall be payable within fifteen (15) days of written notice of discovery of such error. If the Company fails to pay any part of the annual payment for thirty (30) days after such payment is due pursuant to this ordinance, and after thirty (30) days written notice from the City, the City may either continue this Franchise in force and/or proceed by suit or action to collect said payment or declare a forfeiture of this Franchise because of the failure to make such payment but without waiving the right to collect earned franchise payments. Any overpayment to the City through error or otherwise shall be offset against the next payment to the City.
- E. The City may, consistent with state law and regulations, direct that the franchise fee and privilege tax, be calculated on volume-based methodologies as specifically described in ORS 221.655 instead of the gross revenue formula set out in Section 8 (B). Notice must be given to the Company in writing, by October 30<sup>th</sup> of each calendar year for implementation of volume-based methodology beginning January 1<sup>st</sup> of the following year. The volumetric calculation must remain in effect for an



entire calendar year (January 1 to December 31 billings). No notice is necessary if the City chooses to remain on the gross revenue-based calculation.

- F. The City reserves the right to cancel this Franchise at any time upon one year's written notice to the Company in the event that the City decides to engage in public ownership of light and power facilities and the public distribution of electric energy.
- G. The Company shall not unjustly discriminate or grant undue preference to any users of the services provided by the Company pursuant to this Franchise.

#### **Section 9 – Franchise Non-Transferable**

- A. **No Transfer Without Consent.** This Franchise may not be sold, assigned, transferred, leased, or disposed of, either in whole or in part, either by involuntary sale or by voluntary sale, merger, consolidation, nor shall title thereto, either legal or equitable, or any right, interest, or property therein pass to or vest in any person, nor may actual working control of the City be changed, transferred or acquired without the prior written consent of the City, which consent shall not be unreasonably withheld.
- B. **Notification.** The Company shall promptly notify the City of any proposed change in, or transfer of, or acquisition by any other party of control of the Company.
- C. **Request for Approval.** The Company shall make a written request to the City for its approval of a sale or transfer of this Franchise and furnish all information required by law and the City.
- D. **City Inquiry into Qualifications.** In reviewing a request for sale or transfer of this Franchise, the City may inquire into the legal, technical and financial qualifications of the prospective transferee, and Company shall assist the City in so inquiring. The City may condition said sale or transfer of this Franchise upon reasonable terms and conditions related to the legal, technical, and financial qualifications of the prospective transferee.
- E. **Filing Evidence of Transfer.** Within thirty (30) days of any transfer or sale of this Franchise, if approved or deemed granted by the City, Company shall file with the City a copy of the deed, agreement, lease or other written instrument evidencing such sale or transfer of ownership or control, certified and sworn to as correct by City and the transferee.
- F. **Approval Not Waiver.** The consent or approval of the City to any transfer by the Company shall not constitute a waiver or release of any rights of the City, and any transfer shall, by its terms, be expressly subordinate to the terms and conditions of this Franchise.

- G. Exceptions. Notwithstanding anything to the contrary in this Section, the prior approval of the City shall not be required for any sale, assignment or transfer of the Franchise to an entity controlling, controlled by or under the same common control as Company provided that the proposed assignee or transferee must show financial responsibility as may be determined necessary by the City and must agree in writing to comply with all provisions of the Franchise.

### **Section 10 – Continuity of Service Mandatory**

- A. As long as the City is included in the service territory allocated to the Company by the Oregon Public Utility Commission ("OPUC") pursuant to ORS 758.400 et seq., the Company shall provide electric service to customers within the corporate limits of the City in accordance with state statutes and regulations.
- B. In the event of purchase, lease-purchase, condemnation, acquisition, taking over and holding of plant and equipment, sale, lease or other transfer to any other person, including any other Grantee of an Electric Light and Power System Franchise, the Company shall cooperate with the City and such person or other Grantee to make sure that customers within the corporate limits of the City continue to receive electric service during any period of transition.

### **Section 11 – Books of Account and Reports**

The Company shall keep and maintain accurate books of account at an office in Oregon for the purpose of determining the amounts due to the City pursuant to Section 8 of this ordinance. The City may inspect the books of account, including computer retrieval information, at any time during the Company's business hours and audit the books from time to time. The City Council may require periodic reports from the company relating to its operation and revenues within the City.

### **Section 12 – Utility Rates Set by the OPUC**

The rates charged by the Company for electric energy shall be as fixed or approved by the OPUC.

### **Section 13 – Changes in Statutes or Rules**

If the State of Oregon or the OPUC amends or adopts a state statute or administrative rule that would affect a material term, condition, right or obligation under this Franchise, either party may reopen Franchise negotiations with regard to such term, condition, right or obligation in order to address the change required or allowed by the new or amended state statute or administrative rule.

**Section 14 – Indemnification**

The Company shall indemnify, defend and save harmless the City and its officers, agents and employees from any and all loss, cost and expense, including reasonable attorneys fees, arising from damage to property and/or injury or death of persons or any other damage resulting in whole or in part from any wrongful or negligent act or omission of the Company, its agents or employees in exercising the rights, privileges and franchise hereby granted.

**Section 15 – Insurance**

Company shall be self-insured for any tort liability for the first \$2 million of coverage or maintain an equivalent insurance policy. Beyond the \$2 million retention, Company shall maintain liability coverage in excess of \$2 million for bodily injury and property damage, including liability assumed under contract.

**Section 16 – Franchise Nonexclusive**

This Franchise shall not be exclusive and shall not be construed as any limitation on the City to grant rights, privileges and authority to other persons or corporations similar to or different from those herein set forth.

**Section 17 – Rights not to be Construed as Enhancement to Company Property**

The City and the Company understand and agree that the privileges granted to the Company by this Franchise in the streets, alleys, roads and other public places of the City are not to operate so as to be an enhancement of the Company's properties or values or to be an asset or item of ownership in any appraisal thereof.

**Section 18 – Remedies and Penalties not Exclusive**

All remedies and penalties under this ordinance, including termination of the Franchise, are cumulative and not exclusive. Failure to enforce shall not be construed as a waiver of a breach of this Franchise. A specific waiver shall not be construed to be a waiver of a future breach or of any other term or condition of this Franchise.

**Section 19 – Severability Clause**

If any portion of this ordinance is deemed unlawful or void by a Court or regulatory body of competent jurisdiction, such decision shall not affect the validity of the remaining portions of this ordinance.

**Section 20 – Prior Ordinance Repealed**

Ordinance No. 2109 is hereby repealed, and upon acceptance by the Company of this Franchise, all rights and obligations arising under Ordinance No. 2109, as amended, shall terminate.

Passed by the Council January 27, 2003 and approved by the Mayor January 29, 2003.

## ORDINANCE NO. 2114

AN ORDINANCE IMPOSING A PRIVILEGE TAX ON PORTLAND GENERAL ELECTRIC COMPANY, AN OREGON CORPORATION, IN THE AMOUNT OF 1.5 PERCENT OF DEFINED GROSS REVENUES, REGULATING USE OF THE REVENUES THEREBY DERIVED, DECLARING AN EMERGENCY AND SETTING AN EFFECTIVE DATE.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Privilege Tax Imposed.** There is hereby imposed a privilege tax on the gross revenues of Portland General Electric Company, an Oregon corporation, in the amount of 1½% (one and one-half percent) of those revenues. As used herein, "gross revenues" means revenues received by Company from the sale of electric energy within the city, less net uncollectibles. Gross revenue shall include revenues from the use, rental or lease of operating facilities of the Company other than residential-type space and water heating equipment. Gross revenues shall not include proceeds from the sale of bonds, mortgage or other evidence of indebtedness, securities or stocks, sales at wholesale prices by one public utility to another when the utility purchasing the service is not the ultimate consumer, or revenue from joint pole use.

The privilege tax provided in this ordinance is in addition to the franchise fee being paid by the Company pursuant to Ordinance No. 2109, which grants to PGE a non-exclusive franchise within the city. That ordinance remains in full force and effect.

**Section 2. Payment Dates.** The tax provided in this ordinance shall be paid annually and shall be due for each calendar year or fraction thereof, on or before the first day of April following the end of the calendar year for which the tax is due; with the first payment, for gross revenues collected during 1994, due on or before April 1, 1995.

**Section 3. Interest on Late Payments.** In the event PGE fails to pay the tax on or before the due date, interest shall be owed on the tax from the due date to the date on which payment is received by the city, compounded daily.

**Section 4. Use of Proceeds.** The proceeds derived from this ordinance shall be dedicated toward funding of transportation improvement projects identified in the city's Capital Improvement Program.

**Section 5. Emergency Clause and Effective Date.** This ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect on January 1, 1994, and shall remain in effect until modified or rescinded by ordinance of the City Council.

*Passed by the Council December 13, 1993 and approved by the Mayor December 16, 1993.*

## ORDINANCE NO. 2118

**AN ORDINANCE PROVIDING FOR THE REGULATION OF BASIC SERVICE TIER RATES AND RELATED EQUIPMENT, INSTALLATION AND SERVICE CHARGES OF ANY CABLE TELEVISION SYSTEM OPERATING IN THE CITY OF WOODBURN AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** The City shall follow the FCC Rate Regulations in its regulation of the Basic Service Rates and Charges of the Company and any other cable television system operating in the City, notwithstanding any different or inconsistent provisions in the Franchise; and

**Section 2.** In connection with such regulation, the City shall ensure a reasonable opportunity for consideration of the views of interested parties; and

**Section 3.** The City Administrator is authorized to execute on behalf of the City and file with the FCC such certification forms or other instruments as are now or may hereafter be required by the FCC Rate Regulations in order to enable the City to regulate Basic Service Rates and Charges.

**Section 4.** This ordinance being necessary for the immediate preservation of the public peace, health and safety, and emergency is declared to exist and this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor.

***Passed by the Council February 28, 1994 and approved by the Mayor  
March 1, 1994.***

## ORDINANCE NO. 2145

AN ORDINANCE IMPOSING A PRIVILEGE TAX ON NORTHWEST NATURAL GAS COMPANY, AN OREGON CORPORATION, IN THE AMOUNT OF 2.0 PERCENT OF DEFINED GROSS REVENUES, REGULATING USE OF THE REVENUES THEREBY DERIVED, DECLARING AN EMERGENCY AND SETTING AN EFFECTIVE DATE.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Privilege Tax Imposed.** There is hereby imposed a privilege tax on the gross revenues of Northwest Natural Gas Company, an Oregon corporation, in the amount of 2% (two percent) of those revenues. "Gross revenue" as used in this ordinance shall be deemed to include any revenue earned within the City from the sale of natural gas after deducting from the total billings of the Grantee the total net writeoff of uncollectible accounts. Gross revenues shall include revenues from the use, rental or lease of operating facilities of the utility other than residential-type space and water heating equipment. Gross revenues shall not include proceeds from the sale of bonds, mortgage or other evidence of indebtedness, securities or stocks, revenues derived from the sale or transportation of gas supplied under an interruptible tariff schedule, sales at wholesale to a public utility when the utility purchasing the service is not the ultimate consumer, or revenue paid directly by the United States of America or any of its agencies.

The privilege tax provided in this ordinance is in addition to the franchise fee being paid by the Company pursuant to Ordinance No. 2133, which grants to Company a non-exclusive franchise within the city. That ordinance remains in full force and effect.

**Section 2. Payment Dates.** The tax provided in this ordinance shall be paid quarterly and shall be due for each calendar quarter or fraction thereof, on or before thirty (30) days following the end of the calendar quarter, or fraction thereof, for which the tax is due; with the first payment, for gross revenues collected during that portion of the 3rd quarter of 1995 in which this ordinance is in effect, due on or before October 1, 1995.

**Section 3. Interest on Late Payments.** In the event Company fails to pay the tax on or before the due date, interest shall be owed on the tax from the due date to the date on which payment is received by the city, compounded daily.

**Section 4. Use of Proceeds.** The proceeds derived from this ordinance shall be dedicated toward funding of transportation improvement projects identified in the city's Capital Improvement Program.

**Section 5. Emergency Clause and Effective Date.** This ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect on June 18, 1995, and shall remain in effect until modified or rescinded by ordinance of the City Council.

*Passed by the Council May 22, 1995 and approved by the Mayor May 23, 1995.*



## ORDINANCE NO. 2177

AN ORDINANCE GRANTING TO U S WEST COMMUNICATIONS, INCORPORATED, ITS SUCCESSORS AND ASSIGNS, THE RIGHT AND PRIVILEGE TO DO A GENERAL COMMUNICATION BUSINESS AND TO OPERATE WITHIN THE CITY OF WOODBURN, REPEALING ORDINANCE NOS. 1934, 2041 AND 2163 AND DECLARING AN EMERGENCY.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1.** There is hereby granted by the City of Woodburn to U S West Communications, Incorporated, its successors and assigns, the right and privilege to do a general communication business within said City of Woodburn and to place, erect, lay, maintain and operate in, upon, over and under the streets, alleys, avenues, thoroughfares, and public highways, places and grounds within the said City, poles, wires and other appliances and conductors for all telephone and other communications purposes. Such wires and other appliances and conductors may be strung upon poles or other fixtures above ground, or at the option of the Grantee, its successors and assigns, may be laid underground, and such other apparatus may be used as may be necessary or proper to operate and maintain the same.

**Section 2.** It shall be lawful for said Grantee, its successors and assigns, to make all needful excavations in any of the streets, alleys, avenues, thoroughfares and public highways, places and grounds in said City for the purpose of placing, erecting, laying and maintaining poles or other supports or conduits for such wires and appliances and auxiliary apparatus or repairing, renewing or replacing the same. The work shall be done in compliance with the necessary rules, regulations, ordinances or orders, which may during the continuance of this franchise be adopted from time to time by the City of Woodburn.

Except in an emergency, Grantee shall not excavate in the rights-of-way without first obtaining a City "Right-of-Way Improvement" permit. Grantee will ensure that all requirements are met as the contractor for the work. In emergency situations, Grantee may make initial contact by telephone, but a permit must be obtained as soon as possible.

**Section 3.** Whenever Grantee, its successors and assigns, shall disturb any of the streets for the purpose aforesaid, it or they shall restore the same to good order and condition as soon as practicable without unnecessary delay, and failing to do so the City of Woodburn shall have the right to fix a reasonable time within which such repairs and restoration of streets shall be completed, and upon failure of such repairs and restoration being made by the Grantee, its successors and assigns, the said City shall cause the repairs to be made at the expense of the Grantee, its successors and assigns.

**Section 4.** Nothing in this Ordinance shall be construed in any way to prevent the proper authorities of the City of Woodburn from sewerage, grading, planking, rocking, paving, repairing, altering, or improving any of the streets, alleys, avenues, thoroughfares and public highways, places and grounds within the City of Woodburn in

or upon which the poles, wires or conductors of the Grantee shall be placed, but all such work or improvements shall be done if possible so as not to obstruct or prevent the free use of said poles, wires, conductors, conduits, pipes or other apparatus. Grantee shall relocate or remove such facilities when in conflict with City work at no cost to the City. However, the costs of relocating or removing Grantee's facilities for the convenience of or at the request of a private developer or development shall be borne by such private developer or development. The City shall not require Grantee to remove or relocate its facilities or vacate any street, alley or other public way incidental to any public housing or renewal project under ORS Chapters 456 or 457 without reserving Grantee's right to access available grant funding. In the event of major improvement projects the City may direct that all aerial transmission and distribution facilities be placed jointly underground. Payment for such work shall be in accordance with applicable Oregon Revised Statutes and Administrative Rules.

**Section 5.** Whenever it becomes necessary to temporarily rearrange, remove, lower or raise the aerial cables or wires or other apparatus of the Grantee to permit the passage of any building, machinery or other object moved over the roads, streets, alleys, avenues, thoroughfares and public highways within the City, the Grantee will perform such a rearrangement within a reasonable period after written notice from the owner or contractor-mover desiring to move said building, machinery or other objects. Said notice shall bear the approval of the City, shall detail the route of movement of the building, machinery, or other object, shall provide that the costs incurred by the Grantee in making such a rearrangement of its aerial facilities will be borne by the contractor-mover and shall further provide that the contractor-mover will indemnify and save the Company harmless of and from any and all damages of claims whatsoever kind or nature, caused directly or indirectly from such temporary rearrangement of the facilities of the Grantee, and if required by the Grantee, shall be accompanied by a cash deposit or a good and sufficient bond to pay any and all such costs as estimated by the Grantee.

**Section 6.** In consideration of the rights, privileges, and franchise hereby granted, said Grantee, U S WEST Communications, Incorporated, its successors and assigns, shall pay to the City of Woodburn from and after the date of the acceptance of this franchise, and until its expiration, quarterly, seven percent (7%) per annum of its gross revenues derived from exchange access services as defined in ORS 401.710 within the corporate limits of the City of Woodburn less net uncollectibles. Payment shall be made quarterly, on or before April 30, July 31, October 31 and January 31 for the preceding calendar quarter. Such payment made by the Grantee will be accepted by the City of Woodburn from the Grantee, also in payment of any license, privilege or occupation tax or fee for revenue or regulation, or any permit or inspection fees or similar charges for street openings, installations, construction or for any other purpose now or hereafter to be imposed by the City of Woodburn upon the Grantee during the term of this franchise.

**Section 7.** The rights, privileges and franchise herein granted shall continue and be in force for the period of ten (10) years from and after the date this Ordinance becomes effective, except that it is understood and agreed that either party may terminate this Agreement after 180 days notice in writing. This Ordinance shall be subject to any and all State and Federal legislative enactments.

**Section 8.** The right to use and occupy said streets, alleys, avenues, thoroughfares and public highways, places and grounds within the said City for the purposes set forth herein shall not be exclusive, and the City reserves the right to grant a similar use of said streets, alleys, avenues, thoroughfares and public highways, places and grounds to any person at any time during the period of this franchise.

**Section 9.** Grantee shall indemnify, defend and hold harmless the City and its officers, agents and employees from damages, costs and expense arising from any injury to persons or property by reason of the negligent act or omission of Grantee, its agents or employees in exercising the rights and privileges herein granted. Grantee shall at all times comply with any lawful present or future charter provisions, ordinances, rules or regulations of the City relating to the manner of occupation or use, or to the repair or improvement of City streets and sidewalks.

**Section 10.** This Ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor. Grantee shall, within thirty (30) days of the passage and approval of this Ordinance, file with the Recorder of the City of Woodburn its written acceptance of all the terms and conditions of the Ordinance. If such written acceptance is not performed within said thirty (30) days, this ordinance shall become null and void.

**Section 11.** Ordinance Nos. 1934, 2041 and 2163 are hereby repealed.

***Passed by the Council September 9, 1996 and approved by the Mayor  
September 10, 1996.***

**ORDINANCE NO. 2211****AN ORDINANCE APPROVING AND CONSENTING TO THE TRANSFER AND ASSIGNMENT OF A CABLE TV FRANCHISE FROM NORTHLAND CABLE TELEVISION, INC. TO NORTH WILLAMETTE TELECOM, INC. AND DECLARING AN EMERGENCY.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** The City hereby approves and consents to the transfer and assignment of the Franchise from Seller to North Willamette.

**Section 2.** The City hereby approves the encumbrance of the Franchise and the assets of the cable television system, and the assignment of same for security purposes, in connection with the acquisition and operation of the system and the financing and refinancing, from time to time, of the business operations of North Willamette.

**Section 3.** The assignment and transfer of the Franchise shall not alter the terms and conditions of the Franchise granted in Ordinance 2093; and North Willamette shall file with the City Recorder a written unconditional assumption and acceptance of the Franchise.

**Section 4.** In addition to the document required by Section 3, North Willamette shall file with the City Recorder a written assurance that:

(A) It shall maintain a system headend in the incorporated City limits of Woodburn during the term of the Franchise.

(B) It shall maintain an office and studio located in the incorporated City limits during the term of the Franchise.

**Section 5.** In connection with the assignment and transfer of the Franchise to North Willamette, the City certifies to Seller and North Willamette that:

(A) The Franchise was duly and validly issued by the City.

(B) The Franchise is in full force and effect as of the date hereof, is valid and enforceable in accordance with its terms and will not expire until October 19, 2002.

(C) No event of default under the Franchise, and no event which could become an event of default with the passage of time or the giving of notice, or both, has occurred and is continuing as of the date of this Ordinance.

(D) All fees owing to the City pursuant to the Franchise have been paid through December 31, 1997.

(E) The City acknowledges receipt of a completed FCC Form 394 from Seller and North Willamette.

**Section 6.** Ordinance Nos. 1766, 2093 and this Ordinance were and are adopted in accordance with the notice and procedure requirements of the laws of the State of Oregon governing cities, and with the notice and procedure requirements prescribed by the City. Ordinance Nos. 1766, 2093 and this ordinance were and are adopted in accordance with and do not conflict with the laws, ordinance, resolutions and other regulations of the City, as presently in effect or as the same were in effect at the time the particular action was taken.

**Section 7.** This ordinance being necessary for the immediate preservation of the public peace, health and safety, an emergency is declared to exist and this ordinance shall take effect immediately upon passage by the Council and approval by the Mayor.

*Passed by the Council April 13, 1998 and approved by the Mayor April 15, 1998.*

## ORDINANCE NO. 2291

**AN ORDINANCE GRANTING A TELECOMMUNICATIONS FRANCHISE TO DATA VISION COMMUNICATIONS, A DIVISION OF GERVAIS TELEPHONE TO OCCUPY CERTAIN RIGHTS-OF-WAY WITHIN THE CITY OF WOODBURN.**

[Whereas clauses.]

**Section 1. Franchise Grant.**

A. Subject to the terms and conditions contained herein, the City of Woodburn does hereby grant to Data Vision Communications, a division of Gervais Telephone (hereinafter "Grantee") a telecommunications franchise to locate its facilities within the rights-of-way of the City, as shown on Exhibit "A" and described in Grantee's application for a franchise.

B. Such grant is subject to all of the laws and ordinances of the City of Woodburn and the State of Oregon.

C. The scope of this grant allows the installation of facilities by Grantee in the City's rights-of-way as depicted in Exhibit "A". Such facilities shall be used by Grantee to provide telecommunications services consistent with the authority granted by the FCC. In the event either the location of Grantee's facilities or the nature of the services provided is proposed for modification, Grantee shall be required to obtain an additional or revised franchise from the City.

**Section 2. Construction Standards.**

A. The construction standards of the City of Woodburn, as well as any other applicable construction standards in existence at the time of this franchise grant or hereafter enacted, shall apply to all work performed by the Grantee in City rights-of-way.

B. The Grantee's facilities shall not interfere in any way with any of the City's communications or other public and city-permitted facilities, including other franchised facilities, either as installed or during operation. The Grantee will compensate the provider of power directly for the cost of power consumed in support of Grantee's facilities, and shall hold the City completely harmless from any power cost.

C. The Grantee shall locate below the surface of the ground all wiring and physical improvements within City rights-of-way, unless it is physically impossible to do so. Placement of any improvements above ground, or on poles shall only be with the prior review and approval of the City.

D. Where permission is granted by the City to locate Grantee's facilities upon poles, Grantee shall independently obtain prior written approval from the owner and/or operator of the poles on which its facilities shall be placed. Upon request, Grantee shall provide copies of such written approvals for City review.

E. Where permission is granted by the City to locate Grantee's facilities upon poles, Grantee shall undertake all wiring and physical improvements required by the owner of each pole to which its facilities are to be attached. In the case of City-owned poles or fixtures, such work shall be performed subject to the approval of the City Engineer or his designee.

**Section 3. Franchise Fee.** The franchise fee payable to the City shall be 7% (seven percent) of the Grantee's gross revenues earned within the corporate limits of the City. In the event no revenues are earned, but Grantee is actually occupying City rights-of-way, Grantee shall pay a minimum annual franchise fee of \$1,000. Franchise fees shall be payable quarterly, on or before April 30, July 31, October 31 and January 31, for the preceding calendar quarter. Such payment made by the Grantee will be accepted by the City of Woodburn from the Grantee, as also in payment of any license, privilege or occupation tax or fee for revenue or regulation, or any permit or inspection fees or similar charges for street openings, installations, construction or for any other purpose now or hereafter to be imposed by the City of Woodburn upon the Grantee during the term of this franchise. Payments made more than ten calendar days beyond the due date shall bear interest at the rate of 9% per annum.

**Section 4. Term.** The term of this franchise shall be five (5) years. This franchise shall be subject to one automatic renewal on the same terms and conditions for an additional period of five (5) years unless notice is given by either party 180 days in advance of the expiration of the franchise of its intention to terminate or renegotiate the franchise. This franchise shall be effective upon the date of Grantee's written acceptance of this grant.

**Section 5. Acceptance.** The grant of franchise herein is conditioned upon Grantee's acceptance of all terms and conditions hereof in writing in a form acceptable to the City.

*Adopted by the Council and Mayor June 11, 2001.*

## ORDINANCE NO. 2299

**AN ORDINANCE APPROVING AND CONSENTING TO THE TRANSFER AND ASSIGNMENT OF A CABLE TELEVISION FRANCHISE FROM NORTH WILLAMETTE TELECOM, INC. (DIRECT LINK) TO WILLAMETTE BROADBAND LLC, AND DECLARING AN EMERGENCY,**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1.** The City hereby approves and consents to the transfer and assignment of the Franchise from North Willamette Telecom, Inc. to Willamette Broadband, LLC contingent upon Willamette's satisfactory completion of the following conditions no later January 2, 2002.

(A) Complete the franchise renewal negotiations, represented in a mutually agreeable new franchise designed to meet current Woodburn regulatory requirements and community needs;

(B) Post a performance bond, to cover all franchise performance by Willamette, in an amount of \$300,000. Said bond shall be in a form acceptable to the City Attorney;

(C) Establish a security fund or letter of credit running to the City in the amount of \$25,000. Such security fund or letter of credit shall be in a form acceptable to the City Attorney, and shall be retained by the City for a period of five years, or until such time as the City Council deems, based upon Willamette's performance under a franchise, that such security is no longer necessary; and

(D) Agree in writing to remedy any historical violation or default under the Franchise, regardless of whether the Seller or Willamette is responsible for the violation or default.

If Willamette fails to complete any of the conditions (A) to (D) above by January 2, 2002, consent to the sale and transfer of the Franchise is denied. (Section 1 as amended by Ordinance No. 2306 dated November 26, 2001)

**Section 2.** Subject to condition (A) to (D) above being met by January 2, 2002, and from and after the closing of the sale of the Franchise and related assets to Willamette, Willamette shall become the operator of the Franchise and shall be bound by the lawful obligations and duties that arise on and after the closing with respect thereto and the Seller shall be released of such obligations and duties. (Section 2 as amended by Ordinance No. 2306 dated November 26, 2001)

**Section 3.** The assignment and transfer of the Franchise shall not alter the terms and conditions of the Franchise granted in Ordinance 2093; and Willamette shall file with the City Recorder a written unconditional assumption and acceptance of the Franchise.



**Section 4.** In addition to the document required by Section 3, Willamette shall file with the City Recorder a written assurance that, for the remainder of the effective period of Ordinance 2093:

(A) It shall maintain a system head end in the incorporated City Limits of Woodburn; and

(B) It shall maintain an office and studio located in the incorporated City limits during the term of the Franchise; and

(C) The City acknowledges receipt of a completed FCC Form 394 from Seller and Willamette.

**Section 6.** [Emergency clause.]

*Passed by the Council and approved by the Mayor August 30, 2001. Amended by Ordinance 2306 dated November 26, 2001.*

## ORDINANCE NO. 2324

AN ORDINANCE GRANTING WOODBURN AMBULANCE SERVICE, INC., A NON-EXCLUSIVE FRANCHISE TO OPERATE AN AMBULANCE SERVICE IN THE CITY OF WOODBURN; DEFINING TERMS AND CONDITIONS OF SAID FRANCHISE; REPEALING ORDINANCE 2158; DECLARING AN EMERGENCY AND SETTING AN EFFECTIVE DATE.

[Whereas clauses.]

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

**Section 1. Title.** This ordinance shall be known as the "Ambulance Service Franchise Ordinance".

**Section 2. Policy and Purpose.** The Council declares it to be in the public's interest of health, safety and welfare to provide for and regulate ambulance services within the City of Woodburn to:

- (1) Ensure effective and efficient emergency ambulance service to the citizens of Woodburn; and
- (2) Comply with the provisions of the Marion County Ambulance Service Area (ASA) Plan.

Pursuant to ORS 682.275, this ordinance shall not be interpreted to require less than is required of Grantee by the applicable Oregon Revised Statutes and administrative rules. Any inconsistency between the provisions of this ordinance and Oregon state law shall be governed by Oregon state law.

**Section 3. Definitions.** The words and phrases used in this ordinance shall have the meaning provided in ORS Chapter 682 unless specifically defined herein to have a different meaning. Other specific definitions include:

- (1) "ASA Plan" - The Marion County Ambulance Service Area Plan.
- (2) "City" - The City of Woodburn
- (3) "Franchise" - A privilege granted by the City pursuant to this ordinance.
- (4) "Grantee" - The person granted a franchise pursuant to this ordinance.

**Section 4. Franchise Granted.** The City hereby grants unto Woodburn Ambulance Service, Inc. the franchise, right and privilege, subject to such modifications as are hereinafter set forth, to operate an ambulance service within the corporate limits of the City of Woodburn, as such limits now exist or may hereafter be expanded.

For the purpose of the franchise, Grantee shall have the right to use the public streets, alleys, public ways and places of the City to provide emergency transportation of persons suffering from illness, injury or disability. This Franchise is not exclusive, and the City reserves the right to grant a similar use of public streets, alleys, public ways and places to any other person at any time during the period of this Franchise, provided said person complies with the regulations of the ASA Plan and with Oregon state law.

**Section 5. Franchise Term.** The rights, privilege and Franchise herein granted shall be valid for a period of ten (10) years following the effective date, or until expiration of any franchise or designation of service area granted pursuant to the ASA Plan, whichever occurs first. If the ten year period described herein occurs first, the term of this franchise may be extended, by ordinance, to a subsequent date coinciding with the expiration of any franchise granted pursuant to the ASA Plan, provided that a finding is made by the City that Grantee has fully complied with the terms and provisions of this Franchise and remains in good standing in respect to any such franchise granted pursuant to the ASA Plan.

**Section 6. Rates and Charges.** Grantee shall furnish ambulance service within the corporate limits of the City of Woodburn as requested and required in a prompt, efficient and effective manner; and in accordance with rates and charges made to persons receiving ambulance service as approved by the City Council by separate resolution following public notice and hearing. In determining the appropriate rates to be charged by Grantee, the City Council shall consider, but not be limited to:

- (1) The current and projected cost of providing such service ;
- (2) The impacts of operating and capital needs, regulatory compliance, and technological change;
- (3) The investment and rate of return required of, or earned by, the Grantee;
- (4) The rates charged in other cities for similar service;
- (5) The public interest in assuring reasonable rates to enable the Grantee to provide effective and efficient services.

**Section 7. Compliance with Laws, Rules and Regulations.** Grantee shall at all times comply with all applicable laws, rules and regulations of the United States of America, the State of Oregon, including all agencies and subdivisions thereof, and the City of Woodburn, having jurisdiction over the operation of ambulance services.

**Section 8. Performance Bond**

- (1) Upon the effective date of this Franchise, Grantee shall furnish proof of the posting of a performance bond running to City, with good and sufficient surety approved by City, in the penal sum of \$50,000, conditioned that Grantee shall well and truly observe, fulfill, and perform each term and condition of this Franchise. Grantee

shall pay all premiums charged for the bond, and shall keep the bond in full force and effect at all times throughout the term of this Franchise. The bond shall contain a provision that it shall not be terminated or otherwise allowed to expire without 30 days prior written notice first being given to City. The bond shall be reviewed and approved as to form by the City Attorney.

(2) During the term of this Franchise, Grantee shall file with City a duplicate copy of the bond along with written evidence of payment of the required premiums. However, in no event shall City exercise its rights against the performance bond if a bona fide, good faith dispute exists between City and Grantee.

**Section 9. Revision of Rates and Fees.** The rates provided in Section 6 hereof, and the administrative fee hereinafter provided in Section 10, may each be changed and revised, either upward or downward, after public notice and hearing before the City Council. Grantee is permitted to request a rate review and possible increases in rates annually, but the decision to grant or deny any changes in rates shall be made by the City Council only after all other provisions of this ordinance pertaining to rates and charges have been met.

**Section 10. Administrative Fee.** For the privilege of the Franchise herein granted, and as compensation for the City's ongoing costs of monitoring the Franchisee's activities, processing rate changes and investigating citizen complaints or inquiries, the Grantee shall pay to the City, through its Finance Director, a quarterly fee of \$3,146, due and payable no later than thirty (30) days following the end of each calendar quarter. The first such payment, for the fourth calendar quarter of 2002, shall be due and payable no later than January 30, 2003, with subsequent payments under this section due and payable no later than thirty (30) days following the end of each succeeding calendar quarter.

This rate will be in effect until July 1, 2003. The rate for each succeeding fiscal year (July 1 through June 30) will be based on the Franchisee's gross revenue derived from calls for service within the City of Woodburn's city limits for the calendar year ended the previous December 31. The quarterly fee will be calculated as one percent (1.0%) of the Franchisee's gross revenue earned in Woodburn divided by four (4).

To facilitate the City's ability to properly monitor this Franchise, Grantee shall furnish to the City's Finance Director, no later than May 31st of each year, a detailed annual statement, signed by a Certified Public Accountant, outlining the nature of Grantee's revenues and expenditures during the preceding calendar year. If requested in writing by the City, the Grantee shall, upon provision of reasonable advance notice, permit the City's Finance Director, or designee, to examine the books of the Grantee.

**Section 11. Ambulance and Equipment Required.** All patient transporting vehicles in the City of Woodburn shall conform to the State of Oregon requirements of ORS Chapter 682 and be licensed for an Advanced Life Support (ALS) unit as defined by The Oregon Administrative Rules. All ALS and BLS vehicles shall maintain the minimum equipment prescribed by state law, and as may be further required under the

ASA Plan. Grantee shall provide a minimum of two (2) operable and properly equipped ALS Units at all times.

**Section 12. Emergency Radio Communications.** Grantee shall equip all vehicles and comply with all emergency radio communications requirements of the ASA Plan or of the Intergovernmental Agreement creating the NORCOM emergency communications agency.

**Section 13. Levels of Care.** All ambulances answering 9-1-1 emergency calls originating in the City of Woodburn shall be ALS Level, with minimum staffing of one EMT-Paramedic and one EMT-Basic. Staffing shall further conform to the requirements of state law.

**Section 14. Insurance.** Grantee shall maintain in full force and effect at its own cost and expense, during the term of the Franchise, Comprehensive General Liability Insurance in the amount of \$1,000,000 combined with a single limit for bodily injury, and property damage. Grantee shall provide to the Finance Director a Certificate of Insurance designating the City of Woodburn as an additional insured. Such insurance shall be noncancellable except upon thirty (30) days prior written notice to the City.

**Section 15. Business Hours.** Grantee shall make available said ambulance services within the City 24 hours per day, seven days per week; and shall maintain a business office with reasonable office hours, open to the public at least five days per week, excluding holidays, within the corporate limits of the City of Woodburn.

**Section 16. Record of Transport Calls.** Grantee shall keep for five years a written record of all transport calls received or made, setting forth the date, time, destination, nature of call, name and address of the patient so far as can be ascertained, the hospital or place to which the patient was taken, the name of the ambulance driver, and the names of all ambulance attendants for that particular call, along with the amounts of charges billed or collected from any such transport or service.

**Section 17. Alternative Ambulance Service.** The Woodburn Fire District, NORCOM, or any other public safety officer may call an ambulance service other than the Grantee if Grantee's ambulances are otherwise in use and unavailable.

**Section 18. Transfer of Franchise.** Grantee shall not sell, assign, dispose of or transfer in any manner whatsoever any interest in this Franchise, nor the controlling company of Grantee, without prior approval by the City expressed by resolution of its City Council.

**Section 19. Indemnity and Hold Harmless.** Grantee shall defend, indemnify, and hold the City of Woodburn, its officers, agents and employees, harmless against all liability, loss or expenses, including attorney's fees, and against all claims, actions or judgments based upon or arising out of damage or injury (including death) to persons or property caused by any act or omission or an act sustained in connection with the performance of Grantee under its Franchise.

**Section 20. Interruption of Service.** Notwithstanding any requirements contained in the ASA Plan, in the event the City finds that failure or threatened failure of ambulance service would adversely impact the health, safety or welfare of the residents of this city, the City Council may, after a minimum of 24 hours notice to the Grantee, hold a public hearing and authorize another Franchisee or other person to provide ambulance service, whether it be on an interim emergency or longer term basis. As a condition to this Franchise, the Grantee agrees that any real property, facilities or equipment, which is the property of Grantee, may be used by the City to provide ambulance services during said situation, as determined by the findings of the City Council at the above-mentioned public hearing. The City shall return any such property of the Grantee upon abatement of the situation which prompted City use of such property.

In the event the City's power and authority under this section is exercised, the usual charges for service shall prevail and Grantee shall be entitled to collect for such usual services, but shall reimburse the provider of such ambulance services for its actual costs, as determined by the City. In no event shall the City collect more in reimbursement than could have been charged by Grantee for the provision of such services. In the event that the City and Grantee are unable to agree to reasonable and proper compensation for reimbursement for such services to the City in such situation, then each party shall name an arbitrator within ten (10) days of notice thereof, and such arbitrators shall, within five (5) days thereafter, name a third arbitrator, and the award or decision of such arbitrators as to the aforesaid matters shall be deemed conclusive upon the parties hereto as to any such matters in dispute. In the event that either party hereto, or the arbitrators chosen, shall fail or neglect to comply with the terms of this arbitration agreement, then the same shall be carried into effect in the manner and as provided by ORS 36.300 through 36.365.

**Section 21. Termination of Franchise.** This Franchise may be canceled or revoked by the City in the event that Grantee shall fail to abide by the terms, conditions, and obligations set forth and imposed upon it herein, but such cancellation or revocation shall not be made until after thirty (30) days' written notice is given to Grantee, and Grantee shall be afforded a hearing, if such it desires, before the City Council before revocation is made, provided such hearing is requested before the expiration of the 30 days. Grantee shall also have the privilege of terminating this Franchise in case the City of Woodburn shall not abide by its terms, on the same terms and conditions described above, upon satisfactory demonstration to the City Council that the City has not so abided.

**Section 22. Remedies Not Exclusive.** All remedies under this ordinance, including termination of the Franchise, are cumulative, and recovery or enforcement of one is not a bar to the recovery or enforcement of any other remedy. Remedies contained in this ordinance, including termination of the Franchise, are not exclusive and the City reserves the right to enforce penal provision of any ordinance and also use any remedy available at law or in equity. Failure to enforce any provision of this ordinance shall not be construed as a waiver or a breach of any other term, condition or obligation of this ordinance.

**Section 23. Evaluation of Service.** Grantee shall meet with the City Administrator and other City officials and staff annually or semi-annually, as requested by the City Administrator, to evaluate the service rendered under this Franchise or review any concern as may be existing with the ambulance service.

**Section 24. Severability.** The provisions of this ordinance are severable. If a portion of this ordinance is for any reason held by a court of competent jurisdiction to be invalid, such decision shall not affect the validity of the remaining portions of the ordinance.

**Section 25. Repeal of Existing Ordinances.** Ordinance 2158 is hereby repealed on the effective date of this ordinance.

**Section 26. Acceptance.** Grantee shall, within thirty (30) days from the date this ordinance takes effect, file with the City its written unconditional acceptance of this franchise in the form attached hereto as Exhibit "A", and if Grantee fails to do so, this ordinance shall be void.

**Section 27.** [Emergency clause and effective date.]

***Passed by the Council September 23, 2002 and approved by the Mayor  
September 24, 2002.***

**ORDINANCE NO: 2376****AN ORDINANCE GRANTING A NON-EXCLUSIVE GAS UTILITY FRANCHISE TO NORTHWEST NATURAL GAS COMPANY, AND FIXING TERMS, CONDITIONS AND COMPENSATION OF SUCH FRANCHISE.****THE CITY OF WOODBURN ORDAINS AS FOLLOWS:****Section 1: Definitions and Explanations.**

- (1) As used in this ordinance.
- (a) "City" means the City of Woodburn and the areas within its boundaries, including its boundaries as extended in the future.
- (b) "Council" means the legislative body of the City.
- (c) "Grantee" means the corporation referred to in Section 2 of this ordinance.
- (d) "Gas" means natural methane-based gas.
- (e) "Gas facilities" means Grantee's gas transmission and distribution facilities, including pipes, pipe lines, mains, laterals, conduits, feeders, regulators, reducing and regulating stations, meters, fixtures, connections and all attachments, appurtenances, and all accessories necessary and incidental thereto located within the City Limits, whether the facilities are located above or below ground.
- (f) "Person" includes an individual, corporation, association, firm, partnership and joint stock company.
- (g) "Public place" means any City-owned property within the City that is open to the public that is not a right-of-way, including public squares and parks.
- (h) "Right-of-way" means the space in, upon, above, or under the public streets, roads, highways, lanes, courts, ways, alleys, boulevards, sidewalks, bicycle lanes, bridges, and places used or intended to be used by the general public for travel as the same now or may hereafter exist, that the City has the right to allow Grantee to use.

- (2) As used in this ordinance, the singular number may include the plural and the plural number may include the singular.

**Section 2: Rights Granted.**

- (1) Subject to the conditions and reservations contained in this ordinance, the City hereby grants to NORTHWEST NATURAL GAS COMPANY, a corporation, the right, privilege and franchise to:



(a) Construct, maintain and operate a natural gas utility system within the City;

(b) Install, maintain and operate gas facilities on, in and under the rights-of-way of the City, residents, agencies and businesses in the City and to territory beyond the limits of the City; and

(c) Transmit, distribute and sell gas within the City and to territory beyond the limits of the City.

(2) The rights granted herein shall not confer on Grantee any right, title or interest in any public way beyond that expressly conferred by the provisions of this Section 2, nor shall it confer any right or privilege to use or occupy any other property of the City or any other entity.

**Section 3: Use of Rights-of-Way by Grantee.**

(1) Before the Grantee may use or occupy any right-of-way, the Grantee shall first obtain permission from the City to do so and shall comply with any special conditions the City may impose on such use or occupation.

(2) The compensation paid by Grantee for this franchise includes all compensation for the use of rights-of-way located within the City as authorized. The City may charge additional compensation for the use of any public place.

**Section 4. Duration.** This franchise is granted for a period of 10 years from and after the effective date of this ordinance.

**Section 5. Franchise Not Exclusive.** This franchise is not exclusive, and shall not be construed as a limitation on the City in:

(1) Granting rights, privileges and authority to other persons similar to or different from those granted by this ordinance.

(2) Constructing, installing, maintaining or operating any City-owned public utility.

**Section 6. Public Works and Improvements Not Affected by Franchise.** The City reserves the right to:

(1) Construct, install, maintain and operate any public improvement, work or facility in, on or over the rights-of-way.

(2) Do any work that the City may find desirable on, over or under any right-of-way.

(3) Vacate, alter or close any street. Whenever the City shall vacate any Right-of-way or public place for the convenience or benefit of any person or governmental agency or instrumentality, Grantee's rights under this Franchise shall be preserved as to any of its Gas facilities then existing in the Right-of-way or public place if reasonably practicable. To the extent Grantee's rights in the Right-of-way cannot be preserved in any street vacation, City shall where reasonably practicable provide an alternative Right-of-way for the location of Grantee's Gas facilities. If Grantee's Gas facilities must be relocated from a vacated Right-of-way, the petitioners of such vacation shall bear the costs of relocating the Gas facilities. Upon receipt of a notice of a petition for vacation, Grantee shall as soon as practicable investigate and advise the City and petitioners in writing whether the Gas facilities must be relocated, the estimated costs of relocation and the time needed for this relocation.

(4) Whenever the City shall perform, cause or permit any work in any present or future right-of-way of the City on its behalf, where such work may disturb Grantee's gas facilities, the City shall, or require its permittee to, notify Grantee in writing, sufficiently in advance of such contemplated work to enable Grantee to take such measures, as Grantee may deem necessary to protect such facilities, at its own expense.

**Section 7: Continuous Service.** Grantee shall maintain and operate an adequate system for the distribution of gas in the City. Grantee shall use due diligence to maintain continuous and uninterrupted 24-hour a day service which shall at all times conform at least to the standards common in the business and to the standards adopted by state authorities and to standards of the City which are not in conflict with those adopted by the state authorities. Under no circumstances shall Grantee be liable for an interruption or failure of service caused by an act of God, unavoidable accident or other circumstances beyond the control of Grantee through no fault of its own.

**Section 8: Safety Standards and Work Specifications.**

(1) The facilities of Grantee shall at all times be maintained in a safe, substantial and workmanlike manner.

(2) For the purpose of carrying out the provisions of this section, the City may provide such specifications relating thereto as may be necessary or convenient for public safety or the orderly development of the City. The City may amend and add to such specifications from time to time.

**Section 9: Control of Construction.**

(1) Before commencing any construction, extension or relocation of facilities in a City right-of-way, Grantee shall file with the City drawings, in such form as may be acceptable to the City Engineer, showing the location of existing facilities and facilities to be constructed, maintained, or relocated and shall obtain from the City approval of the location and plans prior to commencement of the work.

(2) All work done within a City right-of-way shall be done in the location approved by the City Engineer and in accordance with plans and specifications approved by the City Engineer. The City Engineer's approval of the plans and specifications may include conditions and the conditions shall be binding on Grantee. Such construction work shall be done in a safe manner subject to the approval of the City Engineer and in accordance with requirements of applicable Federal and State laws and City ordinances. All work done shall be subject to the rejection or correction requirements of the City Engineer and subject to the City Engineer's approval.

**Section 10: Street Excavations and Restorations.**

(1) Subject to the provisions of this ordinance, the Grantee or its subcontractor may make necessary excavations for the purpose of constructing, installing, maintaining and operating its gas facilities. In all circumstances pertinent to this agreement, any action by Grantee's subcontractors shall be the responsibility of Grantee. Any subcontractor of Grantee shall be bound to the requirements of this agreement.

(2) Except in emergencies, and in the performance of routine service connections and ordinary maintenance, on private property, prior to making an excavation in the traveled portion of any right-of-way, and, when required by the City, in any untraveled portion of any right-of-way, Grantee shall obtain from the City approval of the proposed excavation and of its location.

(3) Grantee shall give notice to the City by telephone, electronic data transmittal or other appropriate means prior to the commencement of service or maintenance work and as soon as is practicable after the commencement of work performed under emergency conditions.

(4) When Grantee does any work in the unimproved portion of a right-of-way, Grantee or its subcontractor, shall promptly restore the affected portion of right-of-way to the same condition in which it was prior to the excavation. When Grantee does any work in an improved portion of a right-of-way, Grantee or its subcontractor shall promptly restore the affected portion of the right-of-way in compliance with the conditions in any permit issued by the City or any specifications, requirements and regulations of the City in effect at the time of the work. All work done shall be subject to the rejection and correction requirements of the City Engineer's approval. If Grantee or its subcontractor fails to restore promptly the affected portion of a right-of-way in accordance with City Standard Construction specifications in effect at the time of the work, the City may make the restoration, and the cost thereof shall be paid by Grantee.

**Section 11: Location and Relocation of Facilities.**

(1) All gas facilities of Grantee shall be placed so that they do not interfere unreasonably with the use of the right-of way by the City and the public and in accordance with any specifications adopted by the City governing the location of facilities.

(2) The City may require the removal or relocation, temporarily or permanently, of facilities maintained by Grantee in the streets of the City. Grantee shall remove and relocate such facilities within 120 days after receiving notice so to do from the City. The cost of such removal or relocation shall be paid by Grantee. In the event that the removal, relocation, change or alteration is needed to accommodate private development or other private use of the right-of-way, the developer or other private party requiring the action shall be responsible for the cost of removal, relocation, change or alteration. Construction of public improvements by a private party within the right-of-way as a condition of City approval shall be considered installation of public improvements of the City if the improvement is not needed to provide service to the private party. In the event of a dispute as to whether the removal, relocation, change or alteration is a public improvement or accommodates private development, the dispute shall be referred to the City Administrator, whose decision shall be final and binding.

## **Section 12: Compensation.**

(1) As compensation for the franchise granted by this ordinance, the grantee shall pay to the City an amount equal to three percent (3%) of the gross revenue collected by the Grantee from its customers for gas consumed within the City. "Gross revenue" as used in this ordinance shall be deemed to include any revenue earned within the City from the sale of natural gas after deducting from the total billings of the Grantee the total net writeoff of uncollectible accounts. Gross revenues shall include revenues from the use, rental or lease of operating facilities of the utility other than residential-type space and water heating equipment. Gross revenues shall not include proceeds from the sale of bonds, mortgage or other evidence of indebtedness, securities or stocks, revenues derived from the sale or transportation of gas supplied under an interruptible tariff schedule, sales at wholesale to a public utility when the utility purchasing the service is not the ultimate consumer, or revenue paid directly by the United States of America or any of its agencies.

(2) The City shall retain the right, as permitted by Oregon Law, to charge a privilege tax in addition to the franchise fee set forth herein based on the gross revenues of the company, payable on the same terms and conditions as the franchise fee itself.

(3) The compensation required by this section shall be due for each calendar year, or fraction thereof, within thirty (30) days after the close of such calendar year, or fraction thereof. Within thirty (30) days after the termination of this franchise, compensation shall be paid for the period elapsing since the close of the last calendar year for which compensation has been paid.

(4) Grantee shall furnish to the City Finance Director with each payment of compensation required by this section a written statement, showing the amount of gross revenue of the Grantee within the City for the period covered by the payment computed on the basis set out in subsection (1) of this section. If Grantee fails to pay the entire amount of compensation due the City through error or otherwise, the

difference due to City shall be paid by the Grantee within fifteen (15) days from discovery of the error or determination of the correct amount. Any overpayment to the City through error or otherwise, shall be offset against the next payment due from Grantee.

(5) Acceptance by the City of any payment due under this section shall not be deemed to be a waiver by the City of any breach of this franchise occurring prior to the acceptance, nor shall the acceptance by the City of any such payments preclude the City from later establishing that a larger amount was actually due, or from collecting any balance due to the City.

**Section 13: Books of Account and Reports.** On an annual basis, upon thirty (30) days prior written notice, the City or its agent shall have the right to conduct an audit or review of Grantee's records reasonably related to the administration or enforcement of this ordinance. If an audit or review of the records determines that franchise fees have been underpaid, Grantee shall reimburse the City for the total cost of the audit or review within thirty (30) days of City's written demand for same. All amounts underpaid shall accrue interest at the statutory rate from the effective date of the underpayment.

**Section 14. Classification of Fees.** The City Council determines that any fees imposed by this franchise are not taxes subject to the property tax limitations of Article XI, Section 11(b) of the Oregon Constitution.

**Section 15: As-Built Drawings.** Subject to the confidentiality limitations of this section, Grantee shall provide City with available maps of the location of its facilities and operational data requested by the City. The Grantee shall also provide as-built plans for those portions of the system that are added to or modified during the year. These records are submitted in confidence, and the City will keep those records in confidence and not allow others to view or copy them. The City agrees to keep the documents confidential and to take the position that they are exempt from public disclosure. The City shall limit access to the as-built drawings to City employees or City contractors with a need to know where the Grantee's facilities are located and shall review the as-built drawings only as necessary to plan City projects, coordinate the use of the rights of way, and to protect the public health and safety.

**Section 16. Indemnification.** Grantee shall indemnify and save harmless the City and its officers, agents and employees from any and all loss, cost and expense arising from damage to property and/or injury to, or death of, persons due to any wrongful or negligent act or omission of Grantee, its agents or employees in exercising the rights, privileges and franchise hereby granted.

**Section 17: Sale or Assignment of Franchise.** Grantee shall not during the term of this Franchise sell, assign, transfer or convey this franchise without first obtaining the consent of the City Council, by ordinance, which consent shall not be unreasonably withheld. All of the provisions of this ordinance shall inure to and bind the successors and assigns of the Grantee. Whenever Northwest Natural shall be mentioned in this ordinance, it shall be understood to include such successors or assigns in interest of Northwest Natural as shall have been so consented to by the City Council.

**Section 18: Termination of Franchise for Cause.** The City may terminate this franchise as provided in this Section, subject to Grantee's right to a court review of the reasonableness of such action, upon the willful failure of the Grantee to perform promptly and completely each and every material term, condition or obligation imposed upon it under or pursuant to this ordinance. The City shall provide the Grantee written notice of any such failure and the Grantee shall have sixty (60) days from receipt of notice to cure such failure, or if such failure cannot reasonably be cured within sixty (60) days, to commence and diligently pursue curing such failure.

**Section 19: Renegotiation of the Franchise.** If the State of Oregon or the PUC amends or adopts a state statute or administrative rule that would affect a term, condition, right or obligation under this agreement, either party may reopen the franchise agreement at any time with regard to such term, conditions, right or obligation in order to address the change required or allowed by the new or amended state statute or administrative rule.

**Section 20: Remedies Not Exclusive, When Requirement Waived.** All remedies and penalties under this ordinance, including termination of the franchise, are cumulative, and the recovery or enforcement of one is not a bar to the recovery or enforcement of any other such remedy or penalty. The remedies and penalties contained in this ordinance, including termination of the franchise, are not exclusive and the City reserves the right to enforce the penal provisions of any ordinance or resolution and to avail itself of any and all remedies available at law or in equity. Failure to enforce shall not be construed as a waiver of a breach of any term, condition or obligation imposed upon the Grantee by or pursuant to this ordinance. A specific waiver of a particular breach of any term, condition or obligation imposed upon Grantee by or pursuant to this ordinance shall not be a waiver of any other or subsequent or future breach of the same or of any other term, condition or obligation, or a waiver of the term, condition or obligation itself.

**Section 21: Acceptance.** The Grantee shall, within thirty (30) days from the date this ordinance takes effect, file with the City its written unconditional acceptance of this franchise, and if the Grantee fails so to do, this ordinance shall be void.

**Section 22: Prior Ordinance Repealed.** Ordinance no. 2133 is hereby repealed.

**Section 23.** [Emergency clause and effective date.]

***Passed by the Council November 8, 2004 and approved by the Mayor  
November 10, 2004.***

## ORDINANCE NO. 2460

AN ORDINANCE REGULATING SOLID WASTE MANAGEMENT INCLUDING, WITHOUT LIMITATION, GRANTING AN EXCLUSIVE SOLID WASTE FRANCHISE TO UNITED DISPOSAL SERVICE, INC., AN OREGON CORPORATION, dba ALLIED WASTE SERVICES OF MARION COUNTY – WOODBURN”; ESTABLISHING SERVICE STANDARDS AND ESTABLISHING PUBLIC RESPONSIBILITY; REPEALING ORDINANCE 1641; PRESCRIBING PENALTIES; AND STATING AN EFFECTIVE DATE.

## THE CITY OF WOODBURN ORDAINS AS FOLLOWS:

## Section 1 - Introduction

**1.1 Short Title.** This ordinance shall be known as the “Solid Waste Management Ordinance,” and may be cited herein as “this Ordinance.”

**1.2 Purpose and Policy.** In order to protect the health, safety and welfare of the people of the City of Woodburn, it is the public policy of the City of Woodburn to regulate and to provide a solid waste management program.

**1.3 Solid Waste Management Goals.**

**1.3.1** Ensure the safe and sanitary accumulation, storage, collection, transportation and disposal or resource recovery of solid wastes. Ensure proper handling of household hazardous waste, ensure that the community has an ongoing resource recovery and disposal service, and ensure that waste shed recycling goals are met.

**1.3.2** Promote technologically and economically feasible resource recovery including source separation, recycling and reuse, and separation by and through the collector. Research, develop and promote waste reduction strategies.

**1.3.3** Ensure efficient, economical and comprehensive solid waste service. Maximize collection services to reduce the adverse environmental impacts of individual collection and disposal efforts. Minimize duplication of service or routes to conserve energy and material resources, to reduce air pollution and truck traffic, and to increase efficiency, thereby minimizing consumer cost, street wear, and public inconvenience.

**1.3.4** Protect and enhance the public health and the environment.

**1.3.5** Protect against improper and dangerous handling of hazardous and infectious wastes.

**1.3.6** Ensure service rates and charges that are just and reasonable and adequate to provide necessary public services.

**1.3.7** Provide for charges to the users of solid waste services that are reasonable, equitable, and adequate to provide necessary service to the public, justify investment in solid waste management systems, and provide for equipment and systems modernization to meet environmental and community service requirements.

**1.3.8** Prohibit discrimination on the basis of race, color, creed, religion, sex, age, and national origin, source of income, political affiliation, disability, sexual orientation, or marital status.

**1.3.9** Work in cooperation with the City of Woodburn, Marion County, and local industries to reduce the quantity of waste produced, increase recycling, generate efficiencies, and conserve resources.

**1.3.10** Demonstrate a responsive, customer-service oriented business philosophy.

**1.4 Definitions.** For the purpose of the ordinance, the following terms shall have the following meaning:

**"Bin"** means receptacle provided by Franchisee, used by customers for the containment and disposal of recyclable material.

**"Can"** means receptacle owned by a customer, used for the containment and disposal of solid waste. The customer's use of a can requires manual collection.

**"Cart"** means receptacle provided by Franchisee, used by a customer for the containment and disposal of solid waste or recyclable material. The customer's use of a cart requires automated collection service.

**"City"** means the City of Woodburn, Oregon, and the area within its boundaries including its boundaries as extended in the future and all property owned by the City, outside City limits.

**"City Administrator"** means the City Administrator or his/her designee.

**"City Council"** means the legislative body of the City.

**"Compact and Compaction"** means the process of, or to engage in the shredding of material, or the manual or mechanical compression of material.

**"Compensation"** means consideration of any kind paid for solid waste management services, including but not limited to, the direct payment of money, including the proceeds from resource recovery or the provision of solid waste services to customers.

**"Container"** means a receptacle one cubic yard or larger in size, used to store



solid waste or wastes or recyclable material, but not a drop box or compactor.

**"Dispose or Disposal"** means the accumulation, storage, discarding, collection, removal, transportation, recycling or resource recovery of solid waste.

**"Drop Box"** means a single receptacle designed for storage and collection of large volumes of solid waste or wastes or recyclable materials, which is usually ten cubic yards or larger in size, and provides for transportation of large volumes of solid waste or recyclable materials and is transported to a disposal or processing site for transfer, landfilling, recycling, materials recovery or utilization and then emptied and returned to either its original location or to some other location.

**"Excluded Waste"** means hazardous waste; household hazardous waste; infectious waste; toxic substances, wastes or pollutants; contaminants; pollutants; or radioactive wastes.

**"Franchisee"** means **UNITED DISPOSAL SERVICE, INC., AN OREGON CORPORATION, dba ALLIED WASTE SERVICES OF MARION COUNTY – WOODBURN** granted a franchise pursuant to Section 2 of this Ordinance or a subsequent ordinance.

**"Generator"** means the person who produces solid waste or recyclable material to be placed, or that is placed for collection and disposal. As used in this Ordinance, "generator" does not include any person who manages an intermediate function resulting in the alteration or compaction of the solid waste or recyclable material after it has been produced by the generator and placed for collection.

**"Hazardous Waste"** means any hazardous wastes as defined by ORS 466.005.

**"Holidays"** means legal holidays observed by the City of Woodburn.

**"Household Hazardous Waste"** means any discarded or unwanted chemical, material, substance or product that is or may be hazardous or toxic to the public or the environment, is commonly used around households and is generated by the household.

**"Infectious Waste"** means biological waste, cultures and stocks, pathological waste, and sharps, or as infectious waste is defined in ORS 459.386.

**Mixed Recycling"** means the process where two or more types of recyclable materials are collected together (i.e., not separated) in a combination allowed by the City Administrator, and as approved by the Oregon Department of Environmental Quality.

**"Persons"** means any individual, partnership, business, association, corporation,

cooperative, trust, firm, estate, joint venture or other private entity or any public agency.

**"Pilot Program"** means a program which allows Franchisee to offer services on a trial basis for six months or less and to determine rates for such services outside the approved rate structure. City Council approval is required prior to implementation of a pilot program.

**"Placed for Collection"** means to put solid waste, recyclable material or yard debris out for collection by Franchisee, as provided by this Ordinance.

**"Public Place"** means any City-owned park, place, facility or grounds within the City that is open to the public, but does not include a street or bridge.

**"Public Rights-of-Way"** means, without limitation, streets, roads, highways, bridges, alleys, sidewalks, trails, paths, park strips and all other public ways or areas, including subsurface and air space over these areas.

**"Putrescible Material"** means organic materials that can decompose, which may create foul-smelling, offensive odors or products.

**"Rate"** means the amount approved by the City Council as a charge for service rendered and charged by Franchisee, including the franchise fee, to users of the service.

**"Receptacle"** means cans, carts, bins, containers, drop boxes, or other vessel used for the disposal of solid waste, recyclable material or yard waste that has been approved by the City Administrator and into which solid waste, recyclable material or yard debris may be placed for collection.

**"Recyclable Material"** means any material or group of materials that can be collected and sold for recycling at a net cost equal to or less than the cost of collection and disposal of the same material and excludes excluded waste.

**"Recycling"** means any process by which solid waste is transformed into new or different products in such a manner that the original products may lose their original identity. As used in this Ordinance, recycling includes the collection, transportation and storage of solid waste, done in order to place the solid waste in the stream of commerce for recycling; or for resource recovery.

**"Resource Recovery"** means the process of obtaining useful material or energy resources from solid waste, including reuse, recycling, and other material recovery or energy recovery of or from solid wastes.

**"Service"** means the collection, transportation, storage, transfer, or disposal of or resource recovery from solid waste by Franchisee. It also includes, without limitation, collection or source separated materials for compensation. "Service"

includes the providing of "Special Service" as defined below.

**"Solid waste"** means all useless or discarded putrescible and non-putrescible materials, including but not limited to garbage, rubbish, refuse, ashes, paper, cardboard, sewage sludge, septic tank and cesspool pumpings, or other sludge, useless or discarded commercial, industrial, demolition, and construction materials, discarded or abandoned vehicles or parts thereof, discarded home and industrial appliances, manure, vegetable or animal solid and semi-solid wastes, dead animals and infectious waste as defined in ORS 459.386. Solid waste does not include excluded waste.

**"Solid Waste Management"** means the business of collection, transportation, storage, treatment, utilization, processing, disposal, recycling and resource recovery of solid waste.

**"Source Separation"** means the separation of waste materials by the generator in preparation for recovery by recycling or reuse.

**"Special Service"** means collection of bulky waste, including furniture, appliances and large quantities of waste.

**"Total Source Separation"** means the complete separation by the source generator or producer of the waste by type or kind of waste from all other types or kinds of waste.

**"Train System"** means a group of small receptacles (typically 1-2 cubic yard capacity) placed in various locations around a customer's property, by the customer and once full, either linked together or placed upon a trailer for transport and disposal to a larger receptacle or compactor on the premises.

**"Waste"** means any material that is no longer wanted by or is no longer usable by the generator, producer or source of the material, which material is to be disposed of or to be resource-recovered by another person. Even though materials which would otherwise come within the definition of "waste" may from time to time have value and thus be resource-recovered does not remove them from this definition. Source-separated wastes are "wastes" within this definition.

**"Yard Debris"** means grass clippings, leaves, tree and shrub prunings of no greater than four inches in diameter, or similar yard and garden vegetation. Yard Debris does not include dirt, sod, stumps, logs or tree/shrub prunings larger than four inches in diameter.

## **Section 2 - Grant of Authority and General Provisions**

**2.1 Franchise.** Subject to the conditions and reservations contained in this ordinance, the City Council hereby grants to **UNITED DISPOSAL SERVICE, INC. , AN OREGON CORPORATION, dba ALLIED WASTE SERVICES OF MARION COUNTY -**

**WOODBURN",** the exclusive right, privilege, and franchise to collect, dispose, sell and transport solid waste and recyclable material generated as of the effective date of this ordinance within the corporate limits of the City of Woodburn and in any area that may thereafter be annexed to the City.

**2.2 Exceptions.** Unless accepted by subsections below, or granted an exclusive franchise pursuant to this Ordinance, no person shall solicit customers for service, or advertise the providing of service, or provide service in the City. Nothing in this ordinance requires a franchise for the following:

**2.2.1** The collection, transportation and reuse of repairable or cleanable discards by a private charitable organization regularly engaged in such activity.

**2.2.2** The collection, transportation, and reuse or recycling of totally source-separated materials or operation of a collection center for totally source-separated materials by a religious, charitable, benevolent or fraternal organization, provided the organization is using the activity for fund raising. Organizations engaged in these activities shall make periodic reports in a form as the City Administrator may reasonably require.

**2.2.3** The collection, transportation or redemption of returnable beverage containers under ORS Chapter 459A and that portion commonly known as the "Bottle Bill."

**2.2.4** The generator or producer who transports and disposes of waste created as an incidental part of regularly carrying on the business of auto wrecking to the extent licensed by the state of Oregon; janitorial service; septic tank pumping, sludge collection or disposal service; or gardening or landscape maintenance. "Janitorial service" does not include primarily collecting wastes generated by a property owner or occupant.

**2.2.5** The transportation of solid waste by an individual, produced by such individual or the individual's household, to a disposal site or resource recovery site. In the case of non-owner-occupied property, the waste is produced and owned by the tenant and not by the landlord, property owner or agent.

**2.2.6** A contractor registered under ORS Chapter 701 for hauling waste created in connection with the demolition, construction, or remodeling of a building structure or in connection with land clearing and development. Such waste shall be generated by the contractor in connection with the contractor's construction site and hauled in equipment owned by the contractor and operated by the contractor's employees.

**2.2.7** Government employees providing solid waste and recycling collection services to City operations and facilities.

**2.3 Term.**

(a) This franchise ordinance and the rights and privileges granted herein shall take effect upon written acceptance by Franchisee and remain in effect for a term of seven (7) years.

(b) Upon an affirmative finding based on its annual review of the material submitted pursuant to Sections 3.16 and 3.17, et. seq. of this agreement, at the end of the franchise term, the Council may add an additional year to the term of the franchise.

(c) The City Council may choose to not extend a franchise after seven (7) years under this section for any reason. If the City Council chooses not to extend a franchise, at least sixty days before the date that the franchise would otherwise expire, the City Council shall provide Franchisee with written notice of the City Council's intent not to extend the franchise. Franchisee shall have thirty days from the date of the notice to request a public hearing. If, following the public hearing, the City Council reaffirms the decision not to extend the franchise term, the franchise shall expire at the end of its existing term, and shall not automatically be extended as provided in this section. Nothing in this subsection shall prevent a Franchisee from applying for a new franchise.

(d) Prior to the issuance or extension of a franchise, the City Council shall provide notice and opportunity for public comment.

(e) If the City Administrator determines service standards are not being met, the City Administrator may re-open this franchise for renegotiation.

(f) The terms of the franchise must be unconditionally accepted by **UNITED DISPOSAL SERVICE, INC. , AN OREGON CORPORATION, d/b/a ALLIED WASTE SERVICES OF MARION COUNTY – WOODBURN** in writing, and signed by an officer of the corporation within 30 days after the date this ordinance is passed by the City. If **UNITED DISPOSAL SERVICE, INC. , AN OREGON CORPORATION, d/b/a ALLIED WASTE SERVICES OF MARION COUNTY – WOODBURN** fails to do so, this ordinance shall be void.

**2.4 Ownership of Waste.** Unless otherwise stated, solid waste properly placed out for collection is the property of the Franchisee.

**2.5 Infectious Waste.** Franchisee is not required to store, collect, transport, dispose of or resource infectious waste.

**2.6 Hazardous Waste.** Except as otherwise provided in this ordinance, Franchisee is not required to store, collect, transport, dispose of or resource recover hazardous waste or excluded waste.

**2.7 Separation of Waste.** The City Council reserves the right to require the separation of component parts or materials in or from solid wastes, and to require the

deposit thereof in receptacles or places and to prescribe the method of disposal or resource recovery.

**2.8 City Authority.** The City reserves the right to determine the services authorized by this franchise agreement.

### **Section 3 - Community Standards for Collection and Disposal of Solid Waste and Recyclable Materials**

**3.1 Collection Standards.** Collection of solid waste and recyclable material shall be performed in such a way as to comply with all Federal, State and local environmental regulations. In addition Franchisee shall:

**3.1.1** Provide solid waste and recycling collection services to all persons living within or conducting business within the City limits of the City.

**3.1.2** Collect putrescible material at least once each week.

**3.1.3** Provide collection of infectious waste as defined in ORS 459.387,. Collection shall be provided in a manner consistent with the requirements of all applicable laws and regulations.

**3.1.4** Perform collections twice weekly in the business districts of the City, except Sundays and holidays. Downtown business district collection hours are 4:30 am to 6:30 am. Collection hours shall be scheduled to minimize noise and disruption to residents in or near the downtown business district.

**3.1.5** Perform curbside collections of solid waste at least once weekly in residential districts or as often as required by ORS 459 and ORS 459.A. Collection hours shall be between the hours of 6:00 am and 5:30 pm, Monday through Friday. All collections shall be made as safely, efficiently and quietly as possible.

**3.1.6** Perform curbside collections of recyclable materials at least bi-weekly or as often as required by ORS 459 and ORS 459.A. Collection of recyclable materials shall be made subject to the same requirements and within the same hours as those made for solid waste.

**3.1.7** Provide collection of residential solid waste carts or cans, recyclable materials, and yard debris carts on the same day of the week. Franchisee shall not go into garages or other buildings to make pick-ups at residences, nor shall Franchisee go into closed areas, through enclosed gates, or up or down stairs to make pick-ups., unless defined as a special service.

**3.1.8** Provide will-call service for container service for residential and commercial customers within 48 hours of initial request for service.

**3.1.9** Use due care to prevent solid waste from being spilled or scattered during

collection. If any solid waste or recyclable material is spilled during collection, Franchisee shall promptly clean up all spilled materials. All can/cart and container lids must be replaced after contents are emptied and the can/cart or container shall be returned to its original position so as to not jeopardize the safety of motorist, pedestrians or bicyclists. Franchisee shall also collect any solid waste or recyclable materials that may have been spilled or scattered prior to collection, in the immediate area of cans and carts.

**3.1.10** Use reasonable care in handling all collection receptacles and enclosures. Damage caused by the negligence of Franchisee's employees to private property, including landscaping, is the responsibility of Franchisee and shall be promptly adjusted with the owner.

**3.1.11** Ensure that all solid waste and recycling collection operations shall be conducted as quietly as possible and shall conform to applicable Federal, State, County and City noise emission standards. Unnecessarily noisy trucks or equipment are prohibited. The City Administrator may conduct random checks of noise emission levels to ensure such compliance.

**3.1.12** Determine, with approval of the City Administrator, the maximum allowable capacity of cans, carts or containers. If Franchisee refuses to service an overweight can, cart or container, a notice describing the problem must be provided. The notice shall include the name of Franchisee, employee, alternative solutions to resolve the problem and a local phone number for additional information. Franchisee must provide double the customer's subscribed service level at no additional charge on the customer's next scheduled collection day, if a special pick-up has not been requested in the meanwhile. If a special pick-up has been requested, Franchisee may charge the normal will-call rate.

**3.1.13** Refuse specific residential collections, if access to a can, cart or container, is blocked by a vehicle. For purposed of this section, "blocked" shall be defined as parked immediately in front of, or at the curb within ten feet to either side of such containers. If Franchisee refuses to service a can, cart or container for this reason, a notice describing the problem must be provided. The notice shall include the name of Franchisee, employee, reason for collection refusal, solution for resolving the problem and a local phone number for additional information. Franchisee must provide double the customer's subscribed service level at no additional charge on the customer's next scheduled collection day, if a special pick-up has not been requested in the meanwhile. If a special pick-up has been requested, Franchisee may charge the normal will-call rate.

**3.1.14** Offer unlimited vacation credits to customers who temporarily discontinue service in a calendar year for any period of two (2) weeks or more. The customer must request the discontinuance no later than noon on the business day, excluding weekends, prior to the date of discontinuance.

**3.1.15** Notify, in the event of changes to the collection schedule, all affected customers within fourteen (14) calendar days of any change. Franchisee shall not permit any customer to go more than seven (7) calendar days without service in connection with a collection schedule change.

**3.1.16** Have the option to limit acceptable methods of payment. Franchise must, however, at a minimum, accept cash, personal checks, cashiers checks, money orders, and bank drafts, and provide for online payment with a credit card.

**3.1.17** Have the option to refuse collection service upon non-payment of a billing or portion of a billing after account becomes 45 days past due, or upon refusal to pay required advance payments, delinquent charges, or charges associated with starting a new service. Franchisee may withhold collection services, providing at least a ten (10) day notice is given to subscriber.

**3.1.18** Continue collection services except in cases of street or road blockage, excessive weather conditions, natural or man-made disasters, or customer violations of public responsibilities beyond Franchisee's control. Adverse labor relations issues such as strikes or walk-outs shall be considered to be within the control of the franchisee and shall not prevent collection and disposal services as required by this ordinance.

**3.1.19** Franchisee shall dispose of solid waste in the nearest disposal site permitted by the Oregon Department of Environmental Quality unless extraordinary circumstances apply. City Council reserves the right to approve any disposal site used by Franchisee.

**3.2. Preventing Interruption of Service.** In the event of an immediate and serious danger to the public creating a health hazard or serious public nuisance, the City Administrator may, after a minimum of 24 hours notice to Franchisee, authorize another person to temporarily provide emergency service under this ordinance or the City may elect to provide such service. Upon request of Franchisee, a public hearing shall be provided before the City Council and the decision to provide temporary service shall be reconsidered. Franchisee agrees as a condition to this franchise that any equipment used for the services provided under this franchise may be used to provide such emergency service. The City shall return any such property of Franchisee upon abatement of the health or nuisance hazards created by the general interruption of service. In the event the power under this section is exercised, the usual charges for service shall prevail and Franchisee shall be entitled to collect for such usual services, but shall reimburse the City for its actual costs, as determined by the City.

**3.3 Recycling Standards.** Recycling services shall include the following:

**3.3.1** For residential customers with regular weekly solid waste service, provide on-route residential recycling service including one 65-gallon (1) roll cart, one (1) recycle bin and one (1) yard debris cart or composter at no additional charge.



Customers may, at their option, upgrade to a 95 gallon roll cart at no additional cost.

Additional carts and bins for recycling shall be provided upon request at a cost not greater than the actual cost incurred by Franchisee.

**3.3.2** For customers in single-family households, the following material at a minimum shall be picked up curbside once every other week on a designated collection day: newspapers, corrugated cardboard, brown paper bags, mixed paper consisting of household mail, paperboard, and magazines, glass bottles and jars, aluminum and tin, plastics, and aerosol cans. Batteries, oil, and latex paint shall also be collected every other week, but shall be segregated from other recyclable materials in a bin provided by the Franchisee for that purpose.

**3.3.3** For apartments and other multi-family households and units requesting such service, the following material at a minimum shall be collected once each week on a designated collection day: newspapers, corrugated cardboard, brown paper bags, mixed paper consisting of household mail, paperboard, and magazines; and glass bottles and jars, aluminum and tin, plastics, and aerosol cans. Batteries, oil and latex paint shall also be collected weekly, but shall be segregated from other recyclable materials in a bin provided by the Franchisee for that purpose. . Materials shall be collected curbside or in a designated collection center in cooperation with the building owner or manager.

**3.3.4** Yard debris carts for residential customers shall be picked up weekly on the same day as solid waste collection. Yard debris must be disposed at a compost/mulch facility registered with the Oregon Department of Environmental Quality.

**3.3.5** Recycling-only customers shall be offered 65 gallon Carts and be provided bi-weekly recycling service at a rate established by the City Council.

**3.3.6** Commercial recycling service includes carts, recycle bins, and cardboard recycling containers and shall be provided at no additional charge.

**3.3.7** For commercial customers, the following recyclable material, at a minimum, shall be collected once each week on a designated collection day: office paper and mail, corrugated cardboard, newspapers, paperboard, magazines, brown paper bags, wood, glass bottles and jars, aluminum and tin, plastic, and aerosol cans. Batteries, oil, and latex paint shall also be collected weekly, but shall be segregated from other recyclable materials in a bin provided by the Franchisee for that purpose.

**3.3.8** For large quantities of cardboard, the frequency of pickup-service shall be determined by agreement between the generator and the collector. Agreements shall give due consideration to the volume of the material, storage capacity of generator, and generator's location.

**3.3.9** Franchisee must provide notice to customer if recyclable material placed at curbside is not collected due to improper preparation. Notice must include

adequate explanation of refusal for collection, name of employee and local phone number for additional information. Employee shall leave notice securely attached to the customer's bin or the customer's front door. Employee shall collect any properly prepared material that is accessible. The purpose of the notice is to educate residents and increase program participation, and shall be written in such a manner as to accomplish this purpose.

**3.3.10** Operate and maintain at least one (1) collection center within the City limits that permits residents to deliver recyclables to the site. Collection center shall be open to the public between the hours of 8 am to 5 pm Monday through Friday, and 8 am to Noon on Saturdays. Said site shall accommodate at a minimum all recyclable materials collected at curbside, as well as scrap metal and other types of glass and plastic. Materials such as Styrofoam, textiles, and electronics shall be recycled when it is technologically or economically feasible to do so.

**3.3.11** Facilitate a reuse program referring useable items to local thrift shops, resale shops, non-profit groups or others who may have a legitimate use for the item. Maintain a list of businesses and groups that submit requests for needed items, and provide this information to others as requested.

**3.3.12** Research and develop improved recycling and reuse systems.

**3.4 Public Education.** Franchisee shall provide the following public education and promotion of activities for waste reduction, recycling, reuse, and source separation, and cooperate with other persons, companies, or local governments providing similar services. Franchisee shall:

**3.4.1** Provide a recycling information center within City limits, with local telephone access and information concerning collection schedules, recycling locations, recyclable material preparation, conservation measures, reuse programs, waste reduction strategies and on-site demonstration projects. Recycling information booths at appropriate community events shall also be provided by Franchisee to promote and increase recycling awareness and participation.

**3.4.2** Provide recycling notification and educational packets for all new residential, commercial, and industrial collection service customers specifying the collection schedule, materials collected, proper material preparation, reuse programs, waste reduction strategies and recycling benefits.

**3.4.3** Provide semi-annual informational/promotional pamphlets to residences and businesses in the City that include the materials collected and the schedule for collection. Information about waste reduction, reuse opportunities, proper handling and disposal of special wastes (household hazardous wastes) and the reduction of junk mail shall be included on a regular basis. Special community solid waste events, and the holiday tree removal program shall also be promoted when appropriate. Informational/promotional pamphlets shall be distributed to all mailing addresses within

the City.

**3.4.4** Develop by December 31, 2009 and then maintain an Internet web site that includes a listing of all franchised solid waste and recycling services and applicable rates charged for such services.

**3.4.5** Perform waste audits for those commercial and industrial customers requesting one, and conduct, at least annually, workshops on waste reduction strategies and reuse opportunities.

**3.4.6** Coordinate with the Woodburn School district and local private schools to assist in promoting awareness of recycling and waste reduction strategies to children, and to cooperate with the district in their recycling efforts and programs.

**3.4.7** Promote solid waste reduction and recycling education through local widespread media, such as radio or newspapers, no less than 18 times each year. Promotional information shall focus on recycling, reuse and waste reduction strategies.

**3.4.8** Provide the City Administrator with sufficient copies of all promotional fliers and other related information as requested.

**3.4.9** Conduct a bi-annual survey to evaluate customer participation in recycling programs and customer opinion of solid waste and recycling services offered by Franchisee. Statistics shall be used to enhance existing recycling educational materials and increase program participation. Significant statistical changes in the survey shall afford the City Administrator the option to renegotiate Section 3 of this agreement.

**3.5 Resource Recovery Services.**

**3.5.1** Aggressively seek markets for reusable, recyclable, and recoverable materials and purchase such materials from others.

**3.5.2** Develop strategies to promote the reduction of solid waste generated by residential, commercial and industrial customers. Promote programs preventing or reducing at the source those materials which would otherwise constitute solid waste.

**3.6 County Wasteshed.** Coordinate recycling efforts with other solid waste collection efforts in the Marion County Wasteshed to further enhance recycling and recovery, efforts, and to meet wasteshed recovery goals as mandated by the state.

**3.7 Additional Recycling Requirements.**

**3.7.1** The City Administrator reserves the right to require specific materials to be separated, collected and recycled.

**3.7.2** Franchisee shall provide other recycling services as required by Oregon Revised Statute 459.A, City Council, ordinance, or municipal code.

**3.7.3** Franchisee shall recycle additional materials when economically feasible and provide for an on-site collection center for household hazardous waste.

**3.8 Community Service Standards.**

**3.8.1** Franchisee shall provide for storm debris collection of tree limbs, leaves, etc., on an as needed basis. Franchisee may charge a fee for such service.

**3.8.2** Franchisee shall provide an annual residential cleanup, collecting scrap and recyclable material, yard debris and appliances, at no additional charge; however, Franchisee may charge, as a pass-through cost, the CFC evacuation fee on appliances.

**3.8.3** Franchisee shall provide collection and recycling of holiday trees placed at curbside for a period of three (3) weeks, beginning December 26<sup>th</sup> of each year, at no additional charge.

**3.8.4** Franchisee shall provide twice weekly solid waste collection and disposal service of public litter receptacles, in the central business district of the City, including the Woodburn Downtown Plaza, except weekends and holidays.

**3.8.5** Franchisee shall provide once weekly solid waste collection and disposal service at the following facilities at no charge to the City:

- a. City Hall
- b. Woodburn Public Library
- c. Woodburn Memorial Aquatic Center
- d. Woodburn Police Facility
- e. Woodburn Public Works Annex
- f. Public Works Corporation Yard

**3.9 Additional Services.** Where a new service or a substantial expansion of an existing service is proposed by the City Administrator, another person or Franchisee, the following shall apply:

**3.9.1** If service is proposed by the City Administrator, Franchisee shall receive prior written notice of the proposed service and justification by the City Administrator. If service is proposed by Franchisee or another person, the City Administrator must be notified in writing prior to any consideration by the City.

**3.9.2** The City may hold a public hearing on the proposed service and justification.

**3.9.3** In determining whether the service is needed, the City shall consider the public need for the service, the effect on rates for service and the impact on other

services being provided or planned, the impact on any city, county or regional solid waste management plan, and compliance with any applicable statutes, ordinances or regulations.

**3.9.4** If the City determines the service is needed, Franchisee shall have the option to provide the service on a temporary basis through a pilot program to determine if the service is functional on a permanent basis or Franchisee may agree to provide the service on a permanent basis within a specified time.

**3.9.5** If Franchisee rejects the service, the City may issue a franchise or permit to another person to provide only that service. The provider of the limited service shall comply with all applicable provisions of this ordinance.

### **3.10 Special Service.**

**3.10.1** If a customer requires an unusual service requiring added or specialized equipment solely to provide that service, Franchisee may require a contract with the customer to finance and assure amortization of such equipment. The purpose of this subsection is to assure that such excess or specialized equipment does not become a charge against other ratepayers.

**3.11 Sub-Contract.** Franchisee may sub-contract with other persons to provide specialized or temporary service covered by this franchise, but shall remain totally responsible for compliance with this agreement. Franchisee shall provide written notice of intent to sub-contract services prior to entering into agreements. If sub-contracting involves a material portion of the franchised service, Franchisee shall seek the approval of the City.

### **3.12 Equipment and Facility Standards.**

**3.12.1** All equipment shall be kept well painted, and properly maintained in good condition. Vehicles and containers used to transport solid waste shall be kept clean to ensure no contamination to the environment or the City's storm water system.

**3.12.2** All vehicles and other equipment shall be stored in a safe and secure facility in accordance with applicable zoning and environmental regulations.

**3.12.3** Trucks shall be equipped with a leak proof metal body of the compactor type including front, rear, or automatic loading capabilities.

**3.12.4** Pick-up trucks, open bed trucks or specially designed, motorized local collection vehicles used for the transporting of solid waste must have a leak proof metal body and an adequate cover over the container portion to prevent scattering of the load.

**3.12.5** All fuel, oil, or vehicle fluid leaks or spills which result from Franchisee's vehicles must be cleaned up immediately. All vehicles must carry an acceptable

absorbent material for use in the event of leaks or spills. Damages caused by fuel, oil, or other vehicle fluid leaks or spills from Franchisee's vehicles or equipment shall be at Franchisee's expense.

**3.12.6** All vehicles used by Franchisee in providing solid waste and recycling collection services shall be registered with the Oregon Department of Motor Vehicles and shall meet or exceed all legal operating standards. In addition, the name of Franchisee, local telephone number and vehicle identification number shall be prominently displayed on all vehicles.

**3.12.7** All collection vehicles shall not exceed safe loading requirements or maximum load limits as determined by the Oregon Department of Transportation. Franchisee shall endeavor to purchase and operate equipment that minimizes damage to City streets.

**3.12.8** Franchisee shall provide and maintain equipment that meets all applicable laws, ordinances, municipal codes, and regulations or as directed by the City Administrator.

**3.12.9** Franchisee shall provide and replace as necessary, garbage collection carts, yard debris carts, and recycle bins at no charge to the public. Cart sizes offered for solid waste disposal include 20, 32, 64, and 90 gallon capacity. Yard debris carts shall be 65 gallon capacity. Recycle carts may be either 65 or 95 gallon capacity, depending on customer choice. Solid waste, yard debris, and recycling carts shall be leak-proof, rigid, fireproof, and of rodent proof construction and not subject to cracking or splitting. The City Administrator has the right to approve all receptacles provided by Franchisee for use in the City and may require additional or alternative receptacle sizes. Customers may, at their election, change their cart size once each calendar year at no cost. For each subsequent change within the same calendar year, Franchisee may charge a fee, to recover the administrative costs of such change, as approved by the City Council.

**3.12.10** Franchisee shall clean containers used by commercial customers once annually if requested by customer for no additional charge. If Franchisee determines such containers are becoming a health hazard, requiring more frequent cleaning, such service shall be an additional maintenance charge to the waste producer or generator.

**3.12.11** In cooperation with the Woodburn Police Department, Franchisee shall remove graffiti from all containers or facilities within of the time Franchisee is notified of such need. Notification may be verbal, or in writing.

**3.12.12** All surface areas around Franchisee's site facilities including vehicle and equipment storage areas, service shops, wash stations, transfer sites, collection centers, and administrative offices must be kept clean to eliminate direct site run-off into the City's storm water and open drainage system.

**3.13 Safety Standards.** Franchisee shall operate within guidelines of the Oregon Refuse and Recycling Association, Oregon Department of Transportation, Oregon Public Utility Commission, Oregon Occupational Health and Safety Administration, Department of Environmental Quality, Woodburn Municipal Code and all other rules and regulations as they apply.

**3.13.1** Franchisee shall provide suitable operational and safety training for all of its employees who maintain, use, or operate vehicles, equipment, or facilities for collection of waste or who are otherwise directly involved in such collection. Employees involved in collection services shall be trained to identify, and not to collect, excluded waste. Employees who do handle such excluded waste shall be properly trained.

**3.14 Right-of-Way Standards.** Franchisee shall ensure proper and safe use of public right-of-ways and provide compensation to the City in consideration of the grant of authority to operate a solid waste collection and disposal system in the City of Woodburn as directed in this franchise agreement.

**3.15 Customer Service Standards.** Franchisee shall:

**3.15.1** Provide sufficient collection vehicles, carts, bins, containers, drop boxes, facilities, personnel and finances to provide the services set forth in this franchise agreement.

**3.15.2** Sufficiently staff, operate and maintain a business office and operations facility within the City.

**3.15.3** Establish minimum office hours of 8:00 am through 5:00 pm, Monday through Friday, not including holidays.

**3.15.4** Ensure a responsive, customer service oriented business. Provide customers with a local telephone number, listed in a local directory, to a local business office. Adequately staff operations to provide prompt response to customer service requests or inquiries and respond promptly and effectively to any complaint regarding service. Calls received by 1:00 pm by office staff shall be returned the same business day as call received, and by noon of the following business day if call is received after 1:00 pm. Franchisee shall promptly respond to all written complaints about service or rates.

**3.15.5** Train collection crews prior to their beginning solid waste and recycling collection, and office staff prior to having public contact. The scope of the training shall include, but is not limited to, acceptable safety practices, acceptable standards of service to the public, courteous customer service, and accuracy and completeness of information

**3.15.6** Require all employees of Franchisee and all employees of persons under

contract with Franchisee under this franchise agreement to present a neat appearance and conduct themselves in a courteous manner. Franchisee shall require its drivers and all other employees who come into contact with the public, to wear suitable and acceptable attire that identifies Franchisee.

**3.15.7** Designate at least one (1) qualified employee as supervisor of field operations. The supervisor shall devote an adequate portion of his/her workday in the field checking on collection operations, including responding to issues.

**3.16 Annual Customer Service Reporting Standards.** Franchisee shall provide annual reports to the City Administrator by March 31st of each year during the term of the franchise.

**3.16.1** Reports shall include a written log of all oral and written complaints or service issues registered with Franchisee from customers within the City. Franchisee shall record the name and address of complainant, date and time of issue, nature of issue, and nature and date of resolution. The City Administrator may require more immediate reports documenting complaints and resolutions.

**3.16.2** Provide a summary of educational and promotional activities as required in Sub-section 3.4.

**3.17 Annual Financial Reporting Standards.** Franchisee shall keep current, accurate records of account. The City may inspect the Records any time during business hours and may audit the Records from time to time. If an audit of the Records is required, the cost of an independent audit, reasonably satisfactory to the City, shall be the responsibility of franchisee. Franchisee shall submit to the City Administrator a report annually, no later than March 31<sup>st</sup> of each year, documenting the activities and achievements of all programs undertaken pursuant to this franchise for the previous year. The City Administrator shall evaluate the effectiveness of the programs in terms of the amount, level, and quality of the services provided by Franchisee. The report shall include the following specified information:

**3.17.1** Total franchise payments remitted and basis for calculations;

**3.17.2** Year-end financial statements of Franchisee for service within the City limits only, including:

- Summary of financial highlights
- Statement of income and retained earnings
- Balance sheet
- Statement of changes in financial position
- Schedule of expenses

**3.17.3** Annual recycling data form as submitted to the Marion County Environmental Services Division.



**3.17.4** Current and previous year total of residential, commercial and industrial customers within City limits, including tons of solid waste generated. Number of recycling customers within City limits and percentage of materials recycled.

**3.17.5** A summary of the customer survey as required in Sub-section 3.4.9 and a summary of the annual customer service reports as required in Sub-section 3.16.

**3.17.6** Document industry trends and direction of Franchisee over the next seven years.

**3.17.7** Provide a summary of Community Involvement activities as required in Section 3.

**3.17.8** Other information pertaining to performance standards specified in the franchise agreement.

## **Section 4 - Rates**

**4.1 Rate Structure.** The City Council reserves the right to examine the rate structure of Franchisee, and to require specific services and approve rate changes which, in the discretion of the City Council, are reasonably required in view of the following considerations:

**4.1.1** Franchisee shall have the right to charge and collect reasonable compensation from those whom it furnishes franchised services. The term "reasonable compensation" shall be defined at the discretion of the City after a study and consideration of rates for similar service under similar conditions in other areas, and as affected by local conditions in the local area. However, nothing in this section prohibits Franchisee from volunteering services at a reduced cost for a civic, community, benevolent or charitable program. Cash or in-kind contributions to such organizations shall be the sole responsibility of Franchisee and shall not be a factor in determining rates or increase the total amounts paid by ratepayers for which Franchisee serves under this agreement and shall not reduce the total amount of revenue paid to the City. Contributions shall not be taken into consideration in the rate approval process.

**4.1.2** Franchisee shall provide to the City Administrator a copy of the published rate schedule which shall contain the rates and charges made for all its operations. The rate schedule shall be kept current. Franchisee shall file with the City Administrator, at least 90 days prior to any contemplated change, a complete, new and revised rate schedule which shall be examined by Council in a public hearing, subject to applicable notice requirements and affording due process. Franchisee shall also provide documented evidence of actual or projected increased operating costs within City limits which may justify proposed increases. Council may approve or deny any request based on criteria consisting of, but not limited to: increases in operating or capital costs, increases in City population; extension of City boundaries; increase of intensive

residential, commercial or industrial development within the City; changes in solid waste or recycling technology; changes in regulatory requirements; inability of Franchisee to adequately handle increased needs for said service; the rates in other cities for similar services; and the public interest by assuring reasonable rates to enable Franchisee to provide efficient and beneficial service to users of the service. The request shall be considered denied unless approved by Council prior to 30 days before the effective date. In the event of denial, the current rate schedule remains in effect and Franchisee may file with the Council further information to justify the rate schedule changes.

**4.1.2.1** Rates established by Council are fixed rates and Franchisee shall not charge more or less than the fixed rate unless changed pursuant to Section 4. Franchisee shall not charge rates not in the rate schedule.

**4.1.2.2** Rates for a given service must be established under the provisions of these guidelines before such service can be provided to customers unless services are being offered under a pilot program. If the City Administrator determines Franchisee is providing services for a fee without following these guidelines, the City Administrator may require Franchisee to continue providing such services at no charge to the customer until such time as the rates are approved as described under Section 4. If rates are not subsequently approved, Franchisee may discontinue service and shall take full responsibility in explaining to customers as to why the service is no longer being provided.

**4.1.3** Franchisee may not give any rate preference to any person, locality, or type of solid waste collected, transported, stored, disposed of or resource recovered. This section shall not prohibit uniform classes of rates based on length of haul, time of haul, type or quantity of solid waste handled, and location of customers, so long as such rates are reasonably based on the cost of service and approved by City Council in the same manner as other rates.

**4.1.4** The rates shall be subject to review and change only one (1) time in a calendar year, beginning January 1 and ending December 31; provided:

**4.1.4.1** The City Council may at its sole discretion and with appropriate documentation submitted by Franchisee, grant an interim or emergency rate for changes in service, including pilot programs.

**4.1.4.2** An additional application for a rate adjustment may be made when the cost of collection is increased by governmental regulations, or there is a single large increase in cost not anticipated at the last rate adjustment.

**4.1.5** The approved rate schedule (Exhibit 1), as of the effective date of this ordinance, shall be deemed to be in effect.

## **Section 5 - Financial**

**5.1 Compensation.** In consideration of the rights and privileges granted by this

ordinance, Franchisee shall pay to the City of Woodburn, five percent (5%) per annum of its gross revenues derived from all services within the City and from the sale of recyclable material collected within the City. Franchisee shall also pay five percent (5%) per annum of the gross revenues derived from franchised services within the City, as defined in this ordinance, earned by subcontractors of Franchisee within the City for services rendered pursuant to this franchise agreement.

**5.1.1** Gross revenue of Franchisee shall mean revenues derived by Contractor within the City pursuant to this franchise agreement.

**5.1.2** No expenses, encumbrances, or expenditures shall be deducted from the gross revenue in determining the total gross revenue subject to the franchise fee, except net uncollectables.

**5.1.3** The compensation required in this section shall be due quarterly, on or before the 30th day of the month following last business day of every quarter. Franchisee shall furnish with each payment a notarized statement, executed by the General Manager, showing the amount of gross revenue of Franchisee within the City for the period covered by the payment computed on the basis as determined by Subsection 5.1, Compensation. If Franchisee fails to pay the entire amount of compensation due to the City through error or otherwise within the time allotted for, the unpaid balance shall be subject to a late penalty of an additional ten percent (10%), plus interest of two percent (2%) per month on the amount of fee due and unpaid from the date due until it is paid together with the late penalty.

**5.1.4** If Franchisee is prohibited by state or federal law from paying a fee based on gross revenues or the City is prohibited by state or federal law from collecting such a fee, or if any legislation reduces the actual or projected amount of compensation collected in any given year, the City Administrator may renegotiate the compensation section of this franchise agreement.

**5.1.5** Franchisee shall not separately identify its franchise fee on billing statements to customers unless it separately identifies all costs which constitute five percent (5%) or more of the costs paid by the revenues received from customers.

**5.1.6** Nothing contained in this franchise shall give Franchisee any credit against any ad valorem property tax levied against real or personal property within the City, or against any local improvement assessment or any business tax imposed on Franchisee, or against any charges imposed upon Franchisee including permit and inspections fees or reimbursement or indemnity paid to the City.

**5.2 Insurance.** Franchisee shall pay, save harmless, protect, defend and indemnify the City from any loss or claim against the City on account of, or in connection with, any activity of Franchisee in the operation or maintenance of its facilities and services except those that arise out of the sole negligence of the City. Franchisee shall, for the purposes of carrying out the provisions of this agreement, have in full force and effect, and file evidence with the City Administrator the following

requirements:

**5.2.1** Workers' Compensation insurance as required by Oregon Law, including Employers Liability Coverage.

**5.2.2** Commercial General Liability insurance as broad as Insurance Services Office (ISO) form CG 00 01, providing Bodily Injury, Property Damage and Personal Injury on an occurrence basis with the following as minimum acceptable limits:

Bodily Injury and Property Damage - Each Occurrence	\$2,000,000
Personal Injury - Each Occurrence	\$2,000,000
Products & Completed Operations - Aggregate	\$3,000,000
General Aggregate	\$3,000,000

**5.2.3** Business Automobile Liability as broad as Insurance Services Office (ISO) form CA 00 01, providing bodily injury and property damage coverage for all owned, non-owned and hired vehicles, with the following as minimum acceptable limits:

Bodily Injury and Property Damage - Each Occurrence	\$1,000,000
---	-------------

**5.2.4** Franchisee shall furnish the City Administrator with Certificates of Insurance and with original endorsements for each insurance policy (if needed). All certificates and endorsements are to be received and approved by the City Administrator before the effective date of this ordinance. The Commercial General Liability Certificate shall name the City of Woodburn, its officers, officials, employees and agents as Additional Insureds as respects to operations performed under this franchise agreement.; Franchisee shall be financially responsible for all pertinent deductibles, self-insured retentions and/or self insurance. All such deductibles, retentions, or self-insurance must be declared to and approved by the City Administrator.

**5.2.5** Any Certificate shall state, "Should any of the above described policies be canceled before the expiration date thereof, the issuing company will mail 30 days written notice to the certificate holder named to the left." Any "will endeavor to" and "but failure to mail such notice shall impose no obligation or liability of any kind upon the company, its agents or representatives." shall be omitted.

**5.3 Hold Harmless.** The Franchisee agrees to indemnify, defend and hold harmless the City, its officers, employees, volunteers and agents from any and all claims, demands, action, or suits arising out of or in connection with the City Council's grant of this franchise. Franchisee shall be responsible to defend any suit or action brought by any person challenging the lawfulness of this franchise or seeking damages as a result of or arising in connection with its grant; and shall likewise be responsible for full satisfaction of any judgment or settlement entered against the City in any such action. The City shall tender the defense to the Franchisee, and Franchisee shall accept the tender whereupon the City shall assign to Franchisee, complete responsibility of litigation including choice of attorneys, strategy and any settlement.

**5.3.1** Franchisee's costs incurred in satisfying its obligations as defined in 5.3 above, shall not decrease the total amount of compensation paid to the City and shall not increase the total amounts paid by the ratepayers for which Franchisee serves under the authority of the franchise agreement. All such expenses shall be the sole responsibility and burden of Franchisee.

**5.3.2 Damages.** Damages and penalties under this Section 5.3 include, but shall not be limited to, damages arising out of personal injury, property damage, copyright infringement, defamation, theft, and fire Franchisee.

## **Section 6 - Administration and Enforcement**

### **6.1 Customer Dispute Resolution Process.**

**6.1.1** Any citizen of Woodburn who is aggrieved or adversely affected by any application of the franchise or policy of Franchisee shall first attempt to settle the dispute by notifying Franchisee of the nature of the dispute and affording Franchisee the opportunity to resolve the dispute.

**6.1.2** If the dispute is unresolved, the citizen may contact the City Administrator. The City Administrator may require a written description of the dispute from either party, and shall attempt to mediate and resolve the grievance with the citizen and Franchisee.

**6.1.3** If the dispute is still unresolved, the citizen or Franchisee may appeal to the City Council who shall hear the dispute. The decision of the City Council shall be final and binding.

**6.2 Penalties and Procedures.** Subject to the requirement of prior notice as set forth in Section 6.3 below, for violations of this ordinance occurring without just cause, the City Administrator may assess penalties against Franchisee as follows:

**6.2.1** For failure to adhere to material provisions of this franchise, as defined in Section 6.4.1, Two Hundred Fifty Dollars (\$250.00) per day for each provision not fulfilled.

**6.2.2** For failure to comply with Oregon Occupational Safety and Health Administration and Oregon Department of Transportation safety requirements or Oregon Department of Environmental Quality rules and regulations, the penalty shall be Two Hundred Fifty Dollars (\$250.00) per day, per occurrence.

**6.2.3** For failure to comply with any provision of this franchise, for which a penalty is not otherwise specifically provided, the penalty shall be One Hundred Twenty Five Dollars (\$125.00) per day, per occurrence.

**6.2.4** For failure to comply with reasonable requests of the City Administrator

related to service, the penalty shall be One hundred Dollars (\$100.00) per day per request.

### **6.3 Procedure for Imposition of Penalties.**

**6.3.1** Whenever the City Administrator finds that Franchisee has violated one (1) or more terms, conditions or provisions of this franchise, a written notice, or a verbal notice followed by a written notice, shall be given to Franchisee informing it of such violation or liability. If the violation concerns requirements mandated by the Oregon Occupational Health and Safety Administration or the Oregon Department of Environmental Quality, a verbal notice followed by a written notice may be given. For these safety or public health violations, Franchisee shall have 24 hours from notification to correct the violation. For all other violations and liabilities the written notice shall describe in reasonable detail the specific violation so as to afford Franchisee an opportunity to remedy the violation. Franchisee shall have ten (10) days subsequent to receipt of the notice in which to correct the violation. Franchisee may, within five (5) days of receipt of notice, notify the City Administrator that there is a dispute as to whether a violation or failure has, in fact, occurred. Such notice by Franchisee to the City Administrator shall specify with particularity the matters disputed by Franchisee.

**6.3.2** The City Council shall hear Franchisee's dispute at its next regularly or specially scheduled meeting. The Council shall supplement its decision with written findings of fact.

**6.3.3** If after hearing the dispute the claim is upheld by the Council, Franchisee shall have ten (10) days from such a determination to remedy the violation or failure. Penalties shall accrue from time of initial notification until such time as the violation or failure is resolved to the satisfaction of the City Administrator.

**6.3.4** Franchisee shall be liable for full payment of all penalties imposed under this section.

**6.4 City's Right to Revoke.** In addition to all other rights which the City has pursuant to law or equity, the Council reserves the right to revoke, terminate, or cancel this franchise, and all rights and privileges pertaining thereto, in the event that:

**6.4.1** Franchisee violates any of the following provisions of this franchise which are deemed to be material to the performance of the franchise, and fails to cure such violation in accordance with Section 6.3:

Standards for Collection and Disposal of Solid Waste and Recyclable Materials (Section 3)

Compensation (Section 4 )

Insurance (Section 5)

Assignment or Sale of Franchise (Section 8)

**6.4.2** Franchisee practices any fraud upon the City or customer.

**6.4.3** Franchisee becomes insolvent, unable or unwilling to pay its debts, or is adjudged bankrupt.

**6.4.4** Franchisee misrepresents a material fact in the negotiation of, or renegotiation of, or renewal of, the franchise.

**6.4.5** After conducting a public hearing and documenting in findings of fact that it is in the best interest of the public to do so.

**6.5 Enforcement.**

**6.5.1** The City Administrator shall have the right to observe and inspect all aspects of collection operations, facilities, services, and records which are subject to the provisions of this franchise, to insure compliance.

**6.5.2** If Franchisee at any time fails to promptly and fully comply with any obligation of this agreement after receiving a written notice and a reasonable opportunity to comply, the City Administrator may elect to perform the obligation at the expense of Franchisee.

**6.5.3** If Franchisee defaults in any of the terms required to be performed by it under the terms of this franchise, and the default continues for ten (10) days after written notification by the City Administrator, this franchise may, at the option of the Council, become null and void.

**6.5.4** The City Administrator reserves the right to make such further regulations as may be deemed necessary to protect the interests, safety, welfare and property of the public and carry out purposes stated in Section 3 of this franchise agreement. The City Administrator or Franchisee may propose amendments to this franchise. Proposals shall be in writing and shall be afforded an adequate review process. After review of the proposed amendments to the franchise, the Council may adopt the amendments.

**6.5.5** All remedies and penalties under this franchise agreement, including termination, are cumulative, and the recovery or enforcement of one is not a waiver or a bar to the recovery or enforcement or any other recovery, remedy or penalty. In addition, the remedies and penalties set out in this ordinance are not exclusive, and the City reserves the right to enforce the penal provisions of any other ordinance, statute or regulation, and to avail itself of any all remedies available at law or in equity. Failure to avail itself of any remedy shall not be construed as a waiver of that remedy. Specific waiver of any right by the City for a particular breach shall not constitute a general waiver of the City's right to seek remedies for any other breach, including a repetition of the waived breach.

**6.6 Non-enforcement by the City.** Franchisee shall not be relieved of its obligation to comply with any of the provisions of this franchise by reason of any failure of the City

Administrator to enforce prompt compliance.

**6.7 Written Notice.** All notices, reports, or demands required to be given in writing under this franchise shall be deemed to be given when a registered or certified mail receipt is returned indicating delivery as follows:

If to the City:                      City of Woodburn  
   270 Montgomery Street  
   Woodburn, Oregon 97071  
   Attn: Mary Tennant, City Recorder

If to Franchisee:                      United Disposal Service, Inc  
   P.O. Box 608  
   Woodburn, Oregon 97071  
   Attn: Robin Murbach, General Manager

Such addresses may be changed by either party upon written notice to the other party given as provided in this section.

## **Section 7 - Public Responsibilities**

**7.1 Excluded Waste.** No person shall place hazardous wastes or excluded waste for collection or disposal by Franchisee at the curbside. Hazardous waste and excluded waste shall only be disposed at collection events for this specific purpose.

**7.2 Accumulation of Waste.** No person shall accumulate or store waste that is unsightly or in violation of the City's nuisance ordinance, or in violation of regulations of the Oregon Environmental Quality Commission.

**7.3 Approved Receptacles.** No customer shall use any waste collection receptacle unless it is supplied by or approved by Franchisee.

**7.4 Safe Loading Requirements.** No stationary compactor, can, cart or container for residential, commercial or industrial use shall exceed the safe loading requirements designated by Franchisee.

**7.5 Access to Receptacle.** No receptacle shall be located behind any locked or latched gate or inside of any building or structure unless authorized by Franchisee. No person shall block the access to a receptacle.

**7.6 Safe Access.** Each customer shall provide safe access to the solid waste or solid waste receptacle without hazard or risk to Franchisee.

**7.7 Can/Cart Placement.** Placement of cans/carts must be within three (3) feet of curb but shall not restrict access to bicycle lanes or sidewalks and shall not be



blocked by vehicles or other items. Items not for collection must be at least three (3) feet from cans/carts. Placement of cans/carts is limited to a time period of 24 hours prior to pick-up and 24 hours after pick-up. Cans/carts within alleys shall be placed to accommodate collection vehicles.

**7.8 Clean Cans/Carts and Surrounding Areas.** Generators or producers of waste shall clean cans/carts and shall keep the area around cans/carts and containers free of accumulated wastes.

**7.9 Removal of Solid Waste Prohibited.** No person, other than the person producing the materials contained therein, or an officer, employee or permittee of the City, or an employee of the Franchisee shall interfere with any solid waste receptacle, compact the contents of a receptacle, or remove any such receptacle or its contents from the location where the same has been placed by the person so producing the contents of said container. This subsection does not apply to the purchase of materials for fair market value as exempted by Section 2, 2.6 of this ordinance.

**7.10 Collection of Solid Waste Prohibited.** No person shall remove the lid from any solid waste receptacle, nor enter into such solid waste receptacle, nor shall any person collect, molest, compact or scatter solid waste placed out for collection and resource recovery, except the person so producing the materials contained therein, or an officer, employee or permittee of the City, or an employee of the Franchisee.

**7.11 Disposal of Unauthorized Solid Waste Prohibited.** No unauthorized person shall remove the lid from or interfere with any solid waste receptacle to deposit solid waste into such receptacle.

**7.12 Stationary Compactor.** No person shall install a stationary compacting device for handling of solid wastes unless it complies with all applicable federal, state, and local laws and regulations. Franchisee shall not service any such device unless these requirements are adhered to at all times.

**7.13 Train System.** No person shall install or operate a "train system" for the purpose of solid waste collection under this franchise agreement.

**7.14 Penalties.** In addition to, and not in lieu of any other available legal remedies, a violation of sections 7.1, 7.2, 7.6, 7.8, 7.9, 7.10, 7.11, or 7.12 of this Ordinance constitutes a Class 2 Civil Infraction, which shall be processed according to the procedures contained in the Woodburn Infraction Ordinance. Each day of continued violation is a separate offense and is separately punishable, but may be joined in a single prosecution.

## Section 8 – Miscellaneous

### 8.1 Transfer of Ownership or Control

**8.1.1** This franchise shall not be sold, assigned, transferred, leased or disposed of either in whole or in part, in any manner, nor shall title thereto, either legal or equitable, or any right, interest or property therein, pass to or vest in any person or entity without the prior written consent of the City Council, which consent shall not be unreasonably withheld.

**8.1.2** Franchisee shall promptly notify the City of any actual or proposed change in or transfer of, or acquisition by any other party of control of the Franchisee. The word "control" as used herein is not limited to majority stockholders, but includes actual

working control in whatever manner exercised. Every change, transfer or acquisition of control of the Franchisee shall make this Franchise subject to cancellation unless and until the City Council has consented thereto.

**8.1.3** The parties to the sale or transfer of this franchise agreement shall make a written request to the City Council for its approval and furnish all information reasonably required for City Council consideration.

**8.1.4** The City Council's approval shall be based upon the financial responsibility of the party whom the franchise is proposing for sale, assignment or transfer. In reviewing a request for sale or transfer, the City Council may inquire into the financial capability, technical ability, legal qualifications, demonstrated ability, and experience of the prospective controlling party or transferee to comply with the terms of the franchise as determined by the City, and must agree to comply with all provisions of the franchise agreement.

**8.1.5** The City shall be deemed to have approved the proposed transfer or assignment in the event that its decision is not communicated in writing to the franchisee within 90 days following receipt of written notice of the proposed transfer.

**8.1.6** Within thirty (30) days of any transfer or sale, if approved or deemed granted by the City Council, Franchisee shall file with the City a copy of the deed, Agreement, lease, bill of sale, stock power or other written instrument evidencing such sale or transfer of ownership or control, certified and sworn to as correct by the Franchisee and the transferee.

**8.2 Performance Bond.** As part of any assignment or transfer of franchise, as provided in Subsection 8.1, Franchisee shall provide a performance bond in the a form acceptable to the City, in the amount of \$1,000,000 with a surety licensed to do business in the State of Oregon conditioned upon the full and faithful performance of this franchise agreement and franchise and this chapter.

**8.3 Change of Law; Amendment of Franchise Agreement.**

**8.3.1.** It is the intent of the parties that this Agreement may be amended from time to time to conform to any changes in the controlling federal or state law or other changes material to this agreement. Each party agrees to bargain in good faith with the other party concerning such proposed amendments.

**8.3.2** This Agreement may be amended or terminated by the mutual consent of the parties and their successors-in interest.

**8.3.3** To the extent any lawful City rule, ordinance or regulation is adopted on a jurisdiction-wide basis and is generally imposed on similarly situated persons or entities, the rule, ordinance or regulation shall apply without need for amendment of this

Agreement. City shall provide Franchisee notice of any such change in law prior to its adoption.

**8.4 Severability and Constitutionality.** If any portion or phrase of this ordinance is for any reason held invalid or declared unconstitutional by any court, such portion shall be deemed a separate and independent provision; and such holding shall not affect the constitutionality of the remaining portion hereof. The council hereby declares that it would have passed this ordinance and each portion and phrase hereof, irrespective of the fact that any one (1) or more portions or phrases be declared illegal, invalid or unconstitutional. If, for any reason, the franchise fee under Section 5 of this ordinance is invalidated or amended by the act of any court or governmental agency, the City Administrator may either renegotiate the compensation section of this agreement or adopt the highest reasonable franchise fee allowed by such court or other governmental agency as the franchise fee charged by this ordinance.

**8.5 Continuity of Service Mandatory.** Upon expiration or the termination of this franchise, the City Administrator may require Franchisee to continue to operate the system for an extended period of time, not to exceed twelve (12) months. Franchisee shall, as trustee for its successor in interest, continue to operate under the terms and conditions of this franchise. In the event Franchisee does not so operate, the City Administrator may take such steps as deemed necessary to assure continued service to subscribers. Costs associated with such actions shall be the sole responsibility of Franchisee.

**8.6 Rules of Construction.** This ordinance shall be construed liberally in order to effectuate its purposes. Unless otherwise specifically prescribed in this ordinance, the following provisions shall govern its interpretation and construction:

**8.6.1** The singular may include the plural number, and the plural may include the singular number.

**8.6.2** "May" is permissive and "shall" is mandatory.

**8.7 Calculation of Time.** Time shall be computed so as to exclude the first and include the last day of the prescribed or fixed period of time unless stipulated otherwise in this agreement. When the last day of the period falls on Saturday, Sunday, or a legal holiday, that day shall be omitted from the computation.

**8.8 Repeal; Effective Date.** This ordinance shall repeal Ordinance 1641. If this ordinance is void for any reason, Ordinance 1641 shall remain repealed in its entirety. This ordinance shall be in full force and effect as of the date indicated below, but this ordinance shall be void unless Franchisee files with the City Recorder, within 30 days, Franchisee's unconditional written acceptance of the terms, conditions, and obligations to be complied with or performed by it under this ordinance.

**Passed by the Council and approved by the Mayor November 25, 2009**

**ORDINANCE NO. 2469**

**AN ORDINANCE GRANTING A TELECOMMUNICATIONS FRANCHISE TO LIGHTSPEED NETWORKS, INC. TO OCCUPY CERTAIN RIGHTS-OF-WAY WITHIN THE CITY OF WOODBURN AND DECLARING AN EMERGENCY.**

[Whereas clauses.]

**THE CITY OF WOODBURN ORDAINS AS FOLLOWS:**

**Section 1. Franchise Grant.**

A. Subject to the terms and conditions contained herein, the City of Woodburn does hereby grant to Lightspeed Networks, Inc., (hereinafter "Grantee") a telecommunications franchise to locate its facilities within the rights-of-way of the City, as shown on Exhibit "A" and described in Grantee's application for a franchise.

B. Such grant is subject to all of the laws and ordinances of the City of Woodburn and to applicable state and federal law. Except as otherwise specifically provided by this Franchise Ordinance, all requirements and conditions of Ordinance 2284, the Telecommunications Franchise Ordinance, shall apply to Franchisee.

C. The scope of this grant allows the installation of facilities by Grantee in the City's rights-of-way as depicted in Exhibit "A". Such facilities shall be used by Grantee to provide telecommunications services consistent with the authority granted by the OPUC. In the event either the location of Grantee's facilities or the nature of the services provided is proposed for modification, Grantee shall be required to obtain an additional or revised franchise from the City.

**Section 2. Construction Standards.**

A. The construction standards of the City of Woodburn, as well as any other applicable construction standards in existence at the time of this franchise grant or hereafter enacted, shall apply to all work performed by the Grantee in City rights-of-way.

B. The Grantee's facilities shall not interfere in any way with any of the City's communications or other public and city-permitted facilities, including other franchised facilities, either as installed or during operation. The Grantee will compensate the provider of power directly for the cost of power consumed

in support of Grantee's facilities, and shall hold the City completely harmless from any power cost.

C. The Grantee shall locate below the surface of the ground all wiring and physical improvements within City rights-of-way, unless it is physically impossible to do so. Placement of any improvements above ground, or on poles shall only be with the prior review and approval of the City.

D. Where permission is granted by the City to locate Grantee's facilities upon poles, Grantee shall independently obtain prior written approval from the owner and/or operator of the poles on which its facilities shall be placed. Upon request, Grantee shall provide copies of such written approvals for City review.

E. Where permission is granted by the City to locate Grantee's facilities upon poles, Grantee shall undertake all wiring and physical improvements required by the owner of each pole to which its facilities are to be attached. In the case of City-owned poles or fixtures, such work shall be performed subject to the approval of the City Engineer or his designee.

**Section 3. Franchise Fee.** Subject to any restrictions imposed by federal law, the franchise fee payable to the City shall be 7% (seven percent) of the Grantee's gross revenues earned within the corporate limits of the City. Notwithstanding the type of telecommunications services provided, Grantee shall pay a minimum annual franchise fee of \$1,000 for the privilege of using the City's rights-of-way. Franchise fees shall be payable quarterly, on or before April 30, July 31, October 31 and January 31, for the preceding calendar quarter. Payments made more than ten calendar days beyond the due date shall bear interest at the rate of 9% per annum. With each franchise fee payment, the Grantee shall furnish a sworn statement setting forth the amount and calculation of the payment. The statement shall detail the revenues received by the Grantee from its operations within the City, and shall specify the nature and amount of all exclusions and deductions from such revenues claimed by the Grantee in calculating the franchise fee.

**Section 4. Audit.** The City shall have the right to annually audit the books and records of the Grantee to verify compliance with the terms and conditions of this franchise. At the City's request, the Grantee shall provide the City's agents access to the Grantee's books and records, as necessary, to conduct a thorough audit.

**Section 5. Term.** The term of this franchise shall be five (5) years. This franchise shall be subject to one automatic renewal on the same terms and

conditions for an additional period of five (5) years unless notice is given by either party 180 days in advance of the expiration of the franchise of its intention to terminate or renegotiate the franchise. This franchise shall be effective upon the date of Grantee's written acceptance of this grant.

**Section 6. Indemnification.** To the extent permitted by law, the Grantee shall defend, indemnify and hold the City and its officers, employees, agents and representatives harmless from and against any and all damages, losses and expenses, including reasonable attorney's fees and costs of suit or defense, arising out of, resulting from or alleged to arise out of or result from the negligent, careless or wrongful acts, omissions, failures to act or misconduct of the grantee or its affiliates, officers, employees, agents, contractors or subcontractors in the construction, operation, maintenance, repair or removal of its telecommunications facilities, and in providing or offering telecommunications services over the facilities or network, whether such acts or omissions are authorized, allowed or prohibited by this Ordinance or by a franchise agreement made or entered into pursuant to this Ordinance.

**Section 7. Acceptance.** The grant of franchise herein is conditioned upon Grantee's acceptance of all terms and conditions hereof in writing in a form acceptable to the City.

**Section 8. [Emergency Clause.]**

**Passed by Council August 9, 2010, and approved by the Mayor August 11, 2010.**

---

# 1.1 ORGANIZATION AND STRUCTURE

## 1.101 Structure

### 1.101.01 Title

This ordinance may be referred to as the “Woodburn Development Ordinance” (**WDO**).

### 1.101.02 Application and Construction of Regulations

- A. The provisions of the **WDO** shall be considered the minimum regulations adopted to promote the public health, safety and general welfare; and shall apply uniformly to each case or kind of use, structure or land unless varied or otherwise conditioned as allowed in the **WDO**.
- B. A period of time to perform expressed in days shall mean consecutive “calendar days” unless otherwise defined. The number of calendar days is counted beginning with the first date after the date or event from which the period begins, and ending at 5 o’clock p.m. on the last day of the number of days stated, unless the last day is not a City business day, in which case the last day of the period shall be the first City business day following the last of the consecutive calendar days.
- C. As used in the WDO:
  - 1. The term “shall” is mandatory. [Section 1.101.02.C.1 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]
  - 2. The term “should” is discretionary. [Section 1.101.02.C.2 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]
  - 3. The term “may” is permissive. [Section 1.101.02.C.3 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]
  - 4. The term “standard” indicates a mandatory requirement. The decision-maker shall require conformance with a standard unless a variance, zoning adjustment, exception, or other relief has been granted. [Section 1.101.02.C.4 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]
  - 5. The term “guideline” indicates a norm that is accepted in the community. The decision-maker shall require conformance with a guideline unless it finds that the guideline is unwarranted, unnecessary, duplicative, or unreasonable under the particular circumstances, or that the intent of the guideline has been substantially met. [Section 1.101.02.C.5 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]



[Section 1.101.02.C as amended by Ordinance No. 2313, §2, passed on September 10, 2008.]

**1.101.03 Relationship to Other Laws and Private Agreements**

It is not the intent of the **WDO** to interfere with, abrogate or annul any easement, covenant or agreement between parties; provided, however, that where the **WDO** imposes greater restrictions than those imposed or required by other rules or regulations, the provisions of the **WDO** shall control.

**1.101.04 Prior Approvals and Conditions of Approvals**

Developments, including subdivisions, partitions, planned unit developments, zone changes, conditional uses, variances, site development review, other development applications for which approvals were granted before the effective date of the **WDO**, may occur pursuant to such approvals; EXCEPT that all subsequent modifications to development approvals shall comply with the **WDO**.

**1.101.05 Official Actions Shall Comply with the WDO**

All officials, departments, employees (including contractor-officials), of the City vested with authority to issue permits or grant approvals shall adhere to and require conformance with the **WDO**, and shall issue no permit or grant approval for any development or use which violates or fails to comply with conditions or standards imposed to carry out the **WDO**.

[Section 1.101.06 repealed by Ordinance No. 2383, §1, passed March 16, 2005.]

**1.101.07 Severability**

If any section, paragraph, subdivision, clause, or sentence of the **WDO** shall be adjudged by any court of competent jurisdiction to be unconstitutional or invalid, such judgment shall not affect, impair, invalidate, or nullify the remainder of the **WDO**.

**1.101.08 Annual Review of the WDO**

The Community Development Director shall maintain a list of potential modifications of the **WDO** due to new state and/or federal laws and rules, case law precedents, scrivener errors, interpretation, or other changes in circumstance. The Director shall report these matters to the City Council at its first regular meeting in the month of November so that the Council may consider initiating appropriate measures to modify the **WDO**.

---

## 1.102 Definitions

**Abutting:** Touching on the edge or on the line, including at a corner. It shall include the terms adjacent, adjoining and contiguous.

**Access:** The place, means or way by which pedestrians or vehicles have ingress and egress to and/or from a lot or use.

**Accessory Building, Structure or Use:** A detached, accessory building, structure or use which is incidental and subordinate to and supports upon the primary use on the same premises.

**Adjacent:** Near, close or bordering but not necessarily contiguous with; adjoining but separated by a right of way.

**Adjustment, Property Line:** The relocation of a common boundary between two contiguous lots where an additional unit of land is not created and where the conditions created for the resulting units of land comply with zoning standards and building code separations.

**Adjustment, Zoning:** A land use action granting a minor variance to zoning standards as provided by the **WDO**.

**Administrative Body:** The City Council, Planning Commission, Design Review Board, or staff member having the jurisdiction to hear and decide proceedings on land use actions.

**Aerial:** A privately owned and operated antenna for noncommercial uses subject to height limitations as specified in the **WDO**. Aerial includes “ham radio antennae”, but is not a “telecommunications facility.”

**Alley:** A public right of way not more than 20 feet wide and not less than ten feet in width that provides secondary access to property and intersects with a public street.

**Alteration, Structural:** Any change in the exterior dimensions of a building, or a change which would affect a supporting member of a building, such as a bearing wall, column, beam or girder.

**Ancillary Facilities, Telecommunications:** The structure and equipment required for operation of the telecommunication equipment, including but not limited to antennae, repeaters, equipment housing structures, and ventilation and other mechanical equipment.

**Antenna(e), Telecommunications:** An electrical conductor or group of electrical conductors that transmit or receive radio waves for commercial uses.

**Anti-graffiti Surface:** Either a preparation applied to the surface area of a wall or fence that is formulated to aid in the removal of unintended paint or other surface markings; or evergreen vegetation planted directly in front of, or covering, a fence or wall in a way that obscures the visibility of at least 75 percent of any element of each exterior face.

Apartment: A dwelling unit in an apartment house.

Apartment House: A multiple family dwelling containing 3 or more dwelling units that are either rented or leased, or in condominium ownership.

Applicant: The property owner of record, contract purchaser or a person authorized by the property owner or contract purchaser to file an application.

Application: Any request for approval of a development or a legislative amendment to the city's land use regulations, comprehensive plan or related maps.

Approval criteria and approval standards: All standards which must be met in order to approve an application. Depending upon the specific application, approval criteria include standards contained in the **WDO**, Woodburn Comprehensive Plan and applicable state law.

Approved: Official acknowledgment by the administrative body or official given specific jurisdiction to grant such approval.

Arbor: A latticework bower intertwined with climbing vines and flowers. [Section 1.102 as amended by Ordinance No. 2383, §2, passed March 16, 2005.]

Archway: A covering or enclosing arch. [Section 1.102 as amended by Ordinance No. 2383, §2, passed March 16, 2005.]

Arterial Street, Major or Minor: See "Street, Major Arterial" and "Minor Arterial."

Articulate/Articulation: The joining and intersecting of building spaces through offsets, projections, overhangs, extensions and similar features.

Assisted Care Facility: A building or portion of building containing living units and providing services as described by NAICS 62331.

Attachment, Telecommunications: An antenna or other piece of related equipment affixed to a transmission tower.

Average Setback: See "Setback, Average."

Backhaul Network, Telecommunications: The lines that connect a provider's towers/cell sites to one or more cellular telephone switching offices, and /or long distance providers, or the public switched telephone network.

Berm: A linear mound of soil, a small rise or hill in a landscape which is intended to buffer or visually screen certain features of development, such as parking.

Block: A unit or contiguous units of land bounded by intersecting streets.

Boundary Street: See “Street, Boundary.”

Buffer: (noun) Landscaping and/or screening between two land uses of differing character to minimize potential conflicts and provide a more aesthetic environment.

Buffer Yard: See “Yard, Buffer.”

Building: Any structure having a roof built for the support, shelter, or enclosure of persons, animals, or property of any kind.

Building, Medium Density Residential: Any building where the predominant use is multiple family, nursing care or assisted care residential.

Building, Primary: A building, within which is conducted the main or principal use of the property.

Cabana: A stationary structure with two or more walls, used in conjunction with a manufactured dwelling to provide additional living space and meant to be moved with the manufactured dwelling.

Caliper: The diameter of a tree measured 6 inches above ground level for trees up to 4 inches in diameter, and 12 inches above ground for larger sizes.

Carport: A permanent structure consisting of a roof and supports for covering a parking space which is not completely enclosed.

Cemetery: Land used or intended to be used for the burial of the dead and dedicated for cemetery purposes, including a columbarium, crematory, mausoleum, or mortuary, when operated in conjunction with and within the boundary of such cemetery.

Change of Occupancy: A change from one type of occupancy of a building to another type of occupancy as defined by the state building code.

Change of Use: A change from one type of use of a building or land to another type of use for uses as defined by the **WDO**.

Child Day Care Center: A facility which provides care or kindergarten for 13 or more children.

Child Day Care Home: The home of a child care provider for 12 or fewer children.

Church: See “House of Worship.”

Club: An organization, group, or association supported by the members, the purpose of which is to render a service primarily for members and their guests, but shall not include any

organization, group or association the chief activity of which is to render a service customarily carried on as business for profit.

City or City of Woodburn: The City of Woodburn, an Oregon municipal corporation.

City Administrator: The City Administrator of the City of Woodburn, or designee.

City Engineer: The City Engineer of the City of Woodburn.

Collocated Telecommunications Facilities: The attachment of new or additional transmission facilities to an existing transmission tower designed for such multiple use.

Commission: The Planning Commission of the City of Woodburn.

Community Building: A facility available for public use for meetings, recreation, education.

Comprehensive Plan: The officially adopted Woodburn Comprehensive Plan, including all components thereof adopted by reference or otherwise lawfully incorporated as parts thereof.

Conditional Use: Any use, which is permitted in a particular zoning district only after review and approval as provided by the **WDO**.

Conditional Use, Specific: Any use which is permitted in a particular zoning district subject to specified standards and only after review and approval as provided by the **WDO**.

Condominium: A building or group of buildings, in which separate buildings or portions of buildings are separately owned, while the land on which the building(s) is located is held in a common ownership.

Conforming: In compliance with the current regulations of the **WDO**.

Contiguous: Touching along a boundary or point.

Corner Clearance: The distance from an intersection of a street to the nearest driveway. The distance shall be measured along the traveled way the street connecting the intersecting street and the driveway, starting from the closest edge of the pavement of the intersecting street and ending at the closest edge of pavement of the driveway.

Corner Lot: See "Lot, Corner."

Council: The City Council of the City of Woodburn.

Cul de sac Street: See "Street, Cul de sac."

Dead End Street: See "Street, Dead End."

---

Department of Public Works or Public Works: The Department of Public Works of the City of Woodburn.

Decision: The formal action by an administrative body regarding its final disposition of a land use action.

Delivery Service: The delivery of packages and the sale and/or delivery of food and/or beverages as permitted by the standards of **Section 2.203.07**.

Density per gross acre: The number of dwelling units or living units per acre prior to the dedication of public right of way; public easements; irrevocable easements for private streets or access ways; and private streets in Manufactured Dwelling Parks..

Density per net acre: The number of dwelling units or living units per acre based on the land area committed to housing and common, private ownership but EXCLUDING public right of way; public easements; irrevocable easements for private streets or access ways; and private streets in Manufactured Dwelling Parks.

Description, Legal: The description of a subject property by either metes and bounds or in reference to a lot, or lot and block, number of a recorded subdivision or partition.

Design Review Board: The Design Review Board of the City of Woodburn.

Development: A building or grading operation, making a material change in the use or appearance of a structure or land, dividing land into two or more parcels, partitioning or subdividing of land as provided in ORS Chapter 92 or the creation or termination of an access right.

Development Standard: The requirement of the City with respect to the quality and quantity of an improvement or activity. All **WDO** standards are both the maximum and the minimum requirement unless otherwise indicated.

Director: The Director of Community Development of the City of Woodburn or designee.

DLCD: The Oregon Department of Land Conservation and Development.

Driveway: A private access way to and from a property, a parking space or area, a garage, or a use, intended to allow vehicular ingress and egress but not intended to provide the traffic circulation function of a street.

Duplex: See “Dwelling, Two-Family.”

Dwelling Unit: A building or portion of a building providing complete, independent living facilities for occupancy by one family including permanent provisions for living, sleeping, eating, cooking and sanitation.

Dwelling, Site Built Single Family: A detached building constructed on a single lot containing one dwelling unit designed exclusively for occupancy by one family.

Dwelling, Two-Family (Duplex): A detached building on a single lot containing 2 dwelling units designed exclusively for occupancy by 2 families living independently of each other.

Dwelling, Manufactured: Any of the following:

1. Residential trailer: A structure constructed for movement on the public highways, has sleeping, cooking and plumbing facilities, that is intended for human occupancy, that is being used for residential purposes and that was constructed before January 1, 1962.
2. Mobile home: A structure constructed for movement on the public highways that has sleeping, cooking and plumbing facilities, that is intended for human occupancy, that is being used for residential purposes and that was constructed between January 1, 1962, and June 15, 1976, and met the construction requirements of the Oregon mobile home law in effect at the time of construction.
3. Manufactured home: A structure constructed for movement on the public highways that has sleeping, cooking and plumbing facilities, that is intended for human occupancy, that is being used for residential purposes and that was constructed in accordance with federal manufactured housing construction and safety standards and regulation in effect at the time of construction.

“Manufactured dwelling” does not mean any building or structure constructed to conform to the State of Oregon Structural Specialty Code or the One and Two Family Dwelling Code adopted pursuant to ORS Chapter 455 or any unit identified as a recreational vehicle by the manufacturer.

Dwelling, Multiple Family: A building on a single lot containing 3 or more dwelling units.

Employees: All person, including proprietors, performing work on a premises during the largest shift or peak season.

Exchange Carrier: A provider of telecommunications services.

Family: An individual or two or more persons related by blood, marriage, legal adoption or guardianship, or a group of not more than five persons (excluding servants) who need not be related by blood or marriage, living together in a dwelling unit. “Family” shall include two or more handicapped persons as defined in the Fair Housing Amendments Act of 1988 living as a single housekeeping unit.

Fence: An unroofed barrier or an unroofed structure used as an enclosure, barrier or restriction to light, sight air or passage.

Final action and final decision: The City's final decision on a permit application for which there is either no appeal to another decision-maker within the City, or, if there is the possibility of a local appeal, an appeal was not timely perfected in accordance with the **WDO**.

Floor Area, Gross: The sum of the gross horizontal areas of the several floors of a building, measured from the exterior faces of the exterior wall or from the centerline of walls separating two buildings, but not including:

1. Attic and basement space providing headroom of less than seven feet;
2. Uncovered steps or fire escapes;
3. Private garages, carports, or porches;
4. Accessory water towers or cooling towers;
5. Off street parking or loading spaces.

Frontage: That portion of a lot which abuts a public street.

Front Lot Line: See, "Lot Line, Front."

Garage: A building, or portion of a building, which is completely enclosed and designed for the storage or parking of a vehicle.

Grade: Adjacent ground elevation is the lowest point of elevation of the finished surface of the ground, paving or sidewalk within the area between the building and property line or, when the property line is more than 5 feet from the building, between the building and a line 5 feet from the building.

Group Home: A residential treatment or training or an adult foster home licensed by or under the authority of the Department of Human Resources under ORS 443.400 to 443.835, a residential facility registered under ORS 443.480 to 443.500 or and adult foster home licensed under ORS 443.705 to 443.825 which provides residential care alone or in conjunction with treatment or training or a combination thereof for five or fewer individuals who need not be related. Staff persons required to meet licensing requirements shall not be counted in the number of facility residents, and need not be related to each other or to any resident of the residential [group] home.

Group Care Facility: A residential care, residential training or residential treatment facility licensed or registered by or under the authority of the Department of Human Resources under ORS 443.400 to 443.460 or licensed by the State Office for Services to Children and Families under ORS 418.205 to 418.327 which provides residential care alone or in conjunction with treatment or training or a combination thereof for six to fifteen individuals who need not be related. Staff person required to meet licensing requirements shall not be counted in the number of facility residents and need not be related to each other or to any resident of the residential [group care] facility.

Guyed Tower, Telecommunications: A transmission tower on which cables (guy wires) are permanent.



**Height, Building:** The vertical distance above a reference datum measured to the highest point of the coping or flat roof or to the deck line of a mansard roof or to the average height of the highest gable of a pitched or hipped roof. The height of a stepped or terraced building is the maximum height of any segment of the building. The reference datum shall be selected by either of the following, whichever yields the greater height of building: (See Figure 6.1)

1. The elevation of the highest adjoining sidewalk or ground surface within 5-foot horizontal distance of the exterior wall of the building when such sidewalk or ground surface is not more than 10 feet above the lowest grade.
2. An elevation 10 feet higher than the lowest grade when the sidewalk or ground surface described in “1” above is more than 10 feet above the lowest grade.

**Home Occupation:** A business or professional activity engaged in by a resident of a dwelling unit as a secondary use of the residence, and in conformance with the provisions of the **WDO**. Such term does not include the lease or rental of a dwelling unit.

**House of Worship:** A church, synagogue, temple, mosque or other permanently located building primarily used for religious worship. A house of worship may also include accessory building for related religious activities and a residence.

**Interested Person:** With respect to a land use action, any person or organization, or the duly authorized representative of either, having a right of appeal under the **WDO**.

**Kennel:** Any lot or premises on which four or more dogs and/or cats over the age four months are kept for sale, lease, boarding or racing.

**Landscaping:** Areas primarily devoted to the planting and preservation of trees, shrubs, lawn and other organic ground cover, together with other natural or artificial supplements such as watercourses, ponds, fountains, decorative lighting, benches, arbors, gazebos, bridges, rock or stone arrangements, pathways, sculpture, trellises and screens.

**Lattice Tower, Telecommunications:** A transmission tower constructed of lateral cross members.

**Legal Description:** See “Description, Legal.”

**Legislative action:** Any final decision of the city that adds to, amends or repeals the City’s land use regulations, comprehensive plan or related maps and does not pertain to a particular property or small set of properties.

**Livestock:** One or more members of any species of cattle, swine, sheep, goat, poultry, horse or other equine, or llama, alpaca or related ruminant, regardless of the purpose of which any of the foregoing may be kept; and any species of rabbit, bee, or fur-bearing animal kept for sale, for sale of by-products, for livestock increase, or for value increase.

**Living Unit:** A room or suite of rooms, providing living and sleeping facilities for one or more persons where either cooking or eating and/or sanitation facilities are shared. In “Rooming” and “Room and Board” facilities each bed rented for compensation is a “Living Unit.”

**Loading Space:** An on-site space or berth on the same lot with a building, or contiguous to a group of buildings, for the temporary parking of a commercial vehicle while loading or unloading merchandise or material, and which abuts upon a street, alley or other appropriate means of access.

**Lot:** A lot or parcel created by subdivision or partition in compliance with ORS Chapter 92 and applicable zoning and subdivision ordinances, or created by deed or land sale contract recorded before subdivision requirements or partition requirements in the City of Woodburn (April 16, 1963) or for land in Marion County not yet incorporated in the City of Woodburn prior to major partition regulations (August 8, 1962) and minor partition regulations (September 1, 1977), exclusive of units of land created solely to establish a separate property tax account. [Section 1.102 as amended by Ordinance No. 2446, §3, passed on September 10, 2008.]

**Lot Area:** The total area of a lot, measured in a horizontal plane, within the boundary lines, EXCLUDING dedicated public rights of way and recorded irrevocable easements for private streets or driveways.

**Lot, Corner:** A lot abutting two segments of street right of way along either, a curvi-linear street, or two intersecting streets, where the projection of the two line segments forms an angle of intersection that is no greater than 135 degrees. (See Figure 6.2)

**Lot Coverage:** The percentage, or portion, of total lot area covered by primary and/or accessory buildings INCLUDING roofed but unenclosed structures but EXCLUDING covered structures less than five feet in height and having less than 20 square feet of gross floor area (such as pet shelters and play houses).

**Lot Depth, Average:** The horizontal distance measured from the midpoint of the front lot line to the midpoint of the rear lot line.

**Lot, Flag:** A lot that is either a) accessed by an easement; or b) accessed by a strip of land; where the width of the driveway access is neither less than, nor exceed by more than 20 percent, the standards of **Section 3.104.05**. (See **Figure 6.2**)

**Lot, Interior:** A lot other than a corner lot. (See **Figure 6.2**)

**Lot Line:** The property lines forming the exterior boundaries of a lot. (See Figure 6.2)

**Lot Line Adjustment:** See “ Adjustment, Property Line.”

**Lot Line, Front:** (See **Figure 6.2**)

1. In the case of an interior lot, a line separating the lot from the street.
2. In the case of a corner lot, a line separating the lot from the street from the architectural front of the existing or contemplated primary building. In the case of a flag lot, the lot line, which is most nearly parallel to the street that provides access to the interior lot.

**Lot Line, Rear:**

1. In the case of a triangular shaped lot, diamond shaped lot, or a trapezoidal lot which is narrowest at the rear and has a distance between the side lot lines at the rear of less than ten feet, the rear line for setback purposes shall be an assumed line within the lot ten feet in length, parallel to and at the maximum distance from the front lot line; or
2. In any other case, the lot line opposite and most distant from the front lot line.

**Lot Line, Side:** Any lot line, which is not a front or rear lot line.

**Lot, Through:** A lot which fronts on two streets, which do not intersect along the boundaries of the lot. (See Figure 6.2)

**Lot Width:** The horizontal distance between the side lot lines, measured at right angles to the lot depth at a point midway between the front and rear lot lines.

**LUBA:** The Oregon Land Use Board of Appeals.

**Manufactured Dwelling:** See “Dwelling, Manufactured.”

**Manufactured Dwelling Park:** Any place where four or more manufactured dwellings are located within 500 feet of one another on a lot, tract or parcel of land under the same ownership, the primary purpose of which is to rent or lease or use facilities or to offer space free in connection with securing the trade or patronage of such person. “Manufactured dwelling park” does not include a lot or lots located within a subdivision being rented or leased for occupancy by no more than one manufactured dwelling per lot if the subdivision was approved pursuant to ORS Chapter 92.

**Manufactured Home:** See “Dwelling, Manufactured.”

**Medium Density Residential Building:** See “Building, Medium Density Residential.”

**Mini-Storage Warehouse:** An area within an enclosed building or structure used for the storage of personal property.

**Mobile Home:** See “Dwelling, Manufactured.”

Monopole, Telecommunications: A transmission tower consisting of a single upright pole support that does not require guy wires or lateral cross.

Mobile Food Services: A vehicle, trailer, wagon or temporary structure, as defined by the state building code used for the preparation and/or sale of food and/or beverages conducted in compliance with the standards of **Section 2.203.17**. [Section 1.102 as amended by Ordinance No. 2383, §3, passed March 16, 2005.]

Multiple Family Dwelling Unit: A residential dwelling unit, including an apartment unit, that is part of a residential complex containing three (3) or more dwelling units on the same lot.

North American Industry Classification System or NAICS: A document of the U.S. Office of Management and Budget, 1997 edition, used to classify uses in the **WDO** as indicated in **Section 2.101.01**.

Nonconforming Development: Any development which met all applicable development standards imposed by applicable city or county zoning ordinance provisions when the development was established, and which has been maintained in compliance with such standards; but which does not comply with the current development standards of the **WDO** solely because of the adoption or amendment of the **WDO**, or because annexation to the City resulted in application of different development standards to the subject property.

Nonconforming Use: A use which met all applicable use standards imposed by applicable City or county zoning ordinance provisions when it was established; but which does not comply with the use standards of the **WDO** solely because of the adoption of or amendment of the **WDO**, or because annexation to the City resulted in the application of different use standards to the subject property.

Non-final decision: Any decision by the Director of Community Development, Planning Commission or Design Review Board which is not a final decision but is appealable to another decision maker within the City.

Notification Area: An area bounded by a line 250 feet equi-distant from all boundaries of the subject property.

Notification List: A certified list prepared by a title company of the owners of property within the notification area, compiled from the most recent property tax assessment roll; the owners of the subject property according to the most recent property tax assessment rolls; the applicant and any neighborhood or community organization recognized by the City of Woodburn and whose boundaries include the subject property.

Nursing Care Facility: A building or portion of building containing living units and providing services as described by NAICS 6231.

OAR: Oregon Administrative Rules.

One-hundred-twenty-day (120 day) period: The one-hundred- twenty-day period within which ORS 227.178 requires the City to take final action on a complete application.

Open Space, Common: An area, feature, building or other facility within a development which has been dedicated in common to the ownership within the development, or to the public, specifically for the purpose of providing places for recreation, conservation or landscaping, intended for the use of the residents and property owners of the development.

Open Space, Usable Common: Common open space, the use of which conforms with use and development guidelines specified by the **WDO** .

ORS: Oregon Revised Statutes.

Owner: The owner of record of real property as shown on the latest tax rolls or deed records of the county, or a person who is purchasing a parcel of property under a written recorded sales contract.

Park Street : A private street which affords principal means of access to abutting individual manufactured dwelling spaces and auxiliary buildings within a manufactured dwelling park.

Park Space: Any area or portion of a manufactured dwelling park, which is designated or used for the placement of one manufactured dwelling and appurtenant facilities.

Parking: The temporary storage of a vehicle where the owner or person entitled to its use intends that its storage shall be for time and in a place where it may be conveniently recovered ready for continued use as transportation.

Parking Lot or Area: An on-site building, structure, or improved area, other than a street or alley, used for the parking of automobiles and other vehicles.

Parking Space: A designated space for the parking of one motor vehicle.

Partition: An act of partitioning land or an area or tract of land partitioned.

Partition Land: To divide an area or tract of land into two or three parcels of land within a calendar year, but does not include:

1. A division of land resulting from a lien foreclosure, foreclosure of recorded contract of sale of real property or the creation of cemetery lots;
2. Adjustment of a property line by the relocation of a common boundary where an additional unit of land is not created and where the existing unit of land reduced in size by the adjustment complies with any applicable zoning ordinance;
3. The division of land resulting from the recording of a subdivision or condominium plat.

**Partition Plat:** A final map and other writing containing all the descriptions, locations, specifications, dedications, provisions and information concerning a partition.

**Pedestrian Facilities:** Improvements, which provide for public pedestrian foot traffic including sidewalks, walkways, crosswalks and other improvements, such as lighting or benches, which provide safe, convenient and attractive walking conditions.

**Permit:** Any form of quasi-judicial approval pertaining to the use of land rendered by the City under the **WDO**, including subdivisions, partitions, lot line adjustments, zone changes and plan amendments, land use, limited land use and expedited land divisions.

**Pergola:** An arbor formed of horizontal trelliswork supported on columns or posts over which vines or other plants are trained. [Section 1.102 as amended by Ordinance No. 2383, §2, passed March 16, 2005.]

**Permitted Use:** Those land uses permitted in a zoning district that are allowed outright, subject to the standards of the WDO, without obtaining a land use approval.

**Pet:** A domestic animal customarily kept, and cared for, by the occupants of a dwelling for personal pleasure, and which is not raised for food, fur, or monetary gain. Neither fowl, herd animals, pigs, goats or horses of any type or breed are classified as pets.

**Planned Unit Development or PUD:** A type of land development which, as a single project, allows for mixed use and design flexibility that is based on a design that is in compliance with the Comprehensive Plan, the uses allowed by underlying zoning, specified exceptions to zoning standards and applicable subdivision, condominium and homeowner association requirements of the **WDO**.

**Planning Commission:** The Planning Commission of the City of Woodburn.

**Plant Unit:** The quantity of specified plant materials, per table 3.1.5. [Section 1.102 as amended by Ordinance No. 2446, §5, passed on September 10, 2008.]

**Plat or Final Plat:** A final subdivision plat, partition plat or replat. See “Plat, Partition” and “Plat, Subdivision.”

**Plat, Preliminary:** A tentative diagram or drawing concerning a partition or subdivision.

**Pre-existing Towers and Pre-existing Antennae, Telecommunications:** Any tower or antenna for which a building permit has been properly issued prior to passage of the **WDO**.

**Private Street:** See “Street, Private.”

**Property Line Adjustment:** See, “Adjustment, Property Line.”

**Quasi-judicial:** Any decision by the City which applies the provisions of the **WDO** in response to an application and that pertains to a specific property or small set of properties.

**Recreational Vehicle:** A unit, with or without motive power, which is designated for human occupancy, and is used temporarily for recreational or emergency purposes. “Recreational vehicle” includes: “camping trailer”, “motor home”, “park trailer”, “travel trailer”, and “truck camper.”

**Recreational Vehicle Park or RV Park:** A plot of land upon which two or more recreational vehicle sites are located, established or maintained for occupancy by recreational vehicles of the general public as temporary living quarters for recreational or vacation purposes.

**Recreational Vehicle Park Space or RV Park Space:** That portion of an RV park reserved for the location of a recreational vehicle.

**Rear Lot Line:** See “Lot Line, Rear.”

**Recycling Station:** An area or structure used for the collection and temporary storage of non-putrescible, discarded materials, which will be transported elsewhere to be reused or recycled.

**Regulatory Wetland:** See “Wetland, Regulatory.”

**Repair:** The reconstruction or renewal of any part of an existing building or structure for the purposes of maintenance. The word “repair” or “repairs” shall not include structural changes.

**Repeater, Telecommunications:** Equipment containing both a receiver and a transmitter; used to relay radio signals over large distances or to provide signals in an area otherwise in a shadow.

**Rooming and Boarding House:** A residential building or portion thereof with guest rooms, providing lodging or lodging and meals, for three (3) or more persons for compensation.

**School, Elementary, Middle or High School:** A public or private institution offering instruction in the several branches of learning and study, in accord with the rules and regulations of the State Department of Education.

**Semi-Public:** A building, structure or use intended for public purpose by a non-profit organization.

**Self-Storage Warehouse:** See “Mini-Storage Warehouse.”

**Setback or Setback Line:** The minimum distance between a specified line and the foundation or exterior wall of a building or structure, whichever is closer. The distance shall be measured from the abutting property line, EXCEPT for “Manufactured Dwelling Parks” and “Interior Flag Lots.” In a Manufactured Dwelling Park setbacks shall be measured from the delineation of a “Park Space.” For Interior Flag Lot setbacks shall be measured from a property line EXCEPT in the case of development that abuts a flag lot driveway access easement or strip of land in fee. In that case the setback shall be measured from the easement line or the property line, whichever is closer to the development. (See **Figure 6.3**)

Setback, Average: For any continuous wall “average setback” shall be as follows:

1. For a straight wall: The distance derived from dividing the sum of the closest and furthest points of the building wall from the property line by 2; or
2. For an articulated wall: The location of a wall where the yard area abutting the property line (accounting for offsets and jogs) is equal to the yard area computed by multiplying the length of the wall by the standard for the allowable average setback.

Shadow, Telecommunications: A geographic area that has less than adequate telecommunication service coverage.

Side Lot Line: See “Lot Line, Side.”

Significant Tree: See “Tree, Significant.”

Space, Park: See “Park Space.”

Space, Parking: See “Parking Space.”

Space, RV: See “Recreational Park Vehicle Space.”

Special Use: A use, which is permitted in a particular zoning district conditioned upon compliance with the applicable standards of the **WDO**.

Specific Conditional Use: See “Conditional Use, Specific.”

Street: See “Street, Public” and “Street, Private.”

Street, Boundary: That portion, or portions, of a street right of way abutting a subject property where existing or proposed development is located within 260 feet of the subject right of way. (**Figure 6.12**)

Street, Major: A street or highway classified in the Woodburn Transportation System Plan as a Major Arterial, Minor Arterial, Service Collector, or Access street.

Street, Major Arterial: A street or highway which provides service to traffic entering and leaving the area and traffic to major centers in Woodburn, pursuant to the Woodburn Transportation System Plan.

Street, Minor Arterial: A street which feeds the major arterial system and supports moderate length trips and service to activity centers pursuant to the Woodburn Transportation System Plan..

Street, Service Collector: A street which provides significant linkages with arterials and tend to accommodate higher volume traffic pursuant to the Woodburn Transportation System Plan.



**Street, Access:** A street which provides primarily single family residential local street access and tends to accommodate lower volumes of traffic pursuant to the Woodburn Transportation System Plan.

**Street, Cul de sac:** A dead end street having a turnaround area at the dead end. Cul de sac length shall be measured along the center line from the nearest right of way line of the nearest intersecting street to the throat or point of beginning of the turnaround.

**Street, Local:** A street whose primary function is to provide access to abutting land uses. “Local Street” includes “Residential Street” and “Skinny Residential Street” pursuant to the Woodburn Transportation System Plan.

**Street, Park:** See “Park Street.”

**Street, Private:** See “Park Street.”

**Street, Public:** The entire width between the right of way lines of a public way capable of providing the principal means of access to abutting property.

**Structural Alteration:** Any alteration, addition or removal of any structural member of a building, or structure.

**Structure:** That which is built or constructed, an edifice or building of any kind, or any piece of work artificially built up or composed of parts joined together in some definite manner, regardless of whether it is wholly or partly above or below grade.

**Subdivide Land:** To divide land into four or more lots within a calendar year.

**Subdivision:** An act of subdividing land or an area or a tract of land subdivided.

**Subdivision Plat:** A final map and other writing containing all the descriptions, locations, specifications, dedications, provisions and information concerning a subdivision.

**Subject Property:** The real property or properties that is/are the subject of a quasi-judicial permit application.

**Telecommunications Facilities:** Facilities designed and used for the purpose of transmitting and receiving voice and data signals from various wireless communications devices.

**Telecommunications Facilities, New:** The installation of new transmission towers. New attachments are not new facilities.

**Tower Footprint, Telecommunications:** The area described at the base of a transmission tower as the perimeter of the transmission tower including the transmission tower foundation and any attached or overhanging equipment, attachments, or structural members but excluding ancillary facilities and guy wires and anchors.

**Tower Pad, Telecommunications:** The area that encompasses the tower footprint, ancillary facilities fencing and screening.

**Tower Height, Telecommunications:** The vertical distance from the highest point on the transmission tower to the original grade of the ground directly below.

**Transmission Tower, Telecommunications:** The structure on which receiving antennae are located.

**Tree, Significant:** Any existing, healthy tree 24 inches or more in diameter measured 12 inches above ground level.

**Trellis:** A frame or support of lattice work. [Section 1.102 as amended by Ordinance No. 2383, §2, passed March 16, 2005.]

**Urban Growth Boundary or UGB:** The demarcation that defines the extent of urbanizable land in and around the City of Woodburn in compliance with adopted statewide planning goals and the Woodburn Comprehensive Plan.

**Use: (noun)** An activity or a beneficial purpose for which a building, structure or land is designed, developed or occupied.

**Utilities:** Water, sanitary sewer, storm drainage, natural gas, electrical, wire communication service, cable television and all persons and companies supplying the same.

**Vision Clearance Area:** An area defined by the standards within which visual obstructions are regulated for safety purposes. (See **Figure 6.4**)

**Wall, Architectural:** A brick, poured concrete, precast concrete, or CMU wall, that has an earth tone coloration other than grey on at least eighty-eight percent (88%) of the surface; incorporates at least two colors; is architecturally treated with scoring, texture, or pattern on at least eighty-eight percent (88%) of the surface; and is provided with an anti-graffiti surface. [Section 1.102 as amended by Ordinance No. 2446, §4, passed on September 10, 2008.]

**Wetlands:** An area that is inundated or saturated by surface water or ground water at a frequency and duration sufficient to support, and that under normal circumstances does support a prevalence of vegetation typically adapted for life in saturated soil conditions.

**Wetlands, Regulatory:** See “Wetlands, Significant.”

**Wetlands, Significant:** Wetlands which are defined by the criteria adopted by the Division of State Lands (DSL) pursuant to ORS Chapter 197 and subject to land use regulation.

**WDO:** The Woodburn Development Ordinance.

**Yard:** An open and unoccupied space unobstructed from the ground to the sky, except where specifically provided by the **WDO**, on the lot on which a building is situated.

---

**Yard, Buffer:** An yard improved with landscaping and/or screening to applicable standards of the *WDO* that is located between two land uses of differing character to minimize potential conflicts and to provide a more aesthetic environment.

**Yard, Front:** The space extending across the full width of a lot, the depth of which is the minimum horizontal distance between the front lot line and a line parallel to the nearest point of the foundation or exterior wall of the primary building or structure, whichever is closer. (See *Figure 6.3*)

**Yard, Rear:** The space extending across the full width of the lot between the rear lot line, the depth of which is the minimum horizontal distance between the rear lot line and a line parallel to the nearest point of the foundation or exterior wall of the primary building or structure, whichever is closer. (See *Figure 6.3*)

**Yard, Side:** The space extending from the front yard line to the rear yard line, the depth of which is the minimum horizontal distance between the side lot line and a line parallel to the nearest point of the foundation or exterior wall of the primary building or structure, whichever is closer. (See *Figure 6.3*)

**Zone or Zoning District or District:** (noun) A district or area which is subject to land use standards and to development guidelines and standards for those uses. The standards and guidelines for each district are set out in the text of the *WDO* and the location of the districts is delineated on the official zoning map.

---

## 1.103 Zoning Map

### **1.103.01 Adoption of the Zoning Map**

An official Zoning Map, entitled, “Official Zoning Map of the City of Woodburn” is hereby adopted and made a part of the **WDO**.

### **1.103.02 Content of the Official Zoning Map**

The location and boundaries of all zoning districts, overlay-combining districts and all other graphic information required by the **WDO** shall be noted on the official Zoning Map. The official Zoning Map shall be filed with City Recorder.

The official Zoning Map, and the record of final decisions amending the Map which have not yet been plotted on the Map, shall constitute a certifiable record of the official Zoning Map.

The Director of Community Development shall control the electronic storage of graphic files used to plot the official Zoning Map. The Director shall, when necessary, certify to the accuracy of copies of the official map or portions thereof.

### **1.103.03 Copies of the Zoning Map**

Regardless of the existence of published purported copies of the official Zoning Map, there shall be only one official Zoning Map, which shall be kept on file by the Community Development Director. The official Zoning Map shall be the final authority as to the zoning status of all land within the City. As to amendments to the official Zoning Map, the Map shall be prima facie evidence of the zoning status of the area shown by the amendment; but in the event of a conflict between the Map and the action effecting the amendment, the action shall control.

### **1.103.04 Maintenance of the Official Zoning Map**

The Community Development Director shall maintain an up-to-date copy of the official Zoning Map, to be revised from time to time so that it accurately portrays changes in zone boundaries. The official Zoning Map may be stored on a computerized geographic information system (GIS). The Director shall adopt rules governing access to and storage of an official GIS Zoning Map to insure against accidental or unauthorized modification or loss of the data.

---

# 1.104 Nonconforming Uses and Development Standards

## **1.104.01**      **Applicability**

The provisions of this *Section* relate exclusively to the use and development standards and conditions imposed by the *WDO*. Nothing in this Section shall be deemed a waiver, relaxation or abrogation of any provision of any other applicable law, ordinance, or regulation controlling the use or development of buildings, structures or land.

## **1.104.02**      **Termination of a Nonconforming Use**

The nonconforming use of a building, structure, or land shall be considered terminated if the Community Development Director finds that the use of the building, structure or land ceased, for any reason, for a continuous period of 6 months. Any findings by the Director shall be subject to *Section 4.102.09*.

## **1.104.03**      **Termination of a Use within a Nonconforming Building or Structure**

A use dependent upon a nonconforming building or structure (with the exception of a single family dwelling) shall be terminated, as noted, under any one of the following circumstances: [Section 1.104.03 as amended by Ordinance No. 2383, §4, passed March 16, 2005.]

- A. Use of a building or structure that is substantially damaged or becomes deteriorated to the extent that it has been declared a “dangerous building or structure” and ordered demolished pursuant to the state Building Code or other federal, state or local regulations, shall be terminated upon such declaration and order;
- B. Use of a building or structure which is substantially damaged or deteriorated to the extent that the cost of repairing the building or structure exceeds 60 percent of its replacement cost shall be terminated upon the date of such damage or deterioration. The replacement cost shall be established by the Building Official assuming new materials and compliance with the state building code; or
- C. Use of a building or structure which is damaged or deteriorated less than 60 percent shall be terminated where permits and full reconstruction has not been initiated within one year of the preparation of a restoration estimate. The restoration cost shall be estimated by a registered engineer or architect assuming new materials and compliance with the state building code.

## **1.104.04**      **Change or Expansion of an Existing Use within a Nonconforming Structure**

- 
- A. Any expansion or addition to buildings or structures with nonconforming height, setback, density or lot coverage shall not make the development more nonconforming.
  - B. Any expansion or addition to single family and duplex dwellings that existed before the effective date of the **WDO**, EXCEPT those located in the NCOD, shall be EXEMPT from the architectural guidelines and standards of the **WDO**.

**1.104.05**      **Change or Expansion of an Existing Use with Nonconforming Parking, Loading and/or Landscaping**

Any additional parking, loading, landscaping, wall and/or refuse facility required by the **WDO** to accommodate a change in use, or expansion of an existing use shall be subject to the following: [Section 1.104.03 as amended by Ordinance No. 2383, §5, passed March 16, 2005.]

- A. Applications subject to Design Review, **Section 5.103.02**, shall conform to all parking, loading, landscaping, wall and refuse facility requirements for the subject use to the standards of the **WDO**. [Section 1.104.05A as amended by Ordinance No. 2383, §5, passed March 16, 2005.]
- B. Applications subject to Design Review, **Section 5.102.02**, where the change or expansion increases the required area for parking, loading, or landscaping by 25 percent or more, shall conform all parking, loading, landscaping, buffer walls and refuse facilities to the standards of the **WDO**. Parking, loading, landscaping, buffer walls and refuse facilities required for changes or expansions of less than 25 percent shall be limited to those necessary to conform with the increment of change or expansion. [Section 1.104.05B as amended by Ordinance No. 2383, §5, passed March 16, 2005.]

**1.104.06**      **Repairs and Maintenance**

Except as otherwise provided in this **Section**, nonconforming structures and development and premises occupied by nonconforming uses may be repaired and maintained, so long as any such repair or maintenance does not in any way increase its nonconformity.

**1.104.07**      **Nonconforming Lots of Record**

Any nonconforming lot of record may be used, provided all standards not involving width or lot area shall comply with the **WDO**.

---

# 1.105 Planning Commission

## 1.105.01      **Composition, Terms and Vacancies**

### A.      Creation of the Commission.

1.      The Woodburn Planning Commission as created and organized pursuant to Ordinance 1807, is hereby recreated and continued as provided herein.
2.      The Commission shall have the duties and powers set forth in this Section and such further and additional powers and duties conferred by the constitutions and laws of the United States and the State of Oregon, the Charter, Ordinances and Resolutions of the City of Woodburn, and as directed by the City Council.
3.      The Commission shall act as the Design Review Board under the **WDO EXCEPT** where the City Council has acted by resolution pursuant to **Section 1.106.01** to appoint a Design Review Board.

### B.      Composition of the Commission

1.      The Commission shall consist of a total seven (7) members appointed by the Mayor to a full or unexpired term, and confirmed by the City Council. Any vacancy in the Commission shall be filled by appointment by the Mayor with the consent of the City Council for the unexpired portion of the term.
2.      All members of the Commission shall be legal residents of the City of Woodburn, with the exception that one member who may reside outside the City.
3.      No more than one member shall be engaged principally in the buying, selling, or developing of real estate for profit as an individual or be a member of any corporation that is engaged principally in the buying, selling or developing of real estate for profit. No more than one member shall be engaged in the same kind of business, trade or profession.

### C.      Terms of Office

1.      The terms of office of each Commissioner shall be four years, or until a successor is appointed and qualified. The terms of the Commissioners shall be staggered so that the term of office of not more than three members will expire in the same year. The terms of office shall expire at midnight on December 31.
2.      Commission members shall be installed at the first regular meeting of the the State of Oregon and impartially perform the duties of the office to best

of their ability.

3. The Council may remove a Commissioner, after hearing, for misconduct or nonperformance of duty.

D. Compensation.

Members of the Commission shall receive no compensation for their services, but may be reimbursed for expenses incurred in the performance of their duties.

**1.105.02 Organization of the Commission**

A. Officers.

1. The Commission shall elect a Chair and a Vice Chair. The terms of office shall comply with the rules and regulations of the Commission and City Council.
2. The Community Development Director shall serve as Secretary of the Commission. The Secretary, supported by other city staff, shall provide notice of public meetings and public hearings, and keep minutes of all proceedings of the Commission in accordance with state law and city ordinances.

B. Meetings.

1. Four (4) members of the Commission shall constitute a quorum.
2. The Commission shall meet at least once each month, and the regular meeting place of the Commission shall be at the City Hall.
3. The Commission may establish rules to conduct its business consistent with the laws of the State of Oregon and with the Charter and Ordinances of the City of Woodburn.

**1.105.03 Functions and Duties of the Commission**

A. General Responsibilities for Recommendations to the City Council and Others.

Except as otherwise provided by the City Council, the Commission shall have the power to make recommendations to the City Council and to all other public authorities regarding the following:

1. The laying out, widening, extending, and locating of public thoroughfares, parking of vehicles and relief of traffic congestion;
2. Betterment of housing and sanitation conditions;



3. Establishment of zones or districts limiting the use, height, area and bulk and other characteristics of buildings and structures related to land development;
4. Protection and assurance of access incident to solar radiation;
5. Protection and assurance of access to wind for potential future electrical generation or mechanical application.
6. Plans for regulating future growth, development and beautification of the city in respect to its public and private buildings and works, streets, parks, grounds and vacant lots, and plans consistent with future growth and development of the city in order to secure to the city and its inhabitants sanitation, proper service of public utilities and telecommunications utilities, including appropriate public incentives for overall energy conservation and transportation facilities.
7. Plans for development and regulation of industrial and economic needs of the community in respect to industrial pursuits.
8. Economic surveys of the present and potential needs of the city.
9. Needs of local industries with a view to strengthening and developing them and stabilizing employment conditions.

B. Recommendations on Planning and Zoning.

The Commission shall make written findings and recommendations to the City Council on all proposed amendments to the Comprehensive Plan; proposed or revised ordinances relating to the regulation of land use; all types of land use applications specified for Commission review by the **WDO** ; and all other matters as directed by the City Council after holding any prescribed public hearing. The Commission may also hold public hearings and make recommendations to the Council on any other matter that relates to the Commission's powers and duties.

C. Review and Tentative Approval of Plats and Planned Unit Developments.

The Commission shall have the duty and power to review and tentatively approve plats, replats and planned unit developments of land laid out in lots, including the streets, alleys, and other portions of the same intended to be dedicated for public or private use within the City of Woodburn, subject to review or appeal to the City Council. [Section 1.105.03.C as amended by Ordinance No. 2446, §6, passed on September 10, 2008.]D. Other Duties of the Commission

The Commission shall have the authority to exercise any and all powers, functions, and authority delegated to or conferred upon the Commission by the laws of Oregon, the Charter of the City of Woodburn, the **WDO**, or any other ordinance or resolution of the City of Woodburn.

---

## **1.106 Design Review Board**

### **1.106.01 Composition, Terms and Vacancies**

#### **A. Creation of the Board.**

1. The City Council may, by resolution, create or dissolve a Design Review Board, which shall have the functions, duties and powers set forth in this Section. Until a Design Review Board is created, the functions, duties and powers set forth in this Section are vested in the Planning Commission.
2. The Board shall have the functions and duties and powers set forth in this Section and such further and additional functions and duties as may be conferred upon it by the Charter, Ordinances and Resolutions of the City of Woodburn, and as directed by the City Council.

#### **B. Composition of the Board.**

1. The Board shall consist of a total of five (5) members appointed by the Mayor to a full or unexpired term and confirmed by the City Council.
2. Voting membership of the Board shall include at least three design professionals or persons with experience and/or knowledge of design. No more than one voting member shall be engaged in the same kind of business, trade or profession.

#### **C. Terms of Office.**

1. The terms of office of the initial appointed members shall run as follows: two members until January 1 of the year that commences one year following their initial appointment and three members until January 1 of the year that commences two years following their initial appointment. The Council shall determine by lot the terms of the initial members.
2. The term of office of a member, other than those initially appointed, shall be for staggered terms of four years, or until a successor is appointed. The terms of office shall expire at midnight on December 31.
3. Board members shall be installed at the first regular meeting of the Board following the expiration of a term or vacancy.
4. The Council may remove a Board member, after hearing, for misconduct or nonperformance of duty.

#### **D. Compensation.**

---

Members of the Board may receive compensation for their services as shall be determined by City Council and may be reimbursed for expenses incurred in the performance of their duties.

**1.106.02**      **Organization of the Board**

A.      Officers.

1.      The Board shall elect a Chair and a Vice Chair. The terms of office shall comply with the rules and regulations of the Board.
2.      The Community Development Director shall serve as Secretary of the Board. The Secretary, supported by other City staff, shall provide notice of public meetings and public hearings, and keep an accurate record of all proceedings and actions of the Board in accordance with state law and city ordinances.

B.      Meetings.

1.      Three (3) members of the Board shall constitute a quorum.
2.      The Board shall have a regular meeting schedule. All meetings of the Board shall be open public meetings. The regular meeting place of the Board shall be at the City Hall.
3.      The Board shall establish rules to conduct its business consistent with the laws of the State of Oregon and with the Charter and Ordinances of the City of Woodburn.

**1.106.03**      **Functions and Duties of the Board**

It shall be the function and duty of the Board to administer the design review provisions of the **WDO** that are identified as functions of the Board. It shall be the duty of the Board to make recommendations or decisions with written findings in compliance with the applicable procedures of the **WDO**.

---

## SECTION 2.1 LAND USE ZONING

### 2.101 General Provisions

#### 2.101.01 Establishment of Zoning

All areas within the corporate limits of the City of Woodburn are divided into distinctive land use categories which shall be applied to all geographic areas of the City and recorded on the Official Zoning Map, as provided in *Section 1.103* of the *WDO*. The use of the territory within a zoning district shall be limited to the uses specified in the zoning district.

#### 2.101.02 Zoning Districts

The City of Woodburn shall be divided into the following zoning districts:

- A. **Residential Single Family (RS).**
- B. **Retirement Community Single Family Residential (R1S).**
- C. **Medium Density Residential (RM).**
- D. **Commercial Office (CO).**
- E. **Commercial General (CG).**
- F. **Downtown Development and Conservation (DDC).**
- G. **Nodal Neighborhood Commercial (NNC)**
- H. **Industrial Park (IP).**
- I. **Light Industrial (IL).**
- J. **Public and Semi-Public (P/SP).**
- K. **Neighborhood Conservation Overlay District (NCOD).**
- L. **Riparian Corridor and Wetlands Overlay District (RCWOD)**
- M. **Southwest Industrial Reserve District (SWIR)**
- N. **Nodal Districts**

1. Nodal Single Family Residential (RSN)
2. Nodal Multi-Family Residential (RMN)

### **2.101.03 Classification of Uses**

- A. Within each zone, uses are classified as “permitted,” “special,” “conditional,” “specific conditional” and “accessory.” Further, uses are functionally classified by description of the particular activity (such as “site-built single family residence”) or by general category with reference to the North American Industry Classification System (NAICS).
- B. Uses functionally classified with reference to North American Industry Classification System (NAICS) are described with the NAICS title for the particular subdivision thereof, followed by the index number assigned in the system for such subdivision.
- C. For purposes of the **WDO**, NAICS refers to the document titled: North American Industry Classification System. U.S. Office of Management and Budget 1997. Published by JIST Works, Inc. Indianapolis, IN.
- D. Uses described without reference to the NAICS are described with ordinary words of common usage which, where it is necessary that their definitions be clarified or restricted for purposes of this ordinance, are defined in **Section 1.102**.
- E. Where a use is not described with reference to the NAICS or otherwise defined in **Section 1.102**, the words of this ordinance describing such a use are to be given their ordinarily accepted meaning except where the context in which they are used otherwise clearly requires.
- F. In many cases, uses are listed under convenient categories, often the division of the NAICS, which are in capital letters or boldface type. Such titles of subsections do not indicate nor shall they be construed as meaning that they themselves independently designate permitted, special, conditional or accessory uses. They are provided for ease of reference only.
- G. The uses listed in each use classification refer to the “predominant use.” The term “predominant use” not only describes the principal use but also allows for “ancillary uses” and “required supporting uses.” “Predominant use” does not differentiate about the duration of a use, uses of both permanent and temporary nature are considered to be the same.
- H. An ancillary use is a use that is subsidiary to a predominant use and is either:
  1. Vertically integrated with [or directly linked with the conduct of] a predominant use: or

2. Exclusively for the benefit of occupants, or employees, of a predominant use.
- I. A required supporting use is an on-site space or facility necessary to fulfill a dimensional or development standard of the **WDO** or a condition of a land use approval. Required supporting uses include access facilities, parking, loading, landscaping, and open space.

## 2.102 Single Family Residential (RS)

### 2.102.01 Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO*, are permitted in the RS zone.

- A. **Site-built single family dwelling.**
- B. **Group home.**
- C. **Family child day care** for 12 or fewer children.
- B.
- D. **Parks and playgrounds.**
- E. **Rights of way, easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines, for storm water facilities and for pump stations.

### 2.102.02 Special Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO* including the special development standards of *Section 2.203*, are permitted in the RS zone.

- A. **Agricultural practices** without livestock subject to *Section 2.203.02*.
- B. **Boat and recreational vehicle storage pad** subject to *Section 2.203.03*.
- C. **Boat and recreational vehicle storage area** subject to *Section 2.203.04*.
- D. **Community club buildings and facilities** subject to *Section 2.203.05*.
- E. **Delivery services** subject to *Section 2.203.08*.
- F. **Duplex dwelling** on a corner lot subject to *Section 2.203.09*.
- G. **Golf courses** without a driving range subject to *Section 2.203.11*.
- H. **Home occupations** subject to *Section 2.203.12*.
- I. **House of worship** subject to *Section 2.203.13*.
- J. **Manufactured home on a lot** subject to *Section 2.203.16*.

K. **Residential sales office** subject to *Section 2.203.18*.

L. **Temporary residential sales** subject to *Section 2.203.20*.

[Section 2.102.02.M as amended by Ordinance No. 2423, §22, effective on July 28, 2007.]

M. **Facilities During Construction** subject to *Section 2.203.10*.

#### **2.102.03** **Conditional Uses**

The following uses may be permitted in the RS zone subject to the applicable development standards of the **WDO** and to the conditions of conditional use approval:

A. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.102.01* and telecommunication facilities subject to *Section 2.204.03*.

B. **Elementary and secondary schools (6111)**.

C. **Golf driving range** in conjunction with a golf course.

D. **Off street parking** in conjunction with a non-residential use allowed in the zone.

E. **Child day care services (6244)**, EXCEPT family child day care for 12 or fewer children, within a non-residential building.

#### **2.102.04** **Specific Conditional Uses**

The uses permitted by the following designation may be allowed in the RS zone subject to approval as a conditional use that conforms to the specific standards referenced below, the applicable provisions of the **WDO** and all other applicable conditions of approval.

A. **Historically or architecturally significant site** subject to *Section 2.204.02*.

#### **2.102.05** **Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202 and 2.203*.

A. **Garage** (or carport in the case of a manufactured home).

B. **Deck or patio**.



- C. **Fence or free standing walls.**
- D. **Greenhouse or hobby shop.**
- E. **Private recreational facilities**, including swimming pool, hot tub or sauna, and game courts.
- F. **Personal storage structure.**

**2.102.06**      **Dimensional Standards**

[Section 2.102.06 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

The following dimensional standards shall be the minimum requirements for all development in the RS zone. If the RS zone has a Nodal Overlay on the Comprehensive Plan Map the dimensional standards of the RSN District, ***Section 2.115***, shall apply.

A.      Minimum Density

A minimum density of 5.2 dwelling units per net buildable acre (after excluding public rights-of-way, public tracts, common open space, and land protected by the RCWOD shall be required for subdivisions.

B.      Lot Standards.

Lots in an RS zone shall comply with the standards of ***Table 2.1.1*** and ***Table 2.1.2***.

(Table is on the next page.)

**TABLE 2.1.1 Lot Standards for Residential Uses in an RS Zone\***\*EXCEPT PUD's subject to *Section 3.109*

Use Type and Lot Location	Minimum Lot Area	Minimum Lot Width	Average Lot Depth	Minimum Street Frontage
<b>Single Family Dwelling, Site Built; Group Home; Family Child Day Care; Manufactured Home, on a Lot; &amp; Residential Sales Office</b>				
<b><u>Interior Lot</u></b>				
For an interior lot.	6000 sq. ft.	50 ft.	90 ft.	40 ft.
<b><u>Corner Lot</u></b>				
For a corner lot.	8000 sq. ft.	80 ft.	90 ft.	50 ft.
<b><u>Flag Lot**/** or Cul de sac Lot</u></b>				
For either a <u>flag or cul de sac lot</u> . ** <u>Flag lot</u> dimension and area standards EXCLUDE the driveway access, per Section 3.104.05 attached. ***Within a subdivision, not more than one (1) flag lot shall be located behind another lot as shown in <i>Figure 6.6</i> attached.	6000 sq. ft.	50 ft. at the front setback line.	90 ft.	<u>Flag lot</u> : The driveway access easement or strip of land per <i>Section 3.104.05</i> .  <u>Cul de sac lot</u> : 40 feet.
<b>Duplex Dwelling on a Corner Lot</b>				
For a corner lot.	10,000 sq. ft.	80 ft.	90 ft.	50 ft.

**TABLE 2.1.2 Lot Standards for Non-Residential Uses in an RS Zone**

In an RS zone the lot area for a non-residential use shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

C. Building Height.

The maximum height of buildings and structures shall not exceed 35 feet, EXCEPT chimneys, spires, domes, flag poles and other features (EXCEPT telecommunication facilities subject to *Section 2.204.03*) not used for human habitation, which shall not exceed 70 feet.

D. Setback and Buffer Improvement Standards.

1. Minimum Front Setback and Setback Abutting a Street [Section 2.102.06.D.1 as amended by Ordinance No. 2446, §7, passed on September 10, 2008.]:
  - a. Dimensions:
    - 1) The minimum setback abutting a street, or front property line shall be 20 feet plus any Special Setback, **Section 3.103.05**, EXCEPT:
      - a) For flag lot that provides a minimum setback of 12 feet in all yards; or
      - b) When the existing pattern of development requires the application of **Section 2.102.06.D.1.a.2**). [Section 2.102.06.D.1.a.1.b as amended by Ordinance No. 2446, §19, passed on September 10, 2008.]
    - 2) When the lots abutting a vacant property are already developed and front the same street, the minimum setback abutting the street for the subject property shall equal the average setback of the existing, abutting residential buildings, plus or minus 5 feet, but in no case shall be less than 10 feet.
  - b. Off Street Parking, Maneuvering and Storage:
    - 1) Off street parking and storage shall be prohibited within a required setback or any yard abutting a street EXCEPT for parking and maneuvering within a driveway leading to a garage (or carport in the case of a manufactured home) or adjacent to a wall. [Section 2.102.06.C.1.b.1 as amended by Ordinance No. 2383, §7, passed March 16, 2005.]
    - 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from the closest edge of a shared driveway and 20 feet from a street right of way line.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.

- d. Vehicular Access: Vehicular access shall be permitted in conformance with **Section 3.104**.
2. Minimum Interior Side and Interior Rear Setbacks [Section 2.102.06.D.2 as amended by Ordinance No. 2446, §7, passed on September 10, 2008].
- a. Dimensions:
    - 1) Side Setback. The minimum side setback shall be 5 feet EXCEPT for a flag lot. The side setback for a flag lot may be either one of the following [Section 2.102.06.D.2.a.1 as amended by Ordinance No. 2446, §7, Passed on September 10, 2008]:
      - a) 12 feet, when all setbacks are a minimum of 12 feet; or [Section 2.102.06.D.2.a.1.a as amended by Ordinance No. 2446, §7, passed on September 10, 2008]
      - b) 5 feet, when the rear setback complies with dimensions of **Section 2.102.06.C.2.a.2)a)**. [Section 2.102.06.D.2.a.1.b as amended by Ordinance No. 2446, §7, passed on September 10, 2008]
    - 2) Rear Setback. [Section 2.102.06.D.2.a.2 as amended by Ordinance No. 2446, §7, passed on September 10, 2008]
      - a) The average rear setback (as defined in **Section 1.102**) for all lots, EXCEPT a flag lot shall be [Section 2.102.06.D.2.a.2.a as amended by Ordinance No. 2446, §7, Passed on September 10, 2008]:
        - (i) 24 feet wide for structure up to 16 feet in height;
        - (ii) 30 feet wide for structure 16.1 to 28 feet in height;
        - (iii) 36 feet wide for structure 28.1 to 35 feet in height
- with no point measuring less than 5 feet from the average dimension.

- ## **2.102.07      Development Standards**

Setbacks and lots shall be subject to ***Section 3.103***.

C. Architectural Design Standards.

1. Site-built single family and duplex dwellings and manufactured homes on lots in the RS zone, EXCEPT those existing on the effective date of the **WDO** or those located in the Neighborhood Conservation Overlay District (NCOD), shall be subject to the architectural design standards of **Section 3.107.03**.
2. All single family and duplex dwellings located within the NCOD shall be subject to the architectural standards or guidelines of **Section 3.107.04**.
3. All primary buildings and structures, other than those noted in Sections 2.102.07.C.1. and 2. shall be subject to the architectural guidelines of **Section 3.107.06**.

D. Signs.

Signs shall be subject to **Section 3.110**. [Section 2.102.07D as amended by Ordinance No. 2359, §3, passed March 22, 2004.]

E. Accessory Uses and Structures.

By definition, prior to the construction or installation of an accessory structure, EXCEPT a fence or free standing wall, an existing primary permitted use, building or structure shall have been established on the same lot. Accessory uses and structures shall be subject to **Section 2.2**.

F. Landscaping and Sidewalks.

1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of **Section 3.101 and 3.106**.
2. No landscaping is required for single family and duplex dwelling lots EXCEPT conservation of significant trees, **Section 3.106.04**.
3. All uses, EXCEPT lots for single family and duplex dwellings shall be landscaped to the applicable standards of **Section 3.106**.

G. Lot Coverage.

Lot coverage by the primary and accessory structures EXCEPT accessory structures in the rear yard area, shall be:

C.

1. A maximum of 40 percent for lots containing a primary building with a average height of 14 feet or less, and
2. A maximum of 35 percent for lots with a primary building with an average height of more than 14 feet.

H. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by *Section 1.102* and developed to the public facility and access standards of *Sections 3.101, 3.102 and 3.104*. No more than one primary building shall be located on a lot.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**
  - b. **Subdivisions, Section 3.108;** or
  - c. **Planned Unit Development Section 3.109.**
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, Section 5.101.07.**
  - b. **Replatting, Section 3.108.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## 2.103 Retirement Community Single Family Residential (R1S)

### 2.103.01 Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO*, are permitted in the R1S zone.

- A. **Site-built single family dwelling.**
- B. **Group home.**
- C. **Family child day care** for 12 or fewer children.
- D. **Parks.**
- E. **Rights of way, easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines, for storm water facilities and for pump stations.

### 2.103.02 Special Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO* including the special development standards of *Section 2.203*, are permitted in the R1S zone.

- A. **Agricultural practices** without livestock subject to *Section 2.203.02*.
- B. **Community club buildings and facilities** subject to *Section 2.203.05*.
- C. **Delivery services** subject to *Section 2.203.08*.
- D. **Golf course** without a driving range subject to *Section 2.203.11*.
- E. **Home occupation** subject to *Section 2.203.12*.
- F. **House of worship** subject to *Section 2.203.13*.
- G. **Manufactured home on a lot** subject to *Section 2.203.16*.
- H. **Temporary residential sales** subject to *Section 2.203.20*.

[Section 2.103.02.I as amended by Ordinance 2423, §23, effective on July 28, 2007.]



- I. **Facilities During Construction** subject to *Section 2.203.10*.

**2.103.03**      **Conditional Uses**

The following uses may be permitted in the R1S zone subject to the applicable development standards of the *WDO* and to the conditions of conditional use approval:

- A. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.103.01*; telecommunication facilities subject to *Section 2.204.03*; and Elementary and secondary schools (6111).
- B. **Off street parking** in conjunction with a non-residential use allowed in the zone.

**2.103.04**      **Accessory Uses**

[Section 2.103.04 as amended by Ordinance No. 2423, §35, effective on July 28, 2007.]

D.

The following uses are permitted as accessory uses subject to *Section 2.201*.

- A. **Garage** with a maximum capacity of three cars (or carport with a maximum capacity of two cars in the case of a manufactured home).
- B. **Fence or free standing wall.**
- C. **Greenhouse or hobby shop.**

**2.103.05**      **Prohibition of Additional R1S Zoning**

The zoning of additional territory as R1S is expressly prohibited.

**2.103.06**      **Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the R1S zone.

- A. Lot Standards.

Lots in an R1S zone shall comply with the standards of *Table 2.1.3* and *Table 2.1.4*.

<b>TABLE 2.1.3      Lot Standards for Residential Uses in an R1S Zone</b>				
<b>Lot Location</b>	<b>Minimum Lot Area</b>	<b>Minimum Lot Width</b>	<b>Average Depth</b>	<b>Min. Street Frontage</b>
<b><u>Interior Lot</u></b>	3600 sq. ft.	50 ft.	None	50 ft.
<b><u>Corner Lot</u></b>	3600 sq. ft.	50 ft.	None	50 ft.
<b><u>Flag Lot</u></b>	3600 sq. ft. [EXCEPT a flag lot driveway required in <i>Section 3.104.05.</i>	50 ft.	None	No direct street frontage shall be required other than the width of the driveway access easement or strip of land in fee ownership required per <i>Section 3.104.05.</i>
	3600 sq. ft.	50 ft.	None	40 feet.

<b>TABLE 2.1.4      Lot Standards for Non-Residential Uses in an R1S Zone</b>
The lot area for a non-residential use in an R1S zone shall be adequate to contain all structures within the required setbacks. In no event shall a lot be less than 7,200 square feet. There shall be no minimum width or depth.

**B.      Building Height.**

The maximum height of buildings shall not exceed 35 feet, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (EXCEPT telecommunication facilities), shall not exceed 70 feet.

**C.      Setback and Buffer Improvement Standards.**

1. Minimum Front Setback and Setback Abutting a Street [Section 2.103.06.C.1 as amended by Ordinance No. 2446, §8, passed on September 10, 2008.]:
  - a. The minimum setback abutting a street, or front property line shall be 20 feet plus any Special Setback, **Section 3.103.05**.
  - b. Off Street Parking, Maneuvering and Storage:
    - 1) Off street parking and storage shall be prohibited within a required setback or any yard abutting a street EXCEPT for parking and maneuvering within a driveway leading to a garage (or carport in the case of a manufactured home) or adjacent to a wall. [Section 2.103.06.C.1.b.1 as amended by Ordinance No. 2383, §8, passed March 16, 2005.]
    - 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from the closest edge of a shared driveway and 20 feet from a street right of way line.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
  - d. Vehicular Access: Vehicular access shall be permitted in conformance with **Section 3.104**.
2. Minimum Interior Side and Interior Rear Setbacks. [Section 2.103.06.C.2 as amended by Ordinance No. 2446, §8, passed on September 10, 2008.]
  - a. Dimensions:
    - 1) Side Setback. The minimum side setback for all lots shall be 5 feet, or 7% of the lot width, whichever is greater. [Section 2.103.06.C.2.a.1 as amended by Ordinance No. 2446, §8, passed on September 10, 2008.]
    - 2) Rear Setback: The minimum rear setback for all lots shall be 5 feet. [Section 2.103.06.C.2.a.2 as amended by Ordinance No. 2446, §8, passed on September 10, 2008.]
  - b. Off Street Parking and Maneuvering:

- 1) Off street parking, maneuvering and storage shall be permitted in the side and rear setback subject to applicable Special Use and Accessory Use standards, **Sections 2.203.03 and 2.201**. [Section 2.103.06.C.2.b.1 as amended by Ordinance No. 2446, §8, passed on September 10, 2008.]
  - 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from the closest edge of a shared driveway and a minimum of 20 feet from a street right of way line.
- c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards **Section 3.103.10**.

#### **2.103.07 Development Standards**

All development in the R1S zone shall comply with the applicable provisions of the **WDO**. The following standards specifically apply to uses in the R1S zone.

A. Off Street Parking.

Off street parking shall be subject to the standards of **Section 2.103.06 and Section 3.105**.

Setbacks and Lots, Generally.

Setbacks and lots shall be subject to **Section 3.103** EXCEPT **Section 3.103.09 B. and D** regarding rear yard setback projections.

B. Architectural Design Standards.

1. Site-built single family and duplex dwellings and manufactured homes on lots in the R1S zone, EXCEPT those existing on the effective date of the **WDO**, shall be subject to the architectural design standards of **Section 3.107.03**.
2. All primary buildings and structures, other than those noted in **Sections 2.102.07.C.1. and 2.** shall be subject to the architectural guidelines of **Section 3.107.06**.

C. Signs.

Signs shall be subject to **Section 3.110**. [Section 2.103.07D as amended by Ordinance No. 2359, §4, passed March 22, 2004.]

D. Accessory Uses and Structures.

By definition, prior to the construction or installation of an accessory structure, EXCEPT a fence or free standing wall, an existing primary permitted use, building or structure shall have been established on the same lot. Accessory structures in the rear setback shall not exceed 25 percent of the rear yard area and shall be set back 3 feet from any property line. The setback for accessory structures in the side yard shall be the same as the primary building.

E. Landscaping and Sidewalks.

1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of **Section 3.101 and 3.106**.

E.

2. No landscaping is required for single family and duplex dwelling lots EXCEPT conservation of significant trees, **Section 3.106.04**.
3. All uses, EXCEPT lots for single family and duplex dwellings shall be landscaped to the applicable standards of **Section 3.106**.

F. Lot Coverage.

Lot coverage by the primary and accessory structures EXCEPT accessory structures in the rear yard area, shall be: [Section 2.103.07.G as amended by Ordinance No. 2383, §9, passed March 16, 2005.]

1. A maximum of 40 percent for lots containing a primary building with an average height of 14 feet or less, and
2. A maximum of 35 percent for lots with a primary building with an average height of more than 14 feet.

G. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104**. No more than one primary building shall be located on a lot.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**

- b. **Subdivisions, *Section 3.108*; or**
  - c. **Planned Unit Development *Section 3.109*.**
- 2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, *Section 5.101.07*.**
  - b. **Replatting, *Section 3.108*.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## 2.104 Medium Density Residential (RM)

### 2.104.01 Permitted Uses

The following uses, when developed under the applicable development standards of the **WDO** are permitted in the RM zone.

- A. **Site-built single family dwelling and Duplex dwelling.**
- B. **Multiple family dwelling units, INCLUDING** apartment houses.
- C. **Assisted living facilities.** (62331)
- D. **Nursing care facilities.** (6231)
- E. **Rooming and boarding house.** (7213)
- F. **Group home or group care facilities.**
- G. **Child day care services.** (6244)
- H. **Parks and playgrounds.**
- I. **Rights of way, easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines, for storm water facilities and for pump stations.

### 2.104.02 Special Permitted Uses

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the RM zone.

- A. **Agricultural practices** without livestock subject to **Section 2.203.01**.
- B. **Boat and recreational vehicle storage** subject to **Section 2.203.03**.
- C. **Boat and recreational vehicle storage area** subject to **Section 2.203.04**.
- D. **Community club buildings and facilities** subject to **Section 2.203.05**.
- E. **Delivery services** subject to **Section 2.203.08**.
- F. **Facilities during construction** subject to **Section 2.203.10**.

G. **Golf course** without a driving range subject to *Section 2.203.11*.

G.

H. **Home occupation** subject to *Section 2.203.12*.

I. **House of worship** subject to *Section 2.203.13*.

J. **Manufactured dwelling park** subject to *Section 2.203.15*.

H.

K. **Manufactured home on a lot** subject to *Section 2.203.16*.

L. **Residential sales office** subject to *Section 2.203.18*.

I.

#### **2.104.03** **Conditional Uses**

The following uses may be permitted in the RM zone subject to the applicable development standards of the **WDO** and to the conditions of conditional use approval:

A. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.104.01* and communications facilities subject to *Section 2.204.03*.

B. **Elementary and secondary schools (6111)**.

C. **Golf driving range** in conjunction with a golf course.

D. **Off street parking** in conjunction with a non-residential use allowed in the zone.

#### **2.104.04** **Specific Conditional Uses**

The uses permitted by the following designation may be allowed in the RM zone subject to approval as a conditional use that conforms to the specific standards referenced below, the applicable provisions of the **WDO** and all other applicable conditions of approval.

A. **Historically or architecturally significant site** subject to *Section 2.204.02*.

#### **2.104.05** **Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202 and 2.203*.

A. **Garage** (or carport in the case of a manufactured home).

B. **Deck or patio**.

C. **Fence or free standing wall**.



- D. **Greenhouse or hobby shop.**
- E. **Private recreational facilities**, including swimming pool, hot tub or sauna, and game courts.
- J.
- F. **Personal storage structure.**

**2.104.06**      **Dimensional Standards**

[Section 2.104.06 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

The following dimensional standards shall be the minimum requirements for all development in the RM zone. If the RM zone has a Nodal Overlay on the Comprehensive Plan Map the dimensional standards of the RMN District, ***Section 2.115***, shall apply.

A.      Minimum Density

A minimum of 12.8 dwelling units per net acre (after excluding public rights-of-way, public tracts, common open space, and land protected by the RCW overlay district) shall be required, except for parcels less than one acre in size.

B.      Lot Standards. [Section 2.104.06.B as amended by Ordinance No. 2446, §20, passed on September 10, 2008.]

Lots in an RM zone shall comply with the standards for the subject use described in ***Tables 2.1.1 (single-family dwelling only), 2.1.5 and 2.1.6.***

(Table is on next page.)

K.

**TABLE 2.1.5      Lot and Density Standards for Duplex Dwellings; Multiple Family Residential Dwelling Units and Living Units; and MDP's in an RM Zone**

- A.      The minimum lot area for **duplex dwellings** on an individual lot shall be 8,000 square feet with a minimum width of 80 feet and minimum depth of 90 feet.
- B.      There shall be no minimum lot area or dimensions for multiple family residential dwellings units or living units in the RM zone.
- C.      The number of multiple family residential dwelling units; living units; or manufactured dwelling units within a MDP on a lot shall be regulated by:
  - 1.      Maximum residential density, not exceeding the following standards:
    - a.      **Multiple family dwellings:** 16 dwelling units per net buildable acre.
    - b.      **Assisted living facility** (62331) or **nursing care facility** (6231): 32 living units per net buildable acre.
    - c.      **Manufactured dwelling park:** 12 dwelling units per net buildable acre.
  - 2.      Compliance with the applicable open space and site design standards and guidelines of *Sections 2.104.07.C. and 2.203.15.*

**TABLE 2.1.6      Lot Standards for Non-Residential Uses in an RM Zone**

The lot area for a non-residential use in an RM zone shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

C.      Building Height.

The maximum height of buildings shall not exceed 35 feet, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (but EXCEPT telecommunication facilities), shall not exceed 70 feet.

D.      Setback and Buffer Improvement Standards.

- 1.      Minimum Front Setback and Setback Abutting a Street [Section 2.104.06.D.1 as amended by Ordinance No. 2446, §9, passed on September 10, 2008.]:
  - a.      Dimensions: The setback abutting a street shall be a minimum of 20 feet plus any Special Setback, *Section 3.103.05.*

- b. Off Street Parking, Maneuvering and Storage:
    - 1) Off street parking and storage shall be prohibited within a required setback or any yard abutting a street EXCEPT for parking and maneuvering within a driveway leading to a garage (or carport in the case of a manufactured home) or adjacent to a wall.
    - 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from the closest edge of a shared driveway and 20 feet from a street right of way line.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, *Section 3.103.10*.
  - d. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and *Section 3.104*.
2. Minimum Interior Side and Interior Rear Setbacks [Section 2.104.06.D.2 as amended by Ordinance No. 2446, §9, passed on September 10, 2008.]:
- a. Development in an RM zone, except for a single family dwelling and duplex dwelling, shall be subject to the setback and buffer requirements of *Table 2.1.7*. [Table 2.1.7 as amended by Ordinance No. 2446, §18, passed on September 10, 2008.

<b>TABLE 2.1.7 Interior Yard and Buffer Standards for RM Zones</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<b>RS or R1S zone; or</b> <b>Existing single family or duplex dwelling</b>	All interior yards shall be fully landscaped subject to <i>Section 3.106.</i>	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height.	24 ft. from any portion of primary building 16 ft. or less in height.  30 ft. from any portion of a primary building 16.1 ft. to 28 ft. in height.  36 ft. from any portion of a primary building 28.1 ft. to 35 ft. in height.
<b>RM, P/SP or CO zone; or</b> <b>Existing medium density residential unit</b>	All interior yards shall be fully landscaped subject to <i>Section 3.106.</i>	Wall requirements shall be determined in conjunction with the applicable Design Review process.	24 ft. from any portion of a primary building 16 ft. or less in height.  30 ft. from any portion of a primary building 16.1 ft. to 28 ft. in height.  36 ft. from any portion of a primary building 28.1 ft. to 35 ft. in height.
<b>DDC, NNC or CG zone</b>	All interior yards shall be fully landscaped subject to <i>Section 3.106.</i>	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height.	10 ft.
<b>IP, SWIR or IL zone</b>	All interior yards shall be fully landscaped subject to <i>Section 3.106.</i>	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height.	15 ft.

- b. A single family dwelling or duplex dwelling in the RM zone shall be subject to the setback and buffer improvement standards in *Section 2.102.06.* [Section 2.104.06.D.2.b as amended by Ordinance No. 2446, §21, passed on September 10, 2008.]
- c. The building setback from a private access easement shall be a minimum of 5 feet.
- d. Off Street Parking, Maneuvering and Storage
  - 1) Off street parking and storage shall be prohibited within a required setback or any yard abutting a street EXCEPT for parking and maneuvering within a driveway leading to a garage (or carport in the case of a manufactured home) or adjacent to a wall.

- 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from the closest edge of a shared driveway and 20 feet from a street right of way line.
- L.
- e. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
  - f. Vehicular Access: Permitted in conformance with **Section 3.104**.

#### **2.104.07 Development Standards**

[Section 2.104.07 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

All development in the RM zone shall comply with the applicable provisions of the **WDO**.

The following standards specifically apply to uses in the RM zone. If the RM zone has a Nodal Overlay on the Comprehensive Plan Map the development standards of the RMN District, **Section 2.115**, shall apply.

##### **A. Off Street Parking.**

Off street parking shall be subject to the standards of **Section 2.104.06 and Section 3.105**.

##### **B. Setbacks and Lots, Generally.**

Setbacks and lots shall be subject to **Section 3.103**.

##### **C. Architectural Design Guidelines and Open Space Standards.**

1. Multiple family dwellings shall be subject to the design standards or guidelines of **Section 3.107.05**. [Section 2.104.07.C.1 as amended by Ordinance No. 2446, §22, passed on September 10, 2008.]
2. Site-built single family and duplex dwellings and manufactured homes on lots, and all manufactured dwellings within a manufactured dwelling park (MDP), in the RM zone, EXCEPT those existing on the effective date of the **WDO** or those located in the NCOD, shall be subject to the architectural design standards of **Section 3.107.03**.
3. All single family and duplex dwellings on lots in an RM zone located within the Neighborhood Conservation Overlay District (NCOD) shall

- be subject to the architectural guidelines of **Section 3.107.04**.
- M.
4. All primary buildings and structures, other than those noted in **Sections 2.104.07.C.1**, 2. and 3. shall be subject to the architectural guidelines of **Section 3.107.06**
- D. Signs.
- Signs shall be subject to Section 3.110.
- E. Accessory Uses and Structures.
- N.
- By definition, prior to the construction or installation of an accessory structure, EXCEPT a fence or free-standing wall, an existing primary permitted use, building or structure shall be established on the same lot. Accessory uses and structures shall be subject to **Section 2.201** Accessory Uses and Structures.
- F. Landscaping and Sidewalks.
1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of **Section 3.101 and 3.106**.
2. The subject property shall be landscaped to the standards of **Sections 3.106 and 3.107.03**.
3. Common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.
- G. Lot Coverage.
- Lot coverage by the primary single family and duplex dwellings and associated accessory structures in a RM zone shall be a maximum of 40 percent for lots containing a primary building with a average height of 14 feet or less and a maximum of 35 percent for lots with a primary building with an average height of more than 14 feet.
- H. Property Disposition.
- All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104**.
1. New lots of record shall be subject to the following standards and procedures:

- a. **Partitions, *Section 3.108*;**
  - b. **Subdivisions, *Section 3.108*; or Planned Unit Development *Section 3.109*.**
  - c. **Planned Unit Development *Section 3.109*.**
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
- a. **Property Line Adjustment, *Section 5.101.07*.**
  - b. **Replatting, *Section 3.108*.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## 2.105 Commercial Office (CO)

### 2.105.01 Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO*, are permitted in the CO zone.

#### Residential

1. **One dwelling unit** in conjunction with a commercial use.

#### C. Transportation & Warehousing

1. **Postal service.** (491)

#### D. Information

O.

**Radio & TV studios & offices** EXCEPT antennae or towers. (5131)

**Cable networks.** (5132)

**Telecommunications** (5133) EXCEPT telecommunication facilities subject to  
*Section 2.204.03.*

**Information & data processing.** (514)

#### E. Finance & Insurance

1. **Finance and insurance** (52) EXCEPT pawn shops (522298) & check cashing, pay day loan and cash transfer establishments [other than banks] as a predominant, ancillary, or required supporting use.

[Section 2.105.01.E.2 as amended by Ordinance No. 2423, §3, effective on July 28, 2007.]

#### F. Real Estate & Rental & Leasing

**Real estate** (531)

**Rental & leasing**, without outdoor display or storage (532) EXCEPT videotape and disc rental. (532230)

#### G. Professional, Scientific & Technical Services

**Legal services.** (5411)

**Accounting.** (5412)

**Architects and engineers.** (5413)

**Specialized design services** (5414) INCLUDING interior design services.

**Computer system design.** (5415)



**Management consulting.** (5416)  
**Advertising.** (5418)  
**Other professional services** (5419), EXCEPT veterinary service  
(541940) not contained in a building. Administrative & Support Services

H. Administrative and Support Services

1. **Administrative and facilities support services.** (5611 and 5612)
2. **Employment services.** (5613)
3. **Business support services** INCLUDING copy shops. (5614)
4. **Travel and tour agencies.** (5615)
5. **Investigation and security services.** (5616)
6. **Services to buildings and dwellings** (5617), offices only.
7. **Other support services.** (56199)

P.

I. Educational Service

**Business schools.** (6114)  
**Technical and trade schools.** (6115)

J. Health Care & Social Services

**Ambulatory health services** (621) EXCEPT ambulance service. (62191)  
**Social assistance** (624) INCLUDING child day care services.

K. Arts, Entertainment & Recreation

**Museums and historic sites** (712) EXCEPT zoos. (712130)  
**Fitness and recreation sports centers.** (71391)

L. Accommodation & Food Service

**Hotels** (EXCEPT casino hotels) **and motels.** (72111)  
**Bed and breakfast inns.** (721191)  
**Food service and drinking places** (722) EXCEPT food contractors (7231) and  
mobile food service.

M. Other Services

**Personal care services** (8121) INCLUDING barber shops and beauty salons.  
**Funeral homes.** (812210)  
**Photo finishing.** (81292)  
**Parking lots and garages** (81293) EXCEPT extended vehicle storage.  
(4939190)  
**All Other Personal Services** (81299) INCLUDING bail bonding and consumer  
buying services.

**Religious, civic, professional and similar organizations. (813)**

N. Public Administration

**Public Administration (92)** INCLUDING government offices, courts and fire protection.

O. Streets & Utilities

**Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines and for storm water facilities and for pump stations.

**2.105.02**      **Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the CO zone.

- A.      **Agricultural practices** without livestock subject to **Section 2.203.02**.
- Q.
- B.      **Delivery services** subject to **Section 2.203.08**.
- R.
- C.      **Facilities during construction** subject to **Section 2.203.10**.

**2.105.03**      **Conditional Uses**

The following uses may be permitted in the CO zone subject to the applicable development standards of the **WDO** and to the conditions of conditional use approval:

- A.      **Ambulance service.** (62191)
- B.      **Multiple family dwelling units, INCLUDING** apartment houses.
- C.      **Assisted living facilities.** (62331)
- D.      **Nursing care facilities.** (6231)
- E.      **Rooming and boarding house.** (7213)
- F.      **Group home or group care facilities.**
- G.      **Government and public utility buildings and structures EXCEPT** uses permitted in **Section 2.105.01** and telecommunications facilities subject to **Section 2.204.03**.

**2.105.04**      **Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202 and 2.203*.

- A. **Fence or free standing wall.**

**2.105.05      Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the CO zone.

- A. Lot Standards.

Lots in a CO zone shall comply with the applicable standards of *Table 2.1.8*.

<b>TABLE 2.1.8      Lot Standards for Uses in a CO Zone</b>	
A.	In an CO zone the lot area for a non-residential use shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.
B.	In a CO zone, residential use shall be subject to the lot standards of <i>Table 2.1.5</i> .

- B. Building Height.

The maximum height of buildings shall not exceed 35 feet, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (EXCEPT telecommunication facilities), shall not exceed 70 feet.

- C. Setback and Buffer Improvement Standards.

1. Minimum Front Setback and Setback Abutting a Street [Section 2.105.05.C.1 as amended by Ordinance No. 2446, §10, passed on September 10, 2008.]:

- a. Dimensions:

- 1) The minimum setback abutting a street shall be 15 feet plus any Special Setback, *Section 3.103.05*.

[Section 2.105.05.C.1.a.2 repealed by Ordinance No. 2383, §13, passed March 16, 2005.]

- b. Off Street Parking and Maneuvering:

- 1) Off street parking, maneuvering and storage shall be prohibited within a required setback EXCEPT for

parking, maneuvering and storage adjacent to a wall.  
[Section 2.105.05.C.1.b.1 as amended by Ordinance No. 2383, §14, passed March 16, 2005.]

- 2) The entrance to a garage shall be set back a minimum of 20 feet from the closest edge of a shared driveway and 20 feet from a street right of way line.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
  - d. Vehicular Access: Permitted in conformance with **Section 3.104**.
2. Minimum Interior Side and Rear Setbacks [Section 2.105.05.C.2 as amended by Ordinance No. 2446, §10, passed on September 10, 2008.]:
- a. Development in an CO zone, EXCEPT conditional uses permitted by **Section 2.105.03. A. through E.**, shall be subject to the setback and buffer requirements of **Table 2.1.9**. Conditional uses permitted by **Section 2.105.03. A. through E.** shall be subject to the setback and buffer requirements of **Table 2.1.7**.

<b>TABLE 2.1.9 Interior Yard and Buffer Standards for Non-Residential Uses in CO Zones</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<b>RS, R1S or RM, zone</b>	All interior yards shall be fully landscaped subject to <b>Section 3.106</b> .	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height.	10 ft.
<b>DDC, NNC, CG, IP, SWIR, or IL zone</b>	All interior yards shall be fully landscaped subject to <b>Section 3.106</b> .	Wall requirements shall be determined in conjunction with the applicable Design Review process.	15 ft.
<b>P/SP or CO zone</b>	All interior yards shall be fully landscaped subject to <b>Section 3.106</b> .	No wall required.	10 ft.

[Table 2.1.9 as amended by Ordinance No. 2391, §3, acknowledged on December 31, 2006]

- b. The building setback from a private access easement shall be a minimum of 5 feet.
- c. Off Street Parking, Maneuvering and Storage:
  - 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking maneuvering and storage adjacent to a wall. [Section 2.105.05.C.2.c.1 as

amended by Ordinance No. 2383, §15, passed March 16, 2005.]

- 2) The entrance to a garage shall be set back a minimum of 20 feet from the closest edge of a shared driveway and 20 feet from a street right of way line.
- 3) The distance between the sidewalk on a public street and a loading dock shall be sized to preclude vehicles using the dock from projecting over the sidewalk.

- d. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
- e. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and **Section 3.104**.

S.  
**2.105.06**      **Development Standards**

All development in the CO zone shall comply with the applicable provisions of the **WDO**. The following standards specifically apply to uses in the CO zone.

T.

A.      Off Street Parking.

Off street parking shall be subject to the standards of **Section 2.105.05** and **Section 3.105**.

B.      Setbacks and Lots, Generally.

Setbacks and lots shall be subject to **Section 3.103**.

C.      Architectural Design Guidelines and Open Space Standards.

1. Multiple density residential buildings shall be subject to the design standards or guidelines of **Section 3.107.05**.
2. All primary buildings and structures, other than those noted in **Section 2.105.05.C.1**, shall be subject to the architectural guidelines of **Section 3.107.06**.

D.      Signs.

Signs shall be subject to **Section 3.110**. [Section 2.105.06D as amended by Ordinance No. 2359, §6, passed March 22, 2004.]

E.      Residential Density.

The density and number of medium density residential units permitted in a CO zone shall be subject to the requirements of **Table 2.1.5**.

F. Landscaping and Sidewalks.

1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of **Section 3.101 and 3.106**.
2. The subject property shall be landscaped to the standards of **Section 3.106 and 3.107.03**.
3. Common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

G. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104**.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**
  - b. **Subdivisions, Section 3.108; or**
  - c. **Planned Unit Development Section 3.109.**

U.

2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, Section 5.101.07.**
  - b. **Replatting, Section 3.108.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## 2.106 Commercial General (CG)

Commercial districts are centers of business and civic life. The General Commercial District regulations apply to those commercial areas outside or adjacent to the central business area. The General Commercial district is intended to:

- A. Promote efficient use of land and urban services;
- B. Accommodate automobile-oriented and automobile-dependent uses;
- C. Use appropriate design standards to guide the appearance and functionality of development sites;
- D. Provide for visitor accommodations and services;
- E. Create a mixture of land uses that encourages employment and housing options in close proximity to one another;
- F. Provide connections to and appropriate transitions between residential areas and commercial areas;
- G. Allow and encourage residential development in the Downtown Gateway subdistrict as a complementary use to commercial uses in the district and in the adjacent Downtown area;
- H. Restrict land extensive commercial, storage, and industrial uses in the Downtown Gateway sub-district.

[Adopted by Ordinance 2463, passed January 25, 2010.]

### **2.106.01 Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO**, are permitted in the CG zone.

- A. **Residential**
  - 1. **One dwelling unit** in conjunction with a commercial use.
  - 2. Multiple-family dwellings (rental or condominium) project at a net density of between 12 and 32 dwelling units per acre are permitted in the Downtown Gateway sub-district. Multiple-family dwellings are subject to the dimensional standards and other development standards of Section 2.104 unless the multiple-family dwellings are built as part of a vertical

mixed use development.

3. Multiple-family dwellings (rental or condominium) built as part of a vertical mixed use development at a maximum net density of 32 dwelling units per acre are permitted in the Downtown Gateway sub-district. Multiple-family dwellings in a vertical mixed use development are subject to the dimensional standards and other development standards of the CG district.
4. Attached single-family residences at a net density of 12 to 24 dwelling units per acre are permitted in the Downtown Gateway sub-district. [§2-4 adopted by Ordinance 2463, passed January 25, 2010.]

B. **Special Trade Contractors**

1. **Plumbing, heating and air-conditioning contractors.** (235110) In the Gateway sub-district, this use is allowed only when located entirely within a building.
2. **Paper and wall coving contractors.** (235210) In the Gateway sub-district, this use is allowed only when located entirely within a building.
3. **Masonry, drywall, insulation and tile.** (2354) In the Gateway sub-district, this use is allowed only when located entirely within a building.
4. **Floor laying contractors.** (235520) In the Gateway sub-district, this use is allowed only when located entirely within a building.
5. **Roofing, siding, and sheet metal construction contractors** (235610) entirely within a building.
6. **Glass and glazing contractors.** (235920) In the Gateway sub-district, this use is allowed only when located entirely within a building.
7. **Building equipment and other machinery installation contractors.** (235950)
8. **Ornamental ironwork contracting.** (235990) In the Gateway sub-district, this use is allowed only when located entirely within a building. [§1-4, 6, and 8 as amended by Ordinance 2463, passed January 25, 2010.]

C. **Fabricated metal products manufacturing**

1. **Fabricated metal product manufacturing** (332) entirely within a building.

D. **Furniture and Related Products Manufacturing, except in the Gateway sub-district.** [§D as amended by Ordinance 2463, passed January 25, 2010.]

1. Household and institutional furniture and kitchen cabinet manufacturing (3371) entirely within a building.



E. **Retail Trade**

1. **Automotive parts** (44131) without installation.
2. **Furniture and home furnishings.** (442)
3. **Electronics and appliance stores.** (443)
4. **Building materials and garden equipment and supplies.** (444) with all outdoor storage and display enclosed by a 7' masonry wall.
5. **Food and beverage stores.** (445)
6. **Health and personal care stores.** (446)
7. **Clothing and accessory stores.** (448)
8. **Sporting goods, hobby, book and music stores.** (451)
9. **General merchandise stores.** (452)
10. **Misc. retail** (453) EXCEPT used merchandise stores (4533), other than antique shops, and EXCEPT manufactured (mobile) home dealers. (45393)

F. **Transportation & Warehousing**

1. **Postal service.** (491)

G. **Information**

1. **Publishing.** (511)
2. **Motion picture theaters** (512131) EXCEPT drive-ins.
3. **Radio and TV.** (5131)
4. **Cable networks.** (5132)
5. **Telecommunications.** (5133) EXCEPT telecommunication facilities subject to Section 2.204.03.
6. **Information and data processing.** (514)

H. **Finance and Insurance**

1. **Finance and insurance** (52) EXCEPT pawn shops (522298) and check cashing, pay day loan and cash transfer establishments [other than banks] as a predominant, ancillary, or required supporting use. Pawn shops (522298) and check cashing, pay day loan, and cash transfer establishments (other than banks) are not permitted in the Gateway sub-district. [As amended by Ordinance No. 2383, §16, passed March 16, 2005, Ordinance No. 2423, §7, effective on July 28, 2007, and Ordinance 2463, passed January 25, 2010.]

I. **Real Estate and Rental and Leasing**

5. **Real estate.** (531)
6. **Video tape and disc rental.** (532230)
7. **General rental centers** (532310) with all outdoor storage and display on

a paved surface. [§2 and 3 as amended by Ordinance No. 2423, §4, effective on July 28, 2007, § 3 as amended by Ordinance 2463, passed January 25, 2010.]

J. Professional, Scientific & Technical Services

1. **Legal services.** (5411)
2. **Accounting.** (5412)
3. **Architects and engineers.** (5413)
4. **Specialized design services.** (5414)
5. **Computer system design.** (5415)
6. **Management consulting.** (5416)
7. **Advertising.** (5418)
8. **Other professional services** (5419) EXCEPT veterinary service contained entirely within a building. (541940)

K. Administrative & Support Services

1. **Administrative and support services** (561) INCLUDING employment, travel and investigation.
2. **Management and corporate offices** (551) [§2 adopted by Ordinance 2463, passed January 25, 2010.]

L. Educational Service

1. **Business schools.** (6114)
2. **Technical and trade schools.** (6115)

M. Health Care and Social Services

1. **Ambulatory health services** (621) EXCEPT ambulance service. (62191)
2. **Social assistance** (624) INCLUDING child day care services.

N. Arts, Entertainment and Recreation

1. **Performing arts and spectator sports**, except in the Gateway sub-district. (711)
2. **Museums and historic sites** (712) EXCEPT zoos. (712130)
3. **Fitness and recreational sports.** (71391)
4. **Bowling centers.** (71395)
5. **Other amusements** INCLUDING ballrooms, except in the Gateway sub-district. (713990) [§1 and 5 as amended by Ordinance 2463, passed January 25, 2010.]

O. Accommodation & Food Service

1. **Hotels** (EXCEPT casino hotels) and motels. (72111)
2. **Bed-and-breakfast inns.** (721191)
3. **Food service and drinking places** (722) EXCEPT mobile food service.

P. Other Services

1. **Electronic and precision equipment repair.** (8112)
2. Electric motor repair entirely within a building.
3. **Reupholstery and furniture repair.** (81142)
4. **Leather repair.** (81143)
5. **Personal care services** (8121) INCLUDING barber shops and beauty salons.
6. **Funeral homes.** (812210)
7. **Dry cleaning and laundry service** (8123) EXCEPT linen supply. (81233)
8. **Photo finishing.** (81292)
9. **Parking lots and garages** (81293) EXCEPT extended vehicle storage. (4939190)
10. **All other personal services** (812990) INCLUDING bail bonding and consumer buying services.
11. **Religious, civic and social organizations.** (813)

Q. Public Administration

1. **Public administration.** (92)

R. Streets & Utilities

1. **Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines and for storm water facilities and for pump stations.

**2.106.02 Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the CG zone.

- A. **Agricultural practices** without livestock, except in the Gateway sub-district, subject to **Section 2.203.02**. [§A as amended by Ordinance 2463, passed January 25, 2010.]
- B. **Complementary residential uses** subject to **Section 2.203.06**.
- C. **Delivery services** subject to **Section 2.203.08**.

- D. **Facilities during construction** subject to *Section 2.203.10*.
- E. **Temporary outdoor marketing and special events** subject to *Section 2.203.19*.

**2.106.03**      **Conditional Uses**

The following uses may be permitted in the CG zone subject to the applicable development standards of the *WDO* and the conditions of conditional use approval:

A.      **Retail Trade**

- 1.      **Motor vehicle and parts dealers** (441) EXCEPT automotive parts without installation.
- 2.      **Tractor and heavy equipment dealers**, except in the Gateway sub-district.
- 3.      **Gasoline stations**. (447)
- 4.      **Used merchandise stores**, other than antique shops. (4533)
- 5.      **Manufactured (mobile) home dealers**, except in the Gateway sub-district. (453930) [§2 and 5 as amended by Ordinance 2463, passed January 25, 2010.]

B.      **Transportation & Warehousing**

- 1.      **Urban transit system**. (48511)
- 2.      **Interurban and rural transit**. (4852)
- 3.      **Taxi service**. (48531)
- 4.      **Limousine service**, except in the Gateway sub-district. (4853)
- 5.      **School transportation**, except in the Gateway sub-district. (4854)
- 6.      **Charter bus service**, except in the Gateway sub-district. (4859)
- 7.      **Special needs transportation**, except in the Gateway sub-district. (485991)
- 8.      **Motor vehicle towing**, except in the Gateway sub-district. (48841)
- 9.      **Self- and mini-storage**, except in the Gateway sub-district. [§4-9 as amended by Ordinance 2463, passed January 25, 2010.]

C.      **Finance and Insurance**

- 1.      **Pawn shops**, except in the Gateway sub-district. (522298)
- 2.      **Check cashing, pay day loans and cash transfer establishments**, other than banks, except in the Gateway sub-district. [§1 and 2 as amended by Ordinance 2463, passed January 25, 2010.]

D.      **Professional, Scientific and Technical Services**

1. **Scientific research and development.** (5417)
2. **Veterinary service.** (541940)

E. **Health Care and Social Services**

1. **Ambulance service.** (62191)

F. **Accommodations and Food Service**

1. **Recreational vehicle parks**, except in the Gateway sub-district. (7212)  
[§1 as amended by Ordinance 2463, passed January 25, 2010.]

G. **Other Services**

1. **Automotive maintenance.** (8111) This use is allowed only when located entirely within an enclosed building, except for short-term outdoor parking of vehicles waiting for service.
2. **Commercial and industrial equipment repair**, except in the Gateway sub-district. (8113) [§1 and 2 as amended by Ordinance 2463, passed January 25, 2010.]
3. **Home goods repair** EXCEPT upholstery (81142) and leather repair (81143). (8114)
4. **Linen supply.** (81233)

H. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.106.01* and telecommunications facilities subject to *Section 2.204.03*.

**2.106.04 Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202 and 2.203*.

- A. **Fence or free standing wall.**

**2.106.05 Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the CG zone.

- A. Lot Standards.

Lots in a CG zone shall comply with the applicable standards of *Table 2.1.10*.

<p><b>TABLE 2.1.10 Lot Standards for Uses in a CG Zone</b></p>
--

<p>In a CG zone the lot area for a non-residential use shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.</p>
--

B. Building Height.

1. The maximum height of buildings shall not exceed 70 feet, or the heights illustrated on Section 6.1 Figure 6.13 for properties in the Gateway subdistrict, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (EXCEPT telecommunication facilities), shall not exceed 100 feet.
2. Exceptions to the applicable maximum height standards for properties in the Gateway subdistrict may be permitted through the conditional use process. [§B as amended by Ordinance 2463, passed January 25, 2010.]

C. Setback and Buffer Improvement Standards.

1. Minimum Front Setback and Setback Abutting a Street [Section 2.106.05.C.1 as amended by Ordinance No. 2446, §11, passed on September 10, 2008.]:
  - a. Dimensions:
    - 1) The minimum setback abutting a street shall be 15 feet plus any Special Setback, **Section 3.103.05.**

[Section 2.106.05.C.1.a.2 repealed by Ordinance No. 2383, §17, passed March 16, 2005.]
  - b. Off Street Parking and Maneuvering:
    - 1) Off street parking and storage shall be prohibited within a required yard or special setback EXCEPT for parking and storage adjacent to a wall. [Section 2.106.05.C.1.b.1 as amended by Ordinance No. 2383, §18, passed March 16, 2005.]
    - 2) The distance between the sidewalk on a public street and a loading dock shall be sized to preclude vehicles using the dock from projecting over the sidewalk.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10.**
  - d. Vehicular Access: Permitted in conformance with **Section 3.104.**
2. Minimum Interior Side and Rear Setbacks [Section 2.106.05.C.2 as amended by Ordinance No. 2446, §11, passed on September 10, 2008.]:

- a. Development in a CG zone shall be subject to the setback and buffer requirements of **Table 2.1.11**.

<b>TABLE 2.1.11 Interior Yard and Buffer Standards for CG Zones</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<b>RS, R1S, or RM zone</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height.	10 ft.
<b>CO, CG, DDC, NNC, P/SP, IP, SWIR or IL zone</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	<p>Alternative A:</p> <p>Wall requirements shall be determined in conjunction with the applicable Design Review process.</p> <p>Alternative B:</p> <p>No wall required.</p>	<p>Alternative A:</p> <p>5 ft.</p> <p>Alternative B:</p> <p>Zero setback abutting a building wall.</p>

[Table 2.1.11 as amended by Ordinance 2391, §3, acknowledged on December 22, 2006.]

- b. The minimum building setback from a private access easement shall be 5 feet.
- c. Off street parking, Maneuvering and Storage:
- Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. [Section 2.106.05.C.2.c as amended by Ordinance No. 2383, §19, passed March 16, 2005.]
- d. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
- e. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and **Section 3.104**.

## **2.106.06 Development Standards**

All development in the CG zone shall comply with the applicable provisions of the **WDO**. The following standards specifically apply to uses in the CG zone.

- A. Off Street Parking.

Off street parking shall be subject to the standards of **Section 2.106.05 and Section 3.105.**

B. Setbacks and Lots, Generally.

Setbacks and lots shall be subject to **Section 3.103.**

C. Architectural Design Guidelines.

1. Multiple density residential buildings shall be subject to the design standards or guidelines of **Section 3.107.05.**
2. All primary buildings and structures, EXCEPT those described in **Section 2.106.05.C.1**, shall be subject to the architectural guidelines of **Section 3.107.06.**

D. Signs.

Signs shall be subject to **Section 3.110.** [Section 2.106.06D as amended by Ordinance No. 2359, §7, passed March 22, 2004.]

E. Landscaping and Sidewalks.

1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of **Section 3.101 and 3.106.**
2. The subject property shall be landscaped to the standards of **Section 3.106.**
3. Common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

F. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104.**

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**



- b. **Subdivisions, *Section 3.108***; or
  - c. **Planned Unit Development *Section 3.109***.
- 2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, *Section 5.101.07***.
  - b. **Replatting, *Section 3.108***.
  - c. **Vacation**, applicable Oregon Revised Statutes.

## 2.107 Downtown Development and Conservation (DDC)

The Downtown Development and Conservation District regulations apply to the central business area. The district is intended as Woodburn's center of vital retail activity, services, entertainment, housing, mixed-use, civic buildings and public spaces. The historic character of the downtown, together with its pedestrian-oriented architecture, streets and public spaces, define the district.

The Downtown Development and Conservation District is intended to:

- A. Promote efficient use of land and urban services;
- B. Create a mixture of land uses that encourages employment and housing options in close proximity to one another;
- C. Provide formal and informal community gathering places and opportunities for socialization (i.e., along an active street front);
- D. Encourage pedestrian-oriented development;
- E. Create a distinct storefront character in the Downtown Development and Conservation District;
- F. Provide connections to and appropriate transitions between nearby residential areas and the downtown;
- G. Implement design standards and guidelines that maintain and enhance the City's historic architecture.

[Adopted by Ordinance 2463, passed January 25, 2010.]

### **2.107.01 Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO**, are permitted in the DDC zone.

#### **A. Residential**

- 1. **One dwelling unit** in conjunction with a commercial use.
- 2. Multiple-family dwellings above ground floor commercial uses or other permitted uses.
- 3. Multiple family dwelling units, **INCLUDING** apartment houses.
- 4. Attached single-family dwellings at a net density of 12 to 16 dwelling units per acre. [§2-4 as adopted by Ordinance 2463, passed January 25,

2010.]

**B. Retail Trade**

1. **Bakeries.** (31181)
2. **Printing and related support activities** (323)
3. **Furniture and home furnishing stores** (442) INCLUDING:
  - a. Floor coverings and installation stores. (44221)
  - b. Window treatment and installation stores. (442291)
  - c. Used furniture stores. (45331)
4. **Electronics and appliance stores and repair** (44310) INCLUDING:
  - a. Camera shops. (44313)
  - b. Radio and TV stores. (443112)
  - c. Sewing machines stores. (443111)
5. **Building material and garden equipment dealers** (4441) LIMITED TO:
  - a. Paint, wallpaper, and interior decorating stores. (444120)
  - b. Hardware stores. (44413)
  - c. Light fixture stores. (444190)
6. **Garden supply store.** (44422)
7. **Food and beverage stores** LIMITED TO:
  - a. Delicatessen stores.
  - b. Meat markets. (44521)
  - c. Fish markets LIMITED TO sales only. (44522)
8. **Other specialty stores** (44529) LIMITED TO:
  - a. Candy, nut, confectionery stores. (445292)
  - b. Dairy products stores LIMITED TO sales only. (44529)
9. **Health and personal care stores** LIMITED TO:
  - a. Drug stores. (44611)
  - b. Optical goods stores. (44613)
  - c. Health food stores. (446191)
  - d. Hearing aid stores. (446199)

10. **Clothing and clothing accessories (448) LIMITED TO:**
  - a. Clothing stores. (44810)
  - b. Dressmaker and tailor shops.
  - c. Furriers and fur shops. (44819)
  - d. Jewelry, watch, and clock stores. (44815 & 44831)
  - e. Shoe stores. (44823)
  - f. Luggage stores. (44832)
11. **Sporting goods stores (445111) INCLUDING:**
  - a. Bicycle shops. (445111)
  - b. Gunsmiths and repair. (45111)
12. **Hobby, toy, and game stores (45112) LIMITED TO:**
  - a. Hobby shops. (45112)
  - b. Toy stores. (45112)
13. **Sewing, needlework and piece goods stores. (45113)**
14. **Music, piano, and musical instrument stores. (45114)**
15. **Record and CD stores. (45122)**
16. **Book stores. (4523)**
17. **Department stores. (45211)**
18. **Other general merchandise stores (4529) INCLUDING variety stores. (45299)**
19. **Miscellaneous store retailers. (453)**
  - a. Antique shops.
  - b. Artists supply stores. (453998)
  - c. Business machines, typewriters and repair. (453210)
  - d. Florist shops. (45311)
  - e. Gift, novelty, souvenir shops. (45322)
  - f. Greeting card stores. (45322)
  - g. Mail order house. (45411)
  - h. Orthopedic and artificial limb stores.
  - i. Pet stores. (45391)
  - j. Stationery stores. (45321)
  - k. Used merchandise stores. (45331)

**C. Transportation & Warehousing**

1. **Support Activities for Rail Transportation** (488210)
2. **Postal service.** (491)

**D. Information**

1. **Newspaper, periodical, and book publishing.** (5111)
2. **Radio and TV studios and offices** (5131) EXCEPT antennae and towers.
3. **Cable networks.** (5132)
4. **Telecommunications** (5133) EXCEPT telecommunication facilities subject to *Section 2.204.03*.
5. **Information & data processing.** (514)

**E. Finance and Insurance**

1. **Finance and insurance** (52) EXCEPT check cashing, pay day loan and cash transfer establishments [other than banks] as a predominant, ancillary, or required supporting use.

**F. Real Estate and Rental and Leasing**

1. **Real estate.** (531)
2. **Rental & leasing,** without outdoor display or storage. (532)

**G. Professional, Scientific & Technical Services**

1. **Legal services.** (5411)
2. **Accounting.** (5412)
3. **Architects and engineers.** (5413)
4. **Specialized design services** (5414) INCLUDING interior design services.
5. **Computer system design.** (5415)
6. **Management consulting.** (5416)
7. **Advertising.** (5418)
8. **Other professional services** (5419), EXCEPT veterinary service (541940) not contained in a building.

**H. Administrative & Support Services**

1. **Administrative and facilities support services.** (5611 and 5612)
2. **Employment services.** (5613)
3. **Business support services** INCLUDING copy shops. (5614)
4. **Travel and tour agencies.** (5615)

5. **Investigation and security services.** (5616)
6. **Services to buildings and dwellings** (5617), offices only.
7. **Management and corporate offices** (551) [\$7 as adopted by Ordinance 2463, passed January 25, 2010.]
8. **Other support services.** (56199)

**I. Educational Service**

1. **Educational services** (611) both public and private, LIMITED TO:
  - a. Elementary and secondary schools. (6111)
  - b. Community college. (6112)
  - c. Business schools. (6114)
  - d. Technical and trade schools. (6115)

**J. Health Care & Social Services**

1. **Ambulatory health care** (621) EXCEPT Ambulance service. (62191)
2. **Social services** (624) INCLUDING child day care services.

**K. Arts, Entertainment & Recreation**

1. **Museums and historic sites** (712) EXCEPT zoos (712130).
2. **Fitness and recreational sports** (71394). [Section 2.107.01.K.2 as amended by Ordinance No. 2383, §20, passed March 16, 2005.]
3. **Community center.**
4. **Taxidermists.** (71151)

[Section 2.107.01.L.3 as amended by Ordinance No. 2423, §2, effective on July 28, 2007.]

**L. Accommodation & Food Service**

1. **Hotels** (EXCEPT casino hotels) **and motels.** (72111)
2. **Bed and breakfast inns.** (21191)
3. **Food service and drinking places** (722) EXCEPT food contractors (72231) and mobile food service.

**M. Other Services**

1. **Personal care services** (8121) INCLUDING:
  - a. Barber shops. (812111)
  - b. Beauty shops. (812112)
2. **Funeral home.** (812210)
3. **Laundry, self service.** (81231)
4. **Dry cleaning, self service.** (81231)

5. **Photo finishing.** (81292)
6. **Parking lots and garages** (81293) EXCEPT extended vehicle storage. (493190)
7. **All Other Personal Services** (81299) INCLUDING bail bonding and consumer buying services.
8. **Religious, civic, professional and similar organizations.** (813)

**N. Public Administration**

1. **Public administration** (92) INCLUDING government offices, courts, and police and fire stations.

**O. Streets and Utilities**

1. **Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil , electric and communication lines and for storm water facilities and for pump stations.

**2.107.02 Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the DDC zone:

- A. **Complementary residential use** subject to **Section 2.203.06**.
- B. **Craft industries** subject to **Section 2.203.07**.
- C. **Delivery services** subject to **Section 2.203.08**.
- D. **Facilities during construction** subject to **Section 2.203.10**.
- E. **Temporary outdoor marketing and special events** subject to **Section 2.203.19**.

**2.107.03 Conditional Uses**

The following uses may be permitted subject to obtaining conditional use approval:

- A. **Nursing care facilities.** (6231)
- B. **Assisted care facilities.** (62331)
- C. **Grocery store, food market, food store.** (44511)
- D. **Gasoline stations** (44719) INCLUDING repair services.

- E. **Wine shops.**
- F. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.107.01* and telecommunications facilities subject to *Section 2.204.03*.

[As amended by Ordinance 2463, passed January 25, 2010.]

#### **2.107.04      Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202 and 2.203*.

- A. **Fence or free standing wall.**

#### **2.107.05      Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the DDC zone.

- A. Lot Standards.

Lots in a DDC zone shall comply with the applicable standards of *Table 2.1.12*.

<b>TABLE 2.1.12      Lot Standards in a DDC Zone</b>
In a DDC zone the lot area shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

- B. Building Height.

1. The maximum height of buildings shall not exceed the heights illustrated on Section 6.1 Figure 6.13 for properties in the DDC zoning district, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (EXCEPT telecommunication facilities), shall not exceed 100 feet.
2. Exceptions to the applicable maximum height standard for properties in the DDC district may be permitted through the conditional use process. [§1 and 2 as amended by Ordinance 2463, passed January 25, 2010.]

- C. Setback and Buffer Standards.

Setback and buffers are subject to the DDC design guidelines of *Section 3.107.07*.



## **2.107.06**      **Development Standards**

All development in the DDC zone shall comply with the applicable provisions of the **WDO**. Where the standards of the DDC zone and the **WDO** differ, the standards of the DDC shall prevail. Standards listed in this section as “shall” are mandatory standards. Guidelines which state “should” or “encouraged” are not mandatory, but are considered desirable by the City. [As amended by Ordinance 2463, passed January 25, 2010.]

### **A. Purpose.**

1. The purpose of these development standards is to guide the design of buildings constructed in the DDC zoning district to ensure that, through appropriate use of facades, windows, building orientation, and architectural details, new structures and alterations of existing structures are physically and visually compatible with other buildings within the downtown business district. The majority of the existing buildings in downtown Woodburn reflect architectural styles that were popular during the late nineteenth and early twentieth century. It is the desire of the City to have buildings conform to architectural styles of this era. The design standards are intended to further define those characteristics that cause buildings to look like they were constructed during this period.
2. These standards are intended to encourage good quality design in new building construction, enhance street safety, and provide a comfortable street environment by providing features of interest to pedestrians. Good design results in buildings that are in visual harmony with nearby buildings, leading to a downtown that is attractive, interesting, active, and safe. These qualities, in turn, contribute to the creation of a downtown core which facilitates easy pedestrian movement and establishment of a rich mixture of uses. [§A as adopted by Ordinance 2463, passed January 25, 2010.]

### **B. Applicability.**

1. The provisions of this ordinance shall apply to the following activities within the DDC:
  - a. All new building construction;
  - b. Any exterior building or site modification that requires a building permit; and,
  - c. All new signage.
2. This ordinance shall not apply to the following activities or uses:
  - a. Maintenance of the exterior of an existing structure, such as re-roofing, re-siding, or repainting where similar materials and colors are used that comply with this ordinance;
  - b. Interior remodeling; and,
  - c. Single-family detached housing.
3. This ordinance shall apply only to those portions of a building or sign

that are proposed for construction or modification and shall not extend to other elements of the building or sign that may be out of compliance with the requirements of this ordinance (i.e., a permit to replace a single window shall not require that all other windows on the building that may be out of compliance with this ordinance to be replaced, unless such action is initiated by the property owner). However, if a building should be destroyed due to fire, accident, or an act of God, the new or replacement structure shall be rebuilt to conform to the requirements of this ordinance.

4. At the time of application, the applicant shall choose whether the review of new residential buildings shall be conducted as a Type I review following the procedures of Section 5.101.01 or as a Type II or III review following the procedures of Section 5.102.02 or 5.103.02, depending on floor area. [§B as adopted by Ordinance 2463, passed January 25, 2010.]

C. Off Street Parking.

All parking and access standards of *Sections 3.104 and 3.105* shall apply EXCEPT that there shall be no required parking ratio for non-residential uses and residential units above first floor commercial uses in the DDC zone. [§C as amended by Ordinance 2463, passed January 25, 2010.]

D. Design Guidelines or Standards.

1. All development, EXCEPT for existing detached single family homes and that described in Section 2.107.B.1, shall be subject to the DDC zone architectural design guidelines and standards of Section 3.107.07 and the standards listed below. Single-family homes that are used for businesses or home occupations are not exempt from compliance with these guidelines and standards. The provisions of this section shall apply to all new construction, restorations, and remodels. Restorations shall be defined as all exterior repairs, replacement of materials, alterations or changes, including reroofing, painting, window, and sign replacement, etc.
  - a. Standards. Standards for new construction shall require builders to conform to the architectural form of Woodburn's historic period (1880s through 1940s). As such, new construction shall conform to the following standards listed below. Throughout the standards, reference is made to Woodburn's historic period, the 1880s through 1940s, and to buildings which display characteristics of that period. The following list of buildings is provided as a reference guide to those buildings which display characteristics intended by the standards. The list is a guide only – other buildings may be used to demonstrate the required elements and/or the basis for visual compatibility.

- b. Examples of historic storefront buildings for determining compatibility with standards:

Association Building on Front Street between Garfield and Hayes.

Fulmer Building on Front Street on the corner of Front Street and Arthur.

2. Site Development.

- a. Building fronts and entrances shall be oriented toward the street. Buildings with frontages on two or more streets shall be oriented to at least one street.
- b. Building facades should be set at the property edge along the sidewalk. A setback of up to ten feet is permitted when occupied by pedestrian amenities (e.g., plaza, outdoor seating). Buildings with frontages on two or more streets should be set at the property edge on at least one street.

3. Building Scale.

- a. The overall size and proportion of new structures shall be compatible with the scale of nearby traditional storefront buildings constructed during the historic period. This standard may be met by either designing the building's size and proportions to be similar to comparable historic structures in the downtown, or by the design of the facade so that it breaks a larger mass into smaller units that are similar to comparable historic structures.
- b. If practical, new buildings should have the same floor height as adjoining buildings in case there is ever a desire to link the storefronts.
- c. The relationship between the height and width of the main facade of the building shall be visibly compatible with adjoining or nearby buildings of the historic period or style. As with subsection (2)(i) of this section, this standard may be met through either similar height and width, or, through design elements that provide visual continuity with the height and width of adjoining or nearby buildings of the historic period.

4. Building Height.

- a. New buildings of at least two stories in height are encouraged.
- b. Maximum allowed building heights shall be as specified in Section 2.107.05B.

5. Building Width.

- a. All new buildings should maximize lot frontage as much as is practicable.
- b. New buildings whose street frontage is more than 50 feet wide shall be designed to convey a sense of division through the use of pilasters, windows and door openings, recessed entries, off-sets or other architectural details.

6. Storefronts.

- a. Primary entrances shall be oriented to the street. Corner buildings shall have corner entrances, or shall provide at least one entrance within 20 feet of the street corner or a corner plaza.
  - b. The upper windows of multi-story buildings shall use multi-pane double-hung sash windows or the equivalent style.
  - c. The relationship between solid walls and window and door openings on the main facade shall be visually compatible with adjoining or nearby structures from the historic period or style. Ideally, first floor storefronts should be about 80 percent glass from approximately 2 feet above grade to approximately 10 feet above grade.
  - d. The relationship of width and height of window and door openings shall be visually compatible with adjoining or nearby buildings from the historic period or style.
  - e. Blank walls, walls without window or door openings, are not permitted along public streets.
  - f. Windows and doorways shall not be covered over with paper, boards, or cardboard except during times of construction or remodeling and shall be limited to a period of 120 days unless an extension is otherwise granted by the city manager.
  - g. Doors shall match the materials, design, and character of the display window framing.
  - h. Architectural features such as awnings, windows, cornices, etc., shall be provided at the second floor to differentiate the storefront from the upper levels of the building, to add visual interest, and to allow the storefront to function as the base for the rest of the building.
7. Facade Materials and Texture.
- a. The materials and texture of the facade shall be compatible with those on buildings constructed during the historic period.
  - b. Permitted exterior facade materials include: brick, cast iron, relatively narrow horizontal wood or masonry siding, and stucco. Plywood siding, T-111, and vertical board and batten are prohibited.
  - c. Exposed concrete block facades facing the street are not allowed. Split-face or scored-face block may be used in small quantities for foundations or other non-dominant features.
  - d. All main facade materials shall be painted (except brick, for which painting is optional).
  - e. Metal siding shall not be used as a building material on the facade facing a street.
8. Windows.
- a. Windows which allow views to the interior activity or display areas are encouraged. Windows shall include sills at the bottom and pediments at the top. Glass curtain walls, reflective glass, and painted or darkly tinted glass shall not be used on the first floor.

- b. Ground Floor Windows. All new buildings must provide ground floor windows along adjacent street rights-of-way.
      - 1) Required window areas must be either windows that allow views into working areas or lobbies, pedestrian entrances, or display windows.
      - 2) Required windows must have a sill no more than four feet above grade. Where interior floor levels prohibit such placement, the sill must be raised to allow it to be no more than two feet above the finished floor level, up to a maximum sill height of six feet above grade.
      - 3) Glass curtain windows are not permitted.
      - 4) Darkly tinted windows and mirrored windows that block two-way visibility are prohibited as ground floor windows along street facades.
      - 5) Any wall that faces a public right-of-way must contain at least 20% of the ground floor wall area in display areas, windows, or doorways. Blank walls are prohibited.
    - c. Upper Floor Window Standards.
      - 1) Glass area dimensions shall not exceed 5-feet by 7-feet. (The longest dimension may be taken either horizontally or vertically.)
      - 2) Windows must have trim or molding at least two inches wide around their perimeters.
      - 3) At least half of all the window area in upper floors must be made up of glass panes with dimensions no greater than 2-feet by 3-feet.
- 9. Roofs.
  - a. Main facade roofs (lower than a 6:12 pitch) shall be concealed behind a square or stepped parapet. Flat roofs are permitted behind a parapet.
  - b. All HVAC systems located on top of a roof shall be located and/or screened so that they are not visible from the street. Dish-style antennas shall be located and/or screened so that they are not visible from the street. All screening material shall be natural and shall be compatible with the facade of the front of the building.
  - c. New roofs on existing buildings, or on additions to existing buildings, shall match the pitch and form of the original roof.
  - d. Shed roofs are permitted on one-story rear additions.
  - e. Back-lit or internally illuminated roofs are prohibited.
- 10. Awnings and Canopies.
  - a. The use of awnings or canopies over sidewalks is encouraged.
  - b. Awnings shall extend out from the building front to cover at least two-thirds of the sidewalk unless it is shown that such a distance will interfere with existing trees, poles, etc., to provide pedestrian protection from the elements.

- c. Awnings shall be flat or sloping. Awnings shall be made of metal, wood, canvas or similar materials. Rounded bubble or plastic awnings are prohibited. Fully glazed awnings are not permitted.
  - d. Awnings shall fit within the window bays (either above the main glass or the transom light) so as not to obscure or distract from significant architectural features.
  - e. The color of the awning shall be compatible with its attached building.
  - f. Awnings shall not be internally illuminated. However, lighting which is intended to provide illumination to the sidewalk and signage is permitted.
  - g. Awnings shall be a minimum of eight feet above the sidewalk.
  - h. Where feasible, awnings shall be placed at the same height as those on adjacent buildings in order to maintain a consistent horizontal rhythm along the street front.
11. Color.
- a. The painting of brick walls is permitted.
  - b. Subtle or subdued tones commonly used during the historic period shall be used. Bright or neon colors are prohibited.
  - c. Different colors shall be used to accentuate and highlight trim, windows, and other building features.
12. Site Design.
- a. Landscaping shall not obliterate street and sidewalk views of signage or architectural features on historic buildings.
13. Parking.
- a. Parking areas shall not be located between the front of the building and the street.
  - b. Street side parking lots shall be set back a minimum of 5-feet from a public sidewalk.
  - c. Parking areas with more than 10 spaces shall be divided by landscaped areas or walkways, or by a building or group of buildings.
  - d. Parking lot landscaping shall consist of a minimum of 10 percent of the total parking area. A minimum of one tree for every 10 parking spaces shall be provided.
  - e. Knee walls are required to screen street side parking lots. Knee walls shall not exceed three feet in height and shall be constructed with masonry. Alternatively, a combination of a wall or fence and landscaping may be approved if they provide an effective buffer and low-level screen of the parking area.
14. Drive through businesses
- a. Drive through businesses are not permitted. [§D as amended by Ordinance 2463, passed January 25, 2010.]

E. Signs.

Signs shall be subject to **Section 3.110**. [Section 2.107.06C as amended by Ordinance No. 2359, §8, passed March 22, 2004.]

F. Landscaping.

Landscaping is subject to the DDC zone architectural design guidelines and standards of **Section 3.107.07**.

G. External Storage of Merchandise. The external storage of merchandise and/or materials, directly or indirectly related to a business, is hereby prohibited within the DDC district. [§G as adopted by Ordinance 2463, passed January 25, 2010.]

H. Outdoor Displays of Merchandise. Outdoor displays of merchandise are permitted during business hours only and shall not exceed ten percent of the total retail sales area. Displays of merchandise on public sidewalks may not reduce usable walking area widths to less than six feet. [§H as adopted by Ordinance 2463, passed January 25, 2010.]

I. Outdoor Eating Areas. Outdoor dining areas are encouraged, and are permitted on public sidewalks. Outdoor food vending carts are permitted. Eating areas and/or vending carts may not reduce usable walking area widths on public sidewalks to less than six feet. Mobile food kitchens are prohibited in the DDC district. [§I as adopted by Ordinance 2463, passed January 25, 2010.]

J. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104**.

1. New lots of record shall be subject to the following standards and procedures:

- a. **Partitions, Section 3.108;**
- b. **Subdivisions, Section 3.108; or**
- c. **Planned Unit Development Section 3.109.**

2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:

- a. **Property Line Adjustment, Section 5.101.07.**
- b. **Replatting, Section 3.108.**
- c. **Vacation, applicable Oregon Revised Statutes.**

## **2.108 Nodal Neighborhood Commercial (NNC)**

[Section 2.108 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

### **2.108.01 Purpose**

The Nodal Neighborhood Commercial zone is intended to serve the routine daily needs of nearby residents and employees. This zone is intended to be accessible to pedestrians and bicyclists, as well as automobiles. It may be applied as a stand-alone neighborhood commercial zone, or as part of a master planned nodal development in accordance with *Section 2.115*.

### **2.108.02 Permitted Uses**

The following uses, when developed under the applicable development standards of the *WDO*, are permitted in the NNC zone.

#### **A. Residential**

1. **One dwelling unit** in conjunction with a commercial use.

#### **B. Retail Trade**

1. **Bakeries.** (31181)
2. **Printing and related support activities** (323)
3. **Furniture and home furnishing stores** (442) INCLUDING:
  - a. Floor coverings and installation stores. (44221)
  - b. Window treatment and installation stores. (442291)
  - c. Used furniture stores. (45331)
4. **Electronics and appliance stores and repair** (44310) INCLUDING:
  - a. Camera shops. (44313)
  - b. Radio and TV stores. (443112)
  - c. Sewing machines stores. (443111)
5. **Building material and garden equipment dealers** (4441) LIMITED TO:
  - a. Paint, wallpaper, and interior decorating stores. (444120)
  - b. Hardware stores. (44413)
  - c. Light fixture stores. (444190)



6. **Garden supply store.** (44422)
7. **Food and beverage stores LIMITED TO:**
  - a. Delicatessen stores.
  - b. Meat markets. (44521)
  - c. Fish markets LIMITED TO sales only. (44522)
  - d. Grocery store, food market, food store. (44511)
8. **Other specialty stores (44529) LIMITED TO:**
  - a. Candy, nut, confectionery stores. (445292)
  - b. Dairy products stores LIMITED TO sales only. (44529)
9. **Health and personal care stores LIMITED TO:**
  - a. Drug stores. (44611)
  - b. Optical goods stores. (44613)
  - c. Health food stores. (446191)
  - d. Hearing aid stores. (446199)
10. **Clothing and clothing accessories (448) LIMITED TO:**
  - a. Clothing stores. (44810)
  - b. Dressmaker and tailor shops.
  - c. Furriers and fur shops. (44819)
  - d. Jewelry, watch, and clock stores. (44815 & 44831)
  - e. Shoe stores. (44823)
  - f. Luggage stores. (44832)
11. **Sporting goods stores (445111) INCLUDING:**
  - a. Bicycle shops. (445111)
  - b. Gunsmiths and repair. (45111)
12. **Hobby, toy, and game stores (45112) LIMITED TO:**
  - a. Hobby shops. (45112)
  - b. Toy stores. (45112)
13. **Sewing, needlework and piece goods stores.** (45113)
14. **Music, piano, and musical instrument stores.** (45114)
15. **Record and CD stores.** (45122)
16. **Book stores.** (4523)

17. **Department stores.** (45211)
18. **Other general merchandise stores** (4529) INCLUDING variety stores. (45299)
19. **Miscellaneous store retailers.** (453)
  - a. Antique shops.
  - b. Artists supply stores. (453998)
  - c. Business machines, typewriters and repair. (453210)
  - d. Florist shops. (45311)
  - e. Gift, novelty, souvenir shops. (45322)
  - f. Greeting card stores. (45322)
  - g. Mail order house. (45411)
  - h. Orthopedic and artificial limb stores.
  - i. Pet stores. (45391)
  - j. Stationery stores. (45321)
  - k. Used merchandise stores. (45331)

**C. Transportation & Warehousing**

1. Support Activities for Rail Transportation (488210)
2. Postal service. (491)

**D. Information**

1. **Newspaper, periodical, and book publishing.** (5111)
2. **Radio and TV studios and offices** (5131) EXCEPT antennae and towers.
3. **Cable networks.** (5132)
4. **Telecommunications** (5133) EXCEPT telecommunication facilities subject to *Section 2.204.03*.
5. **Information & data processing.** (514)

**E. Finance and Insurance**

1. **Finance and insurance** (52) EXCEPT check cashing, pay day loan and cash transfer establishments [other than banks] as a predominant, ancillary, or required supporting use.

**F. Real Estate and Rental and Leasing**

1. **Real estate.** (531)
2. **Rental & leasing**, without outdoor display or storage. (532)

**G. Professional, Scientific & Technical Services**

1. **Legal services.** (5411)
2. **Accounting.** (5412)
3. **Architects and engineers.** (5413)
4. **Specialized design services** (5414) INCLUDING interior design services.
5. **Computer system design.** (5415)
6. **Management consulting.** (5416)
7. **Advertising.** (5418)
8. **Other professional services** (5419), EXCEPT veterinary service (541940) not contained in a building.

#### H. **Administrative & Support Services**

1. **Administrative and facilities support services.** (5611 and 5612)
2. **Employment services.** (5613)
3. **Business support services** INCLUDING copy shops. (5614)
4. **Travel and tour agencies.** (5615)
5. **Investigation and security services.** (5616)
6. **Services to buildings and dwellings** (5617), offices only.
7. **Other support services.** (56199)

#### I. **Educational Service**

1. **Educational services** (611) both public and private, LIMITED TO:
  - a. Elementary and secondary schools. (6111)
  - b. Community college. (6112)
  - c. Business schools. (6114)
  - d. Technical and trade schools. (6115)

#### J. **Health Care & Social Services**

1. **Ambulatory health care** (621) EXCEPT Ambulance service. (62191)
2. **Social services** (624) INCLUDING child day care services.

#### K. **Arts, Entertainment & Recreation**

1. **Museums and historic sites** (712) EXCEPT zoos (712130).
2. **Fitness and recreational sports** (71391) **Community center.**
3. **Taxidermists.** (71151)

#### L. **Accommodation & Food Service**

1. **Hotels** (EXCEPT casino hotels) and motels. (72111)
2. **Bed and breakfast inns.** (21191)
3. **Food service and drinking places** (722) EXCEPT food contractors (7231) and mobile food service.

M. **Other Services**

1. **Personal care services** (8121) INCLUDING:
  - a. Barber shops. (812111)
  - b. Beauty shops. (812112)
2. **Funeral home.** (812210)
3. **Laundry, self service.** (81231)
4. **Dry cleaning, self service.** (81231)
5. **Photo finishing.** (81292)
6. **Parking lots and garages** (81293) EXCEPT extended vehicle storage. (493190)
7. **All Other Personal Services** (81299) INCLUDING bail bonding and consumer buying services.
8. **Religious, civic, professional and similar organizations.** (813)

N. **Public Administration**

1. **Public administration** (92) INCLUDING government offices, courts, and police and fire stations.

O. **Streets and Utilities**

1. **Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil , electric and communication lines and for storm water facilities and for pump stations.

**2.108.03 Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the NNC zone:

- A. **Complementary residential use** subject to **Section 2.203.06**.
- B. **Craft industries** subject to **Section 2.203.07**.
- C. **Delivery services** subject to **Section 2.203.08**.
- D. **Facilities during construction** subject to **Section 2.203.10**.
- E. **Temporary outdoor marketing and special events** subject to **Section 2.203.19**.

**2.108.04 Conditional Uses**

The following uses may be permitted subject to obtaining conditional use approval:

- A. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.107.01* and telecommunications facilities subject to *Section 2.204.03*.

**2.108.05**      **Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202 and 2.203*.

- A. Fence or free standing wall.

**2.108.06**      **Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the NNC zone.

- A. Maximum Zone and Square Footage Requirement.
1. The maximum size for an NNC zone shall be 12 acres.
  2. NNC zones shall be served by at least one collector or arterial street.
  3. The maximum floor area for any single business in the NNC zone shall not exceed 60,000 square feet.
- B. Lot Standards.

Lots in a NNC zone shall comply with the applicable standards of *Table 2.1.13*.

<b>TABLE 2.1.13   Lot Standards in a NNC Zone</b>
In a NNC zone the lot area shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

C. Building Height.

The maximum building height shall be 45 feet in the NNC zone.

D. Setback and Buffer Standards.

Setback and buffers are subject to the NNC design guidelines of **Section 3.107.07**.

**2.108.07 Development Standards**

All development in the NNC zone shall comply with the applicable provisions of the **WDO**. If the NNC Zone is within a Nodal Overlay on the Comprehensive Plan Map the Nodal standards shall prevail. Otherwise, where the standards of the NNC zone and the **WDO** differ, the standards of the NNC shall prevail.

A. Off Street Parking.

All parking and access standards of **Sections 3.104 and 3.105** shall apply.

B. Design Guidelines and Standards.

1. Multiple density residential buildings shall be subject to the design standards or guidelines of **Section 3.107.05**
2. All development, EXCEPT that described in **Section 2.108.07.B.1**, shall be subject to the NNC zone architectural design guidelines and standards of **Section 3.107.07**.

C. Signs.

Signs shall be subject to **Section 3.110**.

D. Landscaping.

1. Landscaping is subject to the NNC zone architectural design guidelines and standards of **Section 3.107.07**.
2. At least one-half acre of common open area shall be improved for every five acres of commercial development. The design of the common open area shall be subject to **Section 5.103.02**.

E. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of

**Sections 3.101, 3.102 and 3.104.** If an NNC site is within a designated Nodal Overlay on the Comprehensive Plan Map the master planning standards of **Section 2.115** shall be met prior to creation or alteration of any lot or parcel, and prior to approval of any street vacation.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**
  - b. **Subdivisions, Section 3.108;** or
  - c. **Planned Unit Development Section 3.109.**
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, Section 5.101.07.**
  - b. **Replatting, Section 3.108.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## 2.109 Industrial Park (IP)

### 2.109.01 Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO*, are permitted in the IP zone.

#### A. Construction

1. **Building, developing and general contracting.** (233)
2. **Heavy construction.** (234)
3. **Special trade contractors.** (235)

#### B. Manufacturing

1. **Food manufacturing.** (311)
2. **Beverage and tobacco product manufacturing.** (312)
3. **Textile product mills.** (314)
4. **Apparel manufacturing.** (315)
5. **Leather and allied products manufacturing.** (316)
6. **Paper manufacturing** (317) limited to assembly.
7. **Printing and related support activities.** (318)
8. **Plastics and rubber product manufacturing.** (326)
9. **Fabricated metal products manufacturing.** (332)
10. **Machinery manufacturing.** (333)
11. **Computer and electronic product manufacturing.** (334)
12. **Electrical equipment, appliance and component manufacturing.** (335)
13. **Transportation equipment manufacturing.** (336)
14. **Furniture and related product manufacturing.** (337)
15. **Misc. manufacturing.** (339)

#### C. Wholesale Trade

1. **Wholesale trade, durable goods.** (421)
2. **Wholesale trade, nondurable goods** (422) EXCEPT motor vehicle wrecking yards.

#### D. Educational Services

1. **Technical and trade schools.** (6115)

#### E. Health Care

1. **Ambulance services.** (62191)



F. **Other Services**

1. **Dwelling** for caretaker or watchperson.
2. **Parking lots and garages** (81293)

G. **Public Administration and Facilities**

1. **Fire protection.** (922160)
2. **Government maintenance facilities and storage yards.**

H. **Streets & Utilities**

1. **Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines and for storm water facilities and for pump stations.

**2.109.02 Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the IP zone.

- A. **Agricultural practices** without livestock subject to **Section 2.203.02**.
- B. **Delivery services** subject to **Section 2.203.08**.
- C. **Facilities during construction** subject to **Section 2.203.10**.
- D. **Industrial sales** subject to **Section 2.203.14**.
- E. **Mobile food service** subject to **Section 2.203.17**.

**2.109.03 Conditional Uses**

The following uses may be permitted in the IP zone subject to the applicable development standards of the **WDO** and the conditions of conditional use approval:

- A. **Manufacturing**
  1. **Wood products manufacturing.** (321)
  2. **Chemical manufacturing.** (325)
- B. **Transportation and Warehousing**
  1. **Truck transportation.** (484)

2. **Transit and ground transportation.** (485)
3. **Freight transportation arrangement.** (488510)
4. **Warehousing and storage .**(493)
5. **Self- and mini-storage.**

C. **Food Services**

1. **Food services and drinking places** (722) for industrial employees  
EXCEPT mobile food service.

D. **Other Services**

1. **Commercial and industrial machinery and equipment repair.** (8113)
2. **Recycling centers.**

E. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.109.01* and telecommunications facilities subject to *Section 2.204.03*.

**2.109.04** **Specific Conditional Uses**

The uses permitted by the following designation may be allowed in the IP zone subject to approval as a conditional use that conforms to the specific standards referenced below, the applicable provisions of the **WDO** and all other applicable conditions of approval.

A. **Telecommunications Facilities** subject to *Section 2.204.03*.

**2.109.05** **Accessory Uses**

The following uses are permitted as accessory uses subject to *Section 2.203*.

A. **Fence or free standing wall.**

**2.109.06** **Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the IP zone.

A. Lot Standards.

Lots in the IP zone shall comply with the applicable standards of **Table 2.1.15**. (Table on next page.) [Section 2.109.06.A as amended by Ordinance No. 2446, §23, passed on September 10, 2008.]

<b>TABLE 2.1.15      Lot Standards in an IP Zone</b>
In an IP zone the lot area for a non-residential use shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

B.      Building Height.

The maximum height of buildings shall not exceed 45 feet, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (but EXCEPT telecommunication facilities), shall not exceed 70 feet.

C.      Setback and Buffer Improvement Standards.

1.      Minimum Front Setback and Setback Abutting a Street [Section 2.109.06.C.1 as amended by Ordinance No. 2446, §12, passed on September 10, 2008.]:

a.      Dimensions:

The minimum setback abutting a street shall be 10 feet plus any Special Setback, **Section 3.103.05**.

[Section 2.109.06.C.1.b as amended by Ordinance No. 2423, §13,      effective on July 28, 2007.]

b.      Off street parking, Maneuvering and Storage:

1)      Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:

- i.      WDO Section 3.105, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.
- ii.     A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued

drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.

- iii. Storage areas that are located within the front setback behind a wall shall be screened to a minimum height of 6 feet.
- 2) The distance between the sidewalk on a public street and a loading dock shall be sized to preclude vehicles using the dock from projecting over the sidewalk.
- c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
- d. Vehicular Access: Permitted in conformance **Section 3.104**.
- 2. Minimum Interior Side and Rear Setbacks [Section 2.109.06.C.2 as amended by Ordinance No. 2446, §12, passed on September 10, 2008.]:
  - a. Development in an IP zone shall be subject to the setback and buffer requirements of **Table 2.1.16**.

(Table on next page)

<b>TABLE 2.1.16 Interior Yard and Buffer Standards for IP Zones</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<b>RS, R1S, RM, CO, P/SP zone; or</b> <b>Existing residential unit</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 9 feet in height.	30 ft.
<b>CG, DDC, NNC, IP, SWIR or IL zone</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	<p>Alternative A:</p> <p>Wall requirements shall be determined in conjunction with the applicable Design Review process.</p> <p>Alternative B:</p> <p>No wall required.</p>	<p>Alternative A:</p> <p>5 ft.</p> <p>Alternative B:</p> <p>Zero setback abutting a building wall.</p>

[Table 2.1.16 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

- b. The building setback from a private access easement shall be a minimum of 5 feet.

[Section 2.109.06.C.2.c as amended by Ordinance 2423, §14, effective on July 28, 2007.]

- c. Off Street Parking, Maneuvering and Storage:

- 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:
  - i. **WDO Section 3.105**, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.
  - ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall

maintain a gravel storage area to ensure continued drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.

- d. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
- e. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and **Section 3.104**.

## **2.109.07**      **Development Standards**

All development in the IP zone shall comply with the applicable provisions of the **WDO**. The following standards specifically apply to uses in the IP zone.

- A. Off Street Parking.  
Off street parking shall be subject to the standards of **Section 2.109.06 and Section 3.105**.
- B. Setbacks and Lots, Generally.  
  
Setbacks and lots shall be subject to **Section 3.103**.
- C. Architectural Design Guidelines.  
  
All primary buildings and structures shall be subject to the architectural guidelines of **Section 3.107.08**.
- D. Signs.  
  
Signs shall be subject to **Section 3.110**. [Section 2.109.07D as amended by Ordinance No. 2359, §9, passed March 22, 2004.]
- E. Landscaping and Sidewalks.
  - 1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of **Section 3.101 and 3.106**.
  - 2. The subject property shall be landscaped to the standards of **Section 3.106**.
  - 3. Common refuse collection facilities shall be screened on all sides by an

architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

F. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104**.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**
  - b. **Subdivisions, Section 3.108;** or
  - c. **Planned Unit Development Section 3.109.**
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, Section 5.101.07.**
  - b. **Replatting, Section 3.108.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## 2.110 Light Industrial (IL)

### 2.110.01 Permitted Uses

The following uses, when developed under the applicable development standards of the *WDO*, are permitted in the IL zone.

#### A. Construction

1. **Building, developing and general contracting.** (233)
2. **Heavy construction.** (234)
3. **Special trade contractors.** (235)

#### B. Manufacturing

1. **Food manufacturing.** (311)
2. **Beverage and tobacco product manufacturing.** (312)
3. **Textile product mills.** (314)
4. **Apparel manufacturing.** (315)
5. **Leather and allied products manufacturing.** (316)
6. **Paper manufacturing** (317) limited to assembly.
7. **Printing and related support activities** .(318)
8. **Wood products manufacturing.** (321)
9. **Plastics and rubber product manufacturing.** (326)
10. **Nonmetallic mineral product manufacturing.** (327)
11. **Fabricated metal products manufacturing.** (332)
12. **Machinery manufacturing.** (333)
13. **Computer and electronic product manufacturing.** (334)
14. **Electrical equipment, appliance and component manufacturing.** (335)
15. **Transportation equipment manufacturing.** (336)
16. **Furniture and related product manufacturing.** (337)
17. **Misc. manufacturing.** (339)

#### C. Wholesale Trade

1. **Wholesale trade, durable goods.** (421)
2. **Wholesale trade, nondurable goods** (422) EXCEPT motor vehicle wrecking yards.

#### D. Retail Trade

1. **Auction houses** EXCEPT livestock and poultry sales.



E. Transportation and Warehousing

1. **Truck transportation.** (484)
2. **Transit and ground transportation.** (485)
3. **Freight transportation arrangement.** (488510)
4. **Warehousing and storage.** (493)
5. **Self- and mini-storage.**

F. Educational Services

1. **Technical and trade schools.** (6115)

G. Health Care

1. **Ambulance services.** (62191)

H. Other Services

1. **Commercial and industrial machinery and equipment repair.** (8113)
2. **Dwelling** for caretaker or watchperson.
3. **Parking lots and garages** (81293)

I. Public Administration and Facilities

1. **Fire protection.** (922160)
2. **Government maintenance facilities and storage yards.**

J. Streets & Utilities

1. **Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines and for storm water facilities and for pump stations.

**2.110.02 Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the IL zone.

- A. **Agricultural practices** without livestock subject to **Section 2.203.02**.
- B. **Delivery services** subject to **Section 2.203.08**.
- C. **Facilities during construction** subject to **Section 2.203.10**.

- D. **Mobile food service** subject to *Section 2.203.17*.

**2.110.03**      **Conditional Uses**

The following uses may be permitted in the IL zone subject to the applicable development standards of the *WDO* and the conditions of conditional use approval:

- A. **Manufacturing**
1. **Paper manufacturing.** (322)
  2. **Petroleum and coal products manufacturing** (324) with all storage underground.
  3. **Chemical manufacturing.** (325)
  4. **Primary metal manufacturing.** (331)
- B. **Food Services**
1. **Food services and drinking places** (722) for industrial employees, EXCEPT mobile food service.
- C. **Other Services**
1. **Motor vehicle wrecking yards.**
  2. **Recycling centers.**
- D. **Government and public utility buildings and structures** EXCEPT *uses permitted in Section 2.110.01* and telecommunications facilities subject to *Section 2.204.03*.

**2.110.04**      **Specific Conditional Uses**

The uses permitted by the following designation may be allowed in the IL zone subject to approval as a conditional use that conforms to the specific standards referenced below, the applicable provisions of the *WDO* and all other applicable conditions of approval.

- A. **Telecommunications Facilities** subject to *Section 2.204.03*.

**2.110.05**      **Accessory Uses**

The following uses are permitted as accessory uses subject to *Section 2.203*.

- A. **Fence or free standing wall.**

**2.110.06**      **Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the IL zone.

A. Lot Standards.

Lots in a IL zone shall comply with the applicable standards of **Table 2.1.17**.

<b>TABLE 2.1.17 Lot Standards in an IL Zone</b>
In an IL zone the lot area for a non-residential use shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

B. Building Height.

The maximum height of buildings shall not exceed 70 feet, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (EXCEPT telecommunication facilities), shall not exceed 100 feet.

C. Setback and Buffer Improvement Standards.

1. Minimum Front Setback and Setback Abutting a Street [Section 2.110.06.C.1 as amended by Ordinance No. 2446, §13, passed on September 10, 2008.]:

- a. Dimensions:

- The minimum setback abutting a street shall be 10 feet plus any Special Setback, **Section 3.103.05**.

- [Section 2.110.06.C.1.b as amended by Ordinance No. 2423, §15, effective on July 28, 2007.]

- b. Off Street Parking, Maneuvering and Storage:

- 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking maneuvering, and storage areas shall be improved consistent with the following:

- i. **WDO Section 3.105**, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.
      - ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure

adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.

- iii. Storage areas that are located within the front setback behind a wall shall be screened to a minimum height of 6 feet.
- 1) The distance between the sidewalk on a public street and a loading dock shall be sized to preclude vehicles using the dock from projecting over the sidewalk.
- c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
- d. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and **Section 3.104**.
- 2. Minimum Interior Side and Yard Setbacks [Section 2.110.06.C.2 as amended by Ordinance No. 2446, §13, passed on September 10, 2008.]:
  - a. Development in an IL zone shall be subject to the setback and buffer requirements of **Table 2.1.18**.

(Table on next page.)

<b>TABLE 2.1.18 Interior Yard and Buffer Standards for IL Zones</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<b>RS, R1S, RM, CO, P/SP zone; or Existing residential unit</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 9 feet in height.	30 ft.
<b>CG, DDC, NNC, IP, SWIR or IL zone</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	<p>Alternative A:</p> <p>Wall requirements shall be determined in conjunction with the applicable Design Review process.</p> <p>Alternative B:</p> <p>No wall required.</p>	<p>Alternative A:</p> <p>5 ft.</p> <p>Alternative B:</p> <p>Zero setback abutting a building wall.</p>

[Table 2.1.18 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

- b. The building setback from a private access easement shall be a minimum of 5 feet.

[Section 2.110.06.C.2.c as amended by Ordinance No. 2423, §16, effective on July 28, 2007.]

- c. Off Street Parking, Maneuvering and Storage:
- 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:
    - i. **WDO Section 3.105**, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.
    - ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued

drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.

- d. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, ***Section 3.103.10***.
- e. Vehicular Access: Permitted in conformance with ***Section 3.104***.

#### **2.110.07**      **Development Standards**

All development in the IL zone shall comply with the applicable provisions of the ***WDO***. The following standards specifically apply to uses in the IL zone.

A. Off Street Parking.

Off street parking shall be subject to the standards of ***Section 2.110.06 and Section 3.105***.

B. Setbacks and Lots, Generally.

Setbacks and lots shall be subject to ***Section 3.103***.

C. Architectural Design Guidelines.

All primary buildings and structures shall be subject to the architectural guidelines of ***Section 3.107.08***.

D. Signs.

Signs shall be subject to ***Section 3.110***. [Section 2.110.07D as amended by Ordinance No. 2359, §9, passed March 22, 2004.]

E. Landscaping and Sidewalks.

- 1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of ***Section 3.101 and 3.106***.
- 2. The subject property shall be landscaped to the standards of ***Section 3.106***.
- 3. Common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

F. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by **Section 1.102** and developed to the public facility and access standards of **Sections 3.101, 3.102 and 3.104**.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, Section 3.108;**
  - b. **Subdivisions, Section 3.108; or**
  - c. **Planned Unit Development Section 3.109.**
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, Section 5.101.07.**
  - b. **Replatting, Section 3.108.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

## **2.111 Public and Semi-Public (P/SP)**

### **2.111.01 Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** are permitted in the P/SP zone.

- A. **Golf Course**, without a driving range.
- B. **Parks**.
- C. **Playgrounds**.
- D. **Rights of way, easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines, for storm water facilities and for pump stations.

### **2.111.02 Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the P/SP zone.

- A. **Agricultural practices** without livestock subject to **Section 2.203.02**.
- B. **Delivery services** subject to **Section 2.203.08**.
- C. **Facilities during construction** subject to **Section 2.203.10**.
- D. **Temporary outdoor marketing and special events** subject to **Section 2.203.19**.

### **2.111.03 Conditional Uses**

The following uses may be permitted in the P/SP zone subject to the applicable development standards of the **WDO** and to the conditions of conditional use approval:

- A. **Ambulatory health care facilities**. (621)
- B. **Aquatic facility**.
- C. **Cemetery**. (812220)
- D. **Elementary and secondary schools** (6111).



- E. **Golf driving range** in conjunction with a golf course.
- F. **Government and public utility buildings and structures** EXCEPT uses permitted in *Section 2.111.01* and telecommunications facilities subject to *Section 2.204.03*.
- G. **Hospitals.** (622)
- H. **Play or Ball Field.**
- I. **Public parking lots and garages** (81293) EXCEPT extended vehicle storage. (4939190) and parking as an Accessory Use.

**2.111.04**      **Accessory Uses**

The following uses are permitted as accessory uses subject to *Sections 2.202*.

- A. **Dwelling** for caretaker or watchperson.
- B. **Fence or free standing wall.**
- C. **Public parking** for uses in the same zoning district.

**2.111.05**      **Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development in the P/SP zone.

- A. Lot Standards.

Lots in a P/SP zone shall comply with the applicable standards of *Table 2.1.19*.

<b>TABLE 2.1.19      Lot Standards for Uses in a P/SP Zone</b>
In a P/SP zone the lot area for a non-residential use shall be adequate to contain all structures within the required setbacks. There shall be no minimum width or depth.

- B. Building Height.

The maximum height of buildings, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (EXCEPT telecommunication facilities), shall be 35 feet.

- C. Setback and Buffer Improvement Standards.

- 1. Minimum Front Setback and Setback Abutting a Street [Section

2.111.05.C.1 as amended by Ordinance No. 2446, §14, passed on September 10, 2008.]:

a. Dimensions:

The minimum setback abutting a street shall be 20 feet plus any Special Setback, **Section 3.103.05**.

[Section 2.111.05.C.1.b as amended by Ordinance No. 2423, §17, effective on July 28, 2007.]

b. Off Street Parking, Maneuvering and Storage:

- 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:

- i. **WDO** Section 3.105, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.
- ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.
- iii. Storage areas that are located within the front setback behind a wall shall be screened to a minimum height of 6 feet.

- 2) The distance between the sidewalk on a public street and a loading dock shall be sized to preclude vehicles using the dock from projecting over the sidewalk.

c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.

- d. Vehicular Access: Permitted in conformance with **Section 3.104.**
- 2. Minimum Interior Side and Rear Setbacks [Section 2.111.05.C.1 as amended by Ordinance No. 2446, §14, passed on September 10, 2008.]:
  - a. Development in an P/SP zone shall be subject to the setback and buffer requirements of **Table 2.1.20.**

(Table on next page)

<b>TABLE 2.1.20 Interior Yard and Buffer Standards for P/SP Zones</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<u><b>Permitted Use in a P/SP Zone Abutting:</b></u>  <b>RS, R1S, RM, CO, P/SP, DDC, NNC, CG, IP, SWIR or IL zone; or</b>  <b>Existing residential unit.</b>	All interior yards shall be fully landscaped subject to <i>Section 3.106.</i>	No wall required.	20 feet
<u><b>Conditional and/or Accessory Use in a P/SP Zone Abutting:</b></u>  <b>RS, R1S, RM, CO, P/SP zone; or</b>  <b>Existing residential unit.</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	Wall requirements shall be determined in conjunction with the applicable Design Review process.	24 ft. from any portion of main building 16 ft. or less in height  30 ft. from any portion of a main building more than 16 ft. and less than 28 ft. in height  36 ft. from any portion of a main building more than 28 ft. and less than 35 ft. in height.
<u><b>Conditional and/or Accessory Use in a P/SP Zone Abutting:</b></u>  <b>DDC, NNC, CG, IP, SWIR or IL zone.</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	Wall requirements shall be determined in conjunction with the applicable Design Review process.	20 ft.

Table 2.1.20 as amended by Ordinance 2391, §3, acknowledged on December 22, 2006.]

- b. The building setback from a private access easement shall be a minimum of 5 feet.

[Section 2.111.05.C.2.c as amended by Ordinance No. 2423, §18, effective on July 28, 2007.]

- c. Off Street Parking, Maneuvering and Storage:

- 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:
  - i. **WDO** Section 3.105, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.

- ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.
- d. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, ***Section 3.103.10***.
- e. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and ***Section 3.104***.

#### **2.111.06**      **Development Standards**

All development in the P/SP zone shall comply with the applicable provisions of the ***WDO***. The following standards specifically apply to uses in the P/SP zone.

A. Off Street Parking.

Off street parking shall be subject to the standards of ***Section 2.111.05 and Section 3.105***.

B. Setbacks and Lots, Generally.

Setbacks and lots shall be subject to ***Section 3.103***.

C. Architectural Design Guidelines.

All primary buildings and structures shall be subject to the architectural guidelines of ***Section 3.107.06***.

D. Signs.

Signs shall be subject to ***Section 3.110***. [Section 2.111.06D as amended by Ordinance No. 2359, §11, passed March 22, 2004.]

E. Landscaping and Sidewalks.

- 1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The

improvement shall be determined at the time of subdivision, PUD or design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of ***Section 3.101 and 3.106.***

2. The subject property shall be landscaped to the standards of ***Section 3.106.***
3. Common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

F. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by ***Section 1.102*** and developed to the public facility and access standards of ***Sections 3.101, 3.102 and 3.104.***

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, *Section 3.108;***
  - b. **Subdivisions, *Section 3.108;*** or
  - c. **Planned Unit Development *Section 3.109.***
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, *Section 5.101.07.***
  - b. **Replatting, *Section 3.108.***
  - c. **Vacation, applicable Oregon Revised Statutes.**

## **2.112 Neighborhood Conservation Overlay District (NCOD)**

### **2.112.01 Purpose**

To conserve the visual character and heritage of Woodburn=s oldest and most central neighborhood.

### **2.112.02 Boundaries of the NCO District**

The area encompassed by the Neighborhood Conservation Overlay (NCOD) district are depicted in *Figure NCOD-1*.

### **2.112.03 Applicable Provisions**

The *NCOD* provides the basis for specific architectural design guidelines. The NCOD architectural guidelines are contained in *Section 3.107.04*. The guidelines are applicable to all single family and duplex dwellings, both existing and proposed.

## **2.113 Riparian Corridor and Wetlands Overlay District (RCWOD)**

[Section 2.113 as amended by Ordinance 2391, §3, acknowledged on December 22, 2006]

### **2.113.01 Purpose**

To conserve significant riparian corridors, undeveloped floodplains and locally significant wetlands in keeping with the requirements of State Planning Goal 5 (Natural Resources) and applicable state statutes and administrative rules, and the Woodburn Comprehensive Plan to protect and enhance water quality; prevent property damage during floods and storms; limit development activity in designated riparian corridors; protect native plant species; maintain and enhance fish and wildlife habitats; and conserve scenic and recreational values.

### **2.113.02 Boundaries of the RCWOD**

The general location of the Riparian Corridor and Wetlands Overlay District (RCWOD) is shown on the Woodburn Comprehensive Plan Map and the Woodburn Zoning Map (for areas within the City Limits). Specifically, the RCWOD includes locally significant wetlands identified on the Woodburn Wetlands Inventory Map, a riparian corridor extending upland 50 feet from the top of the bank of the main stem of Senecal Creek and Mill Creek and their tributaries, and the 100-year floodplain on properties identified as vacant or partly vacant on the 2005 Woodburn Buildable Lands Inventory. Where a significant wetland is located fully or partially within the riparian corridor, the riparian corridor shall extend 50 feet from the upland edge of the wetland.

### **2.113.03 Permitted Uses Within RCW Overlay District.**

- A. Trails.
- B. Passive recreation uses and activities.
- C. Maintenance of existing structures, lawns and gardens.
- D. Normal maintenance and expansion of existing public facilities.
- E. Removal of invasive (non-native) plant species.

### **2.113.04 Development Regulations**

- A. In addition to the requirements of the underlying zone, the following restrictions and exceptions shall apply within the RCWOD:
  - 1. Removal of native vegetation. The removal of vegetation from the RCWOD is prohibited EXCEPT for the following:



- a. Perimeter mowing of a wetland for fire protection purposes;
  - b. Removal of non-native vegetation and replacement with native plant species;
  - c. For the development of water-related or water-dependent uses, provided they are designed and constructed to minimize impact on the existing riparian vegetation;
  - d. Removal of emergent in-channel vegetation that has the potential to cause flooding;
  - e. Hazardous tree removal. Hazardous trees are those that pose an imminent health, safety, or welfare threat to persons or property.
2. Building, Paving, Grading, and Fill. Within the RCWOD, the placement of structures or impervious surfaces, including grading and the placement of fill is prohibited EXCEPT for the following:
- a. Replacement of existing structures with structures located on the original building footprint that do not disturb additional wetland or riparian corridor surface area;
  - b. Streets, roads and paths that are included in the Woodburn Transportation System Plan;
  - c. Water-related and water-dependent uses, including drainage facilities, water and sewer facilities, flood control projects, drainage pumps, public paths, access ways, trails, picnic areas or interpretive and educational displays and overlooks, including benches and outdoor furniture;
  - d. Routine maintenance or replacement of existing public facilities projects and public emergencies, including emergency repairs to public facilities;
  - e. In-channel erosion or flood control measures that have been approved by the Oregon Division of State Lands (DSL), the U.S. Army Corps of engineers or another state or federal regulatory agency, that utilize bio-engineering methods (rather than rip rap).
3. The following uses and activities are prohibited within the RCWOD:
- a. New residential, commercial, industrial, or public/semi-public construction;

- b. Expansion of existing buildings or structures; [Section 2.113.04.A.3.b as amended by Ordinance No. 2446, §24, passed on September 10, 2008.]
  - c. Expansion of areas of pre-existing non-native ornamental landscaping such as lawn, gardens, etc.; [Section 2.113.04.A.3.c as amended by Ordinance No. 2446, §24, passed on September 10, 2008.]
  - d. Dumping, piling, or disposal of refuse, yard debris, or other material. [Section 2.113.04.A.3.d as amended by Ordinance No. 2446, §24, passed on September 10, 2008.]
- B. Site Maintenance. Any use, sign or structure, and the maintenance thereof, lawfully existing on the date of adoption of this ordinance, is permitted within the RCWOD. Such use, sign or structure may continue at a similar level and manner as existed on the date of the adoption of this ordinance. The maintenance and alteration of pre-existing ornamental landscaping is permitted within the RCWOD as long as no additional native vegetation is disturbed. Maintenance of lawns, planted vegetation and landscaping shall be kept to a minimum and not include the spraying of pesticides or herbicides. Vegetation shall be replanted with native species. Maintenance trimming of existing trees shall be kept at a minimum and under no circumstances can the trimming maintenance be so severe as to compromise the tree's health, longevity, and resource functions. Vegetation within utility easements shall be kept in a natural state and replanted when necessary with native plant species.
- C. When a use or activity that requires the issuance of a building permit or approval of a land use application is proposed on a parcel within, or partially within the RCWOD, the property owner shall submit the following for review by the Director:
  - 1. Site Map. A professional quality to-scale map showing the precise location of the top-of-bank, 100-year flood elevation, jurisdictional delineation of the wetland boundary, approved by the Oregon Division of State Lands (if applicable), riparian setback, existing vegetation, site improvements existing and proposed, topography, and other relevant features;
- D. Wetlands Notification to Oregon Division of State Lands. The Oregon Division of State Lands shall be notified in writing of all applications to the City of Woodburn for development activities, including applications for plan authorizations, development permits, or building permits, and of development proposals by the City of Woodburn, that may affect any wetlands, creeks or waterways identified in the Local Wetlands Inventory.

**2.113.05**      **Variances**

- A. Prohibited uses or activities may only be allowed within the RCWOD with the approval of a variance, pursuant to ***Section 5.103.11***

## **2.114 Southwest Industrial Reserve (SWIR)**

[Section 2.114 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

### **2.114.01 Purpose**

To protect suitable industrial sites in Southwest Woodburn, near Interstate 5, for the exclusive use of targeted industries identified in the Woodburn Economic Opportunities Analysis (EOA). This broad objective is accomplished by master planning, retention of large industrial parcels, and restricting non-industrial land uses.

### **2.114.02 Application of the SWIR Zone**

Land designated on the Comprehensive Plan Map as Southwest Industrial Reserve shall only be zoned SWIR.

### **2.114.03 Permitted Uses**

- A. Targeted industries and services identified in Table 2.1.21 are permitted uses in the SWIR zone, subject to compliance with applicable provisions of the WDO and this chapter.

(Table on next page.)

**TABLE 2.1.21 Targeted Employers Listed By Standard Industrial Classification (SIC)**

Targeted Employer	Description
<b>Industry 27:</b> Printing, Publishing, and Allied Industries	<p>This industry includes establishments engaged in printing by one or more common processes, such as letterpress; lithography (including offset), gravure, or screen; and those establishments, which perform services for the printing trade, such as bookbinding and platemaking. This industry also includes establishments engaged in publishing newspapers, books, and periodicals, regardless of whether or not they do their own printing. News syndicates are classified in Services, Industry 7383. Establishments primarily engaged in textile printing and finishing fabrics are classified in Industry 22, and those engaged in printing and stamping on fabric articles are classified in Industry 2396. Establishments manufacturing products that contain incidental printing, such as advertising or instructions, are classified according to the nature of the products for example, as cartons, bags, plastics film, or paper.</p>
<b>Industry 32:</b> Stone, Clay, Glass, and Concrete Products	<p>This industry includes establishments engaged in manufacturing flat glass and other glass products, cement, structural clay products, pottery, concrete and gypsum products, cut stone, abrasive and asbestos products, and other products from materials taken principally from the earth in the form of stone, clay, and sand. When separate reports are available for mines and quarries operated by manufacturing establishments classified in this industry, the mining and quarrying activities are classified in Division B, Mining. When separate reports are not available, the mining and quarrying activities, other than those of Industry 3295, are classified herein with the manufacturing operations. If separate reports are not available for crushing, grinding, and other preparation activities of Industry 3295, these establishments are classified in Division B, Mining.</p>
<b>Industry 34:</b> Fabricated Metal Products, except Machinery and Transportation Equipment	<p>This industry includes establishments engaged in fabricating ferrous and nonferrous metal products, such as metal cans, tinware, handtools, cutlery, general hardware, nonelectric heating apparatus, fabricated structural metal products, metal forgings, metal stampings, ordnance (except vehicles and guided missiles), and a variety of metal and wire products, not elsewhere classified. Certain important segments of the metal fabricating industries are classified in other industries, such as machinery in Industries 35 and 36; transportation equipment, including tanks, in Industry 37; professional scientific and controlling instruments, watches, and clocks in Industry 38; and jewelry and silverware in Industry 39. Establishments primarily engaged in producing ferrous and nonferrous metals and their alloys are classified in Industry 33.</p>

<b>Industry 35:</b> Industrial and Commercial Machinery and Computer Equipment	This industry includes establishments engaged in manufacturing industrial and commercial machinery and equipment and computers. Included are the manufacture of engines and turbines; farm and garden machinery; construction, mining, and oil field machinery; elevators and conveying equipment; hoists, cranes, monorails, and industrial trucks and tractors; metalworking machinery; special industry machinery; general industrial machinery; computer and peripheral equipment and office machinery; and refrigeration and service industry machinery. Machines powered by built-in or detachable motors ordinarily are included in this industry, with the exception of electrical household appliances. Power-driven handtools are included in this industry, whether electric or otherwise driven. Establishments primarily engaged in manufacturing electrical equipment are classified in Industry 36, and those manufacturing handtools, except powered, are classified in Industry 34.
<b>Industry 36:</b> Electronic and Other Electrical Equipment and Components, except Computer Equipment	This industry includes establishments engaged in manufacturing machinery, apparatus, and supplies for the generation, storage, transmission, transformation, and utilization of electrical energy. Included are the manufacturing of electricity distribution equipment; electrical industrial apparatus; household appliances; electrical lighting and wiring equipment; radio and television receiving equipment; communications equipment; electronic components and accessories; and other electrical equipment and supplies. The manufacture of household appliances is included in this group, but industrial machinery and equipment powered by built-in or detachable electric motors is classified in Industry 35. Establishments primarily engaged in manufacturing instruments are classified in Industry 38.
<b>Industry 37:</b> Transportation Equipment	This industry includes establishments engaged in manufacturing equipment for transportation of passengers and cargo by land, air, and water. Important products produced by establishments classified in this industry include motor vehicles, aircraft, guided missiles and space vehicles, ships, boats, railroad equipment, and miscellaneous transportation equipment, such as motorcycles, bicycles, and snowmobiles. Establishments primarily engaged in manufacturing mobile homes are classified in Industry 2451. Establishments primarily engaged in manufacturing equipment used for moving materials on farms; in mines and on construction sites; in individual plants; in airports; or on other locations off the highway are classified in Industry 35.
<b>Industry 42:</b> Motor Freight Transportation and Warehousing	This industry includes establishments furnishing local or long-distance trucking or transfer services, or those engaged in the storage of farm products, furniture and other household goods, or commercial goods of any nature. The operation of terminal facilities for handling freight, with or without maintenance facilities, is also included. Establishments primarily engaged in the storage of natural gas are classified in Industry 4922. Field warehousing is classified in Services, Industry 7389. Establishments of the United States Postal Service are classified in Industry 43.
<b>Industry 50:</b> Wholesale Trade–Durable Goods	This industry includes establishments primarily engaged in the wholesale distribution of durable goods.

<b>Industry 51:</b> wholesale trade– non-durable goods	This industry includes establishments primarily engaged in the wholesale distribution of non-durable goods.
<b>Industry 61:</b> Non-Depository Credit Institutions	This industry includes establishments engaged in extending credit in the form of loans, but not engaged in deposit banking.
<b>Industry 73:</b> Business Services	This industry includes establishments primarily engaged in rendering services, not elsewhere classified, to business establishments on a contract or fee basis, such as advertising, credit reporting, collection of claims, mailing, reproduction, stenographic, news syndicates, computer programming, photocopying, duplicating, data processing, services to buildings, and help supply services. Establishments primarily engaged in providing engineering, accounting, research, management, and related services are classified in Industry 87. Establishments which provide specialized services closely allied to activities covered in other divisions are classified in such divisions.
<b>Industry 80:</b> Health Services	This industry includes establishments primarily engaged in furnishing medical, surgical, and other health services to persons. Establishments of associations or groups, such as Health Maintenance Organizations (HMOs), primarily engaged in providing medical or other health services to members are included, but those which limit their services to the provision of insurance against hospitalization or medical costs are classified in Insurance, Industry 63. Hospices are also included in this industry and are classified according to the primary service provided. Industry groups 801 through 804 includes individual practitioners, group clinics in which a group of practitioners is associated for the purpose of carrying on their profession, and clinics which provide the same services through practitioners that are employees.
<b>Industry 87:</b> Professional Services	This industry includes establishments primarily engaged in providing engineering, architectural, and surveying services; accounting, auditing, and bookkeeping services; research, development, and testing services; and management and public relations services.

B. Other Services

1. **Dwelling** for caretaker or watchperson.

C. Public Administration and Facilities

1. **Fire protection.** (922160)
2. **Government maintenance facilities and storage yards.**

D. Streets & Utilities

1. **Rights of way and easements and the improvements therein** for streets, water, sanitary sewer, gas, oil, electric and communication lines

and for storm water facilities and for pump stations.

#### **2.114.04**      **Special Permitted Uses**

The following uses, when developed under the applicable development standards of the **WDO** including the special development standards of **Section 2.203**, are permitted in the SWIR zone.

- A.     **Agricultural practices** without livestock subject to **Section 2.203.02**.
- B.     **Delivery services** subject to **Section 2.203.08**.
- C.     **Facilities** during construction subject to **Section 2.203.10**.
- D.     **Mobile food service** subject to **Section 2.203.17**.

#### **2.114.05**      **Conditional Uses**

- A.     **Government and public utility buildings and structures EXCEPT uses permitted in Section 2.110.01** and telecommunications facilities subject to **Section 2.204.03**

#### **2.114.06**      **Specific Conditional Uses**

The uses permitted by the following designation may be allowed in the SWIR zone subject to approval as a conditional use that conforms to the specific standards referenced below, the applicable provisions of the **WDO** and all other applicable conditions of approval.

- A.     **Telecommunications Facilities** subject to **Section 2.204.03**.

#### **2.114.07**      **Accessory Uses**

The following uses are permitted as accessory uses subject to **Section 2.203**.

- A.     **Fence or free standing wall.**

#### **2.114.08**      **Dimensional Standards**

The following dimensional standards shall be the minimum requirements for all development within the SWIR zone.

- A.     Lot Standards
  - 1.     Land divisions may only be approved following approval of a master plan as required in **Section 2.114.10**.



2. Lots in a SWIR zone shall comply with the applicable standards of **Table 2.1.22**. For a land division, at least one lot shall be sized to meet each of the required lot size ranges listed in **Table 2.1.22** for each site, except smaller required lots may be combined to create larger required lots.

**Table 2.1.22 Lot Standards**

Sites (by assessor tax lot number)	Buildable Acres	Required Lot Sizes (ranges shown in acres)	Conceptual Lot Sizes (in acres)	Special Standards
52W11 TL 300        <b>Subtotal:</b>	88	25-50 10-25 10-25 5-10 5-10 2-5 2-5	35 15 15 8 8 4 3 <b>88</b>	Land division permitted with master plan approval
52W14 TL 200 52W14 TL 600  <b>Subtotal:</b>	22	10-25 5-10	15 7 <b>22</b>	Land division not permitted
52W13 TL 1100 52W14 TL 1500 52W14 TL 1600	96	96	96	Land division not permitted  Shall be developed with a use <u>with at least</u> 300 employees
52W14 TL 800 52W14 TL 900 52W14 TL 1000 52W14 TL 1100  <b>Subtotal:</b>	106	50-100 25-50 2-5 2-5	65 33 4 4 <b>106</b>	Land division permitted with master plan approval  50-100 acre lot shall be developed with a use <u>with at least</u> 200 employees
52W14 TL 1200	4	2-5	4	Land division not permitted
52W23 TL 100   <b>Subtotal:</b>	46	25-50 5-10 2-5	35 8 3 <b>46</b>	Land division permitted with master plan approval
<b>Total SWIR</b>	<b>362</b>		<b>362</b>	

**B. Building Height.**

The maximum height of buildings shall not exceed 45 feet, EXCEPT chimneys, spires, domes, flag poles and other features not used for human habitation (but EXCEPT telecommunication facilities), shall not exceed 70 feet.

C. Setback and Buffer Improvement Standards.

1. Minimum Front Setback and Setback Abutting a Street[Section 1.101.02.C.1 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]

- a. Dimensions:

The minimum setback abutting a street shall be 10 feet plus any Special Setback, **Section 3.103.05**.

[Section 2.114.08.C.1.b as amended by Ordinance No. 2423, §19, effective on July 28, 2007.]

- b. Off street parking, Maneuvering and Storage:

- 1) Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:

- i. **WDO** Section 3.105, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.
- ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.
- iii. Storage areas that are located within the front setback behind a wall shall be screened to a minimum height of 6 feet.

- 2) The distance between the sidewalk on a public street and a loading dock shall be sized to preclude vehicles using the dock from projecting over the sidewalk.

- c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, **Section 3.103.10**.
  - d. Vehicular Access: Permitted in conformance **Section 3.104**.
2. Minimum Interior Side and Rear Setbacks. [Section 1.101.02.C.2 as amended by Ordinance No. 2446, §2, passed on September 10, 2008.]
- a. Development in a SWIR zone shall be subject to the setback and buffer requirements of **Table 2.1.23**.

<b>TABLE 2.1.23 Interior Yard and Buffer Standards for SWIR Zone</b>			
<b>Abutting Property</b>	<b>Landscaping</b>	<b>Wall</b>	<b>Interior Setback</b>
<b>RS, RIS, RM, CO, P/SP zone; or Existing residential unit</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	Solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 9 feet in height.	30 ft.
<b>CG, DDC, NNC, IP, IL, or SWIR zone</b>	There is no buffer yard landscaping requirement for an interior yard abutting a buffer wall.	<p>Alternative A:</p> <p>Wall requirements shall be determined in conjunction with the applicable Design Review process.</p> <p>-----</p> <p>Alternative B:</p> <p>No wall required.</p>	<p>Alternative A:</p> <p>5 ft.</p> <p>-----</p> <p>Alternative B:</p> <p>Zero setback abutting a building wall.</p>

- b. The building setback from a private access easement shall be a minimum of 5 feet.

[Section 2.114.08.C.2.c as amended by Ordinance No. 2423, §20, effective on July 28, 2007.]

- c. Off Street Parking, Maneuvering and Storage:

Off street parking and storage shall be prohibited within a required setback EXCEPT for parking and storage adjacent to a wall. All parking, maneuvering, and storage areas shall be improved consistent with the following:

- i. **WDO** Section 3.105, except that storage areas used for equipment that may damage pavement (metal track equipment, heavy machinery, etc.) may be stored on a gravel-surface storage area.

- ii. A gravel storage area shall be adequately designed, graded, drained, and improved to ensure adequate drainage. A gravel storage area shall be constructed to a minimum of surfacing based on the standard of: six (6) inches of one (1) inch minus gravel to three (3) inch minus; if three (3) inch minus is used the top two (2) inches shall be one (1) inch minus. The property owner shall maintain a gravel storage area to ensure continued drainage and dust control. A paved access apron to any paved access road is required regardless of the storage area surface.
- d. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards, ***Section 3.103.10***.
- e. Vehicular Access: Permitted in conformance with Woodburn Access Management Ordinance and ***Section 3.104***.

#### **2.114.09**      **Development Standards**

All development in the SWIR zone shall comply with the applicable provisions of the ***WDO***. The following standards specifically apply to uses in the SWIR zone.

A. Off Street Parking.

Off street parking shall be subject to the standards of ***Section 2.114.08 and Section 3.105***.

B. Setbacks and Lots, Generally.

Setbacks and lots shall be subject to ***Section 3.103***.

C. Architectural Design Guidelines.

All primary buildings and structures shall be subject to the architectural guidelines of ***Section 3.107.08***.

D. Signs.

Signs shall be subject to ***Section 3.110***.

E. Landscaping and Sidewalks.

- 1. The street frontage of a subject property shall be improved with either property line sidewalks and street trees or curb line sidewalks. The improvement shall be determined at the time of subdivision, PUD or

design review as applicable. Sidewalks and trees shall be installed by the property owner to the standards of *Section 3.101 and 3.106*.

2. The subject property shall be landscaped to the standards of *Section 3.106*.
3. Common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

F. Property Disposition.

All uses shall be established and conducted on lots of record, as defined by *Section 1.102* and developed to the public facility and access standards of *Sections 3.101, 3.102 and 3.104*.

1. New lots of record shall be subject to the following standards and procedures:
  - a. **Partitions, *Section 3.108*;**
  - b. **Subdivisions, *Section 3.108*; or**
  - c. **Planned Unit Development *Section 3.109*.**
2. Alteration of the property lines of existing lots of record shall be subject to the applicable following standards and procedures:
  - a. **Property Line Adjustment, *Section 5.101.07*.**
  - b. **Replatting, *Section 3.108*.**
  - c. **Vacation, applicable Oregon Revised Statutes.**

**2.114.10 Master Planning Requirement**

- A. A master development plan shall be approved by the City Council for the entire area designated SWIR on the Comprehensive Plan Map, prior to annexation of any property within the SWIR Comprehensive Plan Map designation. The master plan shall be conceptual and non-binding in nature, but may be used as a general guide for development within the SWIR.
- B. The required master plan shall show:
  1. The location and rights-of-way for existing and planned arterial, collector and local access streets. These streets shall provide access to all existing and proposed parcels, consistent with the Woodburn Transportation System Plan.
  2. The location and size of existing and planned sanitary sewer, storm water and water facilities, at adequate levels to serve existing and proposed

industrial development.

3. The location and area of the RCW Overlay District as it affects existing and proposed industrial parcels. Planned streets and public facilities that cannot reasonably avoid the RCW Overlay District shall be indicated.
4. Conceptual land divisions, consistent with the lot sizes indicated in ***Table 2.1.22***.
5. Conceptual pedestrian and bicycle connections within the SWIR zone consistent with the TSP , and pedestrian and bicycle connections to the Nodal Overlay residential, commercial and park areas.

**2.114.11**      **Removal of the SWIR District**

A. Removal of the SWIR District from any area or parcel shall require the following:

1. A revised Economic Opportunities Analysis and Industrial Site Suitability Analysis, consistent with the Goal 9 Rule (OAR Chapter 660, Division 9).
2. A new Statewide Planning Goal 2 Exception, that explains why other land within or adjacent to the UGB that does not require an exception cannot meet the purported need.
3. A Comprehensive Plan Amendment, that demonstrates compliance with all applicable Statewide Planning Goals, applicable goals and policies of the Marion County Framework Plan, and applicable goals and policies of the Woodburn Comprehensive Plan.
4. A zoning map amendment that demonstrates consistency with the Woodburn Comprehensive Plan.

## 2.115 Nodal Overlay Districts

1. [Section 2.115 as amended by Ordinance 2391, §3, acknowledged on December 22, 2006.]

### **2.115.01 Purpose**

Nodal districts are shown on the Comprehensive Plan Map and encourage neighborhood-serving commercial developments surrounded by well-designed multi-family, attached single family (row houses) and small lot single family development, with active and accessible parks. The intent is to provide a community identity and services to higher density, nodal residential development within walking distance (generally one-half mile or less) of the center. Nodal development will be designed with a pedestrian focus, with interconnected streets and pedestrian walkways, alleys serving garages located at the rear of lots, and with limited parking. To ensure that land is efficiently used within the UGB, master plans shall be required for land within Nodal districts.

### **2.115.02 Nodal Single Family Residential (RSN) District**

#### **A. Allowed Uses.**

The following uses are allowed in the RSN District, subject to the applicable provisions of *Section 2.102* and *Section 2.115*, and other applicable provisions of the WDO:

1. Permitted, special permitted, conditional, specific conditional and accessory uses allowed in the Single Family Residential (RS) zone, *Sections 2.102.01-05*, are allowed subject to the same use provisions of *Sections 2.102.01-05*.
2. Small lot single family detached dwellings are permitted.

#### **B. Dimensional and Development Standards.** The dimensional and development standards of *Sections 2.102.06-07* shall apply, EXCEPT where specifically superseded by the provisions of *Section 2.115*. In case of conflict, the standards of *Section 2.115* supersede the standards in *Section 2.102*.

#### **C. Land Division and Density Standards**

1. An application for a subdivision shall not be approved before approval of a master plan as required in *Section 2.115.04*.
2. A minimum density of 7.9 dwelling units per net buildable acre (after excluding public rights-of-way, public tracts, common open space, and land protected by the RCW overlay district) shall be required for residential development through the subdivision or PUD process.

3. Standard single family residential lots in the RSN Overlay District shall comply with the standards of **Table 2.1.1** in the RS zone.
4. Non-residential lots shall comply with the standards of **Table 2.1.2** in the RS zone.
5. Small lot single family residential lots in an RSN Overlay District shall comply with the standards of **Table 2.1.24**. Flag lots are not permitted.

<b>TABLE 2.1.24 Small Lot Residential Standards in RSN</b>				
Use Type and Location	Minimum Lot Area	Minimum Lot Width	Average Lot Depth	Minimum Street Frontage
<b>A. Small Lot Single Family Dwelling, Site Built; &amp; Residential Sales Office</b>  <u><b>Interior Lot</b></u>  1. For an interior lot.  <u><b>Corner Lot</b></u>  1. For a corner lot.  2. For a <u>cul de sac lot</u> .				
	4000 sq. ft.	45 ft.	80 ft.	40 ft.
	5000 sq. ft.	60 ft.	80 ft.	50 ft.
	4000 sq. ft.	45 ft.	80 ft.	30 ft.

D. Development Standards for Small Lot Single Family Residential Developments. The following development standards shall apply only to small lot single family residential developments. Standards for other developments and uses shall comply with the *RS zone*.

1. Minimum Front Setback and Setback Abutting a Street: The minimum setback abutting a street, or front property line for small lot single family dwellings shall be 10 feet plus any Special Setback, **Section 3.103.05**. [Section 2.115.02.D.1 as amended by Ordinance No. 2446, §16, passed on September 10, 2008.]

a. Off Street Parking, Maneuvering and Storage:

- 1) Vehicular access directly to a public street is prohibited and alley access to garages facing the alley is required. Off street parking and storage shall be prohibited within a required front yard setback or any yard abutting a street.
- 2) Clear Vision Area: Fences, walls, landscaping and signs



shall be subject to clear vision area standards, **Section 3.103.10**.

2. Minimum Interior Side and Interior Rear Setbacks. [Section 2.115.02.D.2 as amended by Ordinance No. 2446, §16, passed on September 10, 2008.]
  - a. Dimensions:
    - 1) Side Setback. The minimum side setback shall be 5 feet. [Section 2.115.02.D.2.a.1 as amended by Ordinance No. 2446, §16, passed on September 10, 2008.]
    - 2) Rear Setback. The average rear setback (as defined in **Section 1.102**) shall be 20 feet. [Section 2.115.02.D.2.a.2 as amended by Ordinance No. 2446, §16, passed on September 10, 2008.]
  - b. Off Street Parking, Maneuvering and Storage:
    - 1) Off street parking, maneuvering and storage shall not be permitted in a side yard setback.
    - 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from an alley or rear property line.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards of **Section 3.103.10**.
3. Alley requirement. Alleys shall be required for all small lot single family residential subdivisions. Alleys shall be dedicated and paved to a minimum width of 20 feet. No parking shall be allowed within an alley right-of-way.
4. Architectural Design Standards. In addition to meeting the architectural design standards of **Section 3.107.03**, small lot single family dwellings shall meet the following design standards. In cases of conflict with other sections of the WDO, these standards prevail.
  - a. Two-car garages shall be required, facing directly on to an alley. Vehicular access to the garage from the street shall be prohibited.
  - b. At least 25% of the ground level façade facing the street shall be windows.

- c. Covered front porches of at least 60 square feet shall be required with no dimension of less than 6 feet.
  - d. The maximum permitted front porch setback shall be 15 feet.
  - e. Direct pedestrian access from the street to the front porch shall be provided.
5. A front yard landscaping and maintenance plan shall be required for all small lot single family subdivisions prior to preliminary plat approval.

**2.115.03**      **Nodal Medium Density Residential (RMN) District**

A. Allowed Uses.

The following uses are allowed in the RMN District, subject to the applicable provisions of *Section 2.104* and *Section 2.115*, and other applicable provisions of the WDO:

- 1. Permitted, special permitted, conditional, specific conditional and accessory uses allowed in the Medium Density Residential (RM) zone, *Sections 2.104.01-05*, are allowed subject to the same use provisions of *Sections 2.104.01-05*.
- 2. Attached single family dwellings (row houses) are permitted.
- 3. Detached single family and manufactured dwellings on individual lots are permitted subject to the development standards for small lot single family dwellings in *Section 2.115.02*.

B. Dimensional and Development Standards. The dimensional and development standards of *Sections 2.104.06-07* shall apply, EXCEPT where specifically superseded by the provisions of *Section 2.115*. In case of conflict, the standards of *Section 2.115* supersede the standards in *Section 2.104*.

C. Land Division and Density Standards

- 1. An application for a subdivision shall not be approved before approval of a master plan as required in *Section 2.115.04*.
- 2. A minimum density of 19 multi-family, or 10 duplex or rowhouse dwelling units per net buildable acre (after excluding public rights-of-way, public tracts, common open space, and land protected by the RCW overlay district) shall be required for residential development through the subdivision or PUD process.

3. Single family and manufactured dwelling residential lots in the RMN District shall comply with the provisions for small lot single family dwellings in **Section 2.115.02**.
4. Non-residential lots shall comply with the standards of **Table 2.1.6** in the RM zone.
5. Multi-family and attached single family (row houses) residential lots in an RMN District shall comply with the standards of **Table 2.1.25**. Flag lots are not permitted.

<b>TABLE 2.1.25 Residential Lot Standards in RMN</b>				
Use Type and Location	Minimum Lot Area / Maximum Density	Minimum Lot Width	Average Lot Depth	Minimum Street Frontage
<b>A. Row Houses with Alley Access</b>				
1. For an interior lot.	3,000 sq. ft.	28 ft.	80 ft.	28 ft.
2. For a corner lot or cul de sac lot.	3600 sq. ft.	40 ft.	80 ft.	40 ft.
<b>B. Duplex dwellings on an individual lot</b>	8,000 sq. ft.	80 ft.	90 ft.	80 ft.
<b>C. Multifamily Dwellings</b>		200 ft.	200 ft.	
1. Minimum Development Area	2 Acres			
2. Maximum residential density	24 units /net acre			
<b>D. Assisted living facility (62331) or nursing care facility (6231)</b>				
1. Minimum Development Area	2 acres	200 ft.	200 ft.	200 ft.
2. Maximum residential density	32 units / net acre			

**D. Building Height.**

The maximum height of buildings and structures within the RMN District shall not exceed 45 feet, EXCEPT chimneys, spires, domes, flag poles and other features (EXCEPT telecommunication facilities subject to **Section 2.204.03**) not used for human habitation, which shall not exceed 70 feet.

**E. Multi-Family and Duplex Residential Development Standards.**

5. The setback abutting a street and the front setback for multi-family and duplex residential uses shall be a minimum of 10 feet and a maximum of 15 feet, EXCEPT where [Section 2.115.03.C.1 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]:
  - a. Abutting a commercial or industrial zone, or an arterial or

collector street, in which case the minimum street or front yard setback shall be 20 feet.

6. Rear and side setbacks shall be a minimum of 10 feet, EXCEPT where [Section 2.115.03.C.2 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]:
  - a. Abutting an RS or R1S zone , in which case, the minimum setback shall be 10 feet for the first floor, and 5 additional feet for each additional story.
7. EXCEPT for duplex lots, parking lots shall:
  - a. Be located behind or to the side of buildings.
  - b. Not occupy more than 50% of any street frontage.
  - c. Not be located within 20 feet of a public street or within 20 feet of an RS, R1S or RM zoned property, unless a minimum 6-foot high architectural wall is provided between the parking lot and the adjacent RS, R1S or RM zoned property, in which case, the parking lot shall not be located within 5 feet of the adjacent property.

**F. Attached Single Family Dwelling (Row Houses) Development Standards.**

1. Minimum Front Setback and Setback Abutting a Street [Section 2.115.03.D.1 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]:

The minimum setback abutting a street, or front property line for attached single family development shall be 10 feet plus any Special Setback, **Section 3.103.05**, EXCEPT the minimum setback abutting an arterial street shall be 20 feet.

- a. Off Street Parking, Maneuvering and Storage:
  - 1) Vehicular access directly to a public street is prohibited and alley access to garages facing the alley is required. Off street parking and storage shall be prohibited within a required front setback or any yard abutting a street. [Section 2.115.03.D.1.a.1 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]:
  - 2) Clear Vision Area: Buildings, fences, walls, landscaping and signs shall be subject to clear vision area standards,

***Section 3.103.10.***

2. Minimum Interior Side and Interior Rear Setbacks. [Section 2.115.03.D.2 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]:
  - a. Dimensions:
    - 1) Side Setback. The minimum side setback shall be 0 feet, EXCEPT for corner lots, in which case, the minimum street side setback shall be 15 feet. [Section 2.115.03.D.2.a.1 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]
    - 2) Rear Setback. The average rear setback (as defined in ***Section 1.102***) shall be 20 feet. [Section 2.115.03.D.2.a.2 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]
  - b. Off Street Parking, Maneuvering and Storage:
    - 1) Off street parking, maneuvering and storage shall not be permitted in a side setback. [Section 2.115.03.D.2.b.1 as amended by Ordinance No. 2446, §17, passed on September 10, 2008.]
    - 2) The entrance to a garage (or carport in the case of a manufactured home) shall be set back a minimum of 20 feet from an alley or rear property line.
  - c. Clear Vision Area: Fences, walls, landscaping and signs shall be subject to clear vision area standards of ***Section 3.103.10.***
3. Alley requirement. Alleys shall be required for all attached single family dwelling developments. Alleys shall be dedicated and paved to a minimum width of 20 feet. No parking shall be allowed within an alley right-of-way.
4. Architectural Design Standards. In addition to meeting the architectural design standards of ***Section 3.107.03***, attached single family dwellings shall meet the following design standards. In cases of conflict with other sections of the WDO, these standards prevail.
  - a. Two-car garages shall be required, facing directly on to an alley.

Vehicular access to the garage from the street shall be prohibited.

- b. At least 25% of the ground level façade facing the street shall be windows.
  - c. Covered front porches of at least 60 square feet shall be required with no dimension of less than 6 feet.
  - d. The maximum permitted front porch setback shall be 15 feet.
  - e. Direct pedestrian access from the street to the front porch shall be provided.
5. A front yard landscaping and maintenance plan shall be required for all attached single-family subdivisions prior to preliminary plat approval.

#### **2.115.04 Master Planning Requirement**

- A. A master development plan shall be approved by the City Council for the entire area designated as Nodal Overlay on the Comprehensive Plan Map, prior to annexation of any property within the Nodal Overlay Comprehensive Plan Map designation. The master plan shall be conceptual and non-binding in nature, but may be used as a general guide for development within the Nodal Overlay Districts.
- B. The required master plan shall show:
  - 1. The location and rights-of-way for existing and planned arterial, collector and local access streets. These streets shall provide access to all existing and proposed parcels, consistent with the Woodburn Transportation System Plan.
  - 2. The location and size of existing and planned sanitary sewer, storm water and water facilities, at adequate levels to serve existing and proposed development.
  - 3. The location and area of the RCW Overlay District as it affects existing and proposed nodal development parcels. Planned streets and public facilities that cannot reasonably avoid the RCW Overlay District shall be indicated.
  - 4. A conceptual development plan for the Nodal Neighborhood Commercial center, neighboring multi-family areas, and potential parks, including planned pedestrian and bicycle connections within the Nodal Overlay District as shown on the TSP, and pedestrian and bicycle connections to Southwest Industrial Reserve areas.

5. A conceptual plan for local streets and alleys, and lotting patterns, showing how small lot and attached single family development could occur consistent with applicable nodal design standards.

**2.115.05      Removal of a Nodal Overlay District**

- A. Removal of a Nodal Overlay District from any area or parcel shall require the following:
  1. A revised transportation, housing and commercial land needs analysis, consistent with the Goal 9, 10 and 12 Rules (OAR Chapter 660, Divisions 8, 9 and 12).
  2. A Comprehensive Plan Amendment, that demonstrates compliance with all applicable Statewide Planning Goals, applicable goals and policies of the Marion County Framework Plan, and applicable goals and policies of the Woodburn Comprehensive Plan.
  3. A zoning map amendment that demonstrates consistency with the Woodburn Comprehensive Plan

## **2.116 Interchange Management Area (IMA) Overlay District**

[Section 2.116 as amended by Ordinance 2391, §3, acknowledged on December 22, 2006.]

### **2.116.01 Purpose**

The purpose of this overlay district is to preserve the long-term capacity of Woodburn's I-5 Interchange with Highway 214, in coordination with the Oregon Department of Transportation (ODOT).

Preserving the capacity of this interchange is an essential element of the City's economic development strategy, because continued access to I-5 is necessary to attract and maintain basic employment within the Woodburn Urban Growth Boundary (UGB). **Section 2.116** complements the provisions of the Southwest Industrial Reserve (SWIR) District by ensuring that industrial land is retained for targeted basic employment called for in the Woodburn Economic Opportunities Analysis (EOA) and the Economic Development Strategy (EDS). **Section 2.116** also ensures that needed industrial, commercial and residential land within the IMA Overlay District is protected from commercial encroachment.

These goals are met by establishing trip generation budgets as called for in Transportation Policy H-7.1 of the Woodburn Comprehensive Plan. The parcel budgets are intended to be high enough to accommodate peak hour trips anticipated by the 2005 Woodburn Comprehensive Plan (WCP) and Transportation Systems Plan (TSP), but low enough to restrict unplanned vehicle trips that could adversely affect the interchange.

### **2.116.02 Boundary of the IMA Overlay District**

The boundary of the IMA Overlay District is shown on the Woodburn Comprehensive Plan Map and Zoning Map.

### **2.116.03 Applicability**

The provisions of **Section 2.116** shall apply to all Type II – V land use applications that propose to allow development that will generate more than 20 peak hour vehicle trips (based on the latest Institute of Transportation Engineers Trip Generation Manual) on parcels identified in **Table 2.116.1**. The provisions of **Section 2.116.07** shall apply to all properties within the boundary of the IMA.



## **2.116.04**      **Vehicle Trip Budgets**

**Section 2.116** establishes a total peak hour trip generation budget for planned employment (commercial and industrial) land uses within the Interchange Management Area – defined as the IMA Trip Budget, and a trip budget for each vacant commercial or industrial parcel – defined as the parcel budget.

### A.      The IMA District Trip Budget

The IMA Trip Budget for vacant commercial and industrial parcels identified in **Table 2.116.1** is 2,500 peak hour vehicle trips (An estimated 1,500 additional peak hour residential trips are planned within the IMA District). The IMA Trip Budget will be allocated to parcels identified in **Table 2.116.1** on a first developed – first served basis.

### B.      2005 (Initial) Vehicle Trip Budget by Parcel

The parcel budget for each vacant commercial or industrial parcel within the IMA Overlay District is shown on **Table 2.116.1**. Parcel budgets are based on 11 peak hour trips per developed industrial acre, and 33 peak hour trips per developed commercial acre.

1.      The parcel budget for each parcel will be reduced in proportion to actual peak hour vehicle trips generated by new development on any portion of the parcel.
2.      The City *may* allow development that exceeds the parcel budget for any parcel in accordance with **Section 2.116.08.B**.

(Table on next page.)

**Table 2.116.1. Vehicle Trip Budget by Parcel (Parcel Budget)**

Assessor Map and Tax Lot Number	Applicable Comprehensive Plan Designation	Vacant Buildable Acres	Maximum Peak Hour Vehicle Trips
052W11 00300	SWIR	88	968
052W13 01100 052W14 01500 052W14 01600	SWIR	96	1056
052W14 00200 052W14 00600	SWIR	22	242
052W14 00800 052W14 00900 052W14 01000 052W14 01100	SWIR	109	1199
052W14 01200	SWIR	4	44
052W23 00100	SWIR	46	506
052W12AC 04301	Commercial	2	66
052W12C 00604	Commercial	1	33
052W12C 00605	Commercial	3	99
052W12C 02100	Commercial	7	231
052W12C 02200	Commercial	6	198
052W12C 02300	Commercial	7	231
052W12C 02400	Commercial	2	66
052W13 01600	Commercial	5	165
052W14 02000	Commercial	8	264
052W14 02100	Commercial	5	165
052W14 02300	Commercial	6	198
052W13BD 00900 (westerly portion) 052W13BD 01500 052W13BD 01600 052W13BD 01700 052W13BD 01800	Nodal Commercial	9	297

**2.116.05 Administration**

*Section 2.116* delineates responsibilities of the City and ODOT to monitor and evaluate vehicle trip generation impacts on the I-5 interchange from development approved under this section.

A. Traffic Impact Analysis (TIA)

A TIA is required for all land use applications subject to the provisions of *Section 2.116*. The TIA must meet City and ODOT administrative rule (OAR Chapter 734, Division 51) requirements and shall include an evaluation and

recommendation of feasible transportation demand management (TDM) measures that will minimize peak hour vehicle trips generated by the proposed development. [Section 2.116.05.A as amended by Ordinance No. 2446, §25, passed on September 10, 2008.]

#### B. ODOT Coordination

For a land use application subject to the provisions of *Section 2.116*:

1. The City shall not deem the land use application complete unless it includes a TIA prepared in accordance with TIA Requirements. [Section 2.116.05.B.1 as amended by Ordinance No. 2446, §25, passed on September 10, 2008.]
2. The City shall provide written notification to ODOT when the application is deemed complete. This notice shall include an invitation to ODOT to participate in the City's facilities review meeting.
3. ODOT shall have at least 20 days to provide written comments to the City, measured from the date the completion notice was mailed. If ODOT does not provide written comments during this 20-day period, the City's decision may be issued without consideration of ODOT comments.

#### C. City Monitoring Responsibilities

The details of City and ODOT monitoring and coordination responsibilities are found in the Woodburn – ODOT Intergovernmental Agreement (IGA).

1. The City shall be responsible for maintaining a current ledger documenting the cumulative peak hour trip generation impact from development approved under *Section 2.116*, compared with the IMA Trip Budget.
2. The City may adjust the ledger based on actual development and employment data, subject to review and concurrence by ODOT.
3. The City will provide written notification to ODOT when land use applications approved under *Section 2.116*, combined with approved building permits, result in traffic generation estimates that exceed 33% and 67% of the IMA Trip Budget.

#### D. Vesting and Expiration of Vehicle Trip Allocations

This section recognizes that vehicle trip allocations may become scarce towards the end of the planning period, as the I-5 Interchange nears capacity. The following rules apply to allocations of vehicle trips against the IMA Trip Budget:

1. Vehicle trip allocations are vested at the time of design review approval.
2. Vehicle trips shall not be allocated based solely on approval of a comprehensive plan amendment or zone change, unless consolidated with a subdivision or design review application.
3. Vesting of vehicle trip allocations shall expire at the same time as the development decision expires, in accordance with *Section 4.102.03-04*.

**2.116.06**      **Allowed Uses**

- A. Uses allowed in the underlying zoning district are allowed subject to other applicable provisions of the WDO and *Section 2.116*.

**2.116.07**      **Comprehensive Plan and Zoning Map Amendments**

*Section 2.116.07* applies to all Comprehensive Plan Map amendments within the IMA Overlay District. This section does not apply to Zoning Map amendments that result in conformance with the applicable Comprehensive Plan Map designation, such as Zoning Map amendments that occur when land is annexed to the City.

- A. Transportation Planning Rule Requirements.

Applications for Comprehensive Plan Map amendments, and for Zoning Map amendments shall determine whether the proposed change will significantly affect a collector or arterial transportation facility, and must meet the requirements of Oregon Administrative Rule (OAR) 660-012-0060 and WDO *Section 5.104.02-04*.

- B. Limitations on Comprehensive Plan Amendments.

To ensure that the remaining capacity of the I-5 Interchange is reserved for targeted employment opportunities identified in Chapter 4 of the Economic Opportunities Analysis (EOA) and needed housing, this section imposes the following prohibitions on Comprehensive Plan Map amendments within the IMA Overlay District:

1. Comprehensive Plan Map amendments that will increase the net Commercial land area within the IMA Overlay District shall be prohibited.
2. Comprehensive Plan Map amendments that allow land uses that will generate traffic in excess of the IMA Trip Budget shall be prohibited.

**2.116.08**      **Interchange Capacity Preservation Standards**

Land use applications subject to the provisions of *Section 2.116* shall comply with the following:

- A. Cumulative Impact Standard. Peak hour vehicle trips generated by the proposed development shall not, in combination with other approved developments subject to **Section 2.116**, exceed the IMA Trip Budget of 2,500.
- B. Parcel-Specific Impact Standard. Peak hour vehicle trips generated by the proposed development shall not exceed the maximum peak hour vehicle trips specified in **Table 2.116.1** for the subject parcel, EXCEPT:
  - 1. Development of uses listed in **Table 2.1.21 (Section 2.114.03, SWIR Zone Permitted Uses)** *may* be allowed to exceed the maximum, *if* the development will contribute substantially to the economic objectives found in Chapter 2 of the Woodburn Economic Development Strategy (EDS).
  - 2. Residential development on a parcel zoned Commercial shall be allowed to exceed the maximum.
- C. Transportation demand management (TDM) measures shall be required to minimize peak hour vehicle trips and shall be subject to annual review by the City.

## 2.2 SPECIFIED USE STANDARDS

### 2.201 Accessory Uses and Structures: Residential Zones and Residential Uses

#### **2.201.01**      **Applicability**

The following standards are applicable to accessory structures in the RS, R1S, and RM zones; residential uses in the CO zone; and existing residential uses.

#### **2.201.02**      **Structures EXCLUDING Fences and Freestanding Walls**

A.      Height.

The maximum height of an accessory structure, EXCLUDING a fence or freestanding wall, shall depend on the yard in which it is located and its location relative to a lot line in that yard, *Sections 2.201.02.B., C. and D.*

B.      Location and Height in a Yard Adjacent to a Street.

1.      The setback for an accessory structure, EXCEPT a fence or freestanding wall, adjacent to a property line abutting a street shall be the same as for a primary use.
2.      The maximum height of the structure at the setback line shall be 15 feet.

C.      Location and Height in an Interior Side Yard.

1.      The interior side yard setback for an accessory structure, EXCEPT a fence or freestanding wall, shall be the same as for the primary structure.
2.      The maximum height of the structure at the set back line shall be 15 feet.

D.      Location and Height in an Interior Rear Yard.

1.      The required interior rear yard setback for an accessory structure, EXCEPT for a fence and freestanding wall, shall be governed by the height of the structure.
2.      A structure with a height of 8 feet or less may be located on the property line, EXCEPT abutting an alley. All structures shall setback one foot from an alley; and

3. For each foot of height, or fraction thereof, in excess of 8 feet, the accessory structure shall set back one additional foot from a lot line. The maximum height of an accessory structure shall be 15 feet, with a corresponding minimum setback from an interior rear lot line of 7 feet.

E. Attachment to a Primary Building.

Covered or enclosed accessory structures, which are attached to a primary building shall be considered as a portion of the primary building and subject to the same zoning requirements as the primary building.

F. Lot Coverage.

The maximum lot coverage for accessory structures, EXCLUDING a fence or freestanding wall, shall be not more than 25 percent of the rear yard area.

**2.201.03**

**Fences and Freestanding Walls**

A. Review Prior to Installation.

Plans for installation or construction of all fences and freestanding walls shall be reviewed as a ***Type I*** application before installation or construction to assure compliance with standards of the state Building Code and the ***WDO***.

B. Location and Height in Yards Adjacent to a Street.

1. The location and height shall comply with the clear vision area standards, ***Section 3.103.10***.
2. The location and height shall not exceed a height of 42 inches above the curb elevation, when located on the front lot line abutting the street. For streets without curbs the maximum height shall be measured relative to the elevation of the center line of the improved street. [Section 2.201.03.B as amended by Ordinance No. 2383, §27(2), passed March 16, 2005.]
3. The location and height shall not exceed a height of 48 inches above the curb elevation, when located on the side lot line abutting the street. For streets without curbs the maximum height shall be measured relative to the elevation of the center line of the improved street. [Section 2.201.03.B as amended by Ordinance No. 2383, §27(3), passed March 16, 2005.]
4. The height relative to the ground elevation under the fence, may increase one foot in height for each 6 feet of setback from the lot line, not to exceed a maximum height of seven feet.

C. Height in Yards Not Adjacent to a Street.

The maximum height of a fence or free standing wall located in a yard not adjacent to a street shall be seven feet.

D. Construction Materials Prohibited.

Fences and freestanding walls constructed of materials that could cause bodily harm, including, but not limited to, those conveying electric current, barbed or razor wire, spikes and broken glass, shall be prohibited.



## **2.202 Accessory Uses and Structures: Non-Residential Zones and Uses**

### **2.202.01 Applicability**

The following standards are applicable to structures accessory to non-residential uses in the CO, DDC, NNC, CG, IP, IL, SWIR and P/SP zones. [Section 2.202.01 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

### **2.202.02 Structures EXCLUDING Fences and Freestanding Walls**

#### **A. Location and Height in All Yards.**

The setback and maximum height for an accessory structure, except for fences and freestanding walls, shall be the same as for a primary use.

#### **B. Lot Coverage.**

Accessory structures shall be included with the primary structures in computing lot coverage.

### **2.202.03 Fences and Freestanding Walls**

#### **A. Safety Review Prior to Fence Installation.**

Plans for installation of all fences and freestanding walls shall be reviewed as a ***Type I*** application prior to installation to assure compliance with safety standards of the state building code and the ***WDO***.

#### **B. Location and Height in Yards Adjacent to a Street.**

1. The location and height shall comply with the clear vision area standards, ***Section 3.103.10***.
2. The location and height shall not exceed a height of 42 inches above the curb elevation, when located on the front lot line abutting the street. For streets without curbs the maximum height shall be measured relative to the elevation of the center line of the improved street. [Section 2.202.03.B as amended by Ordinance No. 2383, §28(2), passed on March 16, 2005.]
3. The location and height shall not exceed a height of 48 inches above the curb elevation, when located on the side lot line abutting the street. For streets without curbs the maximum height shall be measured relative to the elevation of the center line of the improved street. [Section 2.202.03.B as amended by Ordinance No. 2383, §28(2), passed on March 16, 2005.]

4. The height relative to the ground elevation under the fence, may increase one foot in height for each 6 feet of setback from the lot line, not to exceed a maximum height of seven feet.

C. Height in Yards Not Adjacent to a Street.

The maximum height in yards not adjacent to a street shall be seven feet.

D. Construction Materials Prohibited.

Fences and freestanding walls constructed of materials that could cause bodily harm, including, but not limited to, those conveying electric current, barbed or razor wire, spikes and broken glass, shall be prohibited, EXCEPT that in an industrial zone fences and freestanding walls may incorporate barbed wire provided the wire is located at least 150 feet from a public street.

## **2.203 Special Use Standards**

### **2.203.01 General Provisions**

#### **A. Application.**

Special uses are subject to specific development standards. These standards are non-discretionary so that special review of a proposed development shall not be required. The standards contained in this Section apply to Special Uses identified in **Section 2.1**. If a special use is listed as a conditional use, the standards contained in this Section shall be considered guidelines and may be modified or eliminated as the result of a **Type III** review.

#### **B. Development Requirements.**

Unless specifically modified by the provisions of this Section, special uses are also subject to the development requirements of the underlying zone. Where the special use standard imposes a standard higher, the special use standard shall apply.

### **2.203.02 Agricultural Practices**

Where permitted as a special use, gardens, orchards and crop cultivation shall comply with the following requirements:

#### **A. Limitations on Animals.**

No coop, stable or barn, cattle or other livestock, or poultry shall be permitted on the premises.

### **2.203.03 Boat and Recreational Vehicle Storage Pad**

Where permitted as a special use in conjunction with a single family dwelling or duplex, the development of any boat and recreational vehicle storage pad shall comply with the following use and development standards:

#### **A. Space Limitation.**

Each dwelling unit shall be limited to storage pad(s) with the capacity to store a total of two boats, recreational vehicles or these items in combination, in addition to permitted off-street parking.

#### **B. Use Prohibited.**

Permitted off street parking shall not be used to store boats or recreational vehicles in violation of any Woodburn City Ordinance.

C. Location.

The boat or recreational space shall be located in either the side or rear yard.

D. Surfacing.

The space shall be paved and shall be drained to prevent standing water.

E. Screening.

A space located closer than 10 feet to an adjacent property line shall be screened by a sight-obscuring fence or wall with anti-graffiti surface, that is no less than 6 feet or greater than 7 feet in height.

**2.203.04 Boat and Recreational Vehicle Storage Area**

Where permitted as a special use, boat and recreational vehicle storage areas shall comply with the following use and development standards, EXCEPT when such uses are incorporated in the site plan review of a residential development the following criteria shall serve as review guidelines:

A. Management.

The storage must be operated by either a homeowners' association or a property manager of the apartment, manufactured home park or residential complex.

B. Use Limitation.

The storage area is limited exclusively to the storage of the resident's boats or trailers, recreational vehicles, utility trailers and horse trailers, none of which are kept or used as part of a business or commercial activity.

C. Screening.

Outdoor storage areas shall be screened from all adjacent properties and from abutting streets by a solid brick or architectural block wall and gate with an anti-graffiti surface, that is no less than 6 feet or greater than 7 feet in height.

D. Landscaping.

All yard areas on the exterior of the wall shall be landscaped to a plant density of one (1) plant unit (PU) per 20 sq. ft. per ***Table 3.1.5.***

E. Paving.

Storage areas and driveways to the storage area shall be paved.

F. Lighting.

Outdoor lighting shall be directed away from residential property and public streets.

**2.203.05 Community Club Buildings and Facilities**

Where permitted as a special use, community club buildings and facilities shall comply with the following use and development standards, EXCEPT when such uses are incorporated in the site plan review of a residential development the following criteria shall serve as design review guidelines:

A. Setbacks.

Buildings shall comply with the setback requirements of the underlying zone. Swimming pools, tennis courts, and similar sports courts or fields shall be set back 20 feet from all abutting residential zones and uses.

B. Parking.

No off-street parking or loading area shall be permitted within 10 feet of the side and rear lot lines.

C. Screening.

All parking shall be screened from abutting residential zones and uses by a solid brick or architectural block wall with an anti-graffiti surface, that is not less than 6 feet, but not more than 7 feet in height.

D. Landscaping.

All yard areas on the exterior of the wall shall be landscaped to a plant density of one (1) plant unit (PU) per 20 sq. ft. ***Table 3.1.5.***

E. Lighting.

Outdoor lighting shall be directed away from residential property and public streets.

**2.203.06 Complementary Residential Uses**

Where permitted as a special use, Complementary Residential Uses shall comply with the following use and development standards:

A. Mixed Use Required.

Residential uses shall be permitted when developed in conjunction with a commercial use.

B. Ground Floor Use.

Residential uses shall be permitted on any level of a mixed use building EXCEPT the ground floor.

C. Parking.

Vehicle and bicycle parking for each residential unit shall be provided to the standards of **Section 3.105** and such parking shall be identified and reserved exclusively for the residential uses.

D. Residential Density.

The residential density per acre of residential use shall be subject to the requirements of **Table 2.1.5**.

**2.203.07**      **Craft Industries**

Where permitted as a special use, craft industries shall comply with the following use and development standards:

A. Uses Permitted.

Primary uses shall be limited to the following:

1.    **Apparel manufacturing** (315)
2.    **Other leather manufacturing** (31699)
3.    **Furniture and related product manufacturing** (337) INCLUDING  
      cabinets
4.    **Sporting goods manufacturing** (33992)
5.    **Doll, toy and game manufacturing** (33993) Facility Design.

The use shall have a retail storefront.

B. Prohibited Outdoor Activities.

No outdoor storage, manufacturing, assembly or staging for shipping.

C. Maximum Size.

Manufacturing and/or assembly shall be limited to either 10, 000 sq. ft., or five (5) or fewer full time equivalent employees, whichever is smaller.

D. Environmental Quality.

Noise, light or odor associated with the manufacturing or assembly shall not emanate from the building.

**2.203.08**      **Delivery Services**

Where permitted as a special use, delivery services shall comply with the following use and development standards:

A. Uses Permitted.

The use shall be limited to the delivery of packages and the sale and/or delivery of food and/or beverages.

B. Types of Units Permitted.

The service shall be transacted from a self contained, mobile unit.

C. Required Mobility.

In conducting the sales and service, the mobile unit and delivery personnel shall be required to move to a new location at intervals of 15 minutes or less.

D. Business License.

The business represented by the mobile delivery service is subject to business license requirements.

**2.203.09**      **Duplex on a Corner Lot**    (See *Figure 6.5*)

Where permitted as a special use, a duplex on a corner lot shall comply with the following additional use and development standards:

A. Lot Area.

The corner lot shall comply with applicable dimensional and platting requirements of *Table 2.1.1*.

B. Access.

Each dwelling unit shall derive its pedestrian and vehicular access from a different street frontage, unless otherwise required by the Public Works Director.

**2.203.10**      **Facilities During Construction**

Where permitted as a special use facilities during construction shall comply with the following use and development standards:

[Section 2.203.10.A as amended by Ordinance 2423, §21, effective on July 28, 2007.]

A.      Uses Permitted.

The use shall be limited to mobile offices, temporary power equipment, temporary housing for night security personnel, portable toilets, and equipment storage during construction.

B.      Removal.

All temporary facilities necessary for construction shall be removed prior to final occupancy.

**2.203.11**      **Golf Courses**

Where permitted as a special use golf courses, EXCLUDING driving ranges, shall comply with the following use and development standards, EXCEPT when such uses are incorporated in the site plan review of a residential development the following criteria shall serve as review guidelines:

A.      Setbacks.

Buildings shall comply with the setback requirements of the underlying zone. Accessory swimming pools, tennis courts, and similar sports courts or fields shall be set back a minimum of 20 feet from all abutting residential zones and uses.

B.      Parking.

No off-street parking or loading area shall be permitted within 10 feet of the side and rear lot lines.

C.      Screening.

All parking shall be screened from abutting residential zones by a solid brick or architectural block wall, with an anti-graffiti surface, that is no less than 6 feet or greater than 7 feet in height.

D.      Lighting.



Outdoor lighting shall be directed away from residential property and public streets.

**2.203.12**      **Home Occupations**

Where permitted as a special use, a home occupation, conducted entirely within a single family residential dwelling or single family dwelling accessory structure, shall comply with the following use and development standards:

A.      Operations.

The owner/operator of the home occupation shall reside in the home in which the home occupation is conducted. No outside employees shall work on-site or use the site as a base of operations that requires a daily visit to the site of the home occupation for instructions, assignments or the distribution of tools or other goods.

B.      Compatibility.

The home occupation shall be continuously conducted in such a manner as not to create any off premise nuisance, public or private, including but not limited to noise, odors, vibration, fumes, smoke, fire hazard, or electronic, electrical, or electromagnetic interference.

C.      Signs.

Signs shall comply with the provisions of ***Section 3.110***. [Section 2.203.12C as amended by Ordinance No. 2359, §12, passed March 22, 2004.]

D.      Location.

The home occupation shall be conducted entirely within the dwelling, any attached garage, or in an unattached accessory building.

E.      Area.

The total floor area devoted to the home occupation shall not exceed 500 square feet.

F.      Alterations.

The structure shall conform with appropriate occupancy standards of the state building code. Structural alterations shall be permitted provided the residential character of the building is not altered.

G. Parking:

1. The number of required off street parking spaces shall not be reduced; however, no additional parking shall be required.
2. The parking or storage of vehicles licensed as commercial vehicles or displaying permanent commercial advertising shall be prohibited on site.

H. Hours of Operation.

Visits by suppliers or customers shall be limited to the hours of 8:00 a.m. and 8:00 p.m.

I. Outdoor Storage.

Outdoor storage or display of materials, equipment, or merchandise shall be prohibited.

J. Prohibited Activities.

1. Vehicle Repair. Repair of vehicles, including automobiles, motorcycles, tractors and similar mechanized equipment, shall be prohibited. Repair of vehicles includes, but is not limited to, mechanical repair, vehicle service, body work, vehicle painting and vehicle detailing.
2. Retail or Wholesale Sales and Distribution. The retail or wholesale sale or distribution of a product or good(s) on the site to customers shall be prohibited. This prohibition shall not apply to operation of a mail order business where customers do not come to the site.

K. Day Care Provisions.

The provisions in this section shall not apply to family day care providers.

L. Business License.

Home occupations are subject to business licensing requirements.

**2.203.13 House of Worship**

Where permitted as a special use, a house of worship shall comply with the following use and development standards.

A. Side and Rear Yard Setbacks.

A house of worship shall be located not less than 20 feet from an abutting RS, R1S or RM zone, or from an existing residential use. In all other instances the required setbacks of the underlying zone of the property containing a house of worship shall otherwise apply.

B. Landscaping.

All required setback areas shall be landscaped to the standards of *Section 3.106*.

C. Off street parking.

1. Off street parking areas shall comply with the required setback. [Section 2.203.13.C.1 as amended by Ordinance No. 2383, §29, passed March 16, 2005.]
2. Any portion of an off street parking area abutting property zoned or used for residential purposes shall be screened by a solid 7 foot brick or architectural block wall with an anti-graffiti surface.

D. Street Access.

Unless permitted by the Public Works Director, no more than two vehicle access driveways per street frontage shall be permitted.

E. Bus and Van Storage.

Storage of buses and vans used by the use shall be permitted if the vehicles are not parked closer than 20 feet to a residential zone or use.

**2.203.14 Industrial Sales**

Where permitted as a special use, industrial sales shall comply with the following use and development standards:

A. Uses Permitted.

The use shall be limited to:

1. **Manufacture (mobile) home dealers** (453930).
2. **Motor vehicle and parts dealers** (441) INCLUDING new car, used car, recreational vehicle, motorcycle, boat, parts and tire dealers.
3. **Truck dealers** INCLUDING new truck, used truck, parts and tire dealers.

4. **Tractor and farm machinery and equipment dealers.**
  5. **Farm, garden and landscaping supplies.**
- B. Location.
- The site for the use shall be located in an IP zone within 500 feet of Pacific Highway 99E.
- C. Development Standards.
- The use is subject to site plan review and all development standards of the **WDO**, including the standard that any area that is not landscaped shall be paved.
- D. Lighting. All lighting shall be oriented so that it does not shine or reflect into an abutting property or street.

**2.203.15**      **Manufactured Dwelling Park (MDP)**

- A. General Requirements.
1. Applicability of Design and Improvement Standards.
- The design and improvement standards are applicable to all Manufactured Dwelling Parks (MDP) adopted pursuant to the **WDO**.
- All standards, EXCEPT **Sections 2.203.15 B.2 and B.3**, are established by state statute (ORS 197.307 and ORS Chapter 446) and/or state administrative rule OAR 918-600). Deviation from these state standards is governed by these statutes and rules.
- All Manufactured Home and Dwelling Parks, and manufactured dwellings in those parks, established prior to the adoption of the **WDO** have nonconforming status under the **WDO**.
2. Approval Requirements.
- Approval of a MDP shall be subject to design review pursuant to **Sections 5.103.04 and 5.101.04**. Site built structures and manufactured dwelling units shall also be subject to applicable design review procedures of the **WDO**.
- B. Design and Improvement Standards
1. Park Area. The minimum site area for a manufactured dwelling park shall be 1.0 acres.

2. Density. The maximum density of a manufactured dwelling park shall be 12.0 manufactured dwellings per net acre of site area. [Net acre includes the total manufactured dwelling park site area EXCLUDING public street right of way, the improved surface of private streets and walkways.]
3. Park Perimeter Setback and Buffer. The required setback at the perimeter property line of each manufacture dwelling park shall be 20 feet, with a brick or architectural block wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height.
4. Minimum Area of a Park Space. The minimum area for each manufactured dwelling space shall be 3600 sq. ft.
5. Dimensions of a Park Space.
  - a. Minimum Width: 30 feet.
  - b. Minimum Length: 40 feet.
6. Access. Each manufactured dwelling space shall have direct unobstructed access to street.
7. Clear Vision Area, as described in **Section 3.103.10**, subject to the following modifications regarding private park streets:
  - a. Intersection of two streets. 30 foot legs measured along outside edge of the right of way for a public street and along the outside edge of the pavement on private park streets.
  - b. Intersection of a driveway and a private park street. 10 foot legs measured along outside edge of pavement on a private park street and a driveway.
8. Fire Separation Clearances. **TABLE 2.2.1.**
9. Vehicular Parking.
  - a. Number of Vehicular Parking Spaces. A minimum of 2 vehicular parking spaces per manufactured dwelling.
  - b. Vehicular Parking Configuration.
    - 1) End to end within a manufactured dwelling space.
    - 2) Side by side within a manufactured dwelling space.

- 3) One on-street space and one within a manufactured dwelling space.

c. Vehicular Parking Space Dimensions and Improvement.

- 1) On-street: 8 feet x 23 feet. [Section 2.203.15.B.9.c.1 as amended by Ordinance No. 2383, §30, passed March 16, 2005.]

**TABLE 2.2.1**  
**In-Park Separations Matrix\***

Clearance From	Manufactured Dwellings & Cabanas	Accessory Buildings	Decks, Landings, Steps, Ramps, Awnings & Carports	Garages
Property line & park street	5 feet	5 feet	5 feet	5 feet
Park sidewalk	2 feet	2 feet	0 feet	2 feet
Mfrd. dwelling or cabana on same lot	0 feet (When Permitted)	3 feet	0 feet	6 feet
Mfrd. dwelling or cabana on adjacent lot	10 feet	6 feet	6 feet	6 feet
Park buildings	10 feet	6 feet	6 feet	10 feet
Accessory bldg. on same lot	3 feet	3 feet	0 feet	3 feet
Accessory bldg. on adjacent lot	6 feet	6 feet	6 feet	6 feet
Decks, landings, steps, ramps, awnings & carports on same lot	0 feet	0 feet	0 feet	0 feet
Decks, landings, steps, ramps, awnings & carports on adjacent lot	6 feet	6 feet	6 feet	6 feet
Garage on same lot	6 feet	3 feet	0 feet	0 feet
Garage on adjacent lot	6 feet	6 feet	6 feet	6 feet
<p>NOTE:</p> <p>a) See Section 904(e) of the <b>2002 Oregon Manufactured Dwelling Standards</b> for exceptions to this schedule.</p> <p>b) Except for clearance between manufactured dwellings on adjacent lots and between manufactured dwellings and property lines, clearance shown in this schedule may be further reduced according to the <b>Oregon One and Two Family Dwelling Specialty Code</b> or the <b>Oregon Structural Code</b> with prior approval from the authority having jurisdiction.</p> <p>c) Set-backs to perimeter property lines may be greater than those shown in the above table. See municipalities planning and zoning ordinance (<b>WDO Section 2.203.15.B.3</b>).</p> <p>d) The set-backs and clearances required in this table shall be measured to the exterior walls of the structures and do not include eave overhangs except for awnings and carports.</p> <p><b>*SOURCE: Table 903, 1996 Oregon Manufactured Dwelling Standards</b></p>				

[Table 2.2.1 as amended by Ordinance No. 2383, §32, passed on March 16, 2005.]

- 2) Within a manufactured dwelling space. 10 feet x 20 feet, measured from the edge of the street pavement or sidewalk, whichever is closer.
- 3) All vehicular parking spaces shall be paved.

- d. Driveways.
  - 1) Width: 10 feet, minimum.
  - 2) Improvement: Paved
- e. Boat and Recreational Vehicle Storage. Storage of boats and recreational vehicles is prohibited except in a common storage area designed as part of the manufactured dwelling park.

10. Exterior Lighting.

- a. All park streets and common park walks shall be illuminated with a minimum of 0.37 candle power of light. [Section 2.203.15.B.10.a as amended by Ordinance No. 2383, §31, passed March 16, 2005.]
- b. All public streets shall be illuminated to Public Works standards.

11. Play Area.

- a. Area Ratio. 100 sq. ft. per each manufactured dwelling occupied by children under 14 years of age.
- b. Minimum Area. 2,500 sq. ft.
- c. Safety Standards. A play area shall be suitably separated or safeguarded from railroads, public streets, sharp declivity or other similar hazards.
- d. EXCEPTION. A play area shall not be required for manufactured dwelling parks established prior to March 13, 1989, and rented spaces as an all adult park.

12. Water, Sanitary Sewer and Storm Drainage. Infrastructure facilities shall be installed to applicable state and City facility standards.

13. Park Streets.

- a. Ownership. Private.
- b. Connectivity. The park street system shall connect to a public street.



- c. Paved Width.
  - 1) Without on-street parking. 20 feet.
  - 2) With on-street parking. 30 feet.
- d. Pavement Design. Pavement shall be to applicable state and City standards.
- e. Sidewalks, Curbs and Drainage. Park streets shall be designed to the ***Local Street Standards of Section 3.301.***
- f. The block length and the length of cul de sac streets shall comply with the standards of ***Section 3.301.***

14. Public Streets.

Provision of Public Streets. All streets depicted in the major street classification plan of the Woodburn Transportation System Plan that abut or are shown to be located within manufactured dwelling park shall be dedicated and improved as a condition of approval.

15. Manufactured Home Design Standards. In manufactured dwelling parks one to three acres in size:

- a. Roof Pitch: Each manufactured home shall have a pitched roof with a slope no less than a nominal three feet in height for each 12 feet in width.
- b. Exterior Siding and Roofing Materials: Each manufactured home shall have exterior siding and roofing which in color, material and appearance, is similar to the exterior siding and roofing material commonly used on residential dwellings within the community or which is comparable to the Apredominant materials used in surrounding dwellings.@ For the purposes of this Section, the definition of Areview area@ for determining the character of Asurrounding dwellings@ and Apredominant material@ defined in ***Sections 2.203.16.H. and I.*** shall apply. [Section 2.203.15.B.15.b as amended by Ordinance No. 2383, §33, passed March 16, 2005.]

16. Accessory Structures and Uses.

- a. Height. The maximum height of an accessory structure, including park buildings, shall be 15 feet.
- b. Solid Waste Collection. Solid waste shall either be collected with

curbside pickup or provisions for common refuse collection facilities shall be screened on all sides by an architectural block wall and solid gate, both with an anti-graffiti surface, a minimum of six feet and a maximum of seven feet in height.

17. Street Naming and Addresses. Each park street shall be named in the same manner as public streets. Each manufactured dwelling space shall be addressed off a park street.

#### **2.203.16**      **Manufactured Home on a Lot**

Where permitted as a special use, a manufactured home located on individual lots outside of a mobile dwelling park shall comply with the following requirements.

These standards are established by statute (ORS 197.307) and therefore non-variable.

A.      **Manufactured Home Certification.**

The manufactured home shall have been manufactured after June 15, 1976, and exhibit the Oregon Department of Commerce “Insignia of Compliance” that indicates conformance with Housing and Urban Development (HUD) standards.

B.      **Minimum Area.**

The manufactured home shall be multi-sectional and enclose a space of not less than 1,000 square feet.

C.      **Foundation.**

The manufactured home shall be placed on an excavated and back-filled foundation and enclosed at the perimeter such that the manufactured home is located not more than 12 inches above grade.

D.      **Roof.**

The manufactured home shall have a pitched roof, except that no standard shall require a slope of greater than a nominal three feet in height for each 12 feet in width.

E.      **Exterior Siding and Roofing.**

The manufactured home shall have exterior siding and roofing which in color, material and appearance is similar to the exterior siding and roofing material commonly used on residential dwellings within the community or which is

comparable to the predominant material used on surrounding dwellings as determined by the City.

F. Energy Efficiency.

The manufactured home shall be certified by the manufacturer to have an exterior thermal envelope meeting performance standards equivalent to the performance standards required of single-family dwellings constructed under the state Building Code as defined in ORS Chapter 455. [Section 2.203.16.F as amended by Ordinance No. 2446, §27, passed on September 10, 2008.]

G. Garage or Carport.

The manufactured home shall have a garage or carport of like materials. An attached or detached garage in lieu of a carport shall be required where such is consistent with the predominant construction of immediately surrounding dwellings. [Section 2.203.16.G as amended by Ordinance No. 2446, §27, passed on September 10, 2008.]

H. Surrounding Dwellings and Immediately Surrounding Dwellings Review Area.

As used in **Section 2.203.16**, “review area” for the character of “surrounding dwellings” and “immediately surrounding dwellings” shall encompass the five nearest dwellings to the subject lot that are on the same street and that are within 250 feet of the subject lot. If there are fewer than five dwellings within 250 feet, only those dwellings within 250 feet shall be used.

I. Predominant Material and Predominant Construction.

As used in **Section 2.203.16**, “predominant material” and “predominant construction” shall be the material used on the majority of the dwellings in the review area. If there is no majority of dwellings using the same material, then the material used on the largest plurality of dwellings in the review area shall be the predominant material. [Section 2.203.16.I as amended by Ordinance No. 2446, §27, passed on September 10, 2008.]

J. Building Permit.

A building permit shall be obtained for each dwelling unit.

**2.203.17 Mobile Food Services**

Where permitted as a special use, mobile food services shall comply with the following use and development standards:

A. Uses Permitted.

The use shall be limited to the preparation and/or sale of food and beverages from a vehicle, trailer, or temporary structure. Temporary structures shall be as defined and regulated by the state building code.

B. Location of Business Operations.

Business operations:

1. Shall not be conducted within public rights of way.
2. Shall be conducted on property with the written consent of the property owner.

C. Hours of Operation.

Business operations shall be conducted between the hours of 7:00 am and 10:00 p.m.

D. Business License.

The use shall operate with a valid business license for each site of operation within the City.

E. Access.

The use shall not block driveways, entrances or parking aisles.

F. Parking.

The use shall provide a minimum of 4 designated off street parking spaces that comply with the standards of **Section 3.105**.

G. Setbacks.

The use shall conform with all setback standards for the zone where it is located, including the clear vision area.

H. Signs.

Signs shall comply with the provisions of **Section 3.110**. [Section 2.203.17H as amended by Ordinance No. 2359, §13, passed March 22, 2004.]

I. Health and Sanitation.

The operator of the use shall possess valid County certification of compliance with health and sanitation standards.

[Section 2.203.17.J as amended by Ordinance 2423, §34, effective on July 28, 2007.]

J. Base of Operations.

The base of operations for mobile food service units shall be from industrial zones. Use of sites in residential zones for the preparation, maintenance, or storage area for mobile food service units is prohibited.

**2.203.18 Residential Sales Office**

Where permitted as a special use, a residential sales office shall comply with the following use and development standards.

A. Location.

The office shall be located on a lot within a subdivision or planned development or on a space within a manufactured dwelling park.

B. Use Limitations.

The principal use of the office shall be the sale of lots or renting of spaces or the sale of dwellings or manufactured homes on lots or spaces within the development

C. Landscaping.

The office shall have a finished exterior and the site must be landscaped.

D. Signs.

Signs shall comply with the provisions of **Section 3.110**. [Section 2.203.18D as amended by Ordinance No. 2359, §14, passed March 22, 2004.]

E. Hours of Operation.

Business shall be conducted between 8:00 a.m. to 8:00 p.m.

**2.203.19 Temporary Outdoor Marketing and Special Events**

Where permitted as a special use, temporary outdoor marketing and special events on private property shall comply with the following use and development standards.

[Section 2.203.19 as amended by Ordinance 2423, §12, effective on July 28, 2007.]

A. Uses Permitted are:

1. **Seasonal sales** of fireworks, Christmas trees, produce or plant materials:
2. **Amusement rides and games:**
3. **Entertainment;** and
4. **Any other merchandise or service.**

B. Duration.

1. Permitted uses, EXCEPT the seasonal sales, shall be limited to events with a maximum duration of three consecutive days with all goods and temporary facilities and signs removed within 24 hours of closing on the last day of each event.
2. Seasonal sales shall be limited to two events, with each event not exceeding more than 30 consecutive days.

C. Hours of Operation.

Each event shall be conducted between the hours of 10:00 a.m. and midnight.

D. On-site Circulation.

The use shall not block driveways, entrances or parking aisles.

E. Parking.

The required parking for all other uses of the property shall not be diminished below that required by **Section 3.105**.

F. Signs.

Signs shall comply with the provisions of **Section 3.110**, including provisions for temporary signs contained in **Section 3.110.13**.

G. Setbacks.

The use shall conform to all setback standards for the zone.

H. Responsibilities.

1. The property owner:
  - a. Shall possess a valid special event permit, **Section 5.101.08**, for each separate event.
  - b. Shall be responsible for compliance with use standards, crowd and traffic control, and for sanitation, including rest rooms, waste disposal, and clean up.
2. The operator of a special use shall possess valid certification of compliance for all applicable health, sanitation and safety standards of the City and other applicable jurisdictions.

I. Location and Size.

The temporary outdoor marketing and special event shall not be located within a public right-of-way unless authorized by the appropriate jurisdiction (Woodburn Public Works Department or the Oregon Department of Transportation). The temporary outdoor marketing and special event shall be limited to an outdoor area that is no more than ten percent (10%) of the square foot of gross floor area of the building(s) on the property, but in no case shall be limited to less than 200 square feet.

J. Exclusions: Outdoor product display areas shall comply with the standards of Section 2.203.19.C-H above. Outdoor product display areas are not required to obtain a Temporary Outdoor Marketing and Special Events permit, but are limited to the following:

1. Products sold within the primary building.
2. Cover no more than 10% of the gross square footage of the buildings on the property.
3. Be located under an eave of the primary structure.
4. Retain a minimum of three (3) feet for pedestrian clearance along any adjacent walkway.

**2.203.20 Temporary Residential Sales**

Where permitted as a special use temporary retail sales within residential zones shall meet the following use and development standards:

A. Uses Permitted.

- A. **Produce and plant materials** grown on the subject property
  - B. **Estate, garage and yard sales**
  - C. **Crafts and other hobby items**
- B. Number of Sales per Year.
- 1. Estate, garage, yard, craft and hobby sales. The number of sales, in any combination, conducted at the same site shall not exceed two in any calendar year. The duration of each sale period shall not exceed three (3) consecutive days.
  - 2. Sale of produce and plant materials grown on site shall be limited to one event no longer than 30 days in duration.
- C. Time and Duration. Sales shall be conducted between the hours of 8:00 a.m. and 8:00 p.m.
- D. Signs. All signs shall be taken down the day the sale ends.



## **2.204 Specific Conditional Uses**

### **2.204.01 General Provisions**

- A. Specific conditional uses require conditional use approval that is subject to:
  - 1. The development standards described for each specific conditional use listed in this section.
  - 2. The supplementary conditional use approval criteria specified in this section.
  - 3. The additional conditions of development found to be appropriate to mitigate impacts of a particular specific conditional use application.
  - 4. The development standards of the underlying zone, unless the specific conditions of approval set a higher standard.
- B. The specific development standards for each type of conditional use listed in this section are mandatory. Any deviation from these standards shall comply with criteria for a variance.
- C. The provisions of this section shall not apply to those uses set forth in this section that are also listed as a permitted use in a particular zone.

### **2.204.02 Historically and Architecturally Significant Buildings**

Certain uses are permitted as specific conditional uses in the RS and RM zones in order to preserve historic and architectural resources by allowing an increase in the intensity of use. The conditional use process is intended to strike a balance between providing the economic incentive to restore and maintain the resource and mitigating any negative impacts of the proposed use on surrounding uses.

- A. Criteria for Building Designation.

To qualify for designation as a historically or architecturally significant building for the purposes of **Section 2.204.02**, the building shall meet one or more of the following criteria:

- 1. Be designated on the “National Register of Historic Places” published by the U.S. Department of Interior, or any other inventory of historic structures acknowledged by the State Historic Preservation Office.
- 2. Be designated an architecturally significant building or awarded recognition for meritorious design by a recognized professional design

organization.

3. Be designated in the cultural resource inventory of the Comprehensive Plan as a historically or architecturally significant building.

B. Supplemental Conditional Use Approval Criteria.

1. The building shall have been previously designated historically or architecturally significant pursuant to ***Section 2.204.02.A***.
2. The more intensive use of the building is necessary to maintain and preserve its continued existence.
3. In addition to the uses permitted in the underlying zoning district, adaptive reuse of the property may be allowed to a more intensive without a concurrent Comprehensive Plan Map amendment. Such adaptive reuse of the property shall be limited to the uses specified in ***Section 2.204.02.C***.
4. The scope and intensity of negative impacts associated with the proposed use can be suitably conditioned to mitigate adverse affects on adjoining uses.

C. Uses Permitted.

1. **Additional dwelling units.** A maximum of 3 dwelling units in an RS zone.
2. **Retail trade**, with a maximum of 3 on-site employees.
  - a. **Art gallery** (45392)
  - b. **Clothing and accessory stores** (448)
  - c. **Picture frame shop** (442299)
3. **Professional services**, with a maximum of 3 on-site employees.
  - a. **Legal services** (5411)
  - b. **Accounting** (5412)
  - c. **Architects and engineers** (5413)
  - d. **Specialized design services** (5414) INCLUDING interior design services

- e. **Computer system design** (5415)
  - f. **Management consulting** (5416)
  - g. **Advertising** (5417)
- 4. **Management and support services**, with a maximum of 3 on-site employees.
  - a. **Telephone answering service** (561421)
- 5. **Health care and social assistance**, with a maximum of 3 on-site employees.
  - a. **Physician, dentist, and other health practitioner offices** (6211, 6212, 6213)
  - b. **Child day care services** (6244)
  - c. **Other individual and family services** (6241)
- 6. **Accommodations**, limited to 2 guest rooms.
  - a. **Bed-and-breakfast inn** (721191)
- D. Development Standards.
  - 1. All proposed exterior: a) alterations of the building, b) additions to the building and c) addition of structures on the same site shall maintain the visible architectural and/or historical features and design character that identify the building as a designated resource.
  - 2. Parking and storage within a yard abutting a street shall be prohibited, except for parking within an access to a garage.

### **2.204.03 Telecommunications Facilities**

All telecommunication facilities as defined in *Section 1.102* shall be regulated by the provisions of *Section 2.204.03*. In the event of any conflict between this and other sections of the *WDO*, the most restrictive provisions shall control.

- A. Standards of Approval.
  - 1. All new telecommunications facilities shall be located on a property of sufficient size to comply with the following:

- a. A setback from all property lines to the tower, which is at least two-thirds the tower height. This standard shall not apply to collocated telecommunications facilities.
- b. A tower pad large enough to allow for additional collocated and ancillary facilities. The tower or towers shall be located centrally on this pad. This standard shall not apply to antennae attached to existing structures or towers located on rooftops.
- c. Protection to adjoining property from the potential impact of tower failure and ice falling from the tower. A registered structural engineer's analysis shall be submitted that demonstrates that the site and facility adequately accommodate measures to mitigate these hazards.
- d. Separation from pre-existing towers. Tower separation shall be measured by following a straight line from the base of the proposed tower to the base of any pre-existing tower. Minimum separation distances shall be as indicated in **TABLE 2.2.2**.

<b>TABLE 2.2.2 Minimum Separation Among Telecommunication Facilities</b>				
	<b>Lattice Tower</b>	<b>Guyed Tower</b>	<b>Monopole 80 or more ft. in height</b>	<b>Monopole Less than 80 ft. in height</b>
<b>Lattice Tower</b>	500 ft.	500 ft.	150 ft.	75 ft.
<b>Guyed Tower</b>	500 ft.	500 ft.	150 ft.	75 ft.
<b>Monopole 80 or more feet in height</b>	150 ft.	150 ft.	150 ft.	75 ft.
<b>Monopole Less than 80 ft. in height</b>	75 ft.	75 ft.	75 ft.	75 ft.

2. Collocation.

- a. Before a proposal for a new transmission tower is considered, an applicant shall exhaust all collocation options including placement of antennae on existing tall structures and multiple antennae or attachments on a single tower. In cases where an existing tower is modified or rebuilt to a taller height to allow collocation, such change may only occur one time per communication tower site and may only occur when the modification or rebuild request has been

initiated by a separate exchange carrier.

- b. New telecommunication facilities shall be constructed so as to accommodate future collocation, based upon expected demand for transmission towers in the service area. Towers shall be designed so as to accommodate a minimum expansion of three two-way antennae for every 40 vertical feet of tower.
  - c. Replacement of existing pole type structures may be permitted for the purpose of collocation, provided that there is no change to the type of tower. Setback and other location criteria of the underlying zone shall still apply.
3. Multiple Attachments on Utility Poles. In conformance with the Telecommunications Act of 1996, Section 703, a utility shall provide any telecommunications carrier with nondiscriminatory access to any pole, duct, conduit, or right of way owned or controlled by it, unless there is insufficient capacity or access cannot be granted for reasons of safety, reliability, and generally applicable engineering purposes.
4. Height. New telecommunication facilities shall not, without exception, exceed the height limits established by the underlying zone. Exceptions to height limitations in the section require a variance.
5. Visual Impact. The applicant shall demonstrate that the tower shall have the smallest practicable visual impact on the environment, considering technical, engineering, economic and other pertinent factors.
- a. The height and mass of the transmission tower shall not exceed that which is essential for its intended use and public safety as demonstrated in a report prepared by a registered structural engineer.
  - b. Towers 100 feet or less in height shall be painted in order to best camouflage the tower with regard to compatibility with surrounding objects and colors. Unless towers are otherwise disguised or collocated, towers shall be camouflaged as trees whenever structurally possible.
  - c. Towers more than 100 feet in height shall be painted in accordance with the Oregon State Aeronautics Division and Federal Aviation Administration standards, unless an appropriate waiver is obtained. Where a waiver has been granted, towers shall be painted and/or camouflaged in accordance with ***Section 2.204.03.A.5.b.***
6. Accessory Uses. Accessory uses shall include only buildings and facilities

that are necessary for transmission functions and associated satellite ground stations, and shall not include broadcast studios (except emergency broadcast), offices, vehicular storage areas or other similar uses not necessary for the transmission or relay functions. No unenclosed storage of materials is allowed.

7. Lighting. No lighting shall be permitted on transmission towers except that required by the Oregon State Aeronautics Division or Federal Aviation Administration. This standard shall not prevent shared use or replacement of an existing light pole. For collocation on existing or replaced light poles the transmission tower shall have no net increase to the spread, intensity or direction of the existing light source.
8. Noise. Noise generated by equipment shall be sound buffered by means of baffling, barriers, or other suitable means to reduce the sound level measured at the property line to 30 dBA when adjacent to residential uses and 45 dBA in other areas.
9. Fences and Landscaping.
  - a. The tower(s) and ancillary facilities shall be enclosed by a six foot fence meeting the requirement of the **WDO**. Chain link fences, when allowed, shall be green vinyl coated. Where a six foot fence in sound condition already exists on a side or sides of the tower pad area, fencing requirements may be waived for that side.
  - b. Landscaping shall be placed outside of fences and shall consist of fast growing vegetation with a minimum planted height of six feet placed densely so as to form a solid hedge.
  - c. Landscaping and fencing shall be compatible with other nearby landscaping and fencing .
  - d. Where antennae or towers and ancillary facilities are to be located on existing buildings or structures and are secure from public access, landscaping and fencing may be waived.
10. Signs. One unilluminated sign, not to exceed 2 square feet in area, that states the contact name and phone number for emergency purposes shall be provided at the main entrance to the facility. Signs shall not be placed on towers and antennae.

B. Abandoned Facilities.

1. When the use of a transmission facility is discontinued for a period of six or more consecutive months is declared abandoned. Abandoned facilities

shall be removed by the property owner no later than 90 days from the date of abandonment.

2. Failure to remove an abandoned facility is declared a public nuisance and is subject to abatement pursuant to the Woodburn Nuisance Ordinance and all other applicable legal remedies.
3. Upon written application prior to the expiration of the six month period, the Director of Community Development shall grant a six month extension for reuse of the facility. Additional extensions beyond the first six month extension may be granted by the Community Development Director subject to any conditions required to bring the project into compliance with current law(s) and to make it compatible with surrounding development.

# 3.1 DEVELOPMENT GUIDELINES AND STANDARDS

## 3.101 Street Standards

### 3.101.01      Scope

The provision of streets shall be guided by the goals and policies of the Woodburn Comprehensive Plan, the Woodburn Transportation System Plan, detailed City adopted planning and design studies and the **WDO**. The right of way standards apply to public streets. The improvement and construction specification standards apply to both public and private facilities, including streets, sidewalks and bikeways under the jurisdiction of the City of Woodburn.

### 3.101.02      General Provisions

- A. The access or driveway, for each lot shall be connected to the existing public street system in compliance with **Section 3.104**.
- B. No access permit shall be issued unless the internal street(s), boundary street(s) and connecting street(s) are constructed pursuant to **Section 3.101.02.C**, UNLESS or until the applicant has obtained an exception as provided in this section. [Section 3.101.02.B as amended by Ordinance No. 2383, §35, passed March 16, 2005.]
- C. Design and Construction Standards.
  - 1. All public streets under the jurisdiction of the City of Woodburn shall comply with the applicable cross section design standards noted in **Section 3.101.03** and construction specifications of the Public Works Department.
  - 2. All private streets in manufactured dwelling parks shall comply with applicable City design standards and specifications and state design standards and specifications where state standards and specifications preempt City standards and specifications.
- D. Street Right of Way and Improvement Standards for Development.

Any development subject to an access permit, **Section 3.104**, shall be responsible for adequate street rights of way and improvements. The standards of **Section 3.101.02.D** may only be modified subject to the approval of an exception, **Section**



**5.103.12.** In no instance may standards be reduced below specified minimum, non-variable standards.

1. Connecting Street Standards. (*Figure 6.12*)

- a. Right of Way Standard. The full right of way for the subject street classification, **Section 3.101.03**, shall be required for a connecting street segment without an approved exception or variance.

The minimum connecting street right of way shall be sufficient to accommodate the connecting street improvement standard in **Section 3.102.D.1.b.** below.

[Section 3.101.02.D.1.b as amended by Ordinance No. 2423, §31, effective on July 28, 2007.]

- b. Street Improvement Standard. The full street improvement for the subject street classification, **Section 3.101.03**, shall be provided for a connecting street segment without an approved exception.

The minimum connecting street improvement standard shall be equivalent to:

- 1) One, 10 foot wide travel lane in each direction, in addition to the required curbs, where the classification specifies a maximum standard of two travel lanes; [Section 3.101.02.D.1.b.1 as amended by Ordinance No. 2383, §36, passed March 16, 2005.]
- 2) Required drainage facilities;
- 3) The pedestrian and bikeway facilities located on one side of the street that comply with the standards for the subject street classification. In locations where the street classification specifies a maximum standard of two travel lanes, the connecting segment on the side with the pedestrian/bikeway facilities shall be completed to standards, including the landscaped parkway strip.

2. Boundary Street Standard. (*Figure 6.12*)

- a. Right of Way Standard. The full right of way for the subject street classification, **Section 3.101.03**, shall be required for a boundary street without an approved exception.

The minimum standard for a boundary street right of way shall be no less than the width necessary to accommodate the boundary street improvement standard.

[Section 3.101.02.D.1.b as amended by Ordinance No. 2423, §32, effective on July 28, 2007.]

- b. Street Improvement Standard. The full street improvement for the subject street classification, **Section 3.101.03**, shall be provided for a boundary street without an approved exception.

The minimum boundary street improvement standard shall be equivalent to:

- 1) One, 10 foot wide travel lane in each direction, in addition to the required curbs in each direction where the classification specifies a maximum standard of two travel lanes; [Section 3.101.02.D.2.b.1 as amended by Ordinance No. 2383, §37, passed March 16, 2005.]
- 2) Required drainage facilities; and
- 3) In addition to the improvements cited in 1) above, the full improvement of the street from the center line to the boundary of the subject property plus any center turn lane as described for the street classification.

3. Internal Street Standards. (**Figure 6.12**)

- a. All public streets within a development shall comply with the full right of way and improvement standards of **Section 3.101.03** without an approved variance.
- b. All private park streets permitted in manufactured dwelling parks shall comply with the full requirements of **Section 2.203.15**, as set by statute.

E. Private Streets.

Private streets are prohibited in conjunction with a development approval, EXCEPT where required as private park streets in manufactured dwelling parks, pursuant to ORS Chapter 446 and OAR 918-600.

F. Termination of Streets, Bikeways and/or Pedestrian Ways.

1. Cul de sac Streets.

- a. The maximum length of a cul de sac street shall be 250 feet.
  - b. The minimum radius of a cul de sac street right of way shall be 55 feet.
  - c. The minimum improved street radius of a cul de sac shall be 45 feet plus curb, planting strip and property line sidewalk.
- 2. Temporary Dead End Streets. Streets extensions that result in temporary dead end street, or stub streets, due to incremental construction shall:
  - a. Be transmitted to the Woodburn Fire District for review and comment.
  - b. Have an all weather sign at the temporary street terminus, installed by the applicant, that states: "This Street is Planned for Future Extension."
  - c. Provide either a one foot reserve strip deeded to the City, or an alternative method for limiting access approved by the City Engineer, at the temporary end of the right of way.
- 3. Continuity of Public Bikeway and Pedestrian Facilities Located Off-Street. Public bikeway and pedestrian facilities, other than those incorporated in a street right of way, shall either :
  - a. Provide for a continuous system with each segment originating/terminating with a connection to a public street or to a designated activity center.
  - b. Provide stubbed facilities that may extend beyond the limits of an approved development, when such a public facility has been specifically endorsed by the City Council.

G. Block Standards.

Block length shall not be less than 200 feet and not more than 600 feet, EXCEPT where the dimensions and alignment of existing blocks and streets adjacent to or in the vicinity of a proposed subdivision, or consideration of access management policies on arterials warrant other dimensions. The maximum block length shall not exceed 1200 feet. [Section 3.101.02.G as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

H. Street Names.

All public streets, and private manufactured dwelling park streets shall be named after providing the Woodburn Fire District an opportunity to review and comment.

1. Principal Street Name.
  - a. The street name shall not duplicate an existing street name, unless there is reasonable assurance the named streets will be connected in the future.
  - b. New streets shall be designated with the same names as existing streets only if they fall in the same grid line and there are reasonable assurances that the street will connect with another section of the numbered street.
  - c. Street names shall not sound like another street name or cause confusion.
  - d. Street names that are deliberately misspelled, frivolous, or reflect the name of the developer or family members shall not be allowed.
2. Street Name Suffix. Streets shall be further named with a suffix. EXCEPT as indicated in the Woodburn Transportation System Plan, the following suffixes designations apply to NEW streets, as follows:
  - a. North-south streets shall be designated “street”, EXCEPT that major streets classified as an arterial in the Woodburn Transportation System Plan may be designated “road” or “highway.”
  - b. East-west streets shall be designated “avenue”, EXCEPT that major streets classified as an arterial in the Woodburn Transportation System Plan may be designated “road” or “highway.”
  - c. A skewed or meandering street shall be named “drive.”
  - d. A street less than 1,000 feet in length may be designated “place,” “way,” or “lane.”
  - e. A cul de sac street with no cross street shall be designated “court.”
  - f. A continuous loop street that has two intersections with the same street shall be segmented, in reference to its orientation to the overall North/South, East/West street grid, so that the each segment of the loop has a unique name.

- g. A street that runs in a circle with only one entrance/exit shall be designated a “circle.”
- h. A street with a continuous landscaped median shall be designated a “boulevard.”
- 3. Lot and Space Numbering. The Building Official shall establish and maintain a street numbering grid for the City and assign individual street numbers to lots and manufactured dwelling spaces at the time of the initial building permit.
- I. Right of Way Landscaping and Street Trees. See “Development Standards” for the subject zoning district, *Section 2.1*.
- J. Sidewalks. All sidewalks shall be a minimum of 5 feet wide, excluding the curb, and located one foot from the right of way line EXCEPT in the DDC Zone or as otherwise approved by variance.
- K. Street Access. No more than 25 dwelling units, including existing units, shall have their only means of public street access to a cul de sac, dead end street, or other street that does not provide two non-overlapping public street routes to a major arterial identified on the Woodburn Transportation System Plan. [Section 3.101.02 as amended by Ordinance No. 2383, §34, passed March 16, 2005.]

### **3.101.03 Right of Way and Improvement Standards**

[Section 3.101.03 as amended by Ordinance No. 2391, acknowledged on December 22, 2006.]

- A. The street right of way and improvement cross-sectional standards required for development are depicted in Figure 7-2 and Table 7-1 of the Woodburn Transportation System Plan. These standards are based on the functional classification of each street as shown in Figure 7-1 of the Woodburn Transportation System Plan. The street right-of-way and improvement standards minimize the amount of pavement and right-of-way required for each street classification consistent with the operational needs of each facility, including requirements for pedestrians, bicycles, and public facilities.
- B. The following additional standards for Local Residential Streets:
  - 1. Local Residential Street with Parking One Side:
    - a. Required common, onsite parking over and above the parking requirements under other provisions of the **WDO**: One (1) space per dwelling unit, located no further than 250 feet from the subject lot.
  - 2. Local Residential without Parking:

- a. Required common, onsite parking over and above the parking requirements under other provisions of the **WDO**: Two (2) spaces per dwelling unit lot, located no further than 250 feet from the subject lot.

## **3.102 Utilities and Easements**

### **3.102.01 Water, Sanitary Sewer and Storm Drainage Facilities**

Municipal water, sanitary sewer and storm drainage facilities shall be installed to applicable Public Works Department and state standards.

### **3.102.02 Underground Utilities**

All permanent utility service to development shall be underground EXCEPT where overhead high-voltage electric facilities exist and for partitioned lots that are currently served by overhead wires or cables. [Section 3.102.02 as amended by Ordinance No. 2383, §38, passed March 16, 2005.]

### **3.102.03 Outdoor Lighting**

#### **A. Public Streets.**

Public streets abutting development shall be illuminated with street lights installed to the standards of the Public Works Department and the electric utility.

#### **B. Manufactured Dwelling Park Private Streets.**

The full length of private streets and walkways in manufactured dwelling parks shall be illuminated with lighting designed to average of 0.25 horizontal candle-power of light.

### **3.102.04 Easements**

#### **A. Municipal Infrastructure Easements.**

The Public Works Department shall require dedication of specific easements for the construction and maintenance of municipal water, sewerage and storm drainage facilities located on private property shall be required in accordance with the Public Works Department standards.

#### **B. Public Utility Easements (PUE).**

Five foot wide public utility easements (i.e., easements for natural gas lines and for electric and telecommunications wire or cable service) shall be dedicated along each lot line abutting a public street. At the time of tentative approval, utilities may request dedication of a public utility easement within a reciprocal access easement or centered along specified rear lot line in those zones where zero setback is not permitted.

C. Creeks and Watercourse Maintenance Easements.

1. Public improvement and maintenance easements shall be dedicated along all creeks and other water courses. On streams and waterways where development is regulated based on Federal Emergency Management Administration flood hazard delineation, the minimum width shall be adequate to accommodate the 100 year floodway.
2. On other open channel water courses, such easements shall, at a minimum, extend from the top of bank to top of bank and include an additional 20 feet width outward from the top of bank along one side of the entire length of the open channel.
3. On all piped (closed conduit) systems the easement shall be a minimum sixteen (16) feet in width. Wider easements may be required by the City Engineer when needed to accommodate installation of or access to larger and/or deeper pipes.

## **3.103 Setback, Open Space and Lot Standards, Generally**

### **3.103.01 Setbacks and Open Space, Generally**

Setbacks and required open space define the areas within a lot or a planned unit development that are to be retained and maintained unobstructed by buildings and structures, EXCEPT for projections, accessory uses and structures and for common facilities required as a condition of a land use decision.

### **3.103.02 Lot Coverage, Generally**

Specific standards for lot size or area, for lot dimensions, and for lot coverage are set forth in the applicable zone. Where a standard for lot coverage is expressed as a percentage, such standard means the percentage of total lot area covered by primary and/or accessory buildings INCLUDING roofed but unenclosed structures but EXCLUDING covered structures less than five feet in height and having less than 20 square feet of gross floor area (such as pet shelters and play houses).

### **3.103.03 Setbacks, Setback Area and Required Open Space, Generally**

#### **A. Setbacks Apply to One Building.**

1. No required setback provided for any building or structure for the purpose of complying with provisions of the **WDO** shall be considered as providing a setback for any other building.
2. No required setback on an adjoining lot shall be considered as providing open space on the lot whereon the building is erected EXCEPT for a common area not required to be located within a lot when owned by a homeowners association in a planned unit development.

#### **B. Setbacks to be Unobstructed.**

A setback is the minimum required yard between a structure and a lot line, whether or not additional open space is actually provided between the structure and the lot line. Every setback area shall be open and unobstructed by buildings or structures from the ground to the sky EXCEPT as may otherwise be permitted in this *Section* and *Sections 2.201 and 2.202*, Accessory Uses and Structures.

#### **C. Setbacks Not to be Reduced.**

No lot shall be so reduced or diminished that the setback or required open space shall be smaller than prescribed in the **WDO**.

### **3.103.04 Separation of Lot or Setback Areas**



A. Reduction of Required Lot Area.

No portion of a lot necessary to meet the standards specified by the use zone in which it is located or required by the **WDO** shall be separated in ownership.

B. Separation of Setback Areas.

No setback area or required open space around an existing building shall be separated from the lot upon which the building is located.

**3.103.05 Special Street Setbacks**

[Section 3.103.05 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

A. Purpose.

The special setbacks in this **Section** are based upon the functional classification of streets and roads described in the Woodburn Transportation System Plan (WTSP). The purpose of these special setbacks is to provide for adequate air movement, solar access, visibility, aesthetics and compliance with the development standards of the **WDO** when a major street is improved.

B. Setback Requirements.

Required setbacks adjacent to a street shall be in addition to the special setbacks required in this Section. The special setback distances shall be measured at right angles to the center line of the original street right of way.

C. Special Provisions.

Buildings, structures and paved surfaces shall not be located within the special setbacks EXCEPT as specifically provided for in the **WDO**. Any portion of a building or structure lawfully established within a special street setback prior to date of the **WDO** shall be considered a nonconforming structure.

D. Special Setback Standards.

Special setback standards by street classification are established in **Table 3.1.1**. The special setback standards shall be applied to streets within the City of Woodburn as functionally classified in the Woodburn Transportation System Plan.

<b>TABLE 3.1.1 Special Setback Standards by Street Classification</b>	
<b>WTSP Functional Classification</b>	<b>Special Setback from Center Line</b>
Major Arterial	50 feet
Minor Arterial	37 feet
Service Collector	36 feet
Access Street/Commercial Street	33 feet

**3.103.06 No Parking or Storage in Setbacks Adjacent to a Street**

Parking and storage shall be prohibited within a required setback adjacent to a street, EXCEPT for parking in driveways.

**3.103.07 Projections into the Setback Adjacent to a Street**

- A. Chimneys and flues; solar collectors; steps; eaves; gutters; and belt courses, leaders, sills, pilasters, lintels, cornices, planter boxes and other ornamental features projecting not more than 24 inches from the primary building shall be EXEMPT from the setback requirement from a lot line adjacent to a street.
- B. Uncovered porches and covered unenclosed porches:
  - 1. Not more than 16 feet high;
  - 2. Extending not more than 10 feet beyond the front walls of the building; and
  - 3. With a floor elevation which does extend more than four feet above grade, shall be EXEMPT from the setback requirement from a lot line adjacent to a street, EXCEPT that no such projection shall be closer than 10 feet to the lot line.
- C. Arbor, Archway, Pergola and Trellis shall be EXEMPT from the setback requirement from a lot line adjacent to a street. [Section 3.103.07 as amended by Ordinance No. 2383, §39, passed March 16, 2005.]

**3.103.08 Projections in the Interior Side Yard Setback**

- A. Cornices, eaves, gutters and fire escapes when not prohibited by any other code or ordinance, may project into a required interior side yard setback not more than one-third of the width of the setback, but not more than three feet in any case.

- B. Chimneys and flues; solar collectors; belt courses, leaders, sills, pilasters, lintels, and ornamental features may project not more than 18 inches into a required interior side yard setback, provided, however, chimneys and flues shall not exceed six feet in width.

**3.103.09**      **Projections in the Interior Rear Yard Setback**

- A. Chimneys and flues; solar collectors; gutters; and belt courses, leaders, sills, pilasters, lintels, and other ornamental features may project not more than 18 inches into a required interior rear yard setback, provided, however, chimneys and flues shall not exceed six feet in width.
- B. A fire escape, balcony, outside stairway, cornice or other unenclosed, unroofed projection may project not more than five feet into a required interior rear yard setback. In no case shall such projection come closer than six feet from any lot line.
- C. Planter boxes; steps; uncovered porches; covered but unenclosed porches and patios, not more than 16 feet high, a floor elevation less than four feet above grade and at least 14 feet from the rear lot line, shall be EXEMPT from the minimum rear yard setback.
- D. No permitted projection into a required interior rear yard setback shall extend within ten feet of the center line of an alley, or of a rear lot line if no alley exists, or within six feet of an accessory structure.

**3.103.10**      **Vision Clearance Area** (See **Figure 6.4**)

- A. Purpose.

A vision clearance area is an area at the intersection of two streets, a street and a driveway or a street and an alley in which visual obstructions are limited for safety purposes. [Section 3.103.10.A as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]

- B. Extent.

- 1. At the intersection of two streets, the vision clearance area is formed by a combination of the following lines: a line extending 30 feet from the two lot lines adjacent to a street, and a third line drawn across the corner of the lot that connects the ends of the lines, creating a triangular vision clearance area. [Section 3.103.10.B.1 as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]

2. At the intersection of a street and an alley, the vision clearance area is formed by a combination of the following lines: a line extending ten feet from the intersection along the back of curb, a line extending ten feet from the property line along the alley and a line drawn across the corner of the lot that connects the ends of the lines, creating a triangular vision clearance area. [Section 3.103.10.B.2 as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]
3. At the intersection of a street and a driveway, the vision clearance area is formed by a combination of the following lines: a line extending ten feet from the intersection along the back of curb, a line extending ten feet along the side of the driveway, a third line drawn across the corner of the lot that connects the ends of the lines, creating a triangular vision clearance area. [Section 3.103.10.B.3 as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]
4. Within the DDC zone, the vision clearance area is formed by a combination of the following lines: a line extending 20 feet from the two curb lines, and a third line drawn across the corner of the lot that connects the ends of the lines, creating a triangular vision clearance area. [Section 3.103.10.B.4 as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]
5. If a street is subject to a Special Setback under Section 3.103.05, the Special Setback shall be used to define the vision clearance area. [Section 3.103.10.B.5 as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]

C. Prohibited Development.

A vision clearance area shall contain no plants, fence, wall, structure, sign, parking space, loading space or temporary or permanent obstruction exceeding 30 inches in height [measured from the top of the curb or, where no curb exists, from the established street centerline grade], EXCEPT as follows [Section 3.103.10.C as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]:

1. Trees, provided branches and foliage are removed to a height of 7 feet above grade;
2. Telephone, power and cable television poles;
3. Telephone and utility boxes less than ten inches at the widest dimension; and
4. Traffic control signs and devices.

D. Authority to Modify

The Community Development Director, with the written concurrence of the Public Works Director, shall have the authority to modify the standards for a

vision clearance area upon finding that the waiver is appropriate due to one-way traffic patterns. [Section 3.103.10.D as amended by Ordinance No. 2446, §28, passed on September 10, 2008.]

## 3.104 Access

### 3.104.01      Applicability

#### A.      Street Access Required.

1.      Every lot shall have direct access to an abutting public street or to a public street by an irrevocable access easement.
2.      Every joint driveway or cross connection between separate lots shall be established by an irrevocable access easement.

#### B.      Access to City Streets, Permit Required.

1.      A City permit shall be required for any new or modified vehicular access to a street that is under City jurisdiction. The following types of access shall be subject to such a permit:
  - a.      Site access to and/or from a City street;
  - b.      An extension of an existing City street; or
  - c.      A new public or private street connecting to a City street.
2.      A Traffic Impact Analysis (TIA) may be required by the Public Works Director prior to the approval of a City access or street construction permit when the Director estimates a development proposal may generate either 100 or more additional, peak hour trips, or 1,000 or more additional daily trips, within ten years of a development application. A TIA shall evaluate the traffic impacts projected of a development proposal and the estimated effectiveness of potential traffic impact mitigation measures. The methodology for a TIA shall be consistent with Public Works Department guidelines.
3.      Administration of City access permit standards and guidelines.
  - a.      Type I Applications. Development subject to one of the following Type I applications:
    - 1)      Design Standards for Single Family and Duplex Residential Dwellings , **Section 5.101.01**; or [Section 3.104.01.B.3(1) as amended by Ordinance No. 2383, '40, passed March 16, 2005.]
    - 2)      Access to a City Street, EXCLUDING Major and Minor Arterial Streets, **Section 5.101.12** [Section 3.104.01.B.3 as

amended by Ordinance No. 2383, '40.a..2, passed March 16, 2005.]

shall be subject to the access standards of this **Section** and street improvement standards in **Section 3.101** EXCEPT when the subject property is bound by the requirements of a precedent land use decision that has not been modified by a subsequent land use decision.

- b. Type II and III Applications. Development subject to one of the following Type II and III applications:
  - 1) Type II Design Review, **Section 5.102.02**;
  - 2) Type III Design Review, **Section 5.103.02**;
  - 3) Access to a City Major or Minor Arterial Street, **Section 5.102.04**;
  - 4) Preliminary Partition Approval, **Section 5.102.01**;
  - 5) Preliminary PUD Plan Approval, **Section 5.103.07**; or
  - 6) Preliminary Subdivision Approval, **Section 5.103.09** shall be subject to the access standards and guidelines specified in this **Section** and street improvement standards in **Section 3.101** EXCEPT when the subject property is bound by the requirements of a precedent land use decision that has not been modified by a subsequent land use decision. [Section 3.104.01.B.3 as amended by Ordinance No. 2383, '40.b.6, passed March 16, 2005.]
- 4. A City access permit shall be subject to the requirements of the **WDO** and Public Works Department standards.

C. Access to State Streets, Highways, and Interchanges.

Access to a transportation facility under the jurisdiction of the Oregon Department of Transportation (ODOT) shall be subject to the requirements of OAR 734-051.

**3.104.02 Driveway and Drive-Through Measurements and Dimensions**

A. Driveways Crossing a Setback.

The portion of a driveway crossing a setback shall be perpendicular to the setback lines.

**B. Driveway Spacing.**

1. Spacing between driveways shall be determined by measurement from the closest edge of the pavement, or curb cut, of the subject driveway to the closest edge of pavement, or curb cut, of an adjoining driveway.
2. Corner clearance between a driveway and a street intersection shall be determined by measurement from the closest edge of the pavement, or curb cut, of the subject driveway to either:
  - a. The closest edge of the special setback of an intersecting street with a special setback, or
  - b. The closest edge of the right of way line of an intersecting street without a special setback.

**C. Driveway Width.**

Driveway width shall be determined by measurement at the property line.

**D. Drive-Through Dimensions and Configuration.**

1. Minimum Lane Width. 12 feet.
2. Minimum Lane Length. 50 feet, unobstructed by lateral vehicular access. Precluded lateral vehicular access shall include the access/maneuvering area for off street parking and overlap onto public street right of way. The unobstructed length shall be measured from the drive up window or stop line, whichever is greater.
3. Turn Radius. 25 feet.
4. By-Pass Lane. A development providing a drive-through for passenger loading and/or unloading or for drive-up services shall include a by-pass lane to a site exit with a minimum width of 8 feet. [Section 3.104.02.D.4 as amended by Ordinance No. 2383, §41, passed March 16, 2005.]

**3.104.03 Driveway Access Guidelines, Type II and III Applications**

**A. Guidelines for the Number and Location of Driveways, Type II and Type III Applications.**

1. The number of driveway accesses should be minimized based on overall site design, including consideration of:



- a. The function classification of abutting streets;
  - b. The on-site access pattern, including cross connected parking and circulation, joint access, turnarounds and building orientation;
  - c. The access needs of the use in terms of volume, intensity and duration characteristics of trip generation.
2. Joint/Shared Access.
- a. Partition lots. All lots created by a partition that access a Major or Minor Arterial street should be accessed via a single, shared driveway with an on-site turnaround, UNLESS otherwise required by **Section 3.104.05**.
  - b. The lot and street layout in a subdivision or PUD should be configured so that lots abutting a major street have access to a local street. Where the layout necessitates access to a major street, access for abutting lots should be shared and provided with an on-site turnaround, UNLESS otherwise required by **Section 3.104.05**.
  - c. Medium density residential, commercial, industrial uses and other development subject to Type II or III Design Review located on the same lot, or on abutting lots, that abut a Major Arterial, Minor Arterial, or Service Collector should be designed to share access to those major streets. A minimum of two vehicular accesses shall be provided in developments with eleven (11) or more medium density residential dwelling or living units.
  - d. Shared/Joint Access Agreements. Shared and/or joint access agreements serving properties under separate ownership shall be subject to legal documentation, to the satisfaction of the City Attorney, establishing permanent use of the access. The agreement shall be recorded with the County Recorder and filed with the Community Development Director.
3. Cross Connections.
- a. All uses sited on one lot should have common, and/or interconnected, off street parking and circulation facilities.
  - b. Similar, and/or compatible, uses on abutting lots should have interconnected on-site access and parking facilities. Such shared facilities serving properties under separate ownership shall be subject to legal documentation, to the satisfaction of the City

Attorney, establishing permanent use of the access and parking facilities. The agreement shall be recorded with the County Recorder and filed with the Community Development Director.

4. Access to lots with multiple street frontages should be from the abutting street(s) with the lowest functional classification.
5. Dysfunctional or unused driveways should be closed.

B. Driveway Spacing Guidelines, Type II and III Applications.

The minimum separation of a driveway from: a) the special setback of a parallel major street, b) the right of way of a parallel local street, or c) from another driveway should be as follows.

1. Major Arterial Street: 300 feet;
2. Minor Arterial Street: 245 feet; and
3. Service Collector, Access or Local Street: 50 feet

EXCEPT where pre-existing conditions preclude such separation the separation should be maximized.

**3.104.04 Driveway Access Standards, Type I Applications**

A. Number and Location of Driveways Standards, Type I Applications.

1. The maximum number of driveways per lot frontage is one. For purposes of controlling driveway access, every 100 feet of frontage is considered a separate lot frontage. Driveway access to a single family dwelling on a lot with more than one frontage shall be limited to the street with the lowest functional classification.
2. All new driveway connections shall conform with applicable design criteria of the **WDO** and the Public Works Department.
3. Any dysfunctional and/or existing driveway that is replaced by a new driveway shall be removed.

B. Driveway Spacing Standards, Type I Applications.

1. The minimum separation between a driveway and the right of way line of an existing local street, or the special setback for a major street intersection corner is as follows:

- a. Single family or duplex dwelling: 30 feet
  - b. Use other than a single family or duplex dwelling: 50 feet.
2. Where more than one driveway is permitted per lot (*Section 3.104.04.A.1.*), the minimum separation between driveways on the same lot shall be 22 feet.

**3.104.05 Driveway Dimension and Improvement Standards, Type I, II and III Applications**

**A. Joint/Shared Driveway.**

Shared, or joint, driveway shall require an access and maintenance agreement that is irrevocable without the concurrence of the Community Development Director.

**B. Driveway Serving One (1) or Two (2) Dwelling Units. (See **Figure 6.7**)**

**1. Paved Driveway Width.**

- a. For a distance less than 40 feet between the access street or shared access driveway and the attached or detached garage doorway:  
[Section 3.104.05.B & C as amended by Ordinance No. 2383, '42, passed March 16, 2005.]

- 1) 20 feet minimum and 26 feet maximum width for a garage with a doorway(s) to serve entry by not more than two vehicles at one time; and
- 2) 20 feet minimum and up to a 30 feet maximum width for a garage with doorway(s) to serve entry by three vehicles at one time provided the maximum width shall not exceed 50 percent of the lot frontage serving the driveway entrance.

[Section 3.104.05.B.1.b as amended by Ordinance No. 2423, §33, effective on July 28,2007.]

- b. For a distance of 40 or more feet between the access street or shared access driveway and the attached or detached garage doorway: 12 feet minimum width, flared to the required exterior parking pad in front of the garage that is 20 feet minimum width.

2. Paved Parking Pad at a Garage Entrance (or carport for a manufactured home). There shall be an improved parking space, or pad, abutting the attached or detached garage doorway for each opposing parking space within the garage. The exterior pad area for each vehicle shall have the

minimum dimensions of 10 feet wide by 20 feet long. [Section 3.104.05.B & C as amended by Ordinance No. 2383, §42, passed March 16, 2005.]

3. Radius of Curb Flare: 15 feet minimum.
4. Flag Lot Driveway Access Width. 20 foot wide, as either an irrevocable easement or a strip of land in fee ownership.
5. Maximum Driveway Length and Turn Around, Improved to Department of Public Works standards. (See **Figure 6.8**)
  - a. For lots accessed from a City street, EXCLUDING a Major or Minor Arterial, the maximum driveway length from the access street to the front lot line of the lot located furthest from the access street shall not exceed 150 feet UNLESS a turn around is provided.
  - b. For lots accessed from a Major or Minor Arterial Street a turn around shall be required.

C. Driveway Serving Three (3) to Four (4) Dwelling Units. (See **Figure 6.7 & 6.8**)

1. Paved Driveway Width.
  - a. For a distance less than 40 feet between the access street or shared access driveway and the attached or detached garage doorway: 20 feet minimum and 26 feet maximum width. [Section 3.104.05.B & C as amended by Ordinance No. 2383, §42, passed March 16, 2005.]
  - b. For a distance of 40 or more feet between the access street or shared access driveway and the attached or detached garage doorway: 20 feet minimum width, including the required exterior parking pad in front of the garage. [Section 3.104.05.B & C as amended by Ordinance No. 2383, §42, passed March 16, 2005.]
2. Paved Parking Pad at a Garage (or carport for a manufactured home) Entrance. There shall be an improved parking space, or pad, abutting the attached or detached garage doorway for each opposing parking space within the garage. The exterior pad area for each vehicle shall have the minimum dimensions of 10 feet wide by 20 feet long. [Section 3.104.05.B & C as amended by Ordinance No. 2383, v42, passed March 16, 2005.]
3. Radius of Curb Flare: 15 feet minimum.
4. Flag Lot Driveway Access Width. 24 foot wide, as either an irrevocable easement or a strip of land in fee ownership.

5. Maximum Driveway Length and Turn Around, Improved to Department of Public Works standards. (See **Figure 6.8**)
  - a. For lots accessed from a City street, EXCLUDING a Major or Minor Arterial, the maximum driveway length from the access street to the front lot line the lot located furthest from the access street shall not exceed 150 feet UNLESS a turn around is provided.
  - b. For lots accessed from a Major or Minor Arterial Street a turn around shall be required.
- D. Residential Driveways Serving Any Number of Multiple Family Dwelling Units; Assisted Care Living Units (62331) or Nursing Care Living Units (6231).
  1. Paved Driveway Width:
    - a. One-way driveway:
      - 1) Width: 12 feet, min/max. No parking restrictions shall be posted by the owner.
      - 2) Parallel parking, one-side only (“No parking” restrictions shall be posted by the owner.): 20 feet, min/max.
    - b. Two-way driveway:
      - 1) Width: 20 feet, min/max. “No parking” restrictions shall be posted by the owner.
      - 2) Parallel parking, one-side only (“No parking” restrictions shall be posted by the owner.): 28 feet, min/max.
  2. Radius of Curb Flare: 25 feet minimum.
  3. Flag Lot Driveway Access Width. 24 foot wide, as either an irrevocable easement or a strip of land in fee ownership.
  4. Throat length of a driveway, extending from the closest off street parking or loading space to the outside edge of right of way for a:
    - a. Driveway accessing a City street, EXCLUDING Major and Minor Arterial Streets: 20 feet minimum, with greater improvement as may be required by a Traffic Impact Analysis (TIA).
    - b. Driveway accessing Major and Minor Arterial Streets: 50 feet

minimum, with greater improvement as may be required by a Traffic Impact Analysis (TIA).

5. Turn arounds shall be required within the off street parking area(s) and/or as specific circulation features, to Department of Public Works requirements based on the review of the Fire District.

E. Commercial and Industrial Use.

1. Paved Driveway Width.

- a. Paved One-way Driveway:

- 1) Width: 12 feet minimum, 20 foot maximum. (“No Parking” restrictions shall be posted by the owner).

- b. Paved Two-Way Driveway:

- 1) With no turn lane: Throat and travel lane width 26 feet minimum, 36 feet maximum. (“No parking” restrictions shall be posted by the owner.)
    - 2) With a turn lane: Throat width 36 feet minimum, 40 feet maximum. (“No parking” restrictions shall be posted by the owner.)

2. Radius of Curb Flare: 30 feet minimum.

3. Flag Lot Driveway Access Width. 30 foot wide, as either an irrevocable easement or a strip of land in fee ownership.

4. Throat length of a driveway, extending from the closest off street parking or loading space to the outside edge of right of way for a:

- a. Local street connection: 20 feet minimum, with greater improvement as may be required by a TIA.
  - b. Major street connection: 50 feet minimum, with greater improvement as may be required by a TIA.

5. Turn arounds shall be required within the off street parking area(s) and/or as specific circulation features, to Department of Public Works requirements based on the review of the Fire District.

F. Improvement Standards

1. Drainage shall be subject to Department of Public Works policies and standards.
2. Paved Surface.
  - a. The portion of driveway within the public right of way: Portland cement concrete.
  - b. The portion of driveway on private property: Portland cement concrete or asphalt.

## 3.105 Off Street Parking and Loading

### 3.105.01      Applicability

The provisions of this *Section* shall apply to the following types of development:

A.      New Building or Structure.

All requirements and standards of *Section 3.105* shall apply to any new building or structure erected after the effective date of the **WDO**.

B.      Expansion or Change of Use.

Any additional parking and/or loading required by the **WDO** to accommodate a change in use, or expansion of an existing use shall be subject to the following.

1.      Applications subject to Type III Design Review, *Section 5.103.02*, shall conform all parking, loading and landscaping for the subject use to the standards of the **WDO**.
2.      Applications subject to Type II Design Review, *Section 5.102.02*, where the change or expansion increases the required area for parking, loading or landscaping by 25 percent or more, shall conform to all parking, loading and landscaping to the standards of the **WDO**. Parking, loading and landscaping required for changes or expansions of less than 25 percent shall be limited to those necessary to conform with the increment of change or expansion.

[Section 3.105.01.C as amended by Ordinance 2423, §8, effective on July 28, 2007.]

C.      Applicability

The Community Development Director may authorize parking for any use not specifically listed in a zone, upon application by the property owner to the Planning Division for a Type II land use decision. The applicant shall submit a site plan showing the proposed use, an analysis that identifies the parking needs, and a description of how the proposed use is similar to other uses in the zone. The proposed use shall not be listed as a use elsewhere in the WDO. The Director may require additional information as needed to document the proposed use is similar to other uses in the zone. Notification of the Director's decision shall be provided as required by WDO Section 4.1

### 3.105.02      General Provisions for Off Street Parking and Loading

A.      Reduction of Parking and Loading Spaces Prohibited.



All required parking and loading spaces shall be retained and maintained or an equivalent parking and loading space provided.

B. Ownership of Parking.

The land for off street parking areas shall either be:

1. Owned in fee title by the owner of the structure or site being served by the parking area; or
2. Subject to legal documentation, to the satisfaction of the City Attorney, establishing permanent use of off street parking that is under separate ownership. The parking subject to such a shared, or joint, use parking agreement shall be in compliance with all requirements and development standards of the **WDO**. The agreement shall be recorded with the County Recorder and filed with the Community Development Director.

C. Fractional Measurements.

When calculations for determining the number of required off street parking or loading spaces results in a fractional space, any fraction of a space less than one-half shall be disregarded, and a fraction of one-half or greater shall be counted as one full space.

D. Location of Off Street Parking.

1. Off street parking spaces shall be provided on the same lot as the primary building or use EXCEPT that:
  - a. In an RS, R1S or RM zone, on-site vehicle parking spaces for non-residential uses permitted in the zone may be located on another site if such site is within 200 feet of the lot containing the primary building, structure or use.
  - b. In any zone other than RS, R1S or RM, the on-site vehicle parking spaces may be located on an alternative site from the primary building, structure or use if the alternative site is within 500 feet of the site containing the primary use.
2. Off street parking is incident to the primary use which it serves. As such it shall be located either in the same use zone, in a more intensive use zone or in a zone where off street parking is allowed as a permitted use, or subject to approval, as a conditional use.

E. Off Street Vehicle Parking Requirements.

1. Off street vehicle parking spaces shall be provided in amounts not less than those set forth in **Table 3.1.2**.
2. Off street vehicle parking spaces shall not exceed 2.0 times the amount required in **Table 3.1.2**.
3. The number of disabled person vehicle parking spaces shall be provided to the standards of the state Building Code and applicable federal standards. The number of disabled person vehicle parking spaces shall be included as part of total required vehicle parking spaces.
4. Vehicle parking within the public right of way shall not be eligible for fulfilling any required off street parking requirement.
5. Required parking spaces shall be available for parking of operable vehicles of residents, customers, patrons and employees and shall not be used for the storage of vehicles or materials or for the parking of fleet vehicles EXCEPT for those fleet vehicles:
  - a. Driven by an employee to the site each work day from home, or
  - b. Stored during periods other than normal business hours.

F. Compact Vehicle Parking.

A maximum of 20 percent of the required vehicle parking spaces may be satisfied by compact vehicle parking spaces.

G. Off Street Loading Requirements.

1. Off street loading spaces shall comply with the dimensional standards and amounts not less than those set forth in **Table 3.1.3**.
2. The off street loading facilities shall be on the same lot, or site, as the use or structure they are intended to serve. Required loading spaces and required parking spaces shall be separate and distinct.

H. On-site Vehicle Parking and Loading Area Improvement Requirements. [Section 3.105.02.H as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

1. Surfacing. All vehicle parking and loading areas shall be paved with asphalt, concrete or other hard surfacing approved by the Public Works Director.
2. Drainage. All vehicle parking and loading areas shall be graded and

provide storm drainage facilities approved by the Public Works Director.

3. Bumper Guards and Wheel Barriers. All vehicle parking spaces, EXCEPT those for single family and duplex dwellings, shall be constructed with bumper guards or wheel barriers that prevent vehicles from damaging structures or projecting over walkways, access ways or abutting property or rights of way.
4. Size of Vehicular Parking Spaces and Maneuvering Areas within Off Street Parking Areas.
  - a. Off street vehicle parking spaces and maneuvering areas, EXCEPT those for single family and duplex dwellings and those for disabled persons, within off street parking areas shall be designed in compliance with **Table 3.1.4**. Three or more off street parking spaces provided subject to **Table 3.1.4** shall be designed so that no backing or maneuvering within a public street right of way is required.
  - b. Off street parking for single family and duplex dwellings shall be governed by **Section 3.104.05.B.2 and C.2 and Table 3.1.2.1**.
  - c. Off street parking for disabled persons shall be designed to the standards of the state Building Code and applicable federal standards.
5. Directional Marking. EXCEPT for vehicle parking areas for single family and duplex dwellings, off street parking and maneuvering areas shall have directional markings and signs to control vehicle movement.
6. Space Marking. EXCEPT for vehicle parking areas for single family and duplex dwellings, off street parking spaces shall be delineated by double parallel lines on each side of a space. The total width of the lines shall delineate a separation of 2 feet.
7. Access. Access to vehicle parking areas shall be in compliance with the standards of **Section 3.104**.
8. Outdoor Lighting. EXCEPT for vehicle parking areas for single family and duplex dwellings, all outdoor lighting shall be designed so as not to shine or reflect into any adjacent residentially zoned or used property, and shall not cast a glare onto moving vehicles on any public street.
9. Landscaping. EXCEPT for vehicle parking spaces for single family and duplex dwellings, all parking areas shall be landscaped to the standards of **Section 3.106**.

10. On-site Bicycle Parking Requirements. All uses required to provide 10 or more off street parking spaces and residential structures with four or more units shall provide a bicycle rack within 50 feet of the main entrance. The number of required rack spaces shall be one plus one per ten vehicle parking spaces, with a maximum of 20 rack spaces.

[Section 3.105.02.I as amended by Ordinance No. 2423, §6, effective on July 28, 2007.]

I. Joint Use Vehicle Parking.

1. A parking area may be used for a loading area during those times when the vehicle parking area is not in use for parking.
2. Up to 20 percent of the required vehicle parking may be satisfied by joint use of the parking area that is used for another use that would require the parking during the same peak hours. An additional amount of joint use parking, of up to 20 percent of the required vehicle parking, may be satisfied by joint use parking that shares a use that would require the parking during alternate peak hours. An additional amount of joint use parking, of up to 10 percent of the required vehicle parking, may be satisfied when the development is located along a transit service route and the development provides transit related uses such as stops, pullouts, and shelters. The determination of the applicability of joint use parking shall be determined as a Zoning Adjustment, a Type II land use permit.
3. The following uses are considered as daytime uses for purposes of joint use parking identified in this section: banks, business offices, retail stores, personal service shops, household equipment or furniture shops, clothing or shoe repair or service shops, manufacturing or wholesale buildings, and other similar primarily daytime uses as determined through the Zoning Adjustment review.
4. The following uses are considered as nighttime or Sunday uses for purposes of joint use parking identified in this section: auditoriums incidental to a public or private school, churches, bowling alleys, dance halls, theaters, drinking and eating establishments, and other similar primarily nighttime uses as determined through the Zoning Adjustment review.
5. Joint use of parking spaces may be allowed if the following standards are met:
  - a. There shall be no substantial conflict in the principal operating hours of the buildings or uses for which the joint use parking is proposed. Future changes of use, such as expansion of a building

or establishment of hours of operation which conflict with or affect a joint use parking agreement shall require review and authorization of a subsequent Zoning Adjustment.

- b. The joint use parking spaces shall be located no more than 400 feet from a building or use to be served by the joint use parking.
- c. Legal documentation, to the satisfaction of the City Attorney, shall be submitted verifying joint use parking between the separate developments. Joint use parking agreements may include provisions covering maintenance, liability, hours of use, and cross easements.
- d. The City Attorney approved legal documentation shall be recorded by the applicant at the Marion County Recorder's Office and a copy of the recorded document submitted to the Woodburn Community Development Department prior to issuance of a building permit.

[Table 3.1.2 as amended by Ordinance No. 2423, §5 and 9, effective on July 28, 2007.]

<b>TABLE 3.1.2      Off Street Parking Ratio Standards</b>	
<b>Use</b>	<b>Parking Ratio</b> - spaces per activity unit or square feet of gross floor area (sfgfa)
<b>RESIDENTIAL</b>	
1.      Single family or duplex dwelling, including manufactured homes and dwellings	2.0/ dwelling unit in a garage
2.      Three or more dwelling units per single family or duplex dwelling, including manufactured homes and dwellings	2.0/ dwelling unit
3.      Rooming/boarding house (72131)	2.0 parking spaces + 1.0/ guest room
4.      Nursing care facilities (6231)	0.25/ living unit
5.      Assisted living facilities (62331)	0.75/ living unit
6.      Group home (623)	0.75/ living unit
7.      Group care facility (623)	0.75/ living unit

**TABLE 3.1.2 Off Street Parking Ratio Standards**

Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)
<p>P.</p> <p><b>Q. COMMERCIAL</b></p>	
8. Hotels (EXCLUDING casinos) & motels (721110)	2.0 parking spaces + 1.0/ guest room
9. Other traveler accommodations (72119)	2.0 parking spaces + 1.0/ guest room
10. Recreational vehicle (RV) parks (7212)	2.0 parking spaces + 1.0/ RV space
11. Food and drinking places (722)	10.0 parking spaces + 1.0/ 200 sfgfa
12. General retail sales a. Motor vehicle parts (444131) b. Food and beverage stores (445) c. Clothing (448) d. Sporting goods (451) e. General merchandise (452) f. Misc. retail (453) g. Health and personal care stores (446) h. Video tape and disc rental (532230)	1.0/ 250 sfgfa
13. Motor vehicle service a. Gasoline stations (447) b. Automotive repair & maintenance (8111)	1.0/ 200 retail sfgfa + 3.0/ service bay + 1.0/ pump island
14. Personal services (8129) a. Barbers b. Beauticians	<u>Greater of:</u> 1.0/ 350 sfgfa; or 2.0/ service chair
15. Offices a. Information (EXCLUDING motion pictures) (51) b. Finance and insurance (52) c. Real estate (53) d. Professional, scientific and technical [Including lawyers and engineers] (54) e. Administrative and support services (56) f. Social assistance (624) g. Membership organizations (813) EXCLUDING houses of worship	1.0/ 350 sfgfa
16. General Repair and Service a. Electronic and precision repair (8112) b. Leather goods repair c. Laundry and dry cleaning (8123)	1/ 500 sfgfa
17. Indoor Sales and Service of Bulky Merchandise a. Electronics and appliance (443) b. Furniture (442) c. Building materials (444) d. Home goods repair (8114)	1/ 900 sfgfa

**TABLE 3.1.2 Off Street Parking Ratio Standards**

Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)
e. Linen and uniform supply (81233)	
18. Sales & Service of Bulky Merchandise	1.0/ 400 sfgfa of structure + 1.0/ 2000 sfgfa outdoor display area
a. Motor vehicle dealers (441)	
b. Tractor sales (42182)	
c. Manufactured dwelling dealers (45393)	
19. Delivery Services	One space per delivery vehicle plus one space per employee per shift.
20. Home Occupations	No reduction from dwelling requirement is allowed.
21. Residential sales office	No reduction from dwelling requirement is allowed.
22. Temporary residential sales	No reduction from dwelling requirement is allowed.
23. Photo finishing (81292)	1.0/ 250 sfgfa
24. Contractors (233, 234, 235)	2.0 parking spaces + 1.0/ employee
25. Fabricated metal products manufacturing	Greater of 1/ 800 sfgfa or 1.0/ employee
26. Temporary outdoor marketing and special events	1.0/ 1,000 square feet of outside event space plus, no reduction from primary zoning for other uses.
27. Urban transit system (48511)	1.0/ bus plus 1.0/ employee
28. Interurban and rural transit (4852)	1.0/ bus plus 1.0/ employee
29. Taxi service (485310)	1.0/ vehicle plus 1.0/ employee
30. Limousine service (4853)	1.0/ vehicle plus 1.0/ employee
31. School transportation (4854)	1.0/ bus plus 1.0/ employee
32. Charter bus service (4859)	1.0/ bus plus 1.0/ employee
33. Special needs transportation (485991)	1.0/ vehicle plus 1.0/ employee
34. Motor vehicle towing (48841)	1.0/ vehicle plus 1.0/ employee
35. Commercial and industrial equipment repair (8113)	1.0/ 800 sfgfa or 1.0/ employee
36. Bakeries (31181) (722210)	Greater of 1/ 800 sfgfa or 1/ employee 1/ 250 sfgfa
37. Printing and related support activities (323)	Greater of 1/ 700 sfgfa or 1/ employee
38. Mail order house (45411)	Greater of 1/ 700 sfgfa or 1/ employee
39. Motor vehicle wrecking yard (423140, 423930)	1/ 700 retail sfgfa + 1/ 1000 wholesale

**TABLE 3.1.2 Off Street Parking Ratio Standards** continued

Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)
<b>INDUSTRIAL</b>	
40. Warehousing (493) <ul style="list-style-type: none"> <li>a. 0 to 49,999 sfgfa</li> <li>b. 50,000 to 99,999 sfgfa</li> <li>c. 100,000 or more sfgfa</li> </ul>	Greater of: <ul style="list-style-type: none"> <li>a. 1.0/ 5000 sfgfa or 1.0/ employee</li> <li>b. 1.0/ 10,000 sfgfa or 1.0/ employee</li> <li>c. 1.0/ 15,000 sfgfa or 1.0/ employee</li> </ul>
41. Self storage	1.0/ 6 storage units, maximum of 6 spaces
42. Manufacturing <ul style="list-style-type: none"> <li>a. 0 to 49,999 sfgfa</li> <li>b. 50,000 to 99,999 sfgfa</li> <li>c. 100,000 or more sfgfa</li> </ul>	Greater of: <ul style="list-style-type: none"> <li>a. 1.0/ 800 sfgfa or 1.0/ employee</li> <li>b. 1.0/ 1000 sfgfa or 1.0/ employee</li> <li>c. 1.0/ 2000 sfgfa or 1.0/ employee</li> </ul>
43. Wholesale trade (421, EXCEPT 42182, and 422)	1.0/ 700 retail sfgfa + 1.0/ 1000 wholesale sfgfa
44. Agricultural practices	Exempt from the parking requirements in Section 3.105.
45. Support activities for Rail Transportation (488210) <ul style="list-style-type: none"> <li>a. 0 to 49,999 sfgfa</li> <li>b. 50,000 to 99,999 sfgfa</li> <li>c. 100,000 or more sfgfa</li> </ul>	Greater of: <ul style="list-style-type: none"> <li>a. 1.0/ 5000 sfgfa or 1.0/ employee</li> <li>b. 1.0/ 10,000 sfgfa or 1.0/ employee</li> <li>c. 1.0/ 15,000 sfgfa or 1.0/ employee</li> </ul>
46. Craft industries	Greater of 1/ 800 sfgfa or 1.0/ employee
47. Telecommunication Facilities	Exempt from the parking requirements in Section 3.105.
48. Recycling Centers (562920) <ul style="list-style-type: none"> <li>a. 0 to 49,999 sfgfa</li> <li>b. 50,000 to 99,999 sfgfa</li> <li>c. 100,000 or more sfgfa</li> </ul>	Greater of: <ul style="list-style-type: none"> <li>a. 1.0/ 5000 sfgfa or 1.0/ employee</li> <li>b. 1.0/ 10,000 sfgfa or 1.0/ employee</li> <li>c. 1.0/ 15,000 sfgfa or 1.0/ employee</li> </ul>
49. Truck transportation (484) <ul style="list-style-type: none"> <li>a. 0 to 49,999 sfgfa</li> <li>b. 50,000 to 99,999 sfgfa</li> <li>c. 100,000 or more sfgfa</li> </ul>	Greater of: <ul style="list-style-type: none"> <li>d. 1.0/ 5000 sfgfa or 1.0/ employee</li> <li>e. 1.0/ 10,000 sfgfa or 1.0/ employee</li> <li>f. 1.0/ 15,000 sfgfa or 1.0/ employee</li> </ul>
50. Transit ground transportation (485)	1.0 transit vehicle space per transit vehicle plus 1.0/ employee
51. Freight transportation arrangement (488510)	1.0/ employee



**TABLE 3.1.2 Off Street Parking Ratio Standards** concluded

Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)
<b>PUBLIC AND SEMI-PUBLIC</b>	
52. Ambulatory health services [Including doctors and dentists] (621)	1.0/ 250 sfgfa
53. Hospital (622)	1.5/ bed
54. Meeting facilities a. Auditorium, Theater (7111 & 71112) b. Motion Picture Theater [in-door] (512131) c. Arena, Stadium d. Funeral Home (81221) e. Lodge Hall f. House of Worship	1.0/ 4 seats or 1.0/ 8 feet of bench or 1.0/ 35 sfgfa of the primary assembly room
55. General indoor recreation a. Dance hall (71399) b. Skating rink c. Fitness and recreational sports (71394)	1.0/ 200 sfgfa
56. Bowling center (71395)	5.0/ alley
57. Golf course (71391)	4.0/ tee
58. Court games [tennis, handball, racquetball]	3.0/ court + 1.0/ 4 feet of bench
59. Day care (6241)	2.0/ caregiver
60. Elementary or middle school (6111)	2.0/ classroom
61. High school	1.0/ unit of capacity for 6 students
62. Community college, college, business school, trade school, technical school, other instruction [Including dance, driving and language] (6112, 6113, 6114, 6115, 6116)	1.0/ unit of capacity for 4 students
63. Libraries (51412)	1.0/ 400 sfgfa
64. Public administration (92)	1.0/ 350 office sfgfa
65. Parks and Playgrounds	Minimum of other uses requiring parking
66. Play or ball field	Greater of 15/ field or 1/ 8 feet of bench
67. Community club building and facilities	1.0/ 4 seats or 1.0/ 8 feet of bench or 1.0/ 35 sfgfa of the primary assembly room
68. Accessory government and public utility buildings	Greater of 2 or one per employee at location

<b>TABLE 3.1.2 Off Street Parking Ratio Standards</b> concluded	
Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)
and structures	
69. Golf driving range, in conjunction with golf course	1/ 8 driving range tee spaces
70. Postal service	1/ 250 sfgfa
71. Museum and historic sites (712) EXCEPT zoos (712130)	1.0/ 4 seats or 1.0/ 8 feet of bench or 1.0/ 35 sfgfa of the primary assembly room
72. Community center	1.0/ 4 seats or 1.0/ 8 feet of bench or 1.0/ 35 sfgfa of the primary assembly room
73. Taxidermist	1/ 500 sfgfa
74. Cemetery	10 plus one per acre

<b>TABLE 3.1.2 Off Street Parking Ratio Standards</b> concluded	
Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)

**SOUTHWEST INDUSTRIAL RESERVE (SWIR) TARGETED EMPLOYMENT INDUSTRIES**

75. Printing, Publishing, and Allied Industries, 27 (SIC), (232 NAICS)	Greater of 1/ 700 sfgfa or 1.0/ employee
76. Stone, Clay, Glass and Concrete Products, 32 (SIC), (327 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of: a. 1.0/ 800 sfgfa or 1.0/ employee b. 1.0/ 1,000 sfgfa or 1.0/ employee c. 1.0/ 2,000 sfgfa or 1.0/ employee
77. Fabricated Metal Products, except machinery and Transportation Equipment, 34 (SIC), (333 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of: a. 1.0/ 800 sfgfa or 1.0/ employee b. 1.0/ 1,000 sfgfa or 1.0/ employee c. 1.0/ 2,000 sfgfa or 1.0/ employee
78. Industrial and Commercial and Machinery and Computer Equipment, 35 (SIC), (333 and 334 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of: a. 1.0/ 800 sfgfa or 1.0/ employee b. 1.0/ 1,000 sfgfa or 1.0/ employee c. 1.0/ 2,000 sfgfa or 1.0/ employee
79. Electronic and Other Electrical Equipment and Components, except Computer Equipment, 36 (SIC), (335 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of: a. 1.0/ 800 sfgfa or 1.0/ employee b. 1.0/ 1,000 sfgfa or 1.0/ employee c. 1.0/ 2,000 sfgfa or 1.0/ employee

**TABLE 3.1.2 Off Street Parking Ratio Standards** concluded

Use	Parking Ratio - spaces per activity unit or square feet of gross floor area (sfgfa)
<b>80.</b> Transportation Equipment 37 (SIC) (336 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of:  a. 1.0/ 800 sfgfa or 1.0/ employee b. 1.0/ 1,000 sfgfa or 1.0/ employee c. 1.0/ 2,000 sfgfa or 1.0/ employee
<b>81.</b> Motor Freight Transportation and Warehousing, 42 (SIC), (48 and 49 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of:  a. 1.0/ 5,000 sfgfa or 1.0/ employee b. 1.0/ 10,000 sfgfa or 1.0/ employee c. 1.0/ 15,000 sfgfa or 1.0/ employee
<b>82.</b> Wholesale Trade – Durable Goods, 50 (SIC), (421 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of:  a. 1.0/ 5,000 sfgfa or 1.0/ employee b. 1.0/ 10,000 sfgfa or 1.0/ employee c. 1.0/ 15,000 sfgfa or 1.0/ employee
<b>83.</b> Wholesale Trade – Non-durable goods, 51 (SIC), (422 NAICS) a. 0 to 49,999 sfgfa b. 50,000 to 99,999 sfgfa c. 100,000 or more sfgfa	Greater of:  a. 1.0/ 5,000 sfgfa or 1.0/ employee b. 1.0/ 10,000 sfgfa or 1.0/ employee c. 1.0/ 15,000 sfgfa or 1.0/ employee
<b>84.</b> Non-Depository Credit Institutions, 61 (SIC), (522 NAICS)	1.0/ 350 sfgfa
<b>85.</b> Business Services, 73 (SIC), (561 NAICS)	1.0/ 350 sfgfa
<b>86.</b> Health Services, 80 (SIC), (621 NAICS. Except Ambulance service, 621910)	1.0/ 250 sfgfa
<b>87.</b> Professional Services, 87 (SIC), (541 NAICS)	1.0/ 350 sfgfa

<b>TABLE 3.1.3 Loading Space Requirements</b>				
			<u>Minimum Size of Space</u>	
Use	Minimum No. of Spaces	Width	Length	Height
<b>Medium Density Dwellings</b>				
0-9 Units	0	---	---	---
10 or more Units	1	12 feet	20 feet	14 feet
<b>For buildings used entirely for office occupancy (sq. ft. gfa*)</b>				
0-1,999	0	---	---	---
2,000-41,999	1	12 feet	20	14
42,000 or more	2	12 feet	20	14
<b>For all uses other than residential or entirely office use:(sq. ft. gfa*)</b>				
0-9,999	1	12 feet	30 feet	14 feet
	2	12 feet	30 feet	14 feet
10,000-41,999	3	12 feet	30 feet	14 feet
42,000-81,999	4	12 feet	30 feet	14 feet
82,000 or more				

\*square feet of gross floor area

**TABLE 3.1.4      Parking Space and Aisle Dimensions    (See Figure 6.10)**

<b>Aisle (A)</b>	<b>Type (B)</b>	<b>Width (Measured from the midpoint of the double stripe) (C)</b>	<b>Curb Length (D)</b>	<b>1-Way Aisle Width (E)</b>	<b>2-Way Aisle Width (E)</b>	<b>Stall Depth (F)</b>
0E (Parallel)	Standard	8.0 feet	22.5 feet	12.0 feet	24.0 feet	8.0 feet
	Compact	8.0 feet	19.5 feet	12.0 feet	24.0 feet	8.0 feet
30E	Standard	9.0 feet	18.0 feet	12.0 feet	24.0 feet	17.0 feet
	Compact	7.5 feet	15.0 feet	12.0 feet	24.0 feet	14.0 feet
45E	Standard	9.0 feet	14.5 feet	15.0 feet	24.0 feet	19.0 feet
	Compact	7.5 feet	12.5 feet	13.0 feet	24.0 feet	16.0 feet
60E	Standard	9.0 feet	10.5 feet	18.0 feet	24.0 feet	20.0feet
	Compact	7.5 feet	8.5 feet	15.0 feet	24.0 feet	17.0 feet
90E	Standard	9.0 feet	9.0 feet	24.0 feet	24.0 feet	19.0 feet
	Compact	7.5 feet	7.5 feet	22.0 feet	24.0 feet	15.0 feet

## 3.106 Landscaping Standards

### **3.106.01**      **Applicability**

The provisions of this section shall apply:

- A. To the site area for all new structures and related parking EXCLUDING single-family and duplex dwellings and accessory structures; and
- B. To the entire site area of the development, where the cumulative effect of additions to structures and/or parking areas increases the total area covered by structure and parking by 50 percent or more than existed at the date of the **WDO** adoption.

### **3.106.02**      **General Requirements**

- A. Landscaping and Irrigation Plans Required.

Building plans for all uses subject to landscaping requirements shall be accompanied by landscaping and irrigation plans to City standards.

- B. Irrigation.

All required landscaped areas shall be permanently irrigated unless a planting plan without irrigation is submitted by a licensed landscape architect or a licensed nursery person demonstrating that the proposed landscaping will thrive without irrigation.

- C. Plant Materials.

All shrubs and ground cover shall be of a size upon installation so as to attain 80% of ground coverage within 3 years.

- D. Installation of Plant Materials and Irrigation.

Installation of plant materials and irrigation specified in an approved landscaping plan shall occur at the time of development and shall be a condition of final occupancy. Should site conditions or seasonal conditions make immediate installation impractical, an acceptable performance guarantee may be approved subject to **Section 4.102.07**.

- E. Maintenance.

The property owner shall be responsible for maintaining all landscaping in good condition so as to present a healthy and orderly appearance. Unhealthy and dead

plants shall be removed and replaced in conformance with the original landscape plan.

### **3.106.03**      **Landscaping Standards**

[Section 3.106.03 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

#### **A. Streetscape.**

1. Street Trees. Within the public street right of way abutting a development, or within an alley right of way in the DDC zone, street trees shall be planted to City standards prior to final occupancy.
  - a. Acceptable Types of Trees. See ***Section 6.103*** for a description of acceptable and unacceptable trees for this purpose, classified by size and species.
  - b. Tree Density. Trees shall be planted at the following intervals within the right of way, subject to Clear Vision Area standards, ***Section 3.103.10 and Section 6.103***:
    - 1) Four (4) small trees per 100 feet of street frontage;
    - 2) Three (3) medium trees per 100 feet of street frontage; or
    - 3) Two (2) large trees per 100 feet of street frontage.
2. Front Yard and Yard Abutting a Street.
  - a. Landscaping Density for non-residential uses in the RS and R1S zone and all uses in the RM, P/SP, IL, IP, and SWIR zones. All front yards and yards abutting a street shall be landscaped at a density of one (1) plant unit (PU) per 20 sq. ft.
  - b. Landscaping Design and Density in CO and CG zones.
    - 1) All yards abutting a street, including off street parking and circulation areas shall be landscaped at a density of one (1) plant unit (PU) per 20 sq. ft.
    - 2) All parking areas abutting a street shall provide a 42-inch vertical visual screen from the abutting street grade. Acceptable design techniques to provide the screening include plant materials; berms; freestanding, architectural walls with an anti-graffiti finish, depressed grade for the parking area. All screening shall comply with the clear

vision standards, **Section 3.103.10**.

**B. Buffer Yards.**

All buffer yards shall be landscaped at the rate of one (1) plant unit (PU) per 20 sq. ft. EXCEPT for interior buffer yards abutting a wall which are paved and which may be used for parking or site access and vehicular circulation.

**C. Off Street Parking Areas.**

[Section 3.106.03.C.1 as amended by Ordinance No. 2423, §10, effective on July 28, 2007.]

1. All unpaved land within the off street parking areas, and within 20 feet of the paved edge of off street parking and/or circulation improvements, shall be landscaped in the following proportions:
  - a. RM, P/SP, CO and CG zones: Landscaped area(s) equivalent to 20% of the paved surface area for off street parking and circulation.
  - b. IP, IL, and SWIR zones: Landscaped area(s) equivalent to 10% of the paved surface area for off street parking and circulation.
2. The density of landscaping required in and adjacent to off street parking and circulation facilities, EXCLUDING required trees, shall be one (1) plant unit per 20 square feet.
3. Trees, **Section 6.103**, shall be planted within and abutting off street parking facilities in a pattern that is in proportion to the distribution of the parking spaces, at the following densities:
  - a. 1 small tree per 5 parking spaces;
  - b. 1 medium tree per 10 parking spaces; or
  - c. 1 large tree per 14 parking spaces.
4. Multi-Purpose Landscaping. Trees and other required landscaping located on private property within a required setback abutting a street or an interior lot line that is within 20 feet of the paved surface of off street parking and circulation facilities, may also be counted in calculating required landscaping for off street parking and circulation areas.

**D. Common Areas.**



All common areas, EXCEPT those approved as natural common areas in a PUD, shall be landscaped with at least three (3) plant units per 50 square feet.

E. Yards.

The entire yard area of a property, EXCLUDING areas subject to more intensive landscaping requirements and all yards of residential uses in a RS or R1S zone, shall be landscaped to a standard of at least one (1) plant unit (PU) per 50 square feet prior to final occupancy.

**3.106.04 Conservation of Significant Trees**

[Section 3.106.04 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.] [Section 3.106.04 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]

A. Purpose.

The purpose of this Section is to establish processes and standards which will minimize cutting or destruction of significant trees within the City. Significant trees enhance neighborhoods by creating a sense of character and permanence. In general, significant trees on private property shall be retained unless determined to be hazardous to life or property. [Section 3.106.04.A as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]

B. Applicability.

The provisions of this *Section* apply to the removal of any significant tree and the replacement requirements for significant tree removal. A “significant tree” is any existing, healthy tree 24 inches or more in diameter, measured 12 inches above ground level.

C. Review Prior to Removal.

A Significant tree removal permit shall be reviewed as a Type I application to authorize the removal of a significant tree, subject to the following [Section 3.106.04.C as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]:

1. The property owner shall replace each tree removed with two new trees. A tree required by the development standards of the zone, Section 3.1, or as a condition of permit or land use approval shall qualify as a replacement tree; [Section 3.106.04.C.1 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]
2. For the removal of a diseased or dangerous tree, a report from a certified

arborist shall be submitted certifying that the tree is dead or dying, structurally unsound, or hazardous to life or property, any significant tree removed under this provision shall be replaced in accordance with Section 3.106.04.D. [Section 3.106.04.C.2 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]

3. A dangerous tree may be removed prior to obtaining a permit in an emergency, and the owner shall apply within three days for the removal permit pursuant to this Section. Any significant tree removed under this provision shall be replaced in accordance with Section 3.106.04.D. [Section 3.106.04.C.3 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]

D. Tree Replacement Requirement.

The issuance of a significant tree removal permit requires the property owner to replace each tree removed with two new trees on the same property. Each new tree shall be at least 2 inches in caliper. Each tree replaced should be of a species not on the prohibited tree list, *Section 6.103* as these trees are not recommended for their negative attributes. The replacement tree should be of the same size range at maturity as the significant tree replaced. The property owner shall choose the method of replacement. Replacement shall be accomplished by [Section 3.106.04.D as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]:

1. Planting two trees on the subject property; [Section 3.106.04.D.1 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]
2. Planting one tree on the subject property and one tree at a location determined by the Woodburn Community Services Department; or [Section 3.106.04.D.2 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]
3. Planting one tree on the subject property and paying a fee-in-lieu to the Woodburn Community Services Department for the planting of one tree at a future time by the City. [Section 3.106.04.D.3 as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]

- E. In-Lieu-of Mitigation Fee. The property owner shall pay a mitigation fee for each required replacement tree that is not planted pursuant to Section 3.106.04.D.3. The applicant shall pay the mitigation fee into the City's tree fund. The amount of the mitigation fee shall be established by the City Council in the Master Fee Schedule, based on the average value of a 2-inch caliper tree available from local nurseries plus planting costs. [Section 3.106.04.E as amended by Ordinance No. 2446, §30, passed on September 10, 2008.]

**3.106.05**      **Planting Standards**

A. Distribution of Plant Materials.

The required number of plant units shall be met by a combination of plant materials listed in **Table 3.1.5**, so that eighty (80) percent of the area to be landscaped is covered within three years. Required plant units need not be allocated uniformly through out specified landscaping areas, but may be grouped for visual effect.

B. Ground Cover.

Landscaped areas that are not covered by plant materials shall be covered by a layer of bark mulch or decorative rock, EXCLUDING ordinary crushed gravel, a minimum of 2 inches in depth.

C. Curbs.

A six-inch concrete curb shall be provided between a landscaped area and a parking area or access way. [Table 3.1.5 as amended by Ordinance No. 2446, §29, passed on September 8, 2008.]

<b>TABLE 3.1.5      Definition of a Plant Unit (PU)</b>		
<b><u>Plant Material</u></b>	<b><u>Plant Unit (PU) Value</u></b>	<b><u>Minimum Size of Plant</u></b>
1. 1 Significant Tree	15 PU	24" Caliper
2. 1 Large Tree, <i>Section 6.103</i>	10 PU	10' Height or 2" Caliper
3. 1 Medium Tree, <i>Section 6.103</i>	8 PU	10' Height or 2" Caliper
4. 1 Small Tree, <i>Section 6.103</i>	4 PU	10' Height or 2" Caliper
5. 1 Large Deciduous or Evergreen shrub (at maturity over 4' wide x 4' high)	2 PU	3 gallon or balled & burlapped
6. 1 Small to Medium shrub (at maturity maximum 4' wide x 4' high)	1 PU	1 gallon
7. Lawn or other living ground cover	1 PU / 50 sq. ft.	
8. Berm	1 PU / 20 lineal feet	Minimum 2 feet high
9. Ornamental fence	1 PU / 20 lineal feet	2 ½ - 4 feet high
10. Boulder	1 PU	Minimum 2 feet high
11. Sundial, obelisk, gnomon, or gazing ball	2 PU	Minimum 3 feet high
12. Fountain	3 PU	Minimum 3 feet high
13. Bench or chair	.5 PU / lineal foot	

<b>TABLE 3.1.5      Definition of a Plant Unit (PU)</b>		
<b><u>Plant Material</u></b>	<b><u>Plant Unit (PU) Value</u></b>	<b><u>Minimum Size of Plant</u></b>
14. Raised Planting bed constructed of brick, stone or similar material EXCEPT CMU	.5 PU / lineal foot of greatest dimension	Minimum 1 foot high, minimum 1 foot wide in lease interior dimension
No more than twenty percent (20%) of the required plant units may be satisfied by items in lines 8 through 14.		

## 3.107 Architectural Design Guidelines and Standards

### A. Purpose

1. The purpose of these architectural design guidelines and standards is to guide the design of buildings constructed in the City of Woodburn to ensure that, through appropriate building orientation, landscape design and architectural details, new structures and alterations of existing structures are physically and visually compatible with other buildings within the city.
2. These standards are intended to encourage good quality design in new building construction, enhance street safety, and provide a comfortable street environment by providing features of interest to pedestrians. Good design results in buildings that are in visual harmony with nearby buildings, leading to a city that is attractive, interesting, active, and safe. [§A adopted by Ordinance 2463, passed January 25, 2010.]

### **3.107.01 Dwellings EXEMPT from Architectural Design Standards and Guidelines**

The following dwellings shall be EXEMPT from the provisions of *Section 3.107*:

- A. Any single family or duplex dwelling (site built dwelling, manufactured dwelling or manufactured home) that exists, or is subject to a building permit that has been issued prior to *WDO*, EXCEPT such dwellings located within the Neighborhood Conservation Overlay (NCOD).
- B. All new dwellings sited in Manufactured Dwelling Parks containing more than 3 acres.

### **3.107.02 Design Standards for Manufactured Homes Sited in Manufactured Dwelling Parks of 1 to 3 Acres**

#### A. Design Standards for Roofing and Siding.

These standards are established by statute (ORS 197.307) and therefore non-variable.

1. Roof. The manufactured home *shall* have a pitched roof with a slope no less than a nominal three feet in height for each 12 feet in width.
2. Exterior Siding and Roofing Materials. Each manufactured home *shall* have exterior siding and roofing which in color, material and appearance is similar to the exterior siding and roofing material commonly used on residential dwellings within the community or which is comparable to the predominant material used on surrounding dwellings as determined by the standards of comparison defined in *Section 3.107.02.B*.

B. Standards of Comparison for Roofing and Siding.

1. Review Area. The “review area” that defines the character of “surrounding dwellings” and “immediately surrounding dwellings” *shall* encompass the five nearest dwellings to the subject lot that are on the same street and that are within 250 feet of the subject lot. If there are fewer than five dwellings within 250 feet, only those dwellings within 250 feet *shall* be used.
2. Predominant Material and Predominant Construction. As used in the *WDO*, “predominant material” and “predominant construction” *shall* be the material used on the majority of the dwellings in the review area. If there is no majority of dwellings using the same material, then the material used on the largest plurality of dwellings in the review area *shall* be the predominant material.

**3.107.03 Design Standards for New Single Family and Duplex Dwellings Sited on Individual Lots**

A. Foundation Standards.

1. Site Built Dwelling. The foundation shall comply with the standards of the state building code.
2. Manufactured Home.

This standard is established by statute (ORS 197.307) and therefore non-variable.

A dwelling *shall* be placed on an excavated and back-filled foundation and enclosed at the perimeter such that the dwelling is located not more than 12 inches above grade for elevations facing a street.

B. Roof Standards.

1. Site Built Dwelling.
  - a. A site built dwelling *shall* have a pitched roof with a minimum slope ratio of four feet in height for each 12 feet in width.
  - b. The roofing material for a site built dwelling *shall* be either composition shingles; clay or concrete tile; metal; or cedar shingles or shakes. Composition shingles *shall* be architectural style with a certified performance of at least 25 years.

2. Manufactured Home.

These standards are established by statute (ORS 197.307) and therefore non-variable.

- a. A manufactured home ***shall*** have a pitched roof with a slope no less than a nominal three feet in height for each 12 feet in width.
- b. A manufactured home ***shall*** have roofing which in color, material and appearance is similar to the roofing material commonly used on residential dwellings within the community or which is comparable to the predominant material used on surrounding dwellings as determined by the standards of comparison defined in ***Section 3.107.02.B.***

C. Exterior Finish.

1. Site Built Dwelling. The exterior finish ***shall*** have the appearance of either horizontal lap siding, shakes, shingles, brick or stucco. Where horizontal lap siding is used, it ***shall*** appear to have a reveal of 3 to 8 inches.

Plain concrete, corrugated metal, plywood and sheet press board ***shall not*** be used as exterior finish material.

2. Manufactured Home.

These standards are established by statute (ORS 197.307) and therefore non-variable.

Each manufactured home ***shall*** have exterior siding which in color, material and appearance is similar to the exterior siding material commonly used on residential dwellings within the community or which is comparable to the predominant material used on surrounding dwellings as determined by the standards of comparison defined in ***Section 3.107.02.B.***

D. Garage (or carport for a manufactured home).

A dwelling ***shall*** have a garage (or carport, in the case of a manufactured home).

1. The facade containing the vehicular entrance(s) for an attached garage ***shall*** either:
  - a. Face away from the street frontage of the main pedestrian entry of the dwelling at an angle of at least 90 degrees; or

- b. Comprise less than half the lateral dimension of the total facade facing a street; or comprise no more than 65 percent of the area, including second stories, dormers, and eye brows, of the total facade of the structure facing the street
- 2. The facade containing the vehicular entrance(s) for a detached garage **shall** either:
  - a. Face away from the street frontage of the main pedestrian entrance of the dwelling at an angle of at least 90 degrees; or
  - b. Setback at least 20 feet from the facade of the dwelling containing the main pedestrian entrance and with the area of the facade of the garage no greater than that of the dwelling.

E. Main Pedestrian Entrance.

- 1. The main pedestrian entrance of each dwelling unit, EXCLUDING manufactured dwellings in a MDP and dwellings on flag lots, **shall** face the street. [Section 3.107.03.E.1 as amended by Ordinance No. 2383, §45, passed March 16, 2005.]
- 2. The main entrance to each dwelling unit **shall** have either:
  - a. A covered porch, at least 48 square feet in area with the minimum dimension of 6 feet on any side; or
  - b. A recessed entry, at least 24 square feet in area with the minimum dimension of 4 feet on any side.

F. Windows on Facades Fronting a Street.

At least 15 percent of the facade wall surface of a dwelling unit facing a front lot line **shall** be windows, excluding roofs and non-habitable wall area under the end of a roof, and excluding the garage facade. [Section 3.107.03.F as amended by Ordinance No. 2383, §46, passed March 16, 2005.]

G. Multi-dimensional Facade and/or Roof Line on the Front of the Dwelling.

The front of the dwelling unit **shall** either contain:

- 1. An articulated roof line incorporating more than one pitch or elevation of the ridge line that is visible in the front elevation, EXCLUDING a porch;
- 2. A gable, dormer, eye brow, off-set roof line or other vertical, architectural extension of the building at least 36 inches above the eave; or



3. An off-set line in the facade of the building of at least 36 inches and ten feet in length, EXCLUDING a recessed pedestrian entrance or porch.

H. Eaves.

Eaves of a dwelling unit or garage *shall* provide a minimum 12 inch projection.

**3.107.04 Design Guidelines and Standards for Single Family and Duplex Dwellings in the Neighborhood Conservation Overlay (NCOD)**

A. Applicability.

1. New Dwellings. For any new single family and duplex dwelling within the Neighborhood Conservation Overlay (NCOD), that the portion of the exterior surface facing a public street shall be subject to architectural review.
  - a. At the time of application, the applicant shall choose whether the review shall be conducted as a Type I review following the procedures of *Section 5.101.01* or as a Type II or III review following the procedures of *Section 5.102.02* or *5.103.02*, depending on floor area.
  - b. For a Type I review, the criteria of *Section 3.107.04.B* shall be read as “*shall*” and shall be applied as standards.
  - c. For a Type II or III review, the criteria *Section 3.107.04.B* shall be read as “*should*” and shall be applied as guidelines.
2. Exterior Remodel of an Existing Single Family or Duplex Dwelling. The exterior remodel of the facade or roof of an existing single family or duplex that faces a street within the NCOD shall be subject to a Type II architectural review following the procedures of *Section 5.102.02*.

The criteria of *Section 3.107.04.B* shall be read as “*should*” and shall be applied as guidelines.

B. Design Guidelines and Standards.

1. The proposed construction *should/shall* provide architectural details, such as dormers, bays, bracketing, cornices and trim, to add aesthetic visual interest and detail.
2. The design *should/shall* minimize the negative visual impact of on-site automobile parking within the district by orienting garage openings so that

they do not front directly onto a public street. An attached garage opening should either be located a minimum of ten (10) feet back of the building facade or the garage should be detached.

3. New structures and additions to existing ones *should/shall* be no higher than 35 feet.
4. Long, flat facades on buildings *should/shall* be avoided. Buildings *should/shall* not be more than 50 feet wide.
5. The character of single family and duplex roofs shall be maintained. The roof pitch *should/shall* range between 6/12 and 12/12.
6. The main entrance of a dwelling *should/shall* face the street and be covered with a roof.
7. Windows in the building *should/shall* be wood sash with trim that is at least 5-1/2 inches wide. No pane of glass *should/shall* be any larger than 30 inches wide by 84 inches high. Glass *should/shall* be clear or stained.
8. Horizontal wood siding, brick or stucco *should/shall* be used for exterior finishes. For building additions the exterior finish *should/shall* be of the same style and character as the existing building.
9. Buffer Wall. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height, *should/shall* be constructed on the perimeter property line of the development where the abutting use is commercial or industrial and no comparable buffer exists.

### **3.107.05 Guidelines and Standards for Medium Density Residential Buildings**

#### **A. Applicability.**

Pursuant to **Section 1.102**, “Medium Density Residential Building” means any building where the predominant use is multiple family, nursing care or assisted care residential.

At the time of application, the applicant shall choose whether the review will be conducted as a Type I review following the procedures of **Section 5.101.01** or as a Type II or III review following the applicable procedures of **Section 5.102.02** or **5.103.02**, depending on floor area.

[Section 3.107.05.A is amended by Ordinance 2423, §28, effective on July 28, 2007.]

1. For a Type I review, the criteria of **Section 3.107.05.B** shall be read as

“**shall**” and shall be applied as standards.

2. For a Type II or III review, the criteria **Section 3.107.05.B** shall be read as “**should**” and shall be applied as guidelines.

B. Open Space Guidelines and Standards.

1. Common Open Space and Facilities.

- a. Common open space and facilities consist of the site area and facilities not devoted to dwellings, parking, streets, driveways or storage areas that are available for use by all residents of a development.
- b. Required yard setbacks **should/shall** be included as common open space.
- c. Open Space and Facility Design Guidelines and Standards.
  - 1) A minimum of 30 percent of the net site area of each medium density residential development **should/shall** be permanently designated for use as common open space and facilities.
  - 2) The common area **should/shall** include at least one open space containing 2000 sq. ft., with a minimum width of 36 feet.
  - 3) Recreation Areas and Facilities. Facilities to accommodate children’s and/or adult recreation, meeting or education activities **should/shall** be provided at a ratio of 36 sq. ft. of outdoor, or 12 sq. ft. of indoor, common area per dwelling unit or living unit. The minimum improved common area for this purpose **should/shall** be 720 square feet of outdoor or 240 sq. ft. indoor space. The space for such improvements may be counted as part of the common area required by **Section 3.107.05.B.1.c.2)**. at a 1:1 ratio for outdoor space and 3:1 ratio for indoor space.

2. Private Open Space.

a. Ground Level Courtyard

- 1) Medium density dwelling units sited on the finished grade, or within 5 feet of the finished grade, **should/shall** have 96 square feet of semi-enclosed, private open space, with no

dimension less than 6 feet.

- 2) Ground level private open space *should/shall* be visually and physically separated from common open space through the use of perimeter landscaping or fencing.

b. Balcony

Medium density dwelling units sited more than 5 feet from the finished grade (a balcony) *should/shall* have 48 square feet of private open space, with no dimension less than 6 feet.

C. Architectural Design Guidelines and Standards.

1. Building Mass and Facade.

- a. Medium density residential buildings *should/shall* have no dimension greater than 150 feet.
- b. Every two attached medium density residential dwelling units *should/shall* be offset by at least 4 feet in depth.
- c. Adjacent medium density residential buildings located within 28 feet of a property line, *should/shall* vary the setback at least 4 feet.
- d. A flat roof, or the ridge of a sloping roof, for a medium density residential building *should/shall* not exceed a horizontal length of 100 feet without providing a difference in elevation of at least 4 feet.
- e. Medium density residential buildings *should/shall* incorporate a porch or recessed entry for each ground level dwelling unit. Covered porches and entries should average at least 30 feet square per unit, with no dimension less than 6 feet.
- f. All habitable rooms, except bath rooms, facing a required front yard *should/shall* incorporate windows.
- g. Stair cases providing access above the first floor level *should/shall* not be visible from a street.

2. Building Materials, Texture and Color.

- a. The exterior finish for at least 90 percent of the facade *should/shall* be:

- 1) Either siding, brick or stucco. Plain concrete, corrugated metal, plywood and sheet press board *should/shall* not be used as exterior finish material; and
  - 2) Either white, tinted with a minimum of 10 parts per 100 of white, or shaded with a minimum of 10 parts per 100 of black or brown. Fluorescent, “day-glo,” or any similar bright color *should/shall* not be used on the facade.
- b. The roofing material for medium density dwellings *should/shall* be either composition shingles; clay or concrete tile; metal; or cedar shingles or shakes. Composition shingles *should/shall* be architectural style with a certified performance of at least 25 years.
3. Pedestrian Circulation.
- a. Connection with Buildings and Streets. The internal pedestrian system in medium density residential developments *should/shall* connect to other areas of the site, to other building entrances and to adjacent streets.
  - b. When a residential building is sited within 24 feet of a street right of way, the building *should/shall* contain entrances directly accessible from the street.
4. Parking. Fifty percent of the required parking *should/shall* be covered by garages.
5. Buffer Wall. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height, *should/shall* be constructed on the perimeter property line of the development where the abutting use is commercial or industrial and no comparable buffer exists.
6. Sidewalk Location and Street Trees. Sidewalks *should/shall* be located at the property line along streets with street trees, **Section 3.106**. . [Section 3.107.05.C as amended by Ordinance No. 2383, §47, passed March 16, 2005.]

**3.107.06**      **Guidelines and Standards for Non-Residential Structures in RS, R1S, RM, CO, CG and P/SP Zones**

A. Applicability.

The following design guidelines shall be applicable to all non-residential structures and buildings in the RS, R1S, RM, CO, CG and P zones.

B. Architectural Design Guidelines.

1. Mass & Bulk Articulation Guidelines.

- a. Building facades visible from streets and public parking areas **should** be articulated in order to avoid the appearance of box-like structures with unbroken wall surfaces.
- b. The appearance of exterior walls **should** be enhanced by incorporating three dimensional design features, including the following:
  - 1) Public doorways and/or passage ways through the building.
  - 2) Wall offsets and/or projections.
  - 3) Variation in building materials and/or textures.
  - 4) Arcades, awnings, canopies and/or porches.

2. Materials and Textures Guidelines.

- a. Building exteriors **should** exhibit finishes and textures that reduce the visual monotony of bulky structures and large structural spaces; enhance visual interest of wall surfaces and harmonize with the structural design.
- b. The appearance of exterior surfaces **should** be enhanced by incorporating the following:
  - 1) At least 30% of the wall surface abutting a street **should** be glass.
  - 2) All walls visible from a street or public parking area **should** be surfaced with wood, brick, stone, designer block, or stucco or with siding that has the appearance of wood lap siding.
  - 3) The use of plain concrete, plain concrete block, corrugated metal, plywood, T-111 and sheet composite siding as exterior finish materials for walls visible from a street or parking area **should** be avoided.
  - 4) The color of at least 90 percent of the wall, roof and awning surface visible from a street or public parking area **should** be an “earth tone” color containing 10 parts or more of

brown or a “tinted” color containing 10 parts or more white. Fluorescent, “day-glo,” or any similar bright color ***should not*** be used on the building exterior.

3. Multi-planed Roof Guidelines.

- a. The roof line at the top of a structure ***should*** establish a distinctive top to the building.
- b. The roof line ***should not*** be flat or hold the same roof line over extended distances. Rather the roof line ***should*** incorporate variations, such as:
  - 1) Offsets and/or jogs in the plane of the roof.
  - 2) Changes in the height of the exterior wall for flat roof buildings, including parapet walls with variations in elevation and/or cornices.

4. Roof Mounted Equipment Guidelines. All roof mounted equipment, EXCEPT solar collectors, ***should*** be screened from view from streets abutting the building site by:

- a. Locating roof mounted equipment below the highest vertical element of the building; or
- b. Screening roof top equipment using materials of the same character as the structure’s basic materials.

5. Weather Protection Guidelines. All building faces abutting a street or a public parking area ***should*** provide weather protection for pedestrians. Features to provide this protection should include:

- a. A continuous walkway at least 8 feet wide along the face of the building utilizing a roof overhang, arcade, awnings and/or canopies.
- b. Awnings and canopies that incorporate the following design features:
  - 1) Angled or curved surfaces facing a street or parking area.
  - 2) A covering of canvas, treated canvas, awning fabric, or matte finish vinyl.
  - 3) A constant color and pattern scheme for all buildings within the same development.

- 4) No internal back lighting.
6. Landscaping and Screening Guidelines. The landscaping required by the standards of the **WDO** *should* be augmented to address site specific visual impacts of abutting uses and the visual character of the surrounding area.
7. Design Character Guidelines. Standardized or characteristic corporate and franchise design elements *should* be refined to reduce domination of the visual environment by corporate icons.
8. Buffer Wall. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height:
  - a. *Should* be constructed on the perimeter property line of non-residential development to mitigate adverse visual, noise and/or light impacts on the abutting use when no comparable buffer exists, and
  - b. *Shall* be constructed where the standards of the underlying zone require such a wall for a non-residential use in, or abutting, a RS, R1S, or RM zoning district.
9. Sidewalk Location and Street Trees. Sidewalks *should* be located at the property line along streets with street trees, **Section 3.106**.
10. Solar Access Protection. Obstruction of existing solar collectors on abutting properties by site development *should* be mitigated.
- C. Site and Building Access Guidelines.
  1. Access to and from the site and circulation within the site *should* separate facilities for cars, trucks and transit from those for bicycles and pedestrians.
  2. Site access in compliance with **Section 3.104** *should* be augmented by the following considerations:
    - a. Vehicle Access.
      - 1) Vehicle access points *should* be identified by accentuated landscaped areas, by entrance throats designed to control access from abutting parking and by monument type entrance signs.
      - 2) New parking lots abutting major streets *should* connect internally with the parking lots of abutting commercial uses



or land zoned for commercial use.

b. Pedestrian Access and Circulation.

- 1) The buildings ***should*** be linked to the sidewalks on abutting streets by internal pedestrian ways. Such pedestrian ways should be either raised or delineated by distinctive pavers.
- 2) Parking areas ***should*** be designed in multiples of no more than 50 spaces separated by landscaped buffers or raised pedestrian ways in order to minimize negative visual impacts associated with expansive parking.

D. Building Location Guidelines. [Section 3.107.06.D as amended by Ordinance No. 2383, §48, passed March 16, 2005.]

1. Within the prescribed setbacks, building location and orientation ***should*** compliment abutting uses and development patterns.
2. The maximum yard abutting a street should be 150 feet.

E. Parking Location Guidelines.

Off street parking between the architectural front of a building and the setback line abutting street ***should*** be limited to a depth of not more than 130 feet.

F. Design Standards.

1. Outdoor Storage Standards. Outdoor storage, when permitted, ***shall*** be screened from the view of abutting streets by a solid brick or architectural block wall not less than 6, nor more than 9 feet in height.
2. Outdoor Lighting Standards. All outdoor lighting ***shall*** be designed so that:
  - a. Parking areas are evenly illuminated at ground level at one foot candle;
  - b. Entrance and loading areas are illuminated at ground level of two foot candles;
  - c. Illumination does not shine or reflect into any adjacent residentially zoned or used property; and
  - d. Lighting does not cast a glare onto moving vehicles on any public street.

### **3.107.07**      **Design Guidelines and Standards for the DDC and NNC Zones**

[Section 3.107.07 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

#### A.      Applicability and Procedure.

The following guidelines and standards shall be applicable to the Downtown Development and Conservation (DDC) and Nodal Neighborhood Commercial (NNC) zones. The Woodburn Downtown Association (WDA) shall be notified as an interested party in conjunction with design review within the DDC zone.

#### B.      Design Guidelines for New Development.

1.      Site Design Guidelines. All new development *should* comply with the following site design guidelines.
  - a.      Building placement. Buildings *should* occupy a minimum of 50 percent of all street frontages along public streets. Buildings should be located at public street intersections.
  - b.      Building setback. The minimum setback from a public street right of way may be 0 feet, the maximum building setback *should* be 10 feet.
  - c.      Front setback and setback abutting a street design. Landscaping, an arcade, or a hard-surfaced expansion of the pedestrian path *should* be provided between a structure and a public street.
    - 1)      Setbacks abutting a street *should* be 5 feet in depth or equal to the building setback, whichever is greater. The setback *should* be landscaped at a planting density of five (5) planting units per 20 square feet to the street tree standards of **Table 3.1.5**.
    - 2)      Setbacks abutting an alleyway *should* be landscaped to the street tree standards of **Section 3.106.03.A.1**.
    - 3)      Hard-surfaced areas *should* be constructed with scored concrete or modular paving material. Benches and other street furnishings *shall* be encouraged.
  - d.      Walkway connection to building entrances. A walkway connection *should* connect a building entrance and a public street. This walkway *should* be at least six (6) feet wide and be paved with scored concrete or modular paving materials. Building entrances at corners near a public street intersection *shall* be

encouraged.

- e. Parking location and landscape design. Parking for buildings or phases adjacent to public street rights of way ***should*** be located to the side or rear of newly constructed buildings. When located abutting a street, off street parking ***should*** be limited to 50 percent of the street frontage. Setbacks abutting a street ***should*** be 5 feet in depth or equal to the building setback, whichever is greater. The setback ***should*** be landscaped at a planting density of five (5) planting units per 20 square feet to the street tree standards of ***Section 3.106.03.A.1.***
- f. Interior side and rear yards setbacks ***should*** be landscaped to the street tree standards of ***Section 3.106.03.A.1.b.***
- g. Any open area not used for building space ***should*** be landscaped in compliance with ***WDO*** standards and guidelines.

2. New Building Architectural Design Guidelines and Standards.

a. Applicability.

- 1) All non-residential buildings shall comply with the following design guidelines (read as “***should***”).
- 2) At the time of application, the applicant shall choose whether the review of new residential buildings shall be conducted as a Type I review following the procedures of ***Section 5.101.01*** or as a Type II or III review following the procedures of ***Section 5.102.02*** or ***5.103.02***, depending on floor area.
  - a) For a Type I review, the criteria of ***Section 3.107.04.B*** shall be read as “***shall***” and shall be applied as standards.
  - b) For a Type II or III review, the criteria ***Section 3.107.04.B*** shall be read as “***should***” and shall be applied as guidelines.

b. Architectural Design Guidelines and Standards.

- 1) Ground floor window. All street-facing building elevations that are set back 10 feet or less from a public street ***should*** include a minimum of 50 percent of the ground floor wall area with windows, display areas or doorway openings.

The ground floor wall area **shall** be measured from three feet above grade to nine feet above grade the entire width of the street-facing elevation. The ground floor window requirement **should** be met within the ground floor wall area and for glass doorway openings to the ground level. Up to 50 percent of the required ground floor window area on a particular street-facing building elevation **may** be met on an adjoining building elevation when the adjoining elevation is also street-facing and setback 10 feet or less.

- 2) Building facades. No building facade **should/shall** extend for more than 300 feet without a pedestrian connection between or through the building. Facades that face a public street **should/shall** extend no more than 50 feet without providing at least one of the following features:
  - a) A variation in building material;
  - b) A building off-set of at least 1 foot;
  - c) A wall area that is entirely separated from other wall areas by a projection, such as an arcade; or
  - d) By other design features that reflect the building's structural system.
- 3) Weather protection. Weather protection for pedestrians, such as awnings, canopies and arcades **should/shall** be provided at building entrances. Weather protection **shall** be encouraged along building frontages abutting a public sidewalk or a hard-surfaced expansion of a sidewalk, and along building frontages between a building entrance and a public street or access way. Awnings and canopies **should/shall not** be back lit.
- 4) Building materials. Corrugated metal, plywood, sheet press board or vinyl siding **should/shall not** be used as exterior finish material. Plain concrete block and plain concrete **should/shall not** be used as exterior finish material EXCEPT as a foundation material where the foundation material **should/shall not** be revealed for more than 2 feet.
- 5) Roofs and roof lines. EXCEPT in the case of a building entrance feature, roofs **should/shall** be designed as an extension of the primary materials used for the building and should respect the building's structural system and


architectural style. False fronts and false roofs ***should/shall not*** be used.

- 6) Roof-mounted equipment. All roof-mounted equipment ***should /shall*** be screened from view from adjacent public streets. Satellite dishes and other communication equipment ***should/shall*** be set back or positioned on a roof so that exposure from adjacent public streets is minimized. Solar heating panels ***shall/shall*** be exempt from this guideline.

C. Architectural Design Guidelines For the Exterior Alteration of Existing Buildings

1. General Scope. An application for exterior alteration of an existing building should be approved if the change or the treatment proposed is determined to be harmonious and compatible with the appearance and character of the building and should not be approved if found to be detrimental to or otherwise adversely affecting the architectural significance, integrity, historic appearance, or historic value of the building.
2. Design Guidelines. The following guidelines shall apply to the exterior alterations to existing buildings:
  - a. Retention of original construction. So far as possible, all original exterior materials and details ***should*** be preserved or reproduced to match the original.
  - b. Height. Additional stories ***may*** be added to buildings provided that:
    - 1) The added height complies with requirements of the state Building Code; and
    - 2) The added height does not alter the traditional scale and proportions of the building style; and
    - 3) The added height is visually compatible with adjacent buildings.
  - c. Bulk. Horizontal additions ***may*** be added to buildings provided that:
    - 1) The building of the addition does not exceed that which was traditional for the building style; and

- 2) The addition maintains the traditional scale and proportion of the building; and
- 3) The addition is visually compatible with adjacent buildings.
- d. Visual Integrity of Structure. The lines of columns, piers, spandrels, and other primary structural elements ***should*** be maintained so far as practicable.
- e. Scale and Proportion. The scale and proportion of altered or added building elements, the relationship of voids to solid (windows to wall) ***should*** be visually compatible with the traditional architectural character of the building.
- f. Material, Color and Texture. The materials, colors and textures used in the alteration or addition ***should*** be fully compatible with the traditional architectural character of the historic building. In general colors ***should*** be emphasized as follows: darker colors for window sashes; medium for building; and lightest for window trim and detailing.
- g. Lighting and Other Appurtenances. Exterior lighting and other appurtenances, such as walls, fences, awnings, and landscaping ***should*** be visually compatible with the traditional architectural character of the building.



[Illustration adopted by Ordinance 2463, passed January 25, 2010.]

### **3.107.08 Design Guidelines for IP, IL and SWIR Zones**

[Section 3.107.08 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

#### **A. Applicability.**

The following design guidelines shall apply to all structures and buildings in the IP, IL and SWIR zones.

#### **B. Design Guidelines.**

1. Loading.
  - a. Loading facilities *should* be located at the rear or side of structures to reduce their unsightly appearance.
  - b. Loading facilities located on the front or side of a structure, the visual impact from the abutting street *should* be mitigated by:
    - 1) Offsetting the location of the driveway entrance and the loading dock; and
    - 2) Screening the loading area with a sight obscuring fence, wall or hedge.
    - 3) Loading areas should be located on the site so that backing onto or off the street frontage is not required.
2. Outdoor Storage. Outdoor storage, when permitted, *should* be screened from the view of abutting streets by a solid brick or architectural block wall not less than 6, nor more than 9 feet in height.
3. Outdoor Lighting. All outdoor lighting *should* be designed so as not to shine or reflect into any adjacent residentially zoned or used property, and shall not cast a glare onto moving vehicles on any public street.
4. Energy Efficiency. Building location, orientation, and design *should* encourage energy conservation and solar access.
5. Building Bulk and Scale. Long blank walls abutting streets *should* be avoided. The visual impact of building and scale *should be* reduced by:
  - a. Articulating building facades;
  - b. Landscaping the area abutting building walls, including plant materials that provide vertical accents;
  - c. Tying entrances to the structure to the overall mass and composition of the building;
  - d. Minimizing the use of smooth concrete, concrete block and all types of metal siding;
  - e. Shading colors with brown or black to create earth tones or tinting colors with white to soften the appearance. Day-glow, fluorescent and other intense colors *shall* be prohibited;



- f. Screening exterior building equipment, including roof top equipment, from view; and
  - g. Altering roof lines, constructing cornices, or parapets that offset the continuous plane of large buildings and extended building lines.
- 6. Buffer Wall. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height:
  - a. ***Should*** be constructed on the perimeter property line of non-residential development to mitigate adverse visual, noise and/or light impacts on the abutting use when no comparable buffer exists; and
  - b. ***Shall*** be constructed where the standards of the underlying zone require such a wall for a non-residential use in, or abutting, a RS, R1S, or RM zoning district.
- 7. Sidewalk Location and Street Trees. Sidewalks ***should*** be located at the property line along streets with street trees, ***Section 3.106***.
- 8. Solar Access Protection. Obstruction of existing solar collectors on abutting properties by site development ***should*** be mitigated.

### **3.107.09 Architectural Walls**

#### **A. Applicability.**

This section shall apply to required architectural walls in all zoning districts. [Section 3.107.09.A as amended by Ordinance No. 2446, §31, passed on September 10, 2008.]

#### **B. Design Guidelines**

- 1. An architectural wall ***shall*** meet the texture, color, and articulation requirements on the face away from the proposed development. [Section 3.107.09.B.1 as amended by Ordinance No. 2446, §31, passed on September 10, 2008.]
- 2. An architectural wall ***should*** meet the texture, color, and articulation requirements on the face toward the proposed development. [Section 3.107.09.B.2 as amended by Ordinance No. 2446, §31, passed on September 10, 2008.]
- 3. An architectural wall ***shall*** have a minimum 3” horizontal articulation of at least 1 linear foot of the wall of intervals not more than 40 feet; and [Section 3.107.09.B.3 as amended by Ordinance No. 2446, §31, passed on September 10, 2008.]

4. An architectural wall *shall* have a minimum 6” vertical articulation of at least 1 linear foot of the wall of intervals not more than 40 feet. [Section 3.107.09.B.4 as amended by Ordinance No. 2446, §31, passed on September 10, 2008.]

C. Retaining walls

Retaining walls *should/shall* meet the texture and color requirements of architectural walls in or abutting residential districts, where the texture and color requirements apply to the visible face of the retaining wall. [Section 3.107.09.C as amended by Ordinance No. 2446, §31, passed on September 10, 2008.]

## 3.108 Partition and Subdivision Standards (See Figure 6.11)

### 3.108.01

### Requirements

All partitions and subdivisions shall comply with the standards of ORS Chapter 92 and all applicable standards of the **WDO**. The applicable requirements of the WDO include, but not limited to, the following:

A. Applicable Zoning Standards.

The standards of the underlying zone, as specified in **Section 2.1**, including the dimensional standards for lots.

B. Applicable Development Standards.

The following standards of the **WDO** shall apply to a partition and to a subdivision:

1. **Section 3.101**, Street Standards, including street names, **Section 3.101.I**.
2. **Section 3.102**, Utilities and Easements;
3. **Section 3.103**, General Lot Standards;
4. **Section 3.104**, Site Access;
5. Buffer Wall. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height, shall be constructed on the perimeter property lines of residential subdivisions where the abutting use is commercial or industrial and no comparable buffer exists; and

[Section 3.108.01.B.06 as amended by Ordinance 2423, §11, effective on July 28, 2007.]

6. Through lots. Through lots should be avoided except where essential to provide separation of residential development from major traffic arterials. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height, should be constructed on the rear property line or side property line adjacent to the arterial or collector street.

all other applicable requirements of the **WDO** as modified by **Sections 5.102.03 and 5.103.11**.

C. Applicable Procedures.

The procedures of the **WDO** shall apply to a partition or subdivision, including **Section 4.1**.

D. Application Requirements.

The application requirements of the **WDO** shall apply to a partition or subdivision including:

1. **Section 5.102.01** for a preliminary partition approval and **Section 5.103.09** for a subdivision preliminary approval,
2. **Section 5.103.05** for a subdivision phasing plan approval, and
3. **Section 5.101.05** for a partition final plat approval and **Section 5.101.09** for a subdivision final plat approval.

E. Description of Applicable Exhibits.

**Section 6.101** provides uniform guidelines regarding the exhibits necessary for a land division application.

## 3.109 Planned Unit Development Standards (See Figure 6.11)

[Section 3.109 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

### **3.109.01**      **Types of PUD's**

#### A.      Single Family Residential PUD.

A "Single Family Residential PUD" shall consist entirely of property zoned RS and/or R1S. All uses allowed (permitted, special, conditional, specific conditional and accessory) by the underlying zone shall be allowed.

#### B.      Mixed Use PUD.

A "Mixed Use PUD" shall include land zoned either RM, CO, NNC, CG, SWIR, IP or IL, and may include land zoned RS or R1S. All uses allowed (permitted, special, conditional, specific conditional and accessory) by the underlying zone shall be allowed.

### **3.109.02**      **Flexible Standards**

The design of a PUD plan may be flexible to the extent that it provides for the following design elements in compliance with stated minimum standards. The minimum standards of the **WDO** stated below shall supercede the standards of the underlying zone for a PUD, except the standards of the Nodal Overlay Districts, **Section 2.115**, shall supercede the standards of **Section 3.109.02.B, C, and F**.

#### A.      Minimum PUD Site Area.

A PUD shall comprise a minimum of 5.0 acres under single ownership or control.

#### B.      Minimum Lot Standards in an RS zone.

##### 1.      The minimum single family dwelling lot area shall be as follows:

##### a.      Without common open space:

- 1)      6,000 sq. ft. for an interior, flag or cul de sac lot; and
- 2)      8,000 sq. ft. for a corner lot

subject to the dimensional standards of **Section 2.102.06**.

##### b.      With common open space:

- 1)      5,000 sq. ft. for an interior lot, flag or cul de sac, subject to the dimensional standards of **Section 2.102.06**. EXCEPT for the following modified standards:

- a) Minimum lot width: 55 feet.
    - b) Minimum average lot depth: 90 feet; and
  - 2) 7,000 sq. ft. for a corner lot, subject to the dimensional standards of ***Section 2.102.06***. EXCEPT for the following modified standards:
    - a) Minimum lot width: 75 feet.
    - b) Minimum average lot depth: 90 feet
- 2. The minimum duplex dwelling lot size, as a Special Use, shall be as follows:
  - a. Without common open space: 12,000 sq. ft.
  - b. With common open space: 10,000 sq. ft.
- C. Residential Density Standards.
  - 1. RS or R1S zone: The maximum residential density shall be 6 dwelling units per gross acre.
  - 2. RM, CO, NNC or CG zone. The maximum residential density shall be as follows:
    - a. Multiple Family: A maximum of 16 dwelling units per net acre.
    - b. Nursing Care and Assisted Care: A maximum of 32 living units per net acre.
    - c. Manufactured Dwellings in a MDP within a RM zone: A maximum of 12 dwelling units per net acre.
- D. Common Ownership of Land and Facilities within any Zone.
  - 1. A Property (Home) Owners Association and CC&R's for maintenance shall be required when a PUD includes common land or facilities.
  - 2. Minimum Common Area.
    - a. RS or R1S zone.
      - 1) No minimum common area shall be required when

residential density is 4 dwellings or less per gross acre.

- 2) When common area is provided, a minimum ratio of 0.1 acre per acre of PUD shall be required;
  - 3) A minimum of 0.5 acres of common area shall be required when a common area is provided. The minimum width of a common area shall average 100 feet.
  - 4) Common areas shall be one or more of the following types:
    - a) Natural Areas. Natural areas shall be significant natural resources, including wetlands, creek corridors, woodlands, flood ways, meadows conserved in a virtually undeveloped state. The intent of any man-made improvements should be to enhance opportunities for viewing, studying and other measures to increase the passive enjoyment of the natural setting. Improvements may include paths, educational signs, view points.
    - b) Activity Areas. Activity areas shall be common open space designated, designed and improved for active recreational use. Improvements should accommodate and stimulate active use and may include playgrounds, swimming pools, tennis courts, bar-b-ques and picnic facilities.
    - c) Landscaped Areas. Landscaped areas are areas of common open space that are designed and improved for passive use and visual enhancement. Typical improvements include lighted paths, benches, fountains and other water features, signs identifying plant materials, and formal and informal gardens.
- b. Medium Density Residential Buildings. The applicable open space and common area requirements of **Section 3.107.05** shall apply.
  - c. All other uses. The common area requirements of the underlying zone shall apply.

E. Architectural Review.

If the hearings authority finds that the CC&R's comprehensively address the intent of all applicable factors in **Section 3.107**, the hearings authority may

approve the CC&R's to supercede City architectural design review requirements, *Section 3.107* and procedures in *Section 5.101.01*.

F. Dimensional Standards.

1. The minimum setback for a yard abutting a street in an RS or R1S zone shall be 10 feet EXCEPT that a 20-foot long by 10-foot wide parking pad shall be provided abutting each garage (or carport for a manufactured home) entrance.
2. The minimum setback for an interior rear yard in an RS, R1S or RM zone shall be 20 feet minimum.
3. Off street parking: The narrower local street standards of *Section 3.101* may be applied in compliance with the requirements for compensating common, off street parking.

G. Applicable Standards.

The following standards of the *WDO* shall apply to a PUD:

1. The underlying use zone, or zones of *Section 2.1*;
2. *Section 3.101*, Street Standards, including street names, *Section 3.101.I*;
3. *Section 3.102*, Utilities and Easements;
4. *Section 3.103*, General Lot Standards;
5. *Section 3.104*, Access;
6. Buffer Wall. A solid brick or architectural wall with anti-graffiti surface, no less than 6 feet or greater than 7 feet in height, shall be constructed on the perimeter property lines of residential subdivisions where the abutting use is commercial or industrial and no comparable buffer exists;
7. *Section 3.109.01*; and

all other applicable requirements of the *WDO* as modified by *Sections 3.109.02, 5.102.03 and 5.103.11*.

H. Applicable Procedures.

The procedures of the *WDO* shall apply to a PUD, including *Section 4.1*.

I. Application Requirements.



The application requirements of the **WDO** shall apply to a PUD, including:

1. **Section 5.103.07** for a PUD preliminary plan approval,
2. **Section 5.103.06** for a PUD design plan final approval.
3. **Section 5.103.05** for a PUD phasing plan approval, and
4. **Section 5.101.06** for a PUD final plan approval.

J. Description of Applicable Exhibits.

**Section 6.101** provides uniform guidelines regarding the exhibits necessary for a PUD application.

## 3.110 Signs

[Section 3.110 (Signs) added by Ordinance No. 2359, §3, passed on March 22, 2004.]

### **3.110.01**      **Purpose**

These regulations balance the need to protect the public safety and welfare, the need for a well, maintained and attractive community, and the need for adequate identification, communication and advertising. The regulations for signs have the following specific objectives:

- A. To ensure that signs are designed, constructed, installed and maintained according to minimum standards to safeguard life, health, property and public welfare;
- B. To allow and promote positive conditions for sign communication while at the same time avoiding nuisances to nearby properties;
- C. To reflect and support the desired character and development patterns of the various zones, overlay zones, and plan districts and promote an attractive environment;
- D. To allow for adequate and effective signs in commercial and industrial zones while preventing signs from dominating the appearance of the area;
- E. To improve pedestrian and traffic safety; and
- F. To ensure that the constitutionally guaranteed right of free speech is protected.

The regulations allow for a variety of sign types and sizes for a site. The provisions do not ensure or provide for every property or business owner's desired level of visibility for the signs. The sign standards are intended to allow signs to have adequate visibility from streets and rights-of-way that abut a site, but not necessarily to streets and rights-of-way farther away.

### **3.110.02**      **Applicability**

**Section 3.110** states the standards for the number, size, placement, and physical characteristics of signs. This section applies to signs in all zoning districts within the City of Woodburn. Other regulations in the City Code may also apply to signs.

No sign shall be placed or constructed on any property within the City of Woodburn that is not in compliance with **Section 3.110** or other applicable provisions of the WDO. Proposals for signs where the code is silent, or where the rules of **Section 3.110** do not provide a basis for concluding that the sign is allowed, are prohibited.

### **3.110.03**      **Definitions**

Words used in **Section 3.110** shall have their normal dictionary meaning unless they are listed in **Section 3.110.03** below or in **Section 1.102**. Words listed in **Section 3.110.03** have the specific meaning stated or referenced, unless the context clearly indicates another meaning.

Area of sign: Sign area is measured by drawing no more than four straight lines around and enclosing each cabinet or sign display surface; these shall be summed and then totaled to determine total area. No more than three cabinets or sign display surfaces or any combination thereof may be used to calculate the total sign area on any freestanding sign or for each tenant's signage on a building wall. The measurable area shall not include embellishments such as pole covers, decorative roofing, foundation or supports provided there is no written advertising copy, symbols or logos on such embellishments. The area of a sign shall include any symbol, material, lighting, or color forming an integral part of the background of the display or used to differentiate the sign from the backdrop or structure against which it is placed.

Sign area includes only one side of a multi-sided sign, regardless of the presence of sign copy on both or all sides. Where a sign is of a three dimensional, round or irregular solid shape, the largest cross section shall be used in a flat projection for the purpose of determining sign area.

The areas of all signs in existence at the time of enactment of this ordinance, whether conforming or nonconforming, shall be counted in determining permitted sign area.

Awning: A shelter projecting from, and supported by, the exterior wall of a building on a supporting framework. The awning may be constructed of rigid or non-rigid materials.

Bench: A seat located upon or adjacent to public property for the use of a combination of passersby or persons awaiting transportation.

Boundaries of the Site: The area inside the legal lot lines of a site and does not include any property in the public right of way.

Building Code: The most current edition of the Oregon State Structural Specialty Code.

Building Frontage: Building elevations that front on a public street, alley or parking lot. Building frontage shall be measured as the length of a straight line extending horizontally between the exterior building walls of a single tenant building or the midpoint of the separation walls between individual tenant spaces in a complex.

Canopy: A permanent unenclosed roof structure for the purpose of providing shelter to patrons in automobiles.

Complex: Any group of two or more buildings, or individual businesses within a single building provided at least two of the businesses have separate exterior entrances, on a site that is planned and developed to function as a unit and which has common on-site

parking, circulation and access. A complex may consist of multiple lots or parcels that may or may not be under common ownership.

Director: Woodburn Director of Community Development or his/her designated representative.

Display Surface: The area made available by the sign structure for the purpose of displaying a message. The display surface includes the area of the message and the background.

Eave: The overhanging lower edge of a roof.

Glare: Illumination of a sign that either directly, or indirectly from reflection, causes illumination on other properties or right of way in excess of a measurement of 0.5 foot candles of light measured at the property line.

Height: Height is measured from the lowest point of the grade below the sign (excluding artificial berm) to the topmost point of the sign.

Marquee: A permanent roofed structure attached to and supported by a building, and projecting out from a building wall, or over public access, but not including a canopy or awning.

Premises: The land and buildings contained within the boundaries of a single tenant site or complex.

Property Owner or Lessee: An individual, corporation, partnership, or other legal entity shown on county records as the owner or contract purchaser of the property, or is named as the lessee in a lease agreement regarding the property.

Sign: Materials placed or constructed, or light projected, that conveys a message or image or is used to inform or attract the attention of the public. Some examples of “signs” are materials or lights meeting the definition of the preceding sentence and which are commonly referred to as signs, placards, A-boards, posters, billboards, murals, diagrams, banners, flags, or projected slides, images or holograms. The scope of the term “sign” does not depend on the content of the message or image conveyed. Specific definitions for signs regulated in **Section 3.110** include the following:

A-Frame Sign: A double faced temporary sign constructed with an A-shaped frame, composed of two sign boards attached at the top and separate at the bottom, not permanently attached to the ground, but secured to the ground or sufficiently weighted to prevent the sign from being blown from its location or easily moved.

Awning Sign: A sign attached to or incorporated into an awning or an awning that is internally illuminated.

Balloon: An inflatable device less than 36 inches in diameter and anchored by some means to a structure or the ground.

Banner Sign: A sign made of fabric or other non-rigid material with no enclosing framework.

Bench Sign: A sign on an outdoor bench.

Blimp: An inflatable device 36 inches or greater in diameter and anchored by some means to a structure or the ground.

Changing Image Sign: Any sign, display, device, or portions thereof which is designed to have the capability of movement or give the semblance of movement of the whole or any part of the sign or that displays any artificial light which is not maintained stationary or constant in intensity and color at all times when such signs are in use or through some other automated method, results in movement, the appearance of movement or change of sign image or text. Such signs include but are not limited to electronic signs including LED, LCD, video or other automatic changeable display, rotating and revolving signs, readerboard signs, flashing signs, and wind driven signs including flags, pennants, and streamers.

Directory: A sign located in a complex that lists tenants and corresponding addresses located within the complex.

Externally Illuminated Sign: A sign where the light source is separate from the sign and is directed so as to shine on the exterior of the sign.

Flag: A sign made of fabric or other similar non-rigid material supported or anchored along only one edge or supported or anchored at only two corners.

Flashing Sign: A sign incorporating intermittent electrical impulses to a source of illumination or revolving in a manner which creates the illusion of flashing or which changes colors or intensity of illumination at intervals of more than once in any 60 second period.

Freestanding Sign: A sign wholly supported by a sign structure in the ground (e.g., monument signs, pole signs).

Historical Marker: A plaque or sign erected and maintained on property, a building, or structure by an organization that is recognized for routinely identifying sites, buildings, or structures of historical value.

Internally Illuminated Sign: A sign where the light source is contained within the sign and is directed so as to shine on the interior of the sign.

Lawn Sign: A temporary freestanding sign made of lightweight materials such as cardboard or vinyl that is supported by a frame, pole, or other support structure placed directly in the ground without foundation or other anchor.

Menu Board: A sign placed adjacent to a designated drive-thru lane of a drive-thru service establishment.

Monument Sign: A low profile freestanding sign that is placed on a solid base that extends a minimum of one-foot above the ground and extends at least 75 percent of the length and width of the sign. The aboveground portion of the base is considered part of the total allowable height of a monument sign.

Off-Premises Sign: A sign designed, intended or used to advertise, inform or attract the attention of the public as to:

- a. Goods, products or services which are not sold, manufactured or distributed on or from the premises on which the sign is located;
- b. Facilities not located on the premises on which the sign is located; or
- c. Activities not conducted on the premises on which the sign is located.

Pennant: A lightweight plastic, fabric, or other material, whether or not containing a message of any kind, suspended from a rope, wire, or string, usually in series, designed to move in the wind.

Permanent Sign: Any sign other than a temporary sign.

Pole Sign: A freestanding sign which exceeds eight feet in height.

Portable Sign: A sign that is not affixed to a structure or the ground in a permanent manner and that may be moved easily from place to place.

Projecting Sign: A sign, other than a wall sign, that projects from, and is supported by a roof or wall of a building or structure and is generally at right angles to the building.

Readerboard Sign, Electronic Changeable Copy: A permanent sign on which copy can be changed electronically by using patterns of lights that may be changed at intervals not exceeding one change in copy or display, or intensity or color of lighting in any 60 second period.

Readerboard Sign, Mechanical Changeable Copy: A permanent sign on which copy can be changed manually in the field.

Roof sign: Any sign erected upon or extending above or over the eave or roof of any building or structure. A sign erected upon a roof, which does not vary more than 20 degrees from vertical shall be regulated as a wall sign.

Subdivision Sign: A sign located on land in a recorded subdivision containing 10 lots or more.

Suspended Sign: A sign suspended from the underside of a canopy, awning, arcade, marquee, or other roofed open structure and oriented to pedestrian traffic.

Temporary Sign: A sign that is not permanently affixed or attached to a building, structure, or the ground. Temporary signs include, but are not limited to A-frames, banners, flags, pennants, balloons, blimps, streamers, lawn signs, and portable signs.

Unsafe sign: A sign constituting a hazard to safety or public welfare by reason of inadequate maintenance, dilapidation, obsolescence, disaster, damage, abandonment or inability to meet lateral and/or vertical loads as determined by the City of Woodburn Building Official.

Wall Sign: Any sign attached to or erected against the wall of a building or structure or attached to or erected against a roof which does not vary more than 20 degrees from vertical, with the exposed face of the sign in a plane parallel to the plane of the wall or roof and which does not project more than 18 inches from the wall or roof.

Window Sign: A sign that is placed inside a building (such as placement on a windowsill) within six inches of a window or attached to the inside of a window.

Sign Maintenance: Normal care needed to keep a sign functional such as painting, cleaning, oiling, and changing light bulbs. Does not include an alteration to the sign.

Sign Repair: Fixing or replacement of broken or worn parts. Replacement includes comparable materials only. Repairs may be made with the sign in position or with the sign removed.

Sign Structure: The structure, supports, uprights, braces, framework and display surfaces of a sign.

Single Tenant Site: A development that is not a complex.

Street Frontage: The portion of a site that abuts a public street.

Structural Alteration: Modification of a sign or sign structure that affects size, shape, height, or sign location; changes in structural materials; or replacement of electrical components with other than comparable materials. The replacement of wood parts with

metal parts, the replacement of incandescent bulbs with light emitting diodes (LED), or the addition of electronic elements to a non-electrified sign are examples of structural alterations. Structural alteration does not include ordinary maintenance or repair, repainting an existing sign surface, including changes of message or image, exchanging painted and pasted or glued materials on painted wall signs, or exchanging display panels of a sign through release and closing of clips or other brackets.

Vision Clearance Area: See **Section 3.103.10**.

#### **3.110.04**      **Sign Permit Required**

- A. A sign permit is required to erect, replace, construct, relocate, or alter a sign, unless such sign or action is exempt under **Section 3.110.11**. The Director shall issue a sign permit if the applicant files an application, filing fee, and plans which demonstrate full compliance with all provisions of **Section 3.110** and other applicable city regulations.
- B. Sign maintenance, sign repair and changing of a sign display surface is allowed without obtaining a sign permit so long as structural alterations are not made and the sign display surface is not increased in size.
- C. A building permit shall be obtained for any signs where the sign installation is regulated under the Building Code.
- D. An electrical permit shall be obtained for all illuminated signs, subject to the provisions of the State Electrical Code.
- E. The Director may require application for sign permits for any existing signage on the premises if no existing permits previously had been approved.

#### **3.110.05 Sign Permit Approval Process**

- A. Initiation of an Application.

An application for a sign permit may only be initiated by the property owner or lessee with the authorization of the property owner.

- B. Application Form.

An application for a sign permit shall be made on forms as prescribed by the Director. Such an application shall be filed with the Planning Department. The application shall be accompanied by any fees as specified by City Council resolution. A sign permit application shall include the following information:

- 1. Sign location



2. Business name and business owner's name, address and phone number
3. Property owner's name, address, and phone number
4. Sign company name, address, and phone number
5. Contact person and phone number
6. Type of sign
7. Illustration of the proposed sign(s), existing signs and location including the following items:
  - a. Site plan and/or building elevation plans drawn to scale and dimensioned showing:
    - 1) Existing structures
    - 2) Driveways
    - 3) Streets and right of ways
    - 4) Existing signs
    - 5) Proposed sign
    - 6) Existing property lines
  - b. Proposed sign drawn to scale and dimensioned, showing (as applicable):
    - 1) Total height from the ground
    - 2) Width
    - 3) Depth
    - 4) Area of sign in square feet
    - 5) Size and style of letters
    - 6) Colors
    - 7) Type of illumination
    - 8) Materials
    - 9) Drawing of the sign on the building elevation with dimensions of the building wall
8. Signatures of the property owner or lessee. If a lessee signs, property owner authorization shall be provided.

C. Process.

1. Permits for new signs or modification of existing signs shall be processed as follows:

- a. Signs subject to a sign permit, except signs listed under **Section 3.110.05.C.1.b** below, shall be processed, using the procedures, standards, and application requirements, provided in **Section 3.110**.
  - b. Pole signs and the placement of neon tubing on the exterior of a building shall be processed as a Type II land use application, using the application requirements of **Section 5.102.02**, except additional exhibits required under **Section 5.102.02.B** are limited to sign information required under **Section 3.110.05.B**, and using the standards and design guidelines of **Section 3.110** as approval criteria. A Type II sign application may be processed concurrently with a separate Type II or III development application.
2. After a sign application is received and deemed complete by the Director, the Director shall provide the applicant with a written decision granting or denying the application for a sign permit. For non-compliant applications, the decision shall explain the reasons why the application was denied. A decision to deny shall be mailed to the address on the application by regular mail.
  3. The Director's decision under **Section 3.110.05.C.1.a** is final for purposes of appeal on the date that it is mailed or otherwise provided to the applicant, whichever occurs first. The Director's decision is not appealable locally, and is the final decision of the City.
  4. A decision under **Section 3.110.05.C.1.b** may be appealed following the appeal procedure for a Type II application.

### **3.110.06**      **Expiration of Approval**

Sign permit approval shall expire 180 days from the date of approval if a building permit is not issued, if required, or substantial construction of the sign has not commenced if a building permit is not required. Signs that require the issuance of a building permit shall be constructed within the time period established by the building permit. Expiration of a Type II sign application approval shall comply with **Section 4.102.03**.

### **3.110.07**      **Inspections**

#### **A. Construction Inspection.**

General requirements for the inspection of signs during and following construction shall be as follows:

1. All construction work for which a permit is required shall be subject to an inspection by the Building Official in accordance with the Building Code

and **Section 3.110**:

- a. A survey of the lot or parcel or proposed location for sign erection may be required by the Building Official to verify compliance of the structure with approved plans.
  - b. Neither the Building Official nor the City of Woodburn shall be liable for expense or other obligations entailed in the removal or replacement of any material required to allow inspection.
2. It shall be the duty of the person doing the work authorized by a permit to notify the Building Official that such work is ready for inspection. The Building Official may require that every request for inspection be filed at least one working day before such inspection is desired.
  3. The applicant shall request a final inspection when all work is completed. This inspection shall cover all items required by the Building Official under State law or City ordinances such as the locations, landscaping if required, and general compliance with the approved plans and requirements of **Section 3.110**.
- B. Director's Inspection.

The Director is authorized and directed to enforce all of the provisions of **Section 3.110**.

1. All signs for which permits are required shall be inspected by the Director.
2. Upon presentation of proper credentials, the Director may enter at reasonable times any building, structure, or premises in the City to perform any duty imposed upon the position by **Section 3.110**.

#### **3.110.08 General Requirements**

- A. Landscaping: Permanent freestanding signs shall be located in a planted landscaped area which is of a size equal to at least twice the sign area. The landscaped area shall be improved and maintained subject to the landscaping standards of **Section 3.106**.
- B. Location: No portion of a freestanding sign shall be located less than five feet from any boundary property line.

## **Design Guidelines for Type II Sign Applications**

The following design guidelines shall be applicable to Type II sign applications:

- A. Each sign should be designed to be consistent with the architectural style of the main building or buildings upon the site.
- B. Signs located upon a site with only one main building should be designed to incorporate at least one of the predominately visual elements of the building, such as type of construction materials or color. Each sign located upon a site with more than one building, such as a complex or other nonresidential development, should be designed to incorporate at least one predominate visual design element common to all such buildings or a majority of the buildings.
- C. Multiple signs located within a single development, or complex should have a common design established through the use of similar sign colors and materials, sign supports, method of illumination, sign cabinet or other configuration of sign area, shape of sign and components, and letter style and size.
- D. Sign colors and materials should be consistent with the color scheme and materials used in the development. The use of fluorescent colors or similar highly reflective materials should be discouraged.
- E. Supporting elements of pole signs should be covered consistent with subsection (D) above. The total width of pole covers should be at least 30 percent of the sign display width.
- F. Freestanding signs should appear to be a single unit and should not have separate or detached cabinets or readerboards that are not architecturally integrated into the primary sign display area.

**3.110.10 Sign Maintenance.**

Signs and sign structures together with their supports, braces, guys, anchors and electrical components must be maintained in a proper state of repair. The Director may order the removal of any sign or sign structure that is not maintained in accordance with **Section 3.110** or the Building Code. Signs and sign structures that are dangerous must be taken down and removed or made safe, as the Director deems necessary.

### **3.110.11      Exemptions.**

The following are exempt from application, permit and fee requirements of **Section 3.110**, but are subject to other applicable portions of **Section 3.110** and the City Code and may require building and electrical permits:

- A. Window signs provided such signs shall not obscure more than 50 percent of the total window area of a building face.
- B. Flags provided that not more than two flags shall be permitted on a lot or parcel in any zone. The area of an individual flag shall not exceed 40 square feet. Flag mounts or poles shall not exceed 40 feet in height.
- C. Temporary freestanding signs in non-residential zones provided that not more than two such signs shall be permitted on a single tenant site or complex. The total area of such signs on a single tenant site or complex shall not exceed 24 square feet and the height shall not exceed eight feet. Such signs shall not be placed in the public right of way or a vision clearance area.
- D. Wall signs on residential dwellings provided that not more than two such signs are permitted on a dwelling unit and the total area of all such signs shall not exceed three square feet.
- E. Additional Permanent Wall and Freestanding Signs. In addition to the wall and freestanding signs permitted under **Sections 3.110.14 through 3.110.18**, the following additional permanent wall and freestanding signs are permitted for all uses, except single and two family dwellings. The area of each such freestanding sign shall not exceed three square feet and a height of five feet. The area of each such wall sign shall not exceed three square feet. Not more than three such freestanding signs shall be permitted on a lot or parcel and not more than two such wall signs shall be placed on a building with a single tenant or on an individual tenant space in a multiple tenant building. A freestanding sign shall not be located within a required front yard setback or setback abutting a street.
- F. Menu boards in conjunction with a drive-thru service establishment. Not more than two menu boards shall be permitted for a drive-thru service establishment. Menu boards shall be located adjacent to the driveway leading to a drive through window and shall not exceed seven feet in height and eight feet in width.
- G. Lawn signs and A-frame signs in RS, RSN, RM, and RMN zones provided that not more than two such signs are located on a lot or parcel and the total area for all such signs does not exceed eight square feet. Such signs shall not exceed seven feet in height and shall not be placed in the public right of way or vision clearance areas.
- H. Lawn signs and A-frame signs in the R1S zone provided that:

1. The signs are established by the property owner or property owner's agent,
  2. Not more than two such signs are located on a lot or in the public right-of-way abutting the lot,
  3. No sign may be established in the right-of-way of State Highway 214, Newberg Highway,
  4. The total area for all such signs does not exceed eight square feet,
  5. Lawn signs shall not exceed seven feet in height,
  6. A-frame signs shall not exceed three feet in height,
  7. Signs shall not be placed in vision clearance areas (Section 3.103.10) or in adjacent rights-of-way,
  8. Signs shall not be on or overhanging a travel or on-street parking lane,
  9. Signs shall not be on or overhanging a sidewalk, and
  10. No portion of a sign shall be less than 3 feet from the back of a curb. [§H as amended by Ordinance 2465, adopted March 22, 2010.]
- I. Signs that are inside a building, except window signs, or signs that do not have a primary purpose of being legible from a public street or another property. Such signs include scoreboard signs, signs on the inside of ball field fences, signs within a stadium, and signs located within the site of a special event such as a festival or carnival.
- J. Signs required by federal, state, or city law on private property if the sign is no more than 32 square feet in area. Such signs include building addresses, handicap parking signs, designation of fire lanes, public hearing notices, and building inspection notices.
- K. Signs owned and maintained by federal or state agencies or the City of Woodburn.
- L. Signs lawfully erected in the public right of way in accordance with applicable state and local laws and regulations, including public utility signs, traffic signs and traffic control devices.
- M. Decorations and lights relating directly to federal, state, or city recognized events or holidays, provided that such decorations and lights shall be placed not more than 45 days before the holiday or event to which they pertain and shall be

removed within 15 days of the passing of the holiday or event to which they pertain.

- N. Signs on phone booths and product dispensers, such as beverage, recycling, newspaper, gasoline, and propane machines provided the total area of signage on an individual unit does not exceed three square feet.
- O. Directories for non-residential complexes with two or more buildings and multiple family residential complexes with four or more buildings. Directories shall be limited to a maximum of one per street access and shall be located a minimum of 50 feet from a street right of way. Each directory shall be limited to a maximum area of 24 square feet. Freestanding directories shall be limited to a maximum height of eight feet.
- P. Bench signs provided the total area of such signs on a bench does not exceed one square foot.

#### **3.110.12 Prohibited signs**

The following signs and advertising devices are prohibited:

- A. Any sign constructed, erected, replaced, relocated, altered, repaired, or maintained in a manner not in compliance with **Section 3.110**.
- B. A temporary sign not otherwise allowed under **Section 3.110.13** or exempt under **Section 3.110.11**.
- C. Off-premises sign.
- D. A sign located on the roof of any building or structure.
- E. A sign located in the vision clearance area established by **Section 3.103.10**.
- F. A sign located in the special setback area established by **Section 3.103.05**.
- G. A sign in public right of ways except awning, projecting, wall, and suspended signs projecting over a public right of way in conformity with **Section 3.110**, or unless specifically exempt under **Section 3.110.11**.
- H. Internally illuminated awning sign.
- I. A changing image sign not otherwise allowed under **Sections 3.110.13 through 3.110.18** or exempt under **Section 3.110.11**.
- J. A permanent sign located on an undeveloped lot or parcel, except subdivision signs.

- K. A beacon light, searchlight, strobe light or a sign containing such lights.
- L. Neon tubing on the exterior of a building unless approved as part of a Type II sign application.
- M. A sign that imitates or resembles official traffic lights, signs or signals or a sign that interferes with the effectiveness of any official traffic light, sign or signal.
- N. An illuminated sign that produces glare. Glare may not directly, or indirectly from reflection, cause illumination on other properties or right of way in excess of a measurement of 0.5-foot candles of light measured at the property line.
- O. A sign required to have been issued a sign permit, but for which no sign permit has been issued.
- P. A sign with visible incandescent bulbs or fluorescent tubes or a sign with a visible direct source of illumination, except neon, and not otherwise allowed under **Section 3.110.13** or exempt under **Section 3.110.11**.
- Q. A sign that is unsafe or constitutes a public nuisance.
- R. A sign that incorporates flames or emits sounds or odors.
- S. A sign supported in whole or in part by cables or guy wires or that has cables or guy wires extending to or from it.
- T. Blimp.

### **3.110.13 Temporary Sign Permit**

- A. Certain temporary signs that are not otherwise exempt under **Section 3.110.11** may be approved for a limited period of time as a means of drawing attention to special events such as grand openings, carnivals, charitable events, seasonable openings, special promotions, etc. Approval of a Temporary Sign Permit application shall be required prior to placement of such signs.
- B. Process.
  - 1. Temporary Sign Permits shall be processed using the procedures, criteria, and application requirements of **Section 3.110.14**.
  - 2. After a Temporary Sign Permit application is received and deemed complete by the Director, the Director shall provide the applicant with a written decision granting or denying the application for a Temporary Sign Permit. For non-compliant applications, the decision shall explain the



reasons why the application was denied. A decision to deny shall be mailed to the address on the application by regular mail.

3. The Director's decision under **Section 3.110.14** is final for purposes of appeal on the date that it is mailed or otherwise provided to the applicant, whichever occurs first. The Director's decision is not appealable locally, and is the final decision of the City.

- C. **Application Requirements.** An application for a Temporary Sign Permit shall be made on forms as prescribed by the Director. Such an application shall be filed with the Planning Department. The application shall be accompanied by any fees as specified by City Council resolution. The following information is required for submittal of a Temporary Sign Permit application:

A completed Temporary Sign Permit application form. The application form shall include the following:

11. Address of location where sign(s) is to be placed.
12. Business name; property owner or tenant name, mailing address, and phone number.
13. Contact person and phone number.
14. Type of signs and total area of signs in square feet.
15. Signatures of the applicant and property owner or tenant.
16. Identification of the location where sign(s) is to be placed as a single tenant site, an individual tenant in a complex, a complex with less than 20 tenants, or a complex with 20 or more tenants.

- D. **Criteria.** The Director shall approve an application for a Temporary Sign Permit only if it complies with the following approval criteria:

1. The following types of temporary signs are permitted with a Temporary Sign Permit: A-frames, banners, flags, pennants, balloons, strings of lights, streamers, and lawn signs. Temporary sign types not specified above including other types of portable signs and blimps are not permitted with a Temporary Sign Permit.
2. A Temporary Sign Permit shall not be granted for single and two family residential uses or for an individual tenant in a multiple family residential complex.
3. An owner or tenant of an individual property, a tenant in a complex, and

the owner of a complex may obtain Temporary Sign Permits. In a complex, a tenant shall be limited to placing only banners and flags on the exterior walls and windows of its tenant space.

4. Temporary Sign Permits shall be limited to a specified number of 15-day periods per calendar year. Said periods may run consecutively; however, unused days from one period shall not be added to another period. The number of Temporary Sign Permits allowed shall be as follows:
  - a. A single tenant site or an individual tenant in a complex shall be permitted a maximum of four Temporary Sign Permits per calendar year.
  - b. A complex consisting of less than 20 tenant spaces shall be permitted a maximum of four Temporary Sign Permits per calendar year, in addition to Temporary Sign Permits allowed for individual tenants.
  - c. A complex consisting of 20 or more tenant spaces shall be permitted a maximum of six Temporary Sign Permits per calendar year, in addition to Temporary Sign Permits allowed for individual tenants.
5. No temporary sign shall extend into or over public right of way or vision clearance areas, as governed by **Section 3.103.10**.
6. No temporary sign shall obstruct on-site pedestrian or vehicular access or circulation.
7. The total area of all temporary signs permitted by a Temporary Sign Permit shall not exceed 100 square feet for an individual tenant in a complex, 200 square feet for a single tenant site or a complex with less than 20 tenant spaces, or 400 square feet for a complex consisting of 20 or more tenant spaces.

**3.110.14 Permitted Signs - Residential and Public/Semi-Public Land Use Districts (RS, RIS, RM, and P/SP)**

Signs in the RS, RIS, RM and P/SP Districts shall be subject to the following provisions and all other applicable provisions of **Section 3.110** and the **WDO**.

- A. Subdivision and Manufactured Home Park Signs. Signs located within a subdivision containing 10 lots or more or a manufactured home park containing 10 lease spaces or more shall be permitted subject to the following limitations:
  1. Type. Monument signs and signs attached to a freestanding wall are

permitted.

2. Area of signs. Each sign shall not exceed 20 square feet in area.
3. Height of sign.
  - a. Monument sign shall not exceed a height of five feet.
  - b. Sign on freestanding wall shall not project above wall.
4. Number of signs. One sign is permitted on each side of each public street entry into the development.
5. Illumination. Only externally illuminated signs are permitted and such signs shall not cause glare.

**B. Multiple Family Dwelling Signs.** Signs associated with multiple family developments containing four or more attached dwelling units shall be permitted subject to the following limitations:

1. Type of sign. Monument and wall signs are permitted.
2. Area of sign.
  - a. Wall sign shall not exceed 20 square feet in area.
  - b. Monument sign shall not exceed 20 square feet in area.
3. Height of sign. Monument sign shall not exceed a height of five feet.
4. Number of signs. Not more than one monument sign and one wall sign shall be permitted
5. Illumination. Only externally illuminated signs are permitted and such signs shall not cause glare.

**C. Non-Residential Use Signs.** Signs for non-residential uses shall be permitted subject to the following limitations:

1. Developed site containing less than three acres:
  - a. Type of Sign. Monument, wall, and mechanical changeable copy readerboard signs are permitted.
  - b. Area of sign.

- 1) Wall sign shall not exceed 20 square feet in area.
  - 2) Monument sign shall not exceed 20 square feet in area including any readerboard sign.
  - 3) Readerboard sign shall not exceed 12 square feet in area.
- c. Height of Sign. Monument sign shall not exceed five feet in height.
  - d. Number of Signs. One monument sign and one wall sign shall be permitted. Readerboard sign may only comprise part of a monument sign and shall be included in the area calculation for a monument sign.
  - e. Illumination. Only externally illuminated signs are permitted and such signs shall not cause glare.
2. Developed site containing three or more acres:
- a. Type of Sign. Monument, wall and mechanical changeable copy readerboard signs are permitted.
  - b. Area of sign.
    - 1) Wall sign shall not exceed 32 square feet in area.
    - 2) Monument sign not exceed 32 square feet in area including any readerboard sign.
    - 3) Readerboard sign shall not exceed 18 square feet in area.
  - c. Height of Sign. Monument sign shall not exceed six feet in height.
  - d. Number of Signs. One monument sign is permitted per public street frontage provided the total number of monument signs shall not exceed two signs. One wall sign is permitted on each building wall that fronts on a public street provided the total number of wall signs shall not exceed two signs. Readerboard signs may only comprise part of a monument sign and shall be included in the area calculation for a monument sign.
  - e. Illumination. Only externally illuminated signs are permitted and such signs shall not cause glare.

**3.110.15**      **Permitted Signs - Commercial Office District (CO)**

Signs in the CO District shall be subject to the following provisions and all other applicable provisions of **Section 3.110** and the **WDO**.

- A. Developed site or complex containing less than three acres.
  - 1. Type of signs. Monument and wall sign(s) are allowed.
  - 2. Area of signs.
    - a. Wall sign. No more than four percent of any building wall shall be covered by wall signs.
    - b. Monument sign. Monument sign shall not exceed 20 square feet in area.
  - 3. Height of monument sign. Monument sign shall not exceed a height of five feet.
  - 4. Number of signs.
    - a. Wall sign. Maximum of one sign per tenant. One additional sign is permitted to identify each building or complex.
    - b. Monument sign. Maximum of one sign per street frontage not to exceed a total of two signs.
  - 5. Illumination. Externally or internally illuminated signs are permitted and such signs shall not cause glare.
- B. Developed site or complex containing three acres or more:
  - 1. Type of signs. Monument and wall sign(s) are allowed.
  - 2. Area of signs.
    - a. Wall sign. No more than four percent of any building wall shall be covered by wall signs.
    - b. Monument sign. Monument sign shall not exceed 32 square feet in area.
  - 3. Height of monument sign. Monument sign shall not exceed a height of six feet.
  - 4. Number of signs.

- a. Wall sign. Maximum of one sign per tenant. One additional sign is permitted to identify each building or complex.
  - b. Monument sign. Maximum of one sign per street frontage not to exceed a total of two signs.
5. Illumination. Externally or internally illuminated signs are permitted and such signs shall not cause glare.

**3.110.16 Permitted Signs - Commercial General District (CG)**

Signs in the CG District shall be subject to the following provisions and all other applicable provisions of **Section 3.110** and the **WDO**.

A. Pole Signs.

1. Single Tenant Site.

- a. A pole sign is permitted on a street frontage that exceeds 100 lineal feet not to exceed one pole sign on a single tenant site. A pole sign shall be permitted instead of a monument sign.
- b. A pole sign on a street with less than 300 lineal feet of frontage shall not exceed 12 feet in height and 32 square feet in area.
- c. A pole sign on a street with 300 lineal feet or more but less than 600 lineal feet of frontage shall not exceed 15 feet in height and 50 square feet in area.
- d. A pole sign on a street with 600 lineal feet or more of frontage shall not exceed 20 feet in height and 100 square feet in area.

2. Complex.

- a. A pole sign is permitted on a street frontage that exceeds 100 lineal feet not to exceed one pole sign for a complex.
- b. A pole sign on a street with less than 300 lineal feet of frontage shall not exceed 15 feet in height and 50 square feet in area.
- c. A pole sign on a street with 300 lineal feet or more but less than 600 lineal feet of frontage shall not exceed 18 feet in height and 75 square feet in area.
- d. A pole sign on a street with 600 lineal feet or more of frontage shall not exceed 20 feet in height and 100 square feet in area.

B. Monument Signs.

1. One primary monument sign is permitted on a single tenant site or complex. If a pole sign is placed on a single tenant site or complex, a primary monument sign is not permitted.
2. In a complex, secondary monument signs are permitted at a ratio of one monument sign for each 300 lineal feet of street frontage on the same street not to exceed two secondary monument signs on a single street frontage and not to exceed a total of four secondary monument signs on a complex.
3. Monument signs on a street frontage with less than 300 lineal feet of frontage shall not exceed six feet in height and 32 square feet in area.
4. Monument signs on a street frontage with 300 lineal feet or more of frontage shall not exceed eight feet in height and 50 square feet in area.

C. Wall Signs.

1. Wall signs are permitted on a primary building frontage. Such signs shall not cover more than six percent of the building wall on a single tenant building or each tenant's leased wall on a multiple tenant building and shall not exceed a maximum area of 200 square feet. However, a minimum sign area of 20 square feet shall be permitted for each single tenant building or tenant in a multiple tenant building. Only one building wall shall be designated as the primary building frontage.
2. Wall signs are permitted on secondary building frontages. Such signs shall not cover more than three percent of the building wall on a single tenant building or each tenant's leased wall on a multiple tenant building and shall not exceed a maximum area of 100 square feet. However, a minimum sign area of 16 square feet is allowed for each single tenant building or tenant in a multiple tenant building.
3. Wall signs are permitted on canopies. Such signs shall be limited to no more than two sides of the canopy and shall not cover more than 15 percent of a canopy face or 50 square feet, whichever is less.

D. Readerboards.

Mechanical and electronic changeable copy readerboards are permitted. Readerboards are permitted on pole and monument signs only. Readerboards shall be integrated into the overall sign to appear as a single unit and shall not comprise more than 50 percent of the total sign display surface.

E.     Awning and Marquee Signs.

Signs on awnings and marquees are permitted as wall signs, except that internally illuminated awning signs are prohibited. Signs on awnings and marquees shall not extend above or below the awning or marquee.

F.     Projecting Signs.

One projecting sign is permitted on a single tenant site or complex. However, no projecting sign shall be permitted on a single tenant site or complex where there is a pole or monument sign. Projecting signs shall not exceed an area of 24 square feet and shall be located a minimum of eight feet above the ground. Such signs shall not project more than six feet from a building wall.

G.     Suspended Signs.

One suspended sign is permitted for each entrance to a building or tenant space. Such sign shall not exceed an area of six square feet and shall be located a minimum of eight feet above the ground. Such sign shall not project past the outer edge of the roof structure.

H.     General Standards.

1.     Pole and monument signs within the same complex shall be located a minimum of 100 feet apart.
2.     Pole signs shall be subject to approval of a Type II application pursuant to **Section 3.110.05.C.1.b.**
3.     Illumination: Externally or internally illuminated signs are permitted and such signs shall not cause glare.

**3.110.17     Permitted Signs - Downtown Development and Conservation District (DDC) and Nodal Neighborhood Commercial District (NNC)** [Section 3.110.17 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

Signs in the DDC and NNC Districts shall be subject to the following provisions and all other applicable provisions of **Section 3.110** and the **WDO**.

A.     Monument Signs.

1.     A monument sign is permitted on a single tenant site or complex.
2.     A monument sign shall not exceed five feet in height and 20 square feet in area.



B. Wall Signs.

1. Wall signs are permitted on a primary building frontage. Such signs shall not cover more than four percent of the building wall on a single tenant building or each tenant's leased wall on a multiple tenant building and shall not exceed a maximum area of 50 square feet. However, a minimum sign area of 16 square feet shall be permitted for each single tenant building or tenant in a multiple tenant building. Only one building wall shall be designated as the primary building frontage.
2. Wall signs are permitted on secondary building frontages. Such signs shall not cover more than two percent of the building wall on a single tenant building or each tenant's leased wall on a multiple tenant building and shall not exceed a maximum area of 30 square feet. However, a minimum sign area of 12 square feet is allowed for each single tenant building or tenant in a multiple tenant building.

C. Readerboards.

Mechanical and electronic changeable copy readerboards are permitted. Readerboards are permitted on monument signs only. Readerboards shall be integrated into the overall sign to appear as a single unit and shall not comprise more than 50 percent of the total sign display surface.

D. Awning and Marquee Signs.

Signs on awnings and marquees are permitted as wall signs, except that internally illuminated awning signs are prohibited. Signs on awnings and marquees shall not extend above or below the awning or marquee.

E. Projecting Signs.

One projecting sign is permitted on a single tenant site or complex for each street or alley frontage. However, no projecting sign shall be permitted on a single tenant site or complex where there is a monument sign on the same street frontage. Projecting signs shall not exceed an area of 12 square feet and shall be located a minimum of eight feet above the ground. Such signs shall not project more than four feet from a building wall.

F. Suspended Signs.

One suspended sign is permitted for each entrance to a building or tenant space. Such sign shall not exceed an area of six square feet and shall be located a minimum of eight feet above the ground. Such sign shall not project past the outer edge of the roof structure.

G. General Standards.

1. Projecting signs shall be subject to approval of a Type II application pursuant to **Section 3.110.05.C.1.b.**
2. Illumination: Externally or internally illuminated signs are permitted and such signs shall not cause glare.

**3.110.18 Permitted Signs - Industrial Districts (IP, IL, and SWIR)** [Section 3.110.18 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

Signs in the IP, IL, and SWIR Districts shall be subject to the following provisions and all other applicable provisions of **Section 3.110** and the **WDO**.

A. Monument Signs.

1. One monument sign is permitted on a single tenant site or complex.
2. In a complex, one additional monument sign is permitted if the complex has at least two street frontages that each exceed 300 lineal feet.
3. Monument signs on a street frontage with less than 300 lineal feet of frontage shall not exceed six feet in height and 32 square feet in area.
4. Monument signs on a street frontage with 300 lineal feet or more of frontage shall not exceed eight feet in height and 50 square feet in area.

B. Wall Signs.

1. Wall signs are permitted on a primary building frontage. Such signs shall not cover more than four percent of the building wall on a single tenant building or each tenant's leased wall on a multiple tenant building and shall not exceed a maximum area of 150 square feet. However, a minimum sign area of 16 square feet shall be permitted for each single tenant building or tenant in a multiple tenant building. Only one building wall shall be designated as the primary building frontage.
2. Wall signs are permitted on secondary building frontages. Such signs shall not cover more than two percent of the building wall on a single tenant building or each tenant's leased wall on a multiple tenant building and shall not exceed a maximum area of 75 square feet. However, a minimum sign area of 12 square feet is allowed for each single tenant building or tenant in a multiple tenant building.

C. Readerboards.

Mechanical and electronic changeable copy readerboards are permitted. Readerboards are permitted on monument signs only. Readerboards shall be integrated into the overall sign to appear as a single unit and shall not comprise more than 50 percent of the total sign display surface.

D.      Awning and Marquee Signs.

Signs on awnings and marquees are permitted as wall signs, except that internally illuminated awning signs are prohibited. Signs on awnings and marquees shall not extend above or below the awning or marquee.

E.      Projecting Signs.

One projecting sign is permitted on a single tenant site or complex. However, no projecting sign shall be permitted on a single tenant site or complex where there is a monument sign. Projecting signs shall not exceed an area of 20 square feet and shall be located a minimum of eight feet above the ground. Such signs shall not project more than four feet from a building wall.

F.      Suspended Signs.

One suspended sign is permitted for each entrance to a building or tenant space. Such sign shall not exceed an area of six square feet and shall be located a minimum of eight feet above the ground. Such sign shall not project past the outer edge of the roof structure.

G.      General Standards.

1.      Monument signs within the same complex shall be located a minimum of 100 feet apart.
2.      Illumination. Externally or internally illuminated signs are permitted and such signs shall not cause glare.

**3.110.19**      **Variances**

A variance may be granted from any regulation of **Section 3.110** in accordance with the provisions of **Section 5.103.11**.

**3.110.20**      **Nonconforming Signs**

- A.      Nonconforming signs are those signs lawfully established prior to the adoption of **Section 3.110** or subsequent amendment thereto or signs lawfully established on property annexed to the City, which do not conform to the requirements of **Section 3.110**. Nonconforming permanent signs may remain provided they comply with the provisions of **Section 3.110.20**. However, nonconforming

temporary signs and off-premises signs that have not been permitted by a variance shall comply with the provisions of **Section 3.110**.

B. Nonconforming permanent signs shall comply with the provisions of **Section 3.110** when one or more of the following occurs:

1. A nonconforming sign is expanded, relocated, replaced or structurally altered.
2. The use of the premises upon which the sign is located terminates for a continuous period of 180 days or more. In a complex, if an individual tenant space is vacant for a continuous period of 180 days or more, only signs attached to such tenant space shall be required to comply with the provisions of **Section 3.110**.
3. The use of the premises upon which the sign is located changes. In a complex, if the use of an individual tenant space changes, only signs attached to such tenant space shall be required to comply with the provisions of **Section 3.110**.
4. A Type II Design Review or Type III Conditional Use or Design Review land use application is approved for the premises upon which the sign is located. In a complex, if an individual tenant space is the subject of a Type II Design Review or Type III Conditional Use or Design Review land use application, only signs attached to such tenant space shall be required to comply with the provisions of **Section 3.110**.
5. A nonconforming sign is damaged, destroyed, or deteriorated by any means where the cost of repairs exceeds 50 percent of its current replacement cost as determined by the Building Official.
6. A sign permit for a conforming sign(s) is issued for the premises upon which a nonconforming sign is located. In such case, all nonconforming signs on the same premises, except signs attached to individual tenant spaces in a complex, shall comply with **Section 3.110** prior to installation of the new sign(s). In a complex, if a sign permit for a conforming sign(s) is issued for an individual tenant space upon which a nonconforming sign is attached, only signs attached to such tenant space shall be required to comply with the provisions of **Section 3.110**.

C. A nonconforming sign or sign structure may be removed for no more than 60 days to perform sign maintenance or sign repair. A nonconforming sign or sign structure removed for more than 60 days shall comply with the provisions of **Section 3.110**.

**3.110.21 Enforcement.**

The violation of any provision of **Section 3.110** is subject to the enforcement provisions contained in **Section 4.102.11**.

# 4.1 ADMINISTRATION AND PROCEDURES

## 4.101 Decision Making Procedures

### **4.101.01 Purpose**

This section provides the review and decision making procedures by which all applications relating to the use of land authorized by ORS Chapters 92, 197 and 227 are reviewed and decided, as well as legislative enactments initiated by the City Council.

### **4.101.02 Consolidated Applications**

Pursuant to ORS 227.175, any applicant may request, in writing, to consolidate zone change and permit applications needed for a single development project. Annexation applications may be consolidated with Comprehensive Plan map amendments and Zoning Map changes. Under a consolidated review, all applications shall be processed following the procedures applicable for the highest type decision requested. It is the express policy of the City that development review not be segmented into discrete parts in a manner that precludes a comprehensive review of the entire development and its cumulative impacts.

### **4.101.03 City Council May Initiate Procedures**

The City Council may initiate any type of land use action by its duly adopted motion designating the appropriate City department to complete and file the application.

### **4.101.04 Formal Pre-application Conference**

#### A. Purpose.

1. Prior to submitting an application, the applicant may schedule and attend a formal pre-application conference with City staff to discuss the proposal before submitting an application of any land use action. A formal pre-application conference is advisory in nature and shall be voluntary, unless specified as an application requirement by the **WDO**.
2. The purpose of a formal pre-application conference is to provide staff from all affected City departments with a summary of the applicant's development proposal and an opportunity for staff to provide the applicant with information on the likely impacts, limitations, requirements, approval standards, fees and other information that may affect the proposal. Following a formal pre-application conference, the Community

Development Director shall provide the applicant with a written summary of the formal pre-application conference.

B. Requirements for a Formal Pre-application Conference.

To schedule a formal pre-application conference, the applicant shall contact the Community Development Director, submit the required materials, and pay the appropriate conference fee. At a minimum, an applicant should submit a short narrative describing the proposal and a proposed site plan, drawn to a scale acceptable to the City, which identifies the proposed land uses, traffic circulation, and public rights of way.

C. Scope of Staff Comments.

Notwithstanding any representations by City staff at a pre-application conference, staff is not authorized to waive any requirements of the **WDO**, and any omission or failure by staff to recite to an applicant all relevant applicable land use requirements shall not constitute a waiver by the City of any standard or requirement.

**4.101.05 Application and Appeal Fees**

Fees are jurisdictional. The City may adopt by resolution, and revise from time to time, a schedule of fees for applications, appeals and other services provided by City departments. Fees shall be based upon the City's actual or average cost of processing the application or conducting the appeal process. The only EXCEPTION shall be the appeal fee for a Type II decision, which shall be limited by ORS 227.175(10)(b). The requirements of this section shall govern the payment, refund and reimbursement of fees.

A. Payment.

All fees shall be due and payable at the time the application or appeal is submitted. No application or appeal shall be accepted without the proper fee being paid.

B. Refunds.

Fees will only be refunded as provided in this subsection:

1. When a fee is paid for an application, which is later found by the City to not be required, the City shall refund the fee.
2. Errors. When an error is made in calculating a fee, overpayment will be refunded.

3. Refund upon Withdrawal of an Application. In the event an applicant withdraws an application, the Community Development Department shall:
  - a. Refund 100 percent of application fee prior to deeming the application complete;
  - b. Refund 50 percent prior to making the public notice; and
  - c. Make no refund after completing the public notice.

#### **4.101.06**      **Types of Decisions: Type I, II, III, IV and V**

See *TABLE 4.1* for a summary of decisions by type.

A.      Type I Decisions. (Ministerial)

Type I decisions do not require interpretation or the exercise of policy or legal judgment in evaluating approval criteria. Because no discretion is involved, Type I decisions do not qualify as a land use, or limited land use, decision. The decision-making process requires no notice to any party other than the applicant. The Community Development Director's decision is final and not appealable by any party through the City land use process.

B.      Type II Decisions. (Administrative)

Type II decisions involve the exercise of limited interpretation or exercise of policy or legislative judgment in evaluating approval criteria. The Community Development Director's decision is appealable to the City Council with notice to the Planning Commission, by any party with standing (i.e., applicant and any person who was mailed a notice of decision). The City Council then conducts a de novo public hearing. The City Council decision is the City's final decision and is appealable to LUBA within 21 days after it becomes final.

C.      Type III Decisions. (Quasi-Judicial)

Type III decisions involve significant discretion and evaluation of subjective approval standards, yet are not required to be heard by the City Council, except upon appeal. The process for these land use decisions is controlled by ORS 197.763. Notice of the application and the Planning Commission or Design Review Board hearing is published and mailed to the applicant, recognized neighborhood associations and property owners within 250 feet of the subject property. Notice must be issued at least 20 days before the initial evidentiary hearing, and the staff report must be available at least seven days before the hearing. At the evidentiary hearing held before the Planning Commission or the Design Review Board, all issues are addressed. The decision of the Planning Commission or Design Review Board is appealable to the City Council for a de



novo public hearing. The City Council decision is the City's final decision and is appealable to LUBA within 21 days after it becomes final. In the event any decision is not classified, it shall be treated as a Type III decision. [Section 4.101.06.C as amended by Ordinance No. 2383, §51, passed March 16, 2005.]

D. Type IV Decisions. (Quasi-Judicial)

Type IV decisions involve the greatest amount of discretion and evaluation of subjective approval standards and are directed at a closely circumscribed factual circumstance or relatively small number of persons. Type IV decisions must be heard by the City Council before a final decision can be rendered. Included are small scale annexations, comprehensive plan map amendments and zoning map amendments. The process for these land use decisions is controlled by ORS 197.763. Notice of the application and Planning Commission or the Design Review Board hearing is published and mailed to the applicant, recognized neighborhood associations and property owners within 250 feet of the subject property. Notice must be issued at least 20 days pre-hearing, and the staff report must be available at least seven days pre- hearing. At the evidentiary hearing held before the Planning Commission or the Design Review Board, all issues are addressed. The Commission or the Board makes a recommendation to the City Council, the City Council holds a de novo public hearing on the matter. The City Council decision is the City's final decision and is appealable to LUBA within 21 days after it becomes final.

E. Type V Legislative Decisions. (Legislative)

Type V decisions involve legislative actions where the City Council enacts or amends the City's land use regulations, comprehensive plan, zoning maps or some other component of any of these documents where changes are such a size, diversity of ownership or interest as to be legislative in nature under state law. Included are large scale annexations, and adopting or amending the comprehensive plan text or the WDO. The Planning Commission holds an initial public hearing on the proposal prior to making a recommendation to the City Council. The City Council then holds a final de novo public hearing and makes the City's final decision. Public notice is provided for all public hearings (**Section 4.101.09**). The City Council's decision is the City's final decision and is appealable to LUBA within 21 days after it becomes final.

TABLE 4.1 SUMMARY OF DECISIONS BY TYPE							
Section	Decision	I	II	III	IV	V	Appeal
5.101.12	Access Permit to a City Street EXCLUDING a Major and Minor Arterial Street	<input type="checkbox"/>	<input type="checkbox"/>				
5.102.04	Access Permit to a City Major or Minor Arterial Street		<input type="checkbox"/>				
5.104.01	Annexation, Quasi-Judicial				<input type="checkbox"/>		
5.104.01	Annexation, Legislative					<input type="checkbox"/>	
4.102.01	Appeals: Type II or III Decision						<input type="checkbox"/>
4.102.02	Call-Up Review by the City Council: Type II or III Decision						<input type="checkbox"/>
5.104.02	Comprehensive Plan Change, Owner Initiated				<input type="checkbox"/>		
4.101.10	Comprehensive Plan Change, Legislative					<input type="checkbox"/>	
5.103.01	Conditional Use			<input type="checkbox"/>			
5.101.01	Design Review of Single Family and Duplex Residential Dwellings	<input type="checkbox"/>	<input type="checkbox"/>				
5.102.02	Design Review for All Structures LESS THAN 1000 Sq. Ft.		<input type="checkbox"/>				
5.103.02	Design Review for All Structures 1000 Sq. Ft. OR MORE			<input type="checkbox"/>			
5.103.12	Exception to Street Right of Way and Improvement Requirements			<input type="checkbox"/>			
4.102.04	Extension for a Development Decision	<input type="checkbox"/>					
5.101.02	Fence and Free Standing Wall Pre-construction Review	<input type="checkbox"/>					
5.101.03	Grading Permit	<input type="checkbox"/>					
5.103.03	Historically or Architecturally Significant Site, Specific Conditional Use			<input type="checkbox"/>			
5.104.03	Formal Interpretation of the <b>WDO</b>				<input type="checkbox"/>		
5.101.04	Manufactured Dwelling Park, Final Plan Approval	<input type="checkbox"/>					
5.103.04	Manufactured Dwelling Park, Preliminary Approval			<input type="checkbox"/>			
4.102.08	Modification of Conditions EXCLUDING Limits on Use					<input type="checkbox"/>	
4.102.08	Modification of Conditions Limiting Use				<input type="checkbox"/>		
5.102.01	Partition, Preliminary Approval		<input type="checkbox"/>				
5.101.05	Partition, Final Plat Approval	<input type="checkbox"/>					
5.103.05	Phasing Plan, Subdivision, PUD, Manufactured Dwelling Park or any other Land Use Permit			<input type="checkbox"/>			
5.103.06	Planned Unit Development (PUD), Design Plan Final Approval			<input type="checkbox"/>			
5.103.07	Planned Unit Development (PUD), Preliminary Plan Approval			<input type="checkbox"/>			
5.101.06	Planned Unit Development (PUD), Final Plan Approval	<input type="checkbox"/>					
5.101.07	Property Line Adjustment; Consolidation of Lots	<input type="checkbox"/>					
5.102.05	Residential Architectural Standards Substitution		<input type="checkbox"/>				
4.102.10	Revocation of Previously Approved Permit				<input type="checkbox"/>		
5.101.11	Significant Wetlands Overlay District (SWOD) Permit	<input type="checkbox"/>					
3.110.05.C.1.b	Sign Design Review [Added by Ord.2359, §16, passed March 22, 2004]		<input type="checkbox"/>				
3.110.05.C.1.a	Sign Permit [Added by Ord.2359, §16, passed March 22, 2004]	<input type="checkbox"/>					
5.103.08	Special Use as a Conditional Use			<input type="checkbox"/>			
5.103.09	Subdivision Preliminary Approval			<input type="checkbox"/>			
5.101.09	Subdivision, Final Plat Approval	<input type="checkbox"/>					
5.103.10	Telecommunications Facility, Specific Conditional Use			<input type="checkbox"/>			
5.101.08	Temporary Outdoor Marketing and Special Event Permit for a <b>WDO</b> Special Use	<input type="checkbox"/>					
3.110.13	Temporary Sign Permit [Added by Ord.2359, §16, passed March 22, 2004]	<input type="checkbox"/>					
5.101.10	Tree Removal Permit	<input type="checkbox"/>					
5.103.11	Variance			<input type="checkbox"/>			
4.101.10	<b>WDO</b> Amendment, City Initiated					<input type="checkbox"/>	
5.102.03	Zoning Adjustment		<input type="checkbox"/>				
5.104.04	Zoning Map Change, Owner Initiated				<input type="checkbox"/>		
4.101.10.E	Zoning Map Change, Legislative					<input type="checkbox"/>	

[Table 4.1 as amended by Ordinance No. 2383, §51, passed March 16, 2005.]

#### **4.101.07**      **Complete Application Requirements: Type I, II, III and IV**

A.      Initiation of an Application.

An application for a land use action may only be initiated by the record property owner or contract purchaser, the City Council or Planning Commission. If there is more than one record owner, then the City will not accept an application without signed authorization from all record owners.

B.      Required Information.

It is the responsibility of the applicant to demonstrate that all applicable criteria are satisfied. Unless stated elsewhere in the **WDO**, a complete application includes all the materials listed in this **Section and Section 5.1**. The number of copies of required information shall be specified in the City application materials, but in no case less than one copy. The Community Development Director may waive the submission of any of these materials if not deemed to be applicable to the specific review sought. Within 30 days of the date the application is first submitted, the Community Development Director may require additional information, beyond that listed in this subsection or elsewhere in the **WDO** to assure all applicable approval criteria are addressed. In any event, the applicant is responsible for the completeness and accuracy of the application and all of the supporting documentation. The City will not deem the application complete until all information required by the Community Development Director is submitted and received.

C.      Application Form.

A permit application shall be submitted on the form provided by the City which shall include the following information:

1.      Signatures of the parties necessary to authorize an application;
2.      Name, address, telephone number of the applicants and contact person if other than the property owner;
3.      A complete list of the permit approvals sought by the applicant with a description of the principal features regarding use, density or size, and design that characterize the request; and
4.      The location and size of the subject property, including tax account number(s) and address.

D. Application Fee.

E. Standard Exhibits.

1. Type I Permit. The exhibits for each Type I permit application are described in ***Section 5.101***.
2. Type II, III or IV Permit.
  - a. Proof of ownership, as evidenced by a current recorded deed or recorded sales contract. The Community Development Director may require that a title report be submitted on the subject property.
  - b. An accurate legal description of the subject property, as evidenced by a current recorded deed. All legal descriptions for properties that are submitted for annexation are subject to verification by the State Department of Revenue.
  - c. The applicant's written narrative statement demonstrating that all applicable criteria stated in ***Sections 5.102, 103 and .104*** are met. [Section 4.101.07.E.2.c as amended by Ordinance No. 2383, §53 passed March 16, 2005.]
  - d. Notification area map and mailing labels.
    - 1) An original copy of a current Assessor's Map with the notification area, depicted by a line drawn 250 feet, equidistant from all boundaries of the subject property.
    - 2) Two (2) sets of self adhesive labels for each property within the notification area, showing the owner's name, the tax lot number of the ownership and the owner's mailing address.
    - 3) An affidavit by the preparer of the notification list, that the address labels reflect the required ownership and address data as contained in the current property tax rolls.
    - 4) The specific exhibits required for the subject application as set out in ***Sections 5.102, 103 and .104***, or otherwise required by the Community Development Director.

**4.101.08**      **Completeness Review and 120-Day Rule: Type I, II, III and IV**

A.      Initial Acceptance. Type I, II, III and IV.

Upon submission, the Community Development Director shall date stamp the application form and verify that the appropriate application fee has been submitted.

B.      120-day Rule. Type II, III and IV applications EXCEPT annexations and Comprehensive Plan amendments.

1.      The Community Development Director shall review the application and all information submitted with it and evaluate whether the application is complete. Within thirty days of receipt of the application, the Community Development Director shall complete this completion review. If the application is incomplete, the Community Development Director shall notify the applicant in writing what information is missing.
2.      Upon receipt of a letter from the Community Development Director indicating the application is incomplete, the applicant has 180 days within which to submit the missing information. If the applicant submits the requested information within the 180-day period, the Community Development Director shall again verify whether the application, as augmented, is complete. Each such review and verification shall follow the procedure prescribed in this *Section*.
3.      If an incomplete application is not made complete within 180 days from the date it was first filed it shall become void on the 181<sup>st</sup> day. If an application becomes void under this subsection, the Community Development Director shall return all materials and the unearned portion of the application fee to the applicant.

C.      An application shall be complete:

1.      When the Community Development Director, within 30 days after the filing date, determines the application is complete; or
2.      On the 31<sup>st</sup> day after filing if the applicant refuses in writing to submit the missing information; or
3.      On the date that the applicant files the missing information if a notice of incompleteness was given; or
4.      On the 31<sup>st</sup> day for any application not previously deemed complete if no

incompleteness notice was given.

The City shall take final action on the application within 120 days of that date unless the applicant extends the 120 day period. Any continuance or extension of the record requested by an applicant shall result in a corresponding extension of the 120-day period.

D. When the 120-day Rule is Not Applicable, Type I and V.

The 120-day rule does not apply to:

1. Any Type I decision;
2. Any application for an amendment to the City's comprehensive plan; or
3. Any application for a permit, the approval of which depends upon a comprehensive plan amendment;
4. Any application that is not wholly within the City's authority and control;
5. Any Type V decision, or
6. Any annexation.

E. Applicable Standards.

The approval standards which control the City's review and decision on a complete application are those which were in effect on the date the application was first submitted.

**4.101.09 Public Notices: Type II, III, IV and V**

[Section 4.101.09 amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

All public notices issued by the City for Type II, III, IV, and V decisions shall comply with the requirements of this *Section*.

A. Mailed Notice.

1. Type II. After the Community Development Director has deemed a Type II application complete, the Community Development Director shall issue a decision. The City shall send notice of the decision, by first class mail, to all record owners of property within 250 feet of the subject property,

any City recognized neighborhood associations whose territory includes the subject property. The City's Type II notice of decision shall include the following information:

- a. An explanation of the nature of the application and the proposed use or uses, which could be authorized;
  - b. Street address or other easily understood location of the subject property;
  - c. The name and telephone number of the planning staff person assigned to the application or is otherwise available to answer questions about the application;
  - d. A statement that the application and all supporting materials may be inspected at no cost, and copies may be obtained at reasonable cost, at City Hall during normal business hours;
  - e. State that the decision will not become final until the period for filing an appeal to the City Council has expired and that the decision cannot be appealed directly to the Land Use Board of Appeals; and
  - f. An explanation of appeal rights, including that any person who is adversely affected or aggrieved or who is entitled to written notice of the decision may appeal the decision.
2. Type III or IV. Notice for all initial evidential public hearings concerning Type III and IV decisions shall conform to the requirements of this subsection. At least 10 days before a Type III initial evidentiary hearing, or at least 10 days before the first hearing of a Type IV application the Director shall prepare and send, by first class mail, notice of the hearing to all record owners of property within 250 feet of the subject property and to any City-recognized neighborhood association whose territory includes the subject property. If an application would change the zone of property that includes any part of a mobile home or manufactured dwelling park, notice shall also be mailed to the tenants at least 20 days before but not more than 40 days before the initial evidentiary hearing. Notice of the application hearing shall include the following information: [Section 4.101.09.A.2 as amended by Ordinance No. 2383, §54, passed March 16, 2005.][Section 4.101.09.A.2 as amended by Ordinance No. 2446, §32, passed on September 10, 2008.]
- a. The time, date and location of the public hearing;

- b. Street address or other easily understood location of the subject property and City-assigned planning file number;
  - c. A description of the applicant's proposal, along with a list of citations of the approval criteria that the City will use to evaluate the proposal;
  - d. A statement that any interested party may testify at the hearing or submit written comments on the proposal at or before the hearing and that a staff report will be prepared and made available to the public at least seven days prior to the hearing;
  - e. A statement that any issue which is intended to provide a basis for an appeal to the City Council must be raised before the close of the public record. Issues must be raised and accompanied by statements or evidence sufficient to afford the City and all parties to respond to the issue;
  - f. A statement that the application and all supporting materials and evidence submitted in support of the application may be inspected at no charge and that copies may be obtained at reasonable cost at City Hall during normal business hours;
  - g. The name and telephone number of the planning staff person responsible for the application or is otherwise available to answer questions about the application; and
  - h. A statement advising that ADA access may be accommodated, upon receipt of a timely request.
3. Type V. At least 20 days before an initial evidentiary public hearing at which a Type V decision is to be considered, the Director shall issue a public notice that conforms to the requirements of this subsection and any applicable state statute. Notice shall be sent to affected governmental entities, special districts, providers of urban services, the Oregon Department of Transportation and any affected recognized neighborhood associations and any party who has requested in writing such notice. [Section 4.101.09.A.3 as amended by Ordinance No. 2383, §55, passed March 16, 2005.]

Notice shall also be published in a newspaper of general circulation within the City. Notice issued under this subsection shall include the following information:



- a. The time, date and location of the public hearing;
- b. The City-assigned planning file number and title of the proposal;
- c. A description of the proposal in sufficient detail for people to determine the nature of the change being proposed;
- d. A statement that any interested party may testify at the hearing or submit written comments on the proposal at or before to the hearing;
- e. The name and telephone number of the planning staff person responsible for the proposal and who interested people may contact for further information; and
- f. A statement advising that ADA access may be accommodated, upon receipt of a timely request.

B. Posted Notice. Type III and IV.

Notice of an initial evidentiary public hearing for a Type III or IV decision shall be posted on the subject property as follows: [Section 4.101.09.B as amended by Ordinance No. 2383, §56, passed March 16, 2005.]

1. City Posting. The Community Development Director shall post all required notices.
2. Number and Location. The Community Development Director shall post a notice on each frontage of the subject property. If the property's frontage exceeds 600 feet, one copy of the notice shall be posted for each 600 feet or fraction thereof. Notices shall be posted within ten feet of the street and shall be visible to pedestrians and motorists.
3. Timing of Notice. The notice shall be posted at least 10 days prior to a public hearing. Once posted, the Director need not maintain a posted notice. The Community Development Director shall remove all signs within ten days following the event announced in the notice.

C. Published Notice. Type IV and V

The Community Development Director shall publish a notice of a Type IV or V public hearing as described in this subsection, unless otherwise specified by statute. The notice shall be published in a newspaper of general circulation within the City at least 7 days prior to the hearing. Such notice shall consist of:

1. The time, date and location of the public hearing;
2. The address or other easily understood location of the subject property and the City-assigned planning file number;
3. A summary of the principal features of the application or legislative proposal; and
4. Any other information required by statute for an annexation or other hearing procedure.

D. Notice to Affected Agencies.

1. Prior to issuing a decision regarding a Preliminary Partition Approval (*Section 5.102.01*) or Access to a City Major or Minor Arterial Street (*Section 5.102.04*), the Community Development Director shall distribute such applications that require preparation of a Transportation Impact Analysis to affected transportation facility and service providers and owning jurisdictions. These agencies shall be given 30 calendar days to review the application and to suggest any revisions in the public's interest to protect the operation of transportation facilities and services.
2. Type IV applications and Type III applications for Preliminary PUD Approval (*Section 5.103.07*), Preliminary Subdivision Approval (*Section 5.105.09*) and Conditional Use Permits (*Section 5.103.01*) for transportation system facilities and improvements that require a Transportation Impact Analysis shall be sent to affected transportation facility and service providers and owning jurisdictions. These agencies shall be given 30 calendar days to review the application and to suggest any revisions in the public's interest to protect the operation of transportation facilities and services.

**4.101.10 Assignment of Decision-Makers: Type I, II, III, IV and V**

The following City entity or official shall decide the following types of decisions:

A. Type I Decisions.

The Community Development Director shall render all Type I decisions. The Community Development Director's decision is the City's final decision on a Type I application and this decision is not appealable by any party through the City's land use process.

B. Type II Decisions.

The Community Development Director shall render the City's decision on all Type II permit applications, which are appealable to the City Council with notice to the Planning Commission. The City Council may call up a Type II decision for review on its own motion. A type II decision is appealable to LUBA within 21 days after it becomes final.

C. Type III Decisions.

The Planning Commission shall render all Type III decisions EXCEPT for Type III design review, with or without a concurrent variance, which shall be decided by the Design Review Board, if one has been created by the City Council. A Type III decision is appealable to the City Council. The City Council may call up a Type III decision for review on its own motion. A Type III decision is the City's final decision and is appealable to LUBA within 21 days after it becomes final.

D. Type IV Decisions.

The Planning Commission shall hold an initial public hearing on all Type IV permit applications before making a recommendation to the City Council. The City Council shall then conduct a de novo public hearing. The City Council decision is the City's final decision on a Type IV application and is appealable to LUBA within 21 days after it becomes final.

E. Type V Legislative Decisions.

Type V decisions involve legislative actions where the City Council enacts or amends the City's land use regulations, comprehensive plan, official zoning maps or some component of these documents. Type V decisions may only be initiated by the City Council. The Planning Commission holds an initial public hearing on the proposal before making a recommendation to the City Council. The City Council then holds a final public hearing and renders a decision. Public notice is provided for all public hearings (***Section 4.101.09***). The City Council's decision is the City's final decision and is appealable to LUBA within 21 days after it becomes final.

**4.101.11 Quasi-Judicial Hearing Process: Type III and IV and Appeals of Type II, III and IV**

All public hearings pertaining to Type III and IV permits, whether before the Planning Commission, Design Review Board, or City Council, and any appeal or review for a Type II, III or IV permit, shall comply with the procedures of this ***Section***. In addition, all public hearings shall comply with the Oregon Public Meetings Law, the applicable provisions of ORS 197.763 and any other applicable law.

A. Scheduling.

Once the Community Development Director determines that an application for a Type III or IV decision is complete, the Planning Department shall schedule a hearing before the Planning Commission or Design Review Board, as applicable. If the Community Development Director has doubt about which Type of procedure is applicable to a particular application, the application shall be processed pursuant to the procedure that provides the greater opportunity for public review. Once the Community Development Director determines that an appeal of a Type II or Type III decision has been properly filed, or that the City Council has called the decision up for review, the Planning Department shall schedule a hearing before the City Council.

B. Public Hearing Notice.

Notice of the hearing shall be issued pursuant to WDO Section 4.101.09. [Section 4.101.11.B as amended by Ordinance No. 2446, §33, passed on September 10, 2008.]

C. Staff Report.

The Community Development Director shall prepare a staff report on the application which lists the applicable approval criteria, describes the application and the applicant's development proposal, summarizes all relevant City department, agency and public comments, describes all other pertinent facts as they relate to the application and the approval criteria, concludes whether each of the approval criteria are met and makes a recommendation to approve or deny the application. The recommendation may include conditions of approval to assure that applicable approval standards or criteria are satisfied.

D. Conduct of Quasi-Judicial Hearings.

At the beginning of the public hearing at which any quasi-judicial application or appeal is reviewed, a statement shall be made to those in attendance that states that:

1. The applicable substantive criteria;
2. The hearing will proceed in the following general order: staff report, applicant's presentation, testimony in favor of the application, testimony in opposition to the application, rebuttal, record closes, deliberation and decision;

3. All testimony and evidence submitted, orally or in writing, must be directed toward the applicable approval criteria. If any person believes that other criteria apply in addition to those addressed in the staff report, those criteria must be listed and discussed on the record. The decision-maker may reasonably limit oral presentations in length or content depending upon time constraints and to content that is relevant to applicable approval criteria. Any party may submit written materials while the public record is open;
4. Failure to raise an issue on the record accompanied by statements or evidence sufficient to afford the City and all parties an opportunity to respond to the issue, will preclude appeal on that issue to LUBA;
5. Failure of the applicant to raise constitutional or other issues relating to proposed conditions of approval with sufficient specificity to allow the City Council/Planning Commission/Design Review Board to respond to the issue precludes an action for damages in Circuit Court; and
6. Any party wanting a continuance or to keep open the record must make that request while the record is still open.

**4.101.12 Requests of Continuance and to Keep the Record Open: Type III and IV and Appeals of Type II, III and IV**

- A. The City Council/Planning Commission/Design Review Board, as the case may be, may continue the hearing from time to time to allow the submission of additional information or for deliberation without additional information. Similarly, the decision-maker may close the hearing but keep the record open for the submission of additional written material or other documents and exhibits.
- B. Before the conclusion of the initial evidentiary hearing, any participant may request an opportunity to present additional evidence. The decision-maker shall grant the request by either continuing the hearing or allowing the record to remain open for at least seven days.
  1. If the decision-maker grants a continuance:
    - a. The hearing shall be continued to a date, time and place certain at least seven days from the date of the initial evidentiary hearing.
    - b. An opportunity shall be provided at the continued hearing for persons to present and rebut new evidence, arguments or testimony.
    - c. If new written evidence is submitted at the continued hearing any

person may request, before conclusion of the continued hearing, that the record be left open for at least seven days to submit additional written evidence, arguments or testimony for the purpose of responding to the new written evidence.

2. If the decision-maker holding the hearing leaves the record open:
    - a. The record shall be left open for at least seven days for additional written evidence, arguments or testimony.
    - b. If new evidence is submitted during the period the record was left open, any participant may file a written request for an opportunity to respond to the new evidence and the decision-maker shall reopen the record.
  3. If the decision-maker reopens a record to admit new evidence, arguments or testimony, any person may raise new issues which relate to the new evidence, arguments, testimony or criteria for decision-making which apply to the matter at issue.
  4. Any continuance or extension of the record granted shall be subject to the limitations of the 120-day rule.
  5. Unless waived by the applicant, the decision-maker shall allow the applicant at least seven days after the record is closed to allow other parties to submit final written arguments, but not new evidence, in support of application.
- C. The City Council/Planning Commission/Design Review Board may limit the factual and legal issues that may be addressed in any continued hearing or open record period.
- D. The City Council on appeal or call-up for review of a Planning Commission or Community Development Director decision, shall consider the Planning Commission or Community Development Director decision. In all appeal or review hearings, the applicant and other parties shall have an opportunity to present testimony, arguments and evidence on all applicable criteria. The presentation of testimony, arguments and evidence shall not be limited to issues raised in a notice of appeal. If the City Council call a Planning Commission decision up for review, the City Council may limit the issues that it will allow. The rights of participants to continuances or open record persons applicable to initial evidentiary hearings do not apply. [Section 4.101.12.D as amended by Ordinance No. 2383, §57, passed March 16, 2005.]

#### **4.101.13 Ex-Parte Contacts, Personal Site Observations, Conflicts of Interest and Bias**

Before the beginning of each hearing item, the City Council/Planning Commission/Design Review Board chair shall ask the members of that decision-making body if there are any declarations of any ex-parte contacts, personal site observations, conflicts of interest or bias.

A. Ex- parte Contacts.

Before rendering a decision, a member of the decision-making body may not communicate, directly or indirectly, with any person interested in the outcome. Should such communication occur, the member must at the beginning of the hearing:

1. Enter into the record the substance of the written or oral communication; and
2. Publicly announce the content of the communication and provide any person an opportunity to rebut the substance of the contact.

This rule does not apply to legislative proceedings or to communications between City staff and a member of the decision-making body.

B. Personal Site Observations.

A member of the decision-making body shall disclose into the record any personal site observations and provide any person an opportunity to rebut the substance of this disclosure. This rule does not apply to legislative proceedings.

C. Conflicts of Interest.

A member of the decision-making body shall review and observe the requirements of the Government Standards and Practices Law (ORS Chapter 224). All potential and actual conflicts of interest shall be publicly disclosed by the member and noted in the meeting minutes. A member shall not participate as a member of the decision-making body in any land use proceeding where the member has an actual conflict of interest.

D. Bias.

All decisions in quasi-judicial matters shall be fair, impartial and based on the applicable approval standards and the evidence in the record. A member of the decision-making body who is unable to render a decision on this basis in any particular matter shall refrain from participating in the deliberations or decision on the matter. This rule does not apply to legislative proceedings.

**4.101.14**      **Objections to Procedure**

Any party who objects to the procedure followed in any particular matter, including bias, conflict of interest and undisclosed ex parte contacts, must make a procedural objection before the City renders a final decision. Procedural objections may be raised at any time before a final decision, after which they are deemed waived. In making a procedural objection, the objecting party must identify the procedural requirement that was not properly followed and identify how the alleged procedural error harmed that person's substantial rights.

#### **4.101.15**      **Conditions of Approval: Type II, III and IV**

A.      Authority to Impose Conditions.

All City decision-making bodies have the authority to impose conditions of approval reasonably related to impacts caused by the development or designed to ensure that all applicable approval standards are, or can be, met on Type II, III and IV decisions EXCEPT annexation. All conditions of approval shall be clear and objective or if the condition requires discretion shall provide for a subsequent opportunity for a public hearing.

B.      Compliance with Conditions.

1.      The applicant shall agree in writing that the applicant and successors shall be bound by the conditions prescribed for approval of the development.
2.      Failure to comply with any condition of approval shall be the basis for revocation of the permit(s) and/or instituting code enforcement proceedings pursuant to the *Section 4.102.10 and 4.104.11* and ORS 30.315.

#### **4.101.16**      **Notice of Decision**

The City shall send, by first class mail, a notice of all Type II, III and IV decisions to all persons with standing, including the applicant, all persons who appeared either orally or in writing before the close of the public record and any persons who requested notice of the decision. The notice of decision shall include the following information:

- A.      The file number and date of decision;
- B.      The name of the applicant, owner and appellant (if different);
- C.      The street address or other easily understood location of the subject property;
- D.      A brief summary of the decision, and if an approval, a description of the permit approved;



- E. A statement that the decision is final unless appealed and description of the requirements for perfecting an appeal; and
- F. The contact person, address and a telephone number whereby a copy of the final decision may be inspected or copies obtained.

**4.101.17 Initiation of a Legislative Proposal: Type V**

- A. The City Council may initiate the consideration of a legislative decision by resolution.
- B. Actions initiated by the Council shall be referred to the Planning Commission for a public hearing and recommendation to the Council.
- C. The City Council shall hold the final public hearing on a proposed legislative decision.

**4.101.18 Legislative Hearing Process: Type V**

- A. Purpose.

Legislative actions involve the adoption or amendment of the City's land use regulations, comprehensive plan, official zoning maps, or some component of these documents.

- B. Planning Commission Recommendation.

1. Hearing Required. The Planning Commission shall hold at least one public hearing before recommending action on a legislative proposal. Any interested person may appear and provide written or oral testimony on the proposal at or before the hearing. The Community Development Director shall notify the Oregon Department of Land Conservation and Development (DLCD) at least 45 days before the first hearing, or as required by the post-acknowledgment procedures of ORS 197.610 to 197.625, as applicable.
2. Community Development Director's Report. Once the Planning Commission hearing has been scheduled and noticed, the Community Development Director shall prepare and make available a report on the legislative proposal at least seven days before the hearing.
3. Planning Commission Recommendation. At the conclusion of the hearing, the Planning Commission shall adopt a recommendation on the proposal to the City Council. The Planning Commission shall make a report and recommendation to the City Council on all legislative proposals. If the

Planning Commission recommends adoption of some form of the proposal, the Planning Commission shall prepare and forward to the City Council a report and recommendation to that effect.

C. City Council Action.

Upon receiving a recommendation from the Planning Commission on a legislative action, the City Council shall hold at least one public hearing on the proposal. Any interested person may provide written or oral testimony on the proposal at or prior to the hearing. At the conclusion of the hearing, the City Council may adopt, modify or reject the legislative proposal, or it may remand the matter to the Planning Commission for further consideration. If the decision is to adopt at least some form of the proposal, and thereby enact or amend the City's land use regulations, comprehensive plan, official zoning maps or some component of any of these documents, the City Council decision shall be enacted as an ordinance.

D. Notice of Final Decision to DLCD.

Not later than five working days following the City Council final decision, the Community Development Director shall mail notice of the decision to DLCD in accordance with ORS Chapter 197.

## **4.102 Review, Interpretation and Enforcement**

### **4.102.01 Appeals: Type II and III Decision**

Appeals of any non-final decisions by the City must comply with the requirements of this section.

#### **A. Standing to Appeal. Type II and III Decision.**

The following rules prescribe who has standing to appeal:

1. Type I. Type I decisions by the Community Development Director are not appealable to any other decision-maker within the City.
2. Type II. For Type II decisions, only those persons who are adversely affected or aggrieved or who are entitled to notice have standing to appeal a Community Development Director decision and is substantially adversely affected.
3. Type III. For Type III decisions, only those persons who participated either orally or in writing or who are adversely affected or aggrieved have standing to appeal the decision of the Planning Commission or Design Review Board, as applicable and is substantially adversely affected.

#### **B. Notice of Intent to Appeal.**

1. A notice of intent to appeal any Type II or Type III decision must be received in writing by the Community Development Director within twelve (12) days from the date notice of the challenged decision is mailed to those entitled to notice. Late filing of any appeal shall be a jurisdictional defect and will result in the automatic rejection of any appeal so filed.
2. The following must be included as part of the notice of appeal:
  - a. The Community Development file number and date the decision to be appealed was rendered;
  - b. The name, mailing address and daytime telephone number for each appellant;
  - c. A statement of how each appellant has standing to appeal;
  - d. A statement of the grounds for the appeal; and

- e. The appropriate appeal fee. Failure to include the appeal fee for the costs of appeal and transcript fee within the appeal period is a jurisdictional defect and will result in the automatic rejection of any appeal so filed. IF an appellant prevails at hearing or on appeal, the transcript fee shall be refunded.

C. Notice of the Appeal Hearing.

The Community Development Department shall issue notice of the appeal hearing to all parties who signed in or participated, either orally or in writing, before the close of the public record. Notice of the appeal hearing shall contain the following information:

1. The file number and date of the decision being appealed;
2. The time, date and location of the public hearing;
3. The name of the applicant, owner and appellant (if different);
4. The street address or other easily understood location of the subject property;
5. A description of the permit requested and the applicant's development proposal;
6. A brief summary of the decision being appealed and the grounds for appeal listed in the notice of appeal;
7. A statement that the appeal hearing is confined to the issues raised in the notice of appeal; and
8. A general explanation of the requirements for participation and the City's hearing procedures.

**4.102.02 Call-Up Review by the City Council: Type II and III Decision**

A. Authority.

Whether or not an appeal is filed, the City Council may by majority vote initiate review of a Type II or III decision.

B. Procedures.

1. A Type II and III decision and all minutes, or draft minutes, of the Planning Commission or Design Review Board hearing proceedings, shall be forwarded to the City Council as an information item by the

Community Development Director at the time the decision is mailed to the applicant.

2. Review under this **Section** shall be initiated before the adjournment of the first regular City Council meeting following the date the City Council receives notification of the decision.
3. Review shall replace a filed or possible appeal of the decision. The appellants of any appeal filed before a City Council call for review shall receive a full refund of the filing fee.
4. The City Recorder will set the hearing date for the City Council review, considering the 120-day rule.
5. The notice, hearing and decision procedures for a City Council review shall follow the provisions of the **WDO** provided for appeals.

#### **4.102.03 Expiration of a Development Decision**

- A. A final decision on a change to the comprehensive plan map, the zoning map, land use regulations or some component of these documents shall be permanent.
- B. A final decision granting preliminary approval of either a partition, a subdivision or a planned unit development (PUD) shall expire within two years of the decision UNLESS:
  1. A complete application for final approval has been filed and deemed complete by the Community Development Director; or [Section 4.102.03.B.1 as amended by Ordinance No. 2383, §58, passed March 16, 2005.]
  2. A time extension, **Section 4.102.04**, has been approved.
- C. A final decision granting preliminary approval of a manufactured dwelling park (MDP) shall expire on the 366<sup>th</sup> day after the date of the decision UNLESS:
  1. A complete application for final approval has been filed and deemed complete by the Community Development Director; or
  2. A time extension has been approved.
- D. A final decision on any application EXCLUDING those indicated in **Sections 4.102.03.A., B, and C.** shall expire within one year of the date of the final decision UNLESS:
  1. A building permit to exercise the right granted by the decision has been

issued;

2. The activity approved in the decision has commenced; or
3. A time extension, ***Section 4.102.04***, has been approved.

E. New Application Required.

Expiration of a final decision shall require a new application for any use or development on the subject property that is not otherwise allowed outright.

F. Deferral of the Expiration Period Due to Appeals.

If a final decision is appealed to a review body beyond the jurisdiction of the City, the expiration period for the decision shall not begin until review before LUBA and the appellate courts has been completed, including any remand proceedings before the City. The expiration period provided for in this ***Section*** will begin to run on the date of final disposition of the appeal.

**4.102.04**      **Extension of a Development Decision**

- A. The effective time period for a final decision, may be extended by the Community Development Director before its expiration subject to a Type I application and decision procedure. Based on a complete application, including a statement indicating the circumstances warranting a time extension, a time extension may be granted for a period up to one year from the date of the final decision EXCEPT for a manufactured dwelling park (MDP).
- B. An extension for a MDP shall not exceed 180 days from the date of the final decision upon written request by the applicant showing the circumstances beyond the control of the applicant have prevented action from being taken. In order to renew action on a MDP application after expiration, the applicant shall resubmit plans and pay a new review fee.

**4.102.05**      **Reapplication Limited**

If the application is denied or withdrawn following the close of the public hearing, no reapplication for the same or substantially similar proposal may be made for one year following the date of final decision denying a permit.

#### **4.102.06**      **Transfer of Approval Right**

Any final decision granted under the **WDO** shall run with the land and shall transfer with ownership of the land UNLESS otherwise specified in the decision. Any conditions, time limits or other restrictions imposed with a decision shall bind all subsequent owners of the subject property.

#### **4.102.07**      **Performance Guarantees**

- A.      When an applicant has an obligation to construct or improve public facilities or to construct improvements imposed as a condition of approval, the obligation shall be fulfilled prior to the issuance of a building permit unless the City Administrator has granted a written waiver of this requirement and the applicant has filed with the City Administrator a performance guarantee. The performance guarantee shall state the nature of the obligation, the time in which the obligation is to be met, identify the property subject to the obligation and contain security in a form acceptable to the City Administrator and in an amount equal to 120 percent of the cost of fulfilling the obligation as estimated by the City Administrator for the year in which fulfillment of the obligation is anticipated. A sufficient performance bond, cash deposit or letter of credit are acceptable forms of security. Return of the security to the applicant shall be conditioned upon the applicant fulfilling the obligation.
- B.      As an additional and separate part of the performance guarantee, the applicant shall agree to maintain the public facility or improvement for a period of one year following acceptance by the City Administrator, to include but not be limited to repair, replacement and all things necessary to insure its operational integrity.
- C.      The security shall be forfeited to the City if the applicant does not fulfill the requirements stated in the performance guarantee and the City may use the security to complete the obligation or any part of it. Until the obligation is completed, the security shall remain in the custody of the City or shall be placed in an escrow account subject to City control.
- D.      Upon receipt of written notice to the City Administrator that the public facility or required improvement has been completed and is ready for final inspection and acceptance, the City Administrator shall, with ten (10) calendar days, make such inspection. If the City Administrator finds the work to be acceptable, there shall promptly be issued a final certificate stating the work has been completed and accepted.
- E.      If the City Administrator determines that an applicant has failed to fulfill the obligation to complete the public facility or required improvement, written notice shall be given detailing the failure and stating the City's intention to use the security given to complete the obligation. If the City completes the obligation and the security which as required is not sufficient to compensate the City for costs

incurred, the excess amount due to the City, plus a 10% administrative charge, shall constitute a lien in favor of the City upon the real property subject to the obligation.

- F. The lien attaches upon entry in the City lien docket and the giving of notice of the claim for the amount due for the completion of the obligation. The notice shall demand that amount due, allege the insufficiency of the bound or other security to compensate the City fully for the cost of the fulfillment of the obligation, and allege the applicant's failure to complete the required obligation.
- G. Once docketed, the lien may be foreclosed in the manner prescribed by ORS Chapter 223 for foreclosing liens on real property.

#### **4.102.08**      **Modification of Conditions**

Any request to modify a condition of approval is to be considered pursuant to the procedure and the standards and criteria applicable to a new application of the type of permit or zone change that is proposed to be amended, EXCEPT the modification of a condition limiting the use of property may only be considered as a Type IV Zoning Map Change application.

#### **4.102.09**      **Interpretation**

- A. Interpretations, Generally
  - 1. An ambiguous term in the **WDO** may be interpreted in the final decision of any Type II, III or IV application or by a request for a formal interpretation by the City Council. A request for a formal interpretation may be initiated by the Community Development Director when in the administration of the code the Director deems it appropriate that a question as to the intent of the **WDO** be formally rather than administratively resolved. Alternatively, any person, upon application, may request a formal interpretation.
  - 2. The purpose of a formal interpretation is to clarify the intent of the **WDO** and its application in particular circumstances. The Council shall not, by interpretation, vary or modify any clear and unambiguous provisions of the **WDO**. Formal interpretations shall be processed as a Type IV application.
  - 3. Formal interpretations made by the Council shall control future administration and enforcement of the **WDO** until vacated or superseded by Council or incorporated as an amendment of the **WDO**. The Community Development Director shall keep a log of all formal interpretations.



B. Interpretation of Zoning District Boundaries.

Where there is uncertainty, contradiction or conflict concerning the intended location of zoning district boundary lines, the boundary lines shall be determined by consideration of the following guidelines in a Type IV review. Such a review may be initiated by the owner of the subject property or by the Community Development Director:

1. Boundaries indicated as approximately following the center of right of way lines of streets, highways, railroad track or alleys shall be construed to be such district boundaries;
2. Boundaries indicated as approximately following the boundaries of a lot shall be construed as following such boundaries;
3. Boundaries indicated as approximately following the City limits shall be construed as following such boundary;
4. Boundaries indicated as approximately following river, stream and/or drainage channels or basins shall be construed as following the center line of the channel of such river, stream or channel; and
5. Whenever any public right of way is lawfully vacated, the lands formerly within the vacated right of way shall automatically be subject to the same zoning district designation that is applicable to lands to which the vacant land attaches.

C. Interpretation of Uses.

The Community Development Director may, as a Type II decision, approve, approve with conditions or deny a request for approval of a determination that a proposed use is similar to a permissible use in the applicable zone. In making a similar use determination the following guidelines shall be considered:

1. Primary or Predominant Use. Use classifications define the primary or predominate activity. For NAICS classifications, the primary activity is determined by the principal product or group of products distributed or services rendered. Ancillary or subordinate activities conducted in the furtherance of the primary activity, shall not be considered in determining the classification of use for purposes of the **WDO**.
2. Uses Included. The description of certain classifications are amplified by a listing of more specific uses preceded by the term "INCLUDING." Such included uses only serve to illustrate the scope of the NAICS classification and are not intended to limit the uses described under the NAICS index number.

3. Uses Excluded. Certain uses excluded from a NAICS classification are preceded by the term "EXCLUDING."
4. For uses which the Community Development Director determines cannot be readily classified with reference to NAICS or particular description in the *WDO* the Director may request a formal interpretation by the City Council. Alternatively, any person, upon application may request such an interpretation. Consideration of a request for formal interpretation shall be a *Type IV* review.

**4.102.10**      **Revocation or Modification of a Previously Approved Permit** [Section 4.102.10 as amended by Ordinance No. 2383, §59, passed March 16, 2005.]

A. Authority to Revoke or Modify.

The Planning Commission may initiate a proceeding to revoke or modify a quasi-judicial permit if the Planning Commission determines there is a substantial likelihood that any of the following conditions exists:

1. An applicant, or the applicant's successor in interest, fails to fully comply with one or more conditions of permit approval or otherwise does not comply fully with the City's approval.
2. An applicant, or the applicant's successor in interest, failed to complete the work within the time frame or in the manner approved without obtaining an extension of time or modification of the permit from the granting authority.
3. The activities of the use, or the use itself, are substantially different or have substantially increased in intensity from what was approved.
4. The use is subject to the nonconforming use regulations, the applicant has not obtained approval, and has substantially changed the use or substantially increased the intensity of the use after the use became nonconforming.
5. The applicant or the applicant's representatives either intentionally or unintentionally committed a material misrepresentation of fact in the application or the evidence submitted in support of the application.
  - a. For purposes of this section, "material misrepresentation of fact" means a misstatement of factual information that:
    - 1) Was submitted by the applicant in support of the application;

- 2) Could have been corrected by the applicant at the time of application; and
- 3) Formed the sole basis for approval of the application pursuant to an applicable approval criterion.

- b. A “material misrepresentation of fact” does not include misstatements of fact made by City staff or caused by failure of another party to appear or adequately testify.

B. Process for Revocation or Modification.

Revocation or modification shall be processed as a Type IV decision. The Community Development Director shall have the burden of proving, based on substantial evidence in the whole record, that the applicant or the applicant’s successor has in some way violated the City’s approval.

C. Possible Actions at the Revocation Hearing.

Depending on the situation, the City may take any of the actions described below. If the decision is to modify the permit, the City may not approve a use that is more intense than originally approved unless the possibility of this change has been stated in the public notice. Uses or development which are alleged to have not fulfilled conditions, violate conditions or to be inconsistent with the City’s approval may be subject to the following actions:

1. The City may find that the use or development is complying with the conditions of the approval. In this case, the permit shall not be altered.
2. The City may modify the permit if it finds that the use or development does not fully comply with the conditions of approval or otherwise does not comply with what was approved, that the violations are not substantial enough to warrant revocation and that the use can comply with the original approval criteria if certain conditions are met. In this case, the City may modify the existing conditions, add new conditions to ensure compliance with the approval criteria, or refer the case to the code compliance officer for enforcement of the existing conditions.
3. The City may revoke a permit if it finds there are substantial violations of conditions or failure to implement conditions of a permit, such that the original approval criteria for the use or development are not being met.

D. Effect of Revocation.

In the event permit approval is revoked, the use or development becomes illegal. The use or development shall be terminated within thirty days of the date that all appeals periods have been exhausted, unless the decision provides otherwise. In

the event the City Council's decision on a revocation request is appealed, the revocation action shall be automatically stayed until the appeal is resolved.

[Section 4.102.10 as amended by Ordinance No. 2383, §59, passed March 16, 2005.]

**4.102.11**      **Enforcement**

A.      Inspection and Right of Entry.

When necessary to investigate a suspected violation of the WDO, or an application for or revocation of any permit issued under the WDO, the Community Development Director may enter on any site or into any structure open to the public for the purpose of investigation, provided entry is done in accordance with law. Absent a search warrant, no site or structure that is closed to the public shall be entered without the consent of the owner or occupant.

B.      Abatement.

Any use or structure established, operated, erected, moved, altered, enlarged, painted, or maintained contrary to the WDO is unlawful and a public nuisance, and may be abated.

C.      Civil Proceeding Initiated by City Attorney.

The City Attorney, after obtaining authorization from the City Council, may initiate a civil proceeding on behalf of the City to enforce the provisions of the WDO. This civil proceeding may include, but is not limited to, injunction, mandamus, abatement, or other appropriate proceedings to prevent, temporarily or permanently enjoin, abate, or set aside any use or structure established, operated, erected, moved, altered, enlarged, painted or maintained contrary to the WDO, including revocation of all permits, to prevent, enjoin, abate or remove the unlawful location, construction, maintenance, repair, alteration or use.

D.      Civil Infraction.

In addition to, and not in lieu of any other enforcement mechanisms, a violation of any provision of the WDO constitutes a Class 1 Civil Infraction, which shall be processed according to the procedures contained in the Woodburn Civil Infraction ordinance.

Each violation is a separate infraction. Each violation of the WDO constitutes a separate Civil Infraction, and each day that a violation of the WDO is committed or permitted to continue shall constitute a separate Civil Infraction.

E.      Remedies - Cumulative.

The remedies provided for in this Section are cumulative and not mutually exclusive.

# 5.1 APPLICATION REQUIREMENTS

## 5.101 Type I Application Requirements

[Section 5.101.01 as amended by Ordinance No. 2423, §25, effective on July 28, 2007.]

### **5.101.01      Design Review of Single Family Duplex Residential Dwellings, and Medium Density Residential Buildings**

- A. Purpose. The purpose is to assure compliance with the site development and architectural design standards of *Sections 3.1*.
- B. Applicability.
  - 1. These standards are applicable to the following development:
    - a. Any new Single Family and Duplex Dwellings within an RS, R1S and RM zone, approved AFTER the effective date of the *WDO*, EXCEPT as noted in *Section 5.101.01.B.2*;
    - b. Any exterior alteration of Single Family and Duplex Dwellings located within an RS, R1S and RM zone, EXCEPT as noted in *Section 5.101.01.B.2*:
      - 1) Where the subject dwelling has a prior *Type I* design review approval; and
      - 2) That is subject to building permit approval.
    - c. Manufactured Dwellings in an approved MDP that are from 1 to 3 acres in area.
    - d. Medium Density Residential Buildings in compliance with Section 3.107.05.
    - e. Façade changes or structural changes requiring a building permit but not increasing the size of any existing structures.
    - f. Change of use of a structure.
    - g. Establishment of a use in a building vacant for 6 months or more.
  - 2. Single Family and Duplex Dwellings that are subject to an approved architectural design review process required by a homeowners association and architectural design review CC & R's approved pursuant to *Section*

**3.109.02.E** that are equal to or better than **WDO** architectural design requirements shall be EXCLUDED from the City architectural design review requirements.

- C. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
  - 1. A complete building permit application, including architectural drawings elevations for facades subject to architectural review standards.
  - 2. Street and Utilities Plan, as applicable.
  - 3. A Grading Permit, EXCLUDING lots within a development [such as a subdivision or PUD] with an approved Grading Permit.
- D. Criteria. The criteria are contained in **Section 3.107**. [Section 5.101.D as amended by Ordinance No. 2383, §60, passed March 16, 2005.]
- E. Procedure. City staff shall review the application materials for compliance with the applicable standards of **Sections 2.1, 2.2 and 3.1** at the time of building permit review. Conforming plans will be noted on the building permit review checklist. The review shall be conducted in accordance with established building permit processing procedures.

**5.101.02 Fence and Free Standing Wall Pre-Construction Review**

- A. Purpose. The purpose is to facilitate the compliance of fence and free standing wall facilities with required standards by reviewing the location and physical characteristics of the proposed facility prior to construction or installation.
- B. Application Requirements. An application shall include a completed City application form and the following exhibit. No filing fee shall be required.

A dimensioned plot plan indicating:

  - 1. The street address;
  - 2. The name of the property owner and the owner's telephone number;
  - 3. The location of property lines; and
  - 4. The location, height and material of the proposed fence and/or free standing wall.
- C. Criteria. Applications shall be reviewed pursuant to the standards of **Sections 2.201 and 2.202**.

- D. Procedure. City staff shall review the proposal and annotate the site plan with any changes necessary to comply with City regulations. The Community Development Director shall provide a copy of the review to the applicant either over the counter or by mail.

### **5.101.03**

### **Grading Permit**

- A. Purpose. The purpose is to insure the adequacy of storm drainage in compliance with the Woodburn Storm Management Plan, Woodburn Flood Plain Ordinance, Public Works Department standards and the State building code.

[Section 5.101.03 as amended by Ordinance 2423, §24, effective on July 28, 2007.]

- B. Applicability. The provisions of a grading permit shall apply to any of the following:
1. Any fill, removal, or grading of land identified within the boundaries of the identified regulatory floodplain,
  2. Any fill, removal, or grading of land identified within the Riparian Corridor and Wetlands Overlay District (RCWOD),
  3. Any fill, removal, or grading of land that requires a permit from the Oregon Department of State Lands,
  4. Any fill, removal, or grading of land area that equals or exceeds one (1.00) acre, or
  5. Any development activity required by the WDO to submit a grading plan or grading permit.
- C. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibit:
1. A Grading Plan for the subject property.
- D. Criteria. An application shall be reviewed pursuant to the policies and standards of the Woodburn Storm Management Plan, Woodburn Flood Plain Ordinance, Public Works Department and state building code, as applicable.
- E. Procedure. Public Works staff shall review the proposal; annotate the Grading Plan and notify the applicant regarding any deficiencies. The Public Works Director shall issue a grading permit for compliant plans.



**5.101.04**      **Manufactured Dwelling Park, Final Plan Approval**

- A. Purpose. The purpose of the review is assure substantial conformance of the final plan and improvements with the conditions of the Manufactured Dwelling Park Preliminary Approval, including compliance with applicable Oregon Administrative Rules.
- B. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
  - 1. A copy of the Preliminary Manufactured Dwelling Park order of approval, annotated by the applicant to indicate the evidence submitted to demonstrate substantial conformance.
  - 2. A check print of the Final Manufactured Dwelling Park Plan;
  - 3. Design and specifications of all public and private facilities required by the preliminary approval;
  - 4. Grading Plan;
  - 5. An approved Phasing Plan, as appropriate;
  - 6. A final draft of any covenants with the City regarding perpetuation of the permanent conditions of approval;
  - 7. A current title report issued by a title company verifying ownership and encumbrances and easements of record for the subject property; and
  - 8. A properly signed copy of any dedications, easements applicable to the park required under separate document.
- C. Criteria.
  - 1. The final plan shall be submitted within two years of date of the order setting forth the final decision pursuant to ***Section 4.102.03***.
  - 2. The final plan shall include all information required by the preliminary approval and applicable Oregon Administrative Rules and shall substantially conform with all conditions of the preliminary approval and applicable Oregon Administrative Rules.
- D. Procedures.
  - 1. Technical Review. City staff shall determine whether the final plan conforms to the preliminary approval, applicable state requirements and

City ordinances.

2. Certification.

a. The City Engineer shall certify that the following items have been provided:

- 1) Properly signed public dedications and/or public utility easements applicable to the park; and
- 2) All public facilities required by the preliminary approval are designed to City standards and either constructed and accepted by the City or covered by the performance guarantee (*Section 4.102.07*) approved by the City Administrator.

b. The Community Development Director shall certify substantial conformance with the requirements of the preliminary approval, other than requirements specified for certification by other parties. Any modification of a preliminary approval that involves one or more of the following, shall not be in substantial conformance with the approval:

- 1) A change in the circulation pattern, including the location or configuration of street intersections;
- 2) An increase in the number of spaces;
- 3) A deletion or addition of a use or facility; or
- 4) Any other substantive change found by the Community Development Director.

c. The Building Official shall certify that all state requirements specifically pertaining to manufactured dwelling parks have been satisfied.

3. Issuance of a MDP Permit and Recordation of Covenants. Upon evidence of all required certifications the Building Official shall issue a manufactured dwelling park permit. The covenants with the City shall be recorded by the applicant with Marion County within 30 calendar days of the issuance of a manufactured dwelling park permit. Any permit with covenants not so recorded is void.

4. If City staff determines that the final plan does not conform, the applicant shall be advised by written notice, which shall list the reason for the

decision.

5. The applicant shall have 30 calendar days to correct the plan or to apply for a formal interpretation of applicable criteria and conditions.
6. Building Permits. Evidence of a Manufactured Dwelling Park Permit; recordation of covenants; and dedication of rights of way; and conveyance of applicable easements to the City authorizes the issuance of building permits and set-up permits. Design review of site built buildings, **Section 3.107.01**, shall be required for all manufactured dwelling parks, and for all dwellings in parks of 1 to 3 acres.

**5.101.05**      **Partition, Final Plat Approval**

- A. Purpose. The purpose of the review is assure substantial conformance of the final plat and improvements with the conditions of the preliminary partition approval.
- B. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
  1. A copy of the Preliminary Partition order of approval, annotated by the applicant to indicate the evidence submitted to demonstrate substantial conformance.
  2. A check print of the Final Partition Plat;
  3. Design and specifications for all public facilities required by the preliminary approval;
  4. Grading Plan, for property in all zones EXCEPT RS and R1S; and
  5. A current title report issued by a title company verifying ownership and encumbrances and easements of record for the subject property.
  6. A copy of deed restrictions, maintenance agreements applying to the partition (or subdivision as applicable).
  7. A properly signed copy of any dedications, easements applicable to the partition (or subdivision as applicable) required under separate document.
- C. Criteria.
  1. The final plat shall be submitted within two years of date of the order setting forth the final decision pursuant to **Section 4.102.03**.
  2. The final plat shall include all information required by the preliminary

approval and shall substantially conform with all conditions of the preliminary approval.

D. Procedures.

1. Technical Review. City staff shall determine whether the final plat conforms to the preliminary approval, including all conditions and other applicable state statutes and City ordinances and certify its findings of conformance.
2. Certifications.
  - a. The City Engineer shall certify the following information is shown on the plat:
    - 1) Location of the plat by section, township and range.
    - 2) The location and width of streets and easements intercepting the boundary of the partition (or subdivision, as applicable).
    - 3) Street rights of way and center lines being dedicated are clearly shown with linear dimensions, bearings, radii, chord distance, and points of curvature.
    - 4) The width of the portion of streets being dedicated and the width of existing rights of way.
    - 5) Required utility easements are clearly identified with respect to length, width and bearing and have sufficient ties to locate the easement with respect to the partition (or subdivision, as applicable).
    - 6) Identification of land to be dedicated for any purpose, public or private, is distinguished from lots or parcels intended for sale.
    - 7) A certificate signed and acknowledged dedicating all land intended for public use, which includes rights of way and public easements.
    - 8) A certificate with the seal of and signed by the surveyor responsible for the survey and the final plat.
  - b. The City Engineer shall certify that all public facilities required by the preliminary approval are designed to City standards and either

constructed and accepted by the City or covered by the performance guarantee (*Section 4.102.07*) approved by the City Administrator.

- c. The Community Development Director shall certify substantial conformance with the requirements of the preliminary approval, other than requirements specified for certification by other parties. Any modification of a preliminary approval that involves one or more of the following, shall not be in substantial conformance with the approval:
    - 1) A change in the circulation pattern, including the location or configuration of street intersections;
    - 2) An increase in the number of lots; or
    - 3) Any other substantive change found by the Community Development Director.
  - d. The County Surveyor shall certify the completeness and accuracy of the final plat, survey and monumentation in compliance with ORS Chapter 92.
- 3. Signing and Recordation. Upon evidence of all required certifications the Community Development Director shall sign the final plat. The final plat and the covenants with the City shall be recorded by the applicant with Marion County within 30 calendar days of signature. Acceptance by the City of the land dedicated to the public by means of a plat occurs upon the recording of the plat. Any plat and covenants not so recorded is void.
  - 4. If City staff determines that the final plat does not conform, the applicant shall be advised by written notice, which shall list the reason for the decision.
  - 5. The applicant shall have 30 calendar days to correct the plat or to apply for a formal interpretation of applicable criteria and conditions by the body granting the tentative approval.
  - 6. Approval and recordation of a final plat and covenants with the City authorizes the issuance of building permits for actions or uses as approved therein.

#### **5.101.06**      **Planned Unit Development (PUD), Final Plan Approval**

- A. Purpose. The purpose of the review is assure substantial conformance of the Final Plan, or Final PUD Plat when applicable, with the conditions of the Preliminary

PUD Plan Approval and the Final PUD Design Plan Approval.

- B. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
1. A copy of the Preliminary Planned Unit Development order of approval, annotated by the applicant to indicate the evidence submitted to demonstrate substantial conformance.
  2. A check print of the Final Planned Unit Development Plan, consisting of either of the following:
    - a. For a Final PUD Plan WITH a concurrent Subdivision: All items specified for final subdivision plat approval in ***Section 5.101.09.B***; or
    - b. For Final PUD Plan WITHOUT a concurrent Subdivision:
      - 1) Site Design Plan;
      - 2) Design and specifications for all required public improvements;
      - 3) Grading Plan; and
      - 4) Approved Phasing Plan, as applicable.
  3. An Approved Final PUD Design Plan.
  4. A current title report issued by a title company verifying ownership and encumbrances and easements of record for the subject property.
  5. A copy of deed restrictions, maintenance agreements applying to the PUD.
  6. A properly signed copy of any dedications, easements applicable to the PUD required under separate document.
- C. Criteria.
1. For a PUD with a concurrent Subdivision, the criteria of ***Section 5.101.09.C*** shall apply.
  2. For a PUD WITHOUT a concurrent Subdivision, substantial conformance with the preliminary approval shall be found.
  3. For all PUD's, substantial conformance with concurrent permit

applications shall be found, including the applicable standards of **Section 3.109** and the Final PUD Design Plan.

D. Procedures.

1. Technical Review. City staff shall determine whether the final plan, of plan and plat, conforms to the preliminary approval, including all conditions and other applicable state statutes and City ordinances and certify its findings of conformance.
2. Certifications.
  - a. The Public Works Director shall certify the final plat pursuant to **Section 5.101.05.D.2.a.and b.** In the case of a PUD WITHOUT a plat, the Public Works Director shall certify that all public facilities required by the preliminary approval are designed to City standards and either constructed and accepted by the City or covered by the performance guarantee approved by the City Administrator.
  - b. The Community Development Director shall certify substantial conformance with the requirements of the Preliminary PUD Plan approval and the Final PUD Design Plan, other than requirements specified for certification by other parties. Any modification of a prior approval that involves one or more of the following, shall not be in substantial conformance with the approval:
    - 1) A change in the circulation pattern, including the location or configuration of street intersections;
    - 2) A change in location and/or a type of use or housing;
    - 3) An increase in the number of lots, dwelling units or gross floor area of non-residential uses;
    - 4) A density increase from that approved or further limited by condition;
    - 5) The deletion or addition of a use or facility;
    - 6) A change in the scale or character of common facility design of the architectural scheme contained in the approved PUD Design Plan;
    - 7) A change in the Home Owners Association agreement and CC & R's regarding provisions for management and

maintenance of common land and facilities; the design review criteria and controls; or covenants with the City; or

- 8) Any other substantive change found by the Community Development Director.
  - c. The City Attorney shall review and approve the planned unit development documents, including the Conditions, Covenants and Restrictions (CC&R's) ONLY for compliance with conditions of development approval. [Section 5.101.06.D.2.c as amended by Ordinance No. 2383, §61, passed March 16, 2005.]
  - d. The County Surveyor shall certify the completeness and accuracy of the final plat, survey and monumentation in compliance with ORS Chapter 92.
3. Final Certification of City Approval.
    - a. Signing and Recordation. In the case of a concurrent subdivision, upon evidence of all required certifications the Community Development Director shall sign the final plat. The final plat and the covenants with the City shall be recorded by the applicant with Marion County within 30 calendar days of signature. Acceptance by the City of the land dedicated to the public by means of a plat occurs upon the recording of the plat. Any plat and covenants not so recorded is void.
    - b. Issuance of a PUD Permit and Recordation of Covenants. Upon evidence of all required certifications the Community Development Director shall issue a planned unit development permit. The covenants with the City shall be recorded by the applicant with Marion County within 30 calendar days of the issuance of a planned unit development permit. Any permit with covenants not so recorded is void.
  4. If City staff determines that the final plat does not conform, the applicant shall be advised by written notice which shall list the reason for the decision.
  5. The applicant shall have 30 calendar days to correct the plat or to apply for a formal interpretation of applicable criteria and conditions by the body granting the tentative approval.
  6. Approval and recordation of a final plat, when applicable, and covenants with the City authorizes the issuance of building permits for actions or uses as approved therein.



**5.101.07**      **Property Line Adjustment; Consolidation of Lots**

- A.      Purpose. The purpose of the review is to assure the proposed adjustment of an existing property line, or the consolidation of existing lots, parcels or other units of land, complies with the definition of a property line adjustment in ORS Chapters 92 and 209 prior to conveyance of the property reflecting the adjusted property description and advise the property owner of the location of utilities requiring easements.
- B.      Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
  - 1.      A plot plan showing:
    - a.      The location [length and bearing] of existing property lines, depicted as solid lines and of the adjusted property lines, depicted as dashed lines;
    - b.      The area of the existing and the adjusted properties; and
    - c.      The location and use of existing structures, utilities and utility service connections abutting the adjusted property lines or otherwise affected by the proposed adjustment.
  - 2.      Deeds for the subject properties.
- C.      Criteria.
  - 1.      The lot area, depth, width, frontage, building setbacks, vehicular access and lot coverage shall comply with the standards of the **WDO**;
  - 2.      The existing land use and development on the subject property shall comply with the requirements of prior land use actions; and
  - 3.      The buildings and structures abutting the adjusted property lines shall comply with state building code and fire code with respect to the current occupancy.
  - 4.      Property line adjustments shall be surveyed and monumented to the requirements set forth in ORS Chapters 92 and 209, and certified and recorded by the County Surveyor.
- D.      Procedure.
  - 1.      Community Development staff shall review the proposal with respect to the **WDO** and the state building code. Public Works staff shall review the

proposal with respect to utilities and utility connections requiring easements. Compliant proposals shall be certified by the Community Development Director and transmitted to the applicant for the applicant's submittal to the County Surveyor.

2. The applicant shall provide proof of a recorded survey in compliance with the adjustment to the Community Development Director, prior to the issuance of any building or other permits that rely on the property line adjustment.

**5.101.08**      **Temporary Outdoor Marketing and Special Event Permit for a WDO Special Use**

- A. Purpose. The purpose is to familiarize the applicant with the performance standards for the particular temporary outdoor marketing or special event conducted as a Special Use, **Section 2.203.19**, and to establish a record that serves as a basis for administering compliance with the **WDO**.
- B. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
  1. A written description of the following:
    - a. The type of event, including days and hours of operation;
    - b. The street address; and
    - c. The property owner and owner's telephone number.
  2. A plot plan, drawn to scale, depicting the location of the proposed event or use; the location and dimensions of facilities; the location and number of off street parking spaces; setbacks and buffers relative to property lines; property access and on-site circulation.
  3. A graphic depiction on the plot plan, or narrative description, of the measures to be taken to comply with specific **WDO** criteria and standards for the special use requiring a special event permit.
  4. Any additional information requested by City staff to clarify the character and scope of the proposal.
- C. Criteria. The special event shall be governed by the applicable requirements of **Section 2.203**.
- D. Procedure. City staff shall review the application and the Community Development Director shall issue a permit based on compliance of the proposal

with applicable requirements of *Section 2.203*.

**5.101.09 Subdivision, Final Plat Approval**

- A. Purpose. The purpose of the review is assure substantial conformance of the final plat and improvements with the conditions of the preliminary subdivision approval.
- B. Application Requirements. The requirements of *Section 5.101.05.B.*, with the application fee appropriate for a subdivision, shall apply.
- C. Criteria. All criteria of *Section 5.101.05.C.* shall apply, EXCEPT that a Grading Plan shall be required for property in all zones.
- D. Procedures. The procedures of *Section 5.101.05.D.* shall apply.

**5.101.10 Tree Removal Permit**

- A. Purpose. The purpose of the permit is to administer the Significant Tree conservation provisions of *Section 3.106.04*.
- B. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:

A plot plan, drawn to scale, depicting the location of the significant trees proposed for removal and the location, caliper or height, and type of trees proposed to replace the trees to be removed.
- C. Criteria. Criteria of *Section 3.106.04* shall apply.
- D. Procedures. City staff shall review the proposal and annotate the site plan with any changes necessary to comply with City regulations. The Community Development Director shall provide a copy of the review to the applicant either over the counter or by mail.

**5.101.11 Significant Wetlands Overlay District (SWOD) Permit**

- A. Purpose: The purpose of the SWOD permit review procedure is to insure that all:
  - 1. Grading,
  - 2. Excavation,
  - 3. Placement of fill, and
  - 4. Vegetation removal, other than perimeter mowing and other cutting

necessary for hazard prevention, within a delineated, significant wetland complies with applicable City and state standards and procedures, including those of ORS Chapter 196 and Chapter 227 and OAR 660-023.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, location map and the following additional exhibits:
1. A written description of the proposed use and/or action in a delineated, significant wetland.
  2. A site plan showing the location and extent of the proposed use and/or action.
  3. A letter from the Division of State Lands describing the Division=s findings and proposed action.

C. Criteria.

A City **SWOD** permit:

1. Shall be subject to the applicable standards of the **WDO** and to the findings and action proposed by the Division of State Lands [DSL], as administered by the Division, and in addition;
2. The scope of the DSL action may be varied by action of the City, upon compliance with the procedures of **Section 5.103.11, A. and B.** subject to the either:
  - a. The criteria of **Section 5.103.11C**; or
  - b. A finding, verified by the DSL, of error in delineation of the SWOD boundary.

- D. An application shall be filed with the Community Development Director prior to the initiation of action to physically alter the subject property, or the plant life thereon, as outlined in **Section 5.101.11.A.**, but no later than the filing of a complete application for a partition, subdivision, planned unit development, conditional use, specific conditional use, variance, flood plain permit, or building permit for a new structure within an identified, significant wetland.

**5.101.12 Access Permit to a City Street, EXCLUDING a Major or Minor Arterial Street**

- A. Purpose. The purpose of an access permit to a City street, EXCLUDING a Major or Minor Arterial, is to implement the standards of **Section 3.104** in circumstances

where the access is not subject to any other Type I, II or III approval.

- B. Application Requirements. An application shall include a completed City application form, filing fee and the following exhibits:
  - 1. A complete building permit application; or
  - 2. A Site Plan.
- C. Criteria. The application shall conform to the applicable standards of ***Section 3.104.***

## 5.102 Type II Application Requirements

### 5.102.01 Partition, Preliminary Approval

- A. Purpose: The purpose of a partition is to divide a single lot into not more than 3 lots within one calendar year. The division may create a street.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. Preliminary Partition Plan; and
  - 2. Traffic Impact Analysis, as may be required in compliance with *Section 3.104.01.B.2.*

- C. Criteria.

Preliminary approval of a Partition shall require compliance with the following:

- 1. That approval does not impede the future best use of the remainder of the property under the same ownership or adversely affect the safe and healthful development of the remainder of any adjoining land or access thereto.
- 2. That the proposed development shall be served with city streets, water, sewer and storm drainage facilities with adequate capacity.
- 3. That the plan for the development takes into account topography, vegetation and other natural features of the site.
- 4. That adequate measures have been planned to alleviate identified hazards and limitations to development:
  - a. For wetlands these shall be the measures required by the Division of State Lands for regulatory wetlands.
  - b. For unstable areas these measures shall be documentation as approved by the Public Works Department, that streets and building sites are on geologically stable soil considering the stress and loads to which the soil maybe subjected.
- 5. The tentative plan complies with all applicable provisions of the **WDO**, except as may be waived by variance granted as provided in **WDO**.

**5.102.02**      **Design Review for All Structures LESS THAN 1000/2000 Sq. Ft.**

- A.      Purpose. The purpose of Type II design review is to insure compliance with all applicable site development standards and architectural design guidelines of ***Section 3.1*** and other standards of the WDO for:

[Section 5.102.02 as amended by Ordinance No. 2423, §26, effective on July 28, 2007 and Ordinance 2463, passed January 25, 2010.]

1.      All new structures LESS THAN 1000 sq. ft. of gross floor area in the RS, R1S, RM, CO, CG, DDC, NNC, and P/SP zones, all new structures or additions LESS THAN 2000 square feet of gross floor area in the IP, IL, and SWIR zones, and single family and duplex dwellings in the NCOD, but EXCLUDING structures subject to TYPE I Design Review.
  2.      Any change in use that results in a greater parking requirement.
- B.      Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
1.      Street and Utilities Plan, as applicable;
  2.      Site Design Plan;
  3.      Grading Plan; and
  4.      Architectural drawings (plan view and elevations). Materials sample board – optional at Planning Director’s discretion.
- C.      Criteria. The applicable guidelines and standards of ***Section 3.1*** shall apply and other applicable sections of the ***WDO***.

**5.102.03**      **Zoning Adjustment**

- A.      Purpose. The purpose of a zoning adjustment is to allow a minor variance, within specified limits, to a zoning development standard where strict adherence to the standard is precluded by circumstances and minor deviation from a standard will not unreasonably impact existing or potential the adjacent uses or development.

Standards cited in ***Section 5.102.03.D.*** below which are set by statute for manufactured homes and manufactured home and dwelling parks are non-variable, and cannot be modified by an adjustment.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibit:
1. Site Plan.
- C. Criteria. A determination of whether the criteria set forth are satisfied necessarily involves the balancing of competing and conflicting interests.
1. The adjustment is necessary to prevent unnecessary hardship relating to the land or structure. Factors to consider in determining whether hardship exists, include:
    - a. Physical circumstances over which the applicant has no control related to the piece of property involved. that distinguish it from other land in the zone, including but not limited to lot size, shape, topography.
    - b. Whether reasonable use similar to other properties in the same zone can be made of the property without the adjustment.
    - c. Whether the hardship was created by the person requesting the adjustment.
  2. Development consistent with the request will not be materially injurious to adjacent properties or to the use of the subject property. Factors to be considered in determining whether development consistent with the adjustment is injurious include but are not limited to: [Section 5.102.03.C.2 as amended by Ordinance No. 2383, §63, passed March 16, 2005.]
    - a. Physical impacts such development will have because the adjustment, such as visual, noise, traffic and drainage, erosion and landslide hazards.
    - b. If the adjustment concerns joint use parking, the hours of operation of the uses sharing vehicle parking shall not create a competing parking demand.
    - c. Incremental impacts occurring as a result of the proposed adjustment.
  3. The adjustment is the minimum deviation from the standard necessary to make reasonable use of the property;



4. The adjustment does not in conflict with the Woodburn Comprehensive Plan.

D. Maximum Adjustment permitted.

1. Lot Area: Up to a 5 percent reduction in the minimum lot area.
2. Lot Coverage: Up to an increase of 5 percent in lot coverage.
3. Front Yard Setback or Setback Abutting a Street: Up to a 10 percent reduction of a setback.
4. Side Yard Setback: Up to a 20 percent reduction in setback, but no less than a 5 foot setback in a RS or R1S Zone or less than the requirements of the state building code, whichever is more restrictive.
5. Rear Yard Setback: Up to a 20 percent reduction in setback, but no less than a 5 foot setback, EXCEPT in those zones permitting zero setback the minimum setback shall be either 5 feet or zero.
6. Lot Width: Up to a 10 percent reduction.
7. Height: Up to a 10 percent increase in height.
8. Parking Standards: Up to a 5 percent reduction in required parking spaces EXCEPT no reduction in the number of handicapped vehicle parking spaces or in dimensional standards.
9. Joint Use Vehicle Parking: Up to 20 percent of the required vehicle parking may be satisfied by joint use of the parking used for another use.
10. Fences and Free Standing Walls: The location or height of a fence or free standing wall, EXCLUDING the adjustment of any such facilities within a clear vision area.
11. Prohibited Adjustments: Adjustments to the number of permitted dwelling or living units and to the use of property shall be prohibited.

**5.102.04 Access Permit to a City Major or Minor Arterial Street**

- A. Purpose. The purpose of an access permit is to implement the standards and guidelines of **Section 3.104** applicable to driveways and streets connecting to a City that is classified as a Major or Minor Arterial street in circumstances where the access is not subject to any other Type I, II or III approval.
- B. Application Requirements. An application shall include a completed City

application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibit:

1. Site Plan.
- C. Criteria. The application shall conform to the applicable standards and guidelines of ***Section 3.104***.

**5.102.05 Residential Architectural Standard Substitution**

- A. Purpose. The purpose is to allow limited substitution of comparable or improved residential architectural standards to reflect circumstances that comply with the approval criteria following an administrative procedure. A maximum of three substitutions may be considered for each residential building covered by an application for substitute standards.

Architectural standards set by statute (ORS 197.307 and 197.314) relating to siding and roofs on manufactured homes are non-variable, and cannot be modified by a substitution.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibit:
1. A complete building permit application, including architectural drawings elevations for facades subject to architectural review standards.
  2. Either a written description or a illustration of each architectural standards proposed for substitution.
- C. Criteria. The suitability of the substitute architectural standards shall be based on consideration of how each substitute standard:
1. Incorporates design elements and materials that reflect a custom design;
  2. Reflects the character of the existing housing within the subject subdivision and/or surrounding area. within 250 feet of subject property;
  3. Incorporates materials, that in substance and visual appeal, are of equal or greater quality;
  4. Assures that needed housing is not discouraged through unreasonable cost, pursuant to ORS 197.307.

[Section 5.102.06 as amended by Ordinance No. 2423, §30, effective on July 28, 2007.]

## 5.102.06 Exception to Street Right of Way and Improvement Requirements

- A. Purpose. The purpose of an exception is to allow a deviation from a WDO development standard required for the functional classification of the street identified in the Transportation System Plan. An exception for a development otherwise reviewed as a Type I or II application shall be considered as a Type II application.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. Street and Utility Plan as applicable;
  - 2. Site Plan; and
  - 3. A “rough proportionality” report prepared addressing the approval criteria.
- C. Criteria.
  - 1. The estimated extent, on a quantitative basis, to which the rights of way and improvements will be used by persons served by the building or development, whether the use is for safety or convenience;
  - 2. The estimated level, on a quantitative basis, of rights of way and improvements needed to meet the estimated extent of use by persons served by the building or development;
  - 3. The estimated impact, on a quantitative basis, of the building or development on the public infrastructure system of which the rights of way and improvements will be a part; and
  - 4. The estimated level, on a quantitative basis, of rights of way and improvements needed to mitigate the estimated impact on the public infrastructure system.
- D. Proportionate Reduction in Standards

An exception to reduce a street right of way or cross section requirement below the functional classification standard may be approved when a lesser standard is justified based on the nature and extent of the impacts of the proposed development. No exception may be granted from applicable construction specifications.
- E. Minimum Standards.

To assure a safe and functional street with capacity to meet current demands and to assure safety for vehicles, bicyclists and pedestrians, as well as other forms of

non-vehicular traffic, there are minimum standards for right of way and improvement that must be provided. The minimum street improvement standard is identified in 3.101.02.D. Deviation from these minimum standards may only be considered by a variance procedure, Section 5.103.11.

## 5.103 Type III Application Requirements

### 5.103.01      Conditional Use

- A.      Purpose. A conditional use is an activity which is permitted in a zone but which, because of some characteristics, which are not entirely compatible with other uses allowed in the zone, cannot be permitted outright. A public hearing and review of the proposed conditional use and the imposition of conditions, if necessary, is intended to insure that the use proposed will be as compatible as practical with surrounding uses, and is in conformance with the requirements of the district and with other applicable criteria and standards. Conditions that increase the maximum development standard of the **WDO** may be imposed without a concurrent variance. Conditions that decrease the minimum standards of a **WDO** development standard require a concurrent variance.
- B.      Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
1.      Street and Utility Plan;
  2.      Transportation Impact Analysis (TIA), as applicable; and
  3.      Site Plan.
- C.      Criteria.
1.      The proposed use shall be permitted as a conditional use within the zoning district.
  2.      The proposed use shall comply with the development standards of the zoning district.
  3.      The proposed use shall be compatible with the surrounding properties.
- Considerations. Relevant factors to be considered in determining whether the proposed use is compatible include:
- a.      The suitability of the size, shape, location and topography of the site for the proposed use;
  - b.      The capacity of public water, sewerage, drainage, street and pedestrian facilities serving the proposed use;
  - c.      The impact of the proposed use on the quality of the living

environment:

- 1) Noise;
  - 2) Illumination;
  - 3) Hours of operation;
  - 4) Air quality;
  - 5) Aesthetics; and
  - 6) Vehicular traffic.
- d. The conformance of the proposed use with applicable Comprehensive Plan policies; and
  - e. The suitability of proposed conditions of approval to insure compatibility of the proposed use with other uses in the vicinity.

**5.103.02**      **Design Review for All Structures 1000/2000 Sq. Ft. OR MORE**

[Section 5.103.02 as amended by Ordinance No. 2423, §27, effective on July 28, 2007.]

- A. Purpose. The purpose of Type III design review is to insure compliance with the applicable site development standards and architectural design guidelines of ***Section 3.1*** for:

All new structures or additions 1000 sq. ft. OR MORE of gross floor area in the RS, R1S, RM, CO, CG, DDC, NNC, and P/SP zones, all new structures or additions 2000 OR MORE square feet of gross floor area in the IP, IL, and SWIR zones, EXCLUDING structures subject to TYPE I Design Review; and single family and duplex dwellings in the ***NCOD***.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:

1. Street and Utilities Plan, as applicable;
2. Site Design Plan;
3. Grading Plan;
4. Architectural drawings (plan view and elevations) and materials sample

board; and

5. Traffic Impact Analysis, as may be required in compliance with ***Section 3.104.01.B.2.***

- C. Criteria. The criteria are pursuant to the standards and guidelines of ***Section 3.1.*** and other applicable sections of the ***WDO.***

**5.103.03 Historically or Architecturally Significant Site, Specific Conditional Use**

- A. Purpose: The purpose is to create a procedure that allows consideration of the adaptive reuse of historically or architecturally significant sites and buildings for a more intensive use than permitted outright within a zone in order to conserve the site or building resource. The procedure is intended to provide appropriate opportunities for the maintenance and productive use of significant cultural resources that would not otherwise be economically practical, and where a zone change would be inappropriate.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:

1. Street and Utility Plan;
2. Transportation Impact Analysis (TIA), as applicable; and
3. Site Plan

- C. Criteria:

1. The proposed use shall be permitted as a conditional use within the zoning district.
2. The proposed use shall comply with the development standards of the zoning district.
3. The proposed use shall be compatible with the surrounding properties.

Considerations. Relevant factors to be considered in determining whether the proposed use is compatible include:

- a. The suitability of the size, shape, location and topography of the site for the proposed use;
- b. The capacity of public water, sewerage, drainage, street and

pedestrian facilities serving the proposed use;

- c. The impact of the proposed use on the quality of the living environment:
    - 1) Noise;
    - 2) Illumination;
    - 3) Hours of operation;
    - 4) Air quality;
    - 5) Aesthetics; and
    - 6) Vehicular traffic.
  - d. The conformance of the proposed use with applicable Comprehensive Plan policies; and
  - e. The suitability of proposed conditions of approval to insure compatibility of the proposed use with other uses in the vicinity. The proposed use shall be compatible with the surrounding properties.
4. The specific standards and criteria of *Section 2.204.02* shall be met.

**5.103.04**      **Manufactured Dwelling Park, Preliminary Approval**

- A. Purpose: The purpose of a Manufactured Dwelling Park (MDP) is to allow for the siting of manufactured dwellings on leased or rented spaces in compliance with not only state requirements, but also, with complementary City standards where permitted by state design criteria.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. Aerial Photograph;
  - 2. Concept Plan for Adjacent Property Interests, as applicable;
  - 3. Phasing Plan, as applicable;
  - 4. Transportation Impact Analysis (TIA), as applicable; and



5. Preliminary Manufactured Dwelling Park (MDP) Plan, including the information described in ***Section 6.101.02.L***.

C. Criteria:

1. The proposed use shall be a special permitted use within the zoning district. [Section 5.103.04.C.1 as amended by Ordinance No. 2383, §65, passed March 16, 2005.]
2. The proposed use shall comply with the applicable standards and criteria of the ***WDO***, including but not limited to the specific standards and criteria of ***Section 2.203.15***.

**5.103.05 Phasing Plan for a Subdivision, PUD, Manufactured Dwelling Park or any other Land Use Permit**

- A. Purpose: The purpose of a Phasing Plan is to allow the incremental implementation of a total development plan for a property, while providing fully functional phases that are developed in compliance with the tentative approval for the development.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  1. Phasing Plan.
- C. Criteria. The proposed phasing of development shall:
  1. Insure that individual phases will be properly coordinated with each other and can be designed to meet City development standards; and
  2. Insure the phases do not unreasonably impede other future development based on the following considerations:
    - a. The City's future latitude in addressing:
      - 1) Changing community goals and expectations about the future development of undeveloped land; and
      - 2) Mandated state land use planning requirements, including those regarding buildable land, needed housing, transportation connectivity.
    - b. The latitude of future developers of abutting properties within the UGB in addressing:

- 1) Changing market conditions; and
- 2) The access and circulation alternatives for a development proposal.

**5.103.06**      **Planned Unit Development (PUD), Design Plan Final Approval**

- A. Purpose: The purpose of a Planned Unit Development (PUD) Design Plan is depict and quantify the design elements of each development proposed under the flexible standards of the PUD provisions of the **WDO, Section 3.109**.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  1. Detailed Designs for all Common Open Spaces and Facilities;
  2. Grading Plan for all Common Facilities;
  3. Architectural Elevations and Materials Sample Board for Common Facilities; and
  4. Approved Phasing Plan, as applicable.
- C. Criteria.

The Final PUD Design Plan shall substantially conform with the Preliminary PUD Design Plan approval, including the conditions relating to:

1. Concurrent permit approvals regarding use, density, and designation of common areas;
2. Design parameters that establish the character of common areas and facilities;
3. Elements of the Homeowners agreement and CC&R's regarding:
  - a. Management and maintenance of common areas and facilities;
  - b. Design review guidelines and procedures for common and individually owned buildings and structures; and
  - c. Covenants with the City regarding permanent conditions of development.

**5.103.07**      **Planned Unit Development (PUD), Preliminary Plan Approval**

- A. Purpose: The purpose of a Planned Unit Development (PUD) is to provide incentives for greater creativity and adaptability in development design through a process that allows flexibility in the application, and deviation from, standards within predetermined limits.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. A declaration that the proposed plan is either a: a) Single Family Residential PUD or b) Mixed Use PUD.
  - 2. Aerial Photograph;
  - 3. Concept Plan for Adjacent Property Interests, as applicable;
  - 4. Phasing Plan, as applicable;
  - 5. Traffic Impact Analysis, as may be required in compliance with ***Section 3.104.01.B.2.***;
  - 6. Preliminary Planned Unit Development (PUD) Plan or Preliminary Subdivision Plat;
  - 7. Preliminary PUD Design Plan; and
  - 8. Concurrent Applications for other permits necessary to implement the Preliminary PUD Plan.
- C. Criteria. Preliminary approval of a Planned Unit Development shall require compliance with the following:
  - 1. Preliminary Plan or Subdivision Plat
    - a. That approval does not impede the future best use of the remainder of the property under the same ownership or adversely affect the safe and healthful development of the remainder of any adjoining land or access thereto.
    - b. That the proposed development shall be served with city streets, water, sewer and storm drainage facilities with adequate capacity.

- c. That the plan for the development takes into account topography, vegetation and other natural features of the site.
- d. That adequate measures have been planned to alleviate identified hazards and limitations to development:
  - 1) For wetlands these shall be the measures required by the Division of State Lands for regulatory wetlands.
  - 2) For unstable areas these measures shall be documentation as approved by the Public Works Department, that streets and building sites are on geologically stable soil considering the stress and loads to which the soil may be subjected.
- e. That the development of the plan is phased to balance with the need for urbanization within the Woodburn Urban Growth Boundary.
- f. The tentative plan complies with all applicable provisions of the **WDO**, except as may be waived by variance granted as provided in **WDO**.

2. Preliminary PUD Design Plan

- a. Specification as a Single Family Residential PUD or Mixed Use PUD application.
- b. Tabular summary, keyed to elements or sub-areas on a copy of the design plan, of:
  - 1) Location of the number of dwelling units and average floor area by housing type.
  - 2) Location, use and gross floor area of other primary buildings and the location and number of accessory parking spaces for non-residential primary uses.
  - 3) Placement and location of:
    - a) All primary buildings and common facilities within setback envelope;
    - b) All common open spaces, including recreation areas and facilities (including size/capacity and major design features), landscaped and natural areas; and

- c) All pedestrian and bicycle facilities, common lighting and common parking areas and the standards for these common facilities.
- c. Site analysis report documenting compliance of the design plan with the underlying zone and **Section 3.1**, including the following development standards and guidelines,:
  - 1) Lot standards;
  - 2) Setbacks;
  - 3) Street standards;
  - 4) Landscaping, wetlands and tree conservation; and
  - 5) **Section 3.109.02.**
- 3. Concurrent Applications

Concurrent applications shall be processed according to applicable provisions of the **WDO**.

**5.103.08 Special Use as a Conditional Use**

- A. Purpose. The purpose is to allow any use listed as a Special Permitted Use in a zone but does not comply with the applicable standards of **Section 2.203** to be approved as a Conditional Use.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. Street and Utility Plan;
  - 2. Transportation Impact Analysis (TIA), as applicable; and
  - 3. Site Plan.
- C. Criteria.
  - 1. The proposed use shall be permitted as a Special Use within the zoning district.
  - 2. The proposed use shall comply with the development standards of the

zoning district.

3. The proposed use shall be compatible with the surrounding properties.

Considerations. Relevant factors to be considered in determining whether the proposed use is compatible include:

- a. The suitability of the size, shape, location and topography of the site for the proposed use;
- b. The capacity of public water, sewerage, drainage, street and pedestrian facilities serving the proposed use;
- c. The impact of the proposed use on the quality of the living environment:
  - 1) Noise;
  - 2) Illumination;
  - 3) Hours of operation;
  - 4) Air quality;
  - 5) Aesthetics; and
  - 6) Vehicular traffic.
- d. The conformance of the proposed use with applicable Comprehensive Plan policies; and
- e. The suitability of appropriate standards of **Section 2.203** and other proposed conditions of approval to insure compatibility of the proposed use with other uses in the vicinity.

#### **5.103.09 Subdivision Preliminary Approval**

- A. Purpose: The purpose of a Subdivision is to divide a single lot into 4 or more lots. The division may create a street.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  1. Aerial Photograph;

2. Concept Plan for Adjacent Property Interests, as applicable;
  3. Phasing Plan, as applicable;
  4. Traffic Impact Analysis, as may be required in compliance with **Section 3.104.01.B.2.**; and
  5. Preliminary Subdivision Plan.
- C. Criteria. Preliminary approval of a Subdivision shall require compliance with the following:
1. That approval does not impede the future best use of the remainder of the property under the same ownership or adversely affect the safe and healthful development of the remainder of any adjoining land or access thereto.
  2. That the proposed development shall be served with city streets, water, sewer and storm drainage facilities with adequate capacity.
  3. That the plan for the development takes into account topography, vegetation and other natural features of the site.
  4. That adequate measures have been planned to alleviate identified hazards and limitations to development:
    - a. For wetlands these shall be the measures required by the Division of State Lands for regulatory wetlands.
    - b. For unstable areas these measures shall be documentation as approved by the Department of Public Works, that streets and building sites are on geologically stable soil considering the stress and loads to which the soil maybe subjected.
  5. That the development of the plan is phased to balance with the need for urbanization within the Woodburn Urban Growth Boundary.
  6. The tentative plan complies with all applicable provisions of the **WDO**, EXCEPT as may be waived by variance granted as provided in **WDO**.

**5.103.10 Telecommunications Facility, Specific Conditional Use**

- A. Purpose: The purpose is to provide a procedure to consider the siting of telecommunication facilities subject to clear and objective standards, and supplemental conditions as may be appropriate.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
1. Street and Utility Plan;
  2. Site Plan;
  3. A visual study containing, at a minimum, a vicinity map for the area within a three mile radius of the proposed site where any portion of the proposed tower could be visible. The study shall include a graphic simulation showing the appearance of the proposed tower and accessory structures from five points within the impacted vicinity. Such points shall be mutually agreed upon by the Director of Community Development and the applicant. The study shall not be required for collocation on existing transmission towers, but shall be required for collocation on other structures;
  4. A demonstration than all alternative technology that does not require the use of towers or structures, such as a cable microcell network using multiple low-powered transmitters/receivers attached to a wireline system is unsuitable. Costs of alternative technology that exceeds a new tower or antenna development shall be presumed to render the technology unsuitable.
  5. A landscape plan drawn to scale showing proposed landscaping, including type, spacing, size and irrigation methods. This plan shall not be required for collocation on existing buildings or where there is no opportunity to provide additional landscaping.
  6. Evidence demonstrating collocation is impractical on existing tower facility sites for reason of safety, available space, or failure to meet service coverage area needs. This evidence shall not be required for collocation proposals.
  7. A report containing the following information:
    - a. A description of the proposed tower and reasons for the tower design and height.
    - b. Documentation to establish the proposed tower has sufficient structural integrity for the proposed uses at the proposed location in conformance with minimum safety requirements as required by the State Structural Specialty Code, latest adopted edition.



- c. A description of mitigation methods, including increased setbacks, and/or de-icing equipment, which will be employed to avoid ice hazards.
- d. The general capacity of the tower in terms of the number and type of antennae it is designed to accommodate.
- e. Documentation demonstrating compliance with non-ionizing electromagnetic radiation (NEIR) emissions standards as set forth by the Federal Communications Commission (FCC).
- f. A signed agreement stating that the applicant will allow collocation with other users, provided all safety and structural requirements are met. This agreement shall also state that any future owners or operators will allow collocation on the tower. This agreement is not necessary if the applicant is collocating and does not own the facility or structure; however, a consent to allow the owner to grant access to other users for the same structure or facility shall be required.
- g. A soils report if the property contains weak foundation soils or has landslide potential.
- h. Documentation that the ancillary facilities will not produce sound levels in excess of *Section 2.204.03.A.8.* and will comply with Department of Environmental Quality standards for noise or a design that shows compliance with those standards.
- i. Identification of the entities providing the backhaul network for the tower(s) described in the application and other cellular sites owned or operated by the applicant within the City of Woodburn.

C. Criteria:

- 1. The proposed use shall be listed as an allowed conditional use within the zoning district.
- 2. The proposed use shall comply with the development standards of the zoning district.
- 3. The proposed use shall be compatible with the surrounding properties.

Considerations. Relevant factors to be considered in determining whether the proposed use is compatible include:

- a. The suitability of the size, shape, location and topography of the site for the proposed use;
- b. The capacity of public water, sewerage, drainage, street and pedestrian facilities serving the proposed use;
- c. The impact of the proposed use on the quality of the living environment:
  - 1) Noise;
  - 2) Illumination;
  - 3) Hours of operation;
  - 4) Air quality;
  - 5) Aesthetics; and
  - 6) Vehicular traffic.
- 4. The conformance of the proposed use with applicable Comprehensive Plan policies; and
- 5. The suitability of proposed conditions of approval to insure needed facility capacity and compatibility of the proposed use with other uses in the vicinity.
- 6. The specific standards and criteria of *Section 2.204.03* shall be met.

#### **5.103.11**      **Variance**

- A. Criteria. A variance may be granted to allow a deviation from a *WDO* development standard where the following criteria is met: [Section 5.103.11.A as amended by Ordinance No. 2446, §34, passed on September 8, 2008.]
  - 1. Strict adherence to the *WDO* standards is not possible or imposes an excessive burden on the property owner, and [Section 5.103.11.A.1 as amended by Ordinance No. 2446, §34, passed on September 8, 2008.]
  - 2. Variance to the standards will not unreasonably impact adjacent existing or potential uses or development. [Section 5.103.11.A.2 as amended by Ordinance No. 2446, §34, passed on September 8, 2008.]

A variance may not be granted from a standard governing use.

Standards set by statute relating to siting of manufactured homes on individual lots; siding and roof of manufactured homes; and manufactured home and dwelling park improvements are non-variable.

Additionally, certain specified minor deviations to development standards are allowed by a *Type II Zoning Adjustment, Section 5.102.03*.

- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
1. Street and Utility Plan as applicable; and
  2. Site Plan
- C. Factors to be Considered. A determination of whether the criteria set forth are satisfied necessarily involves the balancing of competing and conflicting interest. The factors that are listed to be considered are not criteria and are not intended to be an exclusive list. The factors to be considered are used as a guide in deliberations on the application. [Section 5.103.11.C as amended by Ordinance No. 2446, §34, passed on September 8, 2008.]
1. The variance is necessary to prevent unnecessary hardship relating to the land or structure, which would cause the property to be unbuildable by application of the **WDO**. Factors to consider in determining whether hardship exists, include:
    - a. Physical circumstances over which the applicant has no control related to the piece of property involved that distinguish it from other land in the zone, including but not limited to lot size, shape, topography.
    - b. Whether reasonable use similar to other properties can be made of the property without the variance.
    - c. Whether the hardship was created by the person requesting the variance.
  2. Development consistent with the request will not be materially injurious to adjacent properties. Factors to be considered in determining whether development consistent with the variance materially injurious include but are not limited to:
    - a. Physical impacts such development will have because of the variance, such as visual, noise, traffic and drainage, erosion and

landslide hazards.

- b. Incremental impacts occurring as a result of the proposed variance.
- 3. Existing physical and natural systems, such as but not limited to traffic, drainage, dramatic land forms or parks will not be adversely affected because of the variance.
- 4. The variance is the minimum deviation necessary to make reasonable economic use of the property;
- 5. The variance does not conflict with the Woodburn Comprehensive Plan.

#### **5.103.12 Exception to Street Right of Way and Improvement Requirements**

[Section 3.103.12 as amended by Ordinance No. 2423, §29, effective on July 28, 2007.]

- A. Purpose. The purpose of an exception is to allow a deviation from a **WDO** development standard required for the functional classification of the street identified in the Transportation System Plan in conjunction with a development proposal that is a Type III application.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. Street and Utility Plan as applicable;
  - 2. Site Plan; and
  - 3. A “rough proportionality” report prepared by a qualified civil or traffic engineer addressing the approval criteria.
- C. Criteria.
  - 1. The estimated extent, on a quantitative basis, to which the rights of way and improvements will be used by persons served by the building or development, whether the use is for safety or convenience;
  - 2. The estimated level, on a quantitative basis, of rights of way and improvements needed to meet the estimated extent of use by persons served by the building or development;
  - 3. The estimated impact, on a quantitative basis, of the building or development on the public infrastructure system of which the rights of

way and improvements will be a part; and

4. The estimated level, on a quantitative basis, of rights of way and improvements needed to mitigate the estimated impact on the public infrastructure system.

D. Proportionate Reduction in Standards

An exception to reduce a street right of way or cross section requirement below the functional classification standard may be approved when a lesser standard is justified based on the nature and extent of the impacts of the proposed development. No exception may be granted from applicable construction specifications.

E. Minimum Standards.

To assure a safe and functional street with capacity to meet current demands and to assure safety for vehicles, bicyclists and pedestrians, as well as other forms of non-vehicular traffic, there are minimum standards for right of way and improvement that must be provided. The minimum street improvement standard is identified in 3.101.02.D. Deviation from these minimum standards may only be considered by a variance procedure, ***Section 5.103.11***.

## 5.104 Type IV Application Requirements

[Section 5.104.01 amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

### **5.104.01**      **Annexation**

- A. Purpose. The purpose is to provide a procedure to incorporate contiguous territory into the City of Woodburn in compliance with state requirements and the Woodburn Comprehensive Plan.
- B. Mandatory Pre-Application Conference.
  - 1. Annexation proposals are subject to a mandatory Pre-application Conference. The Conference shall be conducted pursuant to ***Section 4.101.04***.
  - 2. Pre-Application materials. Anyone proposing an annexation shall submit the following materials when applying for the Mandatory Pre-Application Conference:
    - a. A preliminary site plan and phasing program for the proposed use and development;
    - b. Certification by the Public Works department of the adequate capacity of public facilities to serve the proposed development or that facilities necessary to provide adequate capacity must be determined;
    - c. Written documentation from the School District regarding adequate capacity, considering current and future enrollment and facilities, to serve the proposed development and from the Fire District regarding adequate capacity and access to serve the proposed development;
    - d. Traffic generation data regarding the proposed development sufficient to determine the need for a Traffic Impact Analysis;
    - e. Consent to annex all property that would be surrounded by the City if the annexation were approved, or written documentation regarding why such consent is unavailable; and
    - f. Written narrative statement showing compliance with applicable Woodburn Comprehensive Plan goals and policies regarding annexation.
- C. Annexation Application Requirements. An application shall include a completed

City application form, filing fee, deeds, notification area map and labels, narrative statement regarding compliance with criteria, location map and the following additional exhibits:

1. A fully executed Annexation Petition, submitted on forms provided by the City of Woodburn;
2. An accurate legal description in a form certifiable by the State Department of Revenue according to ORS 308.225;
3. Complete applications for all concurrent Comprehensive Plan Map amendment and/or Zoning Map change requests.

D. Application Criteria.

1. Annexation

- a. Findings showing compliance with applicable Woodburn Comprehensive Plan goals and policies regarding annexation, with the applicant bearing responsibility for the burden of proof.
- b. Territory to be annexed
  - 1) Shall be contiguous to the City of Woodburn; and
  - 2) Shall either:
    - a) Link to master plan public facilities with adequate capacity to serve development of the uses and densities indicated by the Woodburn Comprehensive Plan; or
    - b) Guarantee the facility linkages with adequate capacity, financed by the applicant.
- c. Annexations shall show a demonstrated community need for additional territory and development based on the following considerations:
  - 1) Lands designated for residential and community uses should demonstrate substantial conformance to: a), b), and e) and at least one of c) (i), c) (ii) or d), as stated below; and [Section 5.104.01.D.1.c.1 as amended by Ordinance No. 2383, §66, passed March 16, 2005.]
  - 2) Lands designated for commercial, industrial and other uses

should demonstrate substantial conformance to: h) and either f) or g), as stated below:

- a) Infill. The territory to be annexed should be contiguous to the City on two or more sides;
- b) Residential Buildable Land Inventory. The territory to be annexed should not increase the inventory of buildable land designated on the Comprehensive Plan as Low or High Density Residential within the City to more than a 5-year supply;
- c) Street Connectivity. It is feasible for development of the site to either:
  - (1) Complete or extend the arterial/collector street pattern as depicted on the Woodburn Transportation System Plan; or
  - (2) Connect existing stub streets, or other discontinuous streets, with another public street.
- d) Community Need. The proposed development in the area to be annexed fulfills a substantial unmet community need, that has been identified by the City Council after a public hearing. Examples of community needs include park space and conservation of significant natural or historic resources.
- e) Reinforcement of Public Investment. The territory proposed for annexation should reflect the City=s goals for directing growth by using public facility capacity that has been funded by the City=s capital improvement program;
- f) Local Employment. The proposed use of the territory to be annexed shall be for industrial or other uses providing employment opportunities;
- g) Reasonable Facility and Service Needs. The proposed industrial or commercial use of the territory does not require the expansion of infrastructure, additional service capacity, or incentives that are in excess of the costs normally



borne by the community for development; [Section 5.104.01.D.2.g as amended by Ordinance No. 2446, §35, passed on September 8, 2008.]

- h) Economic Diversification. The proposed industrial or commercial use of the territory provides an economic opportunity for the City to diversify its economy.
- d. Right to Farm Covenant. An application to annex land that is designated Low or Medium Density Residential on the Comprehensive Plan Map shall include a covenant on such property to be annexed where the owners, their successors, heirs, assigns and lessees, accept possible impacts from farming practices as normal, necessary and part of the risk of establishing a dwelling, structure, or use in the area; acknowledge the need to avoid activities that conflict with farming practices on nearby property; and, covenant not to pursue any claim for relief or cause of action alleging injury from farming practices for which no action is specifically allowed under **ORS 30.936 or 30.937**.

E. Procedures.

- 1. Annexation Initiated by Consent. *[ORS 222.125 and 222.170 (2)]* An annexation may be initiated by petition based on the written consent of:
  - a. The owners of more than half of the territory proposed for annexation and more than half of the resident electors within the territory proposed to be annexed; or
  - b. One hundred percent of the owners and fifty percent of the electors within the territory proposed to be annexed; or
  - c. A lesser number of property owners.
- 2. If an annexation is initiated by Section 5.104.01.E.1.c., after holding a public hearing and if the City Council approves the proposed annexation, the City Council shall call for an election within the territory to be annexed. Otherwise no election on a proposed annexation is required.
- 3. City Initiated Annexation of an Island. An island is an unincorporated territory surrounded by the boundaries of the City. The Oregon Revised Statutes (ORS) enables the City to initiate annexation of an island (ORS 222.750), with or without the consent of the property owners or the resident electors. Initiation of such an action is at the discretion of the City Council.

- F. Zoning Designation for Annexed Property. [Section 5.104.01.F as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
1. All land annexed to the City shall be zoned as follows unless an application to rezone the property to another zone has been submitted: [Section 5.104.01.F.1 as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
- a. Property shall be designated as RS, when the comprehensive plan designation is Low Density Residential. [Section 5.104.01.F.1.a as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
  - b. Property shall be designated as RM, when the comprehensive plan designation is Medium Density Residential. [Section 5.104.01.F.1.b as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
  - c. Property shall be designated as CO, when the comprehensive plan designation is Commercial. [Section 5.104.01.F.1.c as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
  - d. Property shall be designated as IL, when the comprehensive plan designation is Industrial. [Section 5.104.01.F.1.d as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
  - e. Property shall be designated as P/SP, when the comprehensive plan designation is open space and parks or public use. [Section 5.104.01.F.1.e as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]
2. If the annexed property is within an overlay designation, overlay shall apply to the annexed property. [Section 5.104.01.F.2 as amended by Ordinance No. 2446, §36, passed on September 8, 2008.]

**5.104.02 Comprehensive Plan Map Change, Owner Initiated**

[Section 5.104.02 as amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

- A. Purpose: The purpose is to provide a procedure for the consideration of a change in use designation on the Woodburn Comprehensive Plan, initiated by the property owner.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibit:
- 1. Transportation Impact Analysis (TIA), as applicable.

The application shall be reviewed to determine whether it significantly affects a transportation facility, in accordance with Oregon Administrative Rule (OAR) 660-012-0060. If the review indicates that a transportation facility could be significantly affected, a TIA may be required. Significant means the proposal would:

- a. Change the functional classification of an existing or planned transportation facility. This would occur, for example, when a proposal causes future traffic to exceed the capacity of “collector” street classification, requiring a change in the classification to an “arterial” street, as identified by the Transportation System Plan; or
- b. Change the standards implementing a functional classification system; or
- c. Allow types or levels of land use that would result in levels of travel or access that are inconsistent with the functional classification of a transportation facility; or
- d. Reduce the level of service of the facility below the minimum acceptable level identified in the Transportation System Plan.

C. Criteria. The applicant shall bear the responsibility for the burden of proof.

- 1. Proof that the current Comprehensive Plan Map is in error, if applicable.
- 2. Substantial evidence showing how changes in the community warrant the proposed change in the pattern and allocation of land use designations.
- 3. Substantial evidence showing how the proposed change in the land use designation complies with:
  - a. Statewide Planning Goals and Oregon Administrative Rules;
  - b. Comprehensive Plan goals and policies; and
  - c. Sustains the balance of needed land uses within the Woodburn Urban Growth Boundary.
- 4. Amendments to the comprehensive plan and land use standards which significantly affect a transportation facility shall assure that allowed land uses are consistent with the function, capacity, and level of service of the facility identified in the Transportation System Plan. This shall be accomplished by one of the following:

- a. Limiting allowed land uses to be consistent with the planned function of the transportation facility; or
- b. Amending the Transportation System Plan to ensure that existing, improved, or new transportation facilities are adequate to support the proposed land uses consistent with the requirement of the Transportation Planning Rule; or,
- c. Altering land use designations, densities, or design requirements to reduce demand for automobile travel and meet travel needs through other modes of transportation.

**5.104.03**      **Formal Interpretation of the WDO**

- A. Purpose: The purpose of a formal interpretation is to provide a procedure for the City Council to consider and to clarify through a public hearings process an ambiguous element of the **WDO**. [Section 5.104.03.A as amended by Ordinance No. 2383, §67, passed March 16, 2005.]
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibits:
  - 1. Citation of the portion of the **WDO** subject to interpretation;
  - 2. A description of specific circumstances for which an interpretation is requested;
  - 3. The proposed interpretation of the subject provisions of the **WDO**; and
  - 4. The positive and negative impacts of the proposed interpretation on the subject property and development, land and activity in the vicinity, and throughout the City in establishing a precedent.

- C. Criteria. The appropriateness of the proposed interpretation shall be reviewed considering the following factors:
1. The consistency of the proposed interpretation with the intent of the Comprehensive Plan based on an evaluation of applicable goals and policies;
  2. The compatibility of the interpretation with associated definitions, guidelines and standards of the **WDO** and applicable state statutes;
  3. The positive and negative consequences of the interpretation on the subject property, properties in the vicinity and its application through out the City as a whole; and
  4. The need for further consideration as either an amendment of the **WDO** or the consideration through the appropriate permitting review procedure.

**5.104.04 Zoning Map Change, Owner Initiated**

[Section 5.104.04 amended by Ordinance No. 2391, §3, acknowledged on December 22, 2006.]

- A. Purpose: The purpose is to provide a procedure to change the Zoning Map use designation, in a manner consistent with the Woodburn Comprehensive Plan.
- B. Application Requirements. An application shall include a completed City application form, filing fee, deeds, notification area map and labels, written narrative statement regarding compliance with criteria, location map and the following additional exhibit:
1. Transportation Impact Analysis (TIA), as applicable.

The application shall be reviewed to determine whether it significantly affects a transportation facility, in accordance with Oregon Administrative Rule (OAR) 660-012-0060. If the review indicates that a transportation facility could be significantly affected, a TIA may be required. Significant means the proposal would:

- a. Change the functional classification of an existing or planned transportation facility. This would occur, for example, when a proposal causes future traffic to exceed the capacity of “collector” street classification, requiring a change in the classification to an “arterial” street, as identified by the Transportation System Plan; or

- b. Change the standards implementing a functional classification system; or
- c. Allow types or levels of land use that would result in levels of travel or access that are inconsistent with the functional classification of a transportation facility; or
- d. Reduce the level of service of the facility below the minimum acceptable level identified in the Transportation System Plan.

C. Criteria. The applicant shall bear the responsibility for the burden of proof.

- 1. Evidence proving a need for the proposed use and the other permitted uses within the proposed zoning designation.
- 2. Evidence that the subject property best meets the need relative to other properties in the existing developable land inventory already designated with the same zone considering size, location, configuration, visibility and other significant attributes of the subject property.
- 3. Amendments to the comprehensive plan, zoning map and land use standards which significantly affect a transportation facility shall assure that allowed land uses are consistent with the function, capacity, and level of service of the facility identified in the Transportation System Plan. This shall be accomplished by one of the following:
  - a. Limiting allowed land uses to be consistent with the planned function of the transportation facility; or
  - b. Amending the Transportation System Plan to ensure that existing, improved, or new transportation facilities are adequate to support the proposed land uses consistent with the requirement of the Transportation Planning Rule; or,
  - c. Altering land use designations, densities, or design requirements to reduce demand for automobile travel and meet travel needs through other modes of transportation.

D. Delineation.

Upon approval, a zone change shall be delineated on the official zoning map by the Community Development Director. A zone change subject to specific conditions shall be annotated on the official zoning map to indicate that such conditions are attached to the designation.

# 6.1 APPENDICES

(Adopted by City Council Resolution)

## 6.101 Description of Application Exhibits

### 6.101.01 General Requirements

- A. Exhibit Standards for Type II, III and IV Permit Applications.

This **Section** describes the exhibit specifications for Type II, III or IV permit applications. Type I application requirements are described in the **WDO**.

- B. Additional Information.

Prior to deeming an application complete, the Community Development Director may request additional information.

- C. City Application Form and Application Fees.

A complete City application form and applicable jurisdictional fees are necessary for a complete application. Both items shall be present prior to deeming an application complete.

- D. Copies of the Application and Exhibits.

1. Unless otherwise indicated in writing by the Community Development Director, the number of copies of the application and exhibits specified in this **Section** is required to deem an application complete.
2. The Director may require subsequent submittal of additional copies of applications materials for an application that is called for review or appeal.
3. An exhibit may be submitted at a scale other than the scale specified in this **Section** when indicated in writing by the Director.

- E. Information Items That Apply to Only A Particular Type of Request.

The exhibit requirements may apply to more than one type of application. Consequently some application requirements make specific note when requirements apply to only specific proposed actions, as follows:

1. **MDP only** indicates the item is only required in a manufacture dwelling park [MDP] application.

2. **PUD only** indicates the item is only required in a planned unit development [PUD] application.

F. Standard Title Block and Legend.

To facilitate identification and review, the following information is required on each exhibit requiring a title block:

1. Type of Application. [Annexation, PUD, Variance, etc.]
2. Type of Exhibit [Location map, site plan, etc.]
3. Name of proposed development. [Required for only for Subdivision, **PUD**, or ***MDP*** applications.]
4. Name of applicant.
5. Scale bar and north arrow.
6. Date prepared and party that prepared the exhibit.
7. Legend of symbols used, including property lines of the subject property, City Limits, and UGB.

**6.101.02**      **Types of Exhibits**

- A. **Application Form and Application Fee.**
- B. **Deed(s).**
- C. **Assessor's Map(s)/Notification Area.**
- D. **Notification List.**
- E. **Location Map.**
- F. **Findings of Conformance with Approval Criteria.**
- G. **Site Plan.**
- H. **Street and Utilities Plan.**
- I. **Site Design Plan.**
- J. **Architectural Drawings and Materials Sample Board.**
- K. **Grading Plan.**
- L. **Preliminary Subdivision, Partition, PUD or Manufactured Dwelling Park Plan.**
- M. **Aerial Photograph.**
- N. **Concept Plan for Adjacent Property Interests.**
- O. **Preliminary PUD Design Plan.**
- P. **Phasing Plan.**
- Q. **Transportation Impact Analysis (TIA) Requirements.**



A. **City Application Form and Application Fee.** [One copy each]

Applications shall be submitted on City forms, accompanied by the requisite application filing fee.

B. **Deed(s).** [One copy each]

A current copy of the recorded deed(s) for the subject property, or the recorded sales contract, including an accurate legal description of the subject property.

C. **Assessor's Map(s)/Notification Area.** [One copy each]

Original prints of the current Assessor's Map(s) obtained from Marion County showing the boundary of the notification area 250 feet equi-distant from all boundaries of the subject property.

D. **Notification List** [Two (2) sets]

1. Two (2) sets of self-adhesive labels for each property within the notification area, showing the owner=s name, the tax lot number of the ownership and the owner=s mailing address.
2. A certification from the preparer of the notification list, that the address labels reflect the required ownership and address data as contained in the current property tax rolls.

E. **Location Map** [Not less than 15 copies, at 8.5" x 11", plus one, 8.5 x 11 inch reproducible copy.]

1. Standard title block and legend.
2. Scale: 1" = 800' or smaller.
3. Image area: 1320' from the perimeter of the site.
4. Data and Information:
  - a. Names and location of:
    - 1) All major streets within the map area
    - 2) All public streets accessing the site.
  - b. Zoning.
  - c. Site location of
    - 1) Public and private schools.

- 2) Public parks and public open space.

**F. Findings of Conformance with Approval Criteria.** [One copy each]

A written narrative by the applicant, making findings of compliance regarding the applicable approval criteria must be submitted for each land use action requested.

**G. Site Plan** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy.]

1. Standard title block and legend.
2. Scale: 1"= 20' to 1"= 50'.
3. Image Area: 250' from the perimeter of the subject property.
4. Site Data [Depicted on plan and summarized in tabular form.]
  - a. Any proposed use limitation.
  - b. Subject property. [Dimensions and area in square feet.]
  - c. Building and parking envelope based on required setbacks.
  - d. Yards/setbacks and buffer improvements. [Dimensions and improvement standards]
  - e. Residential units:
    - 1) Dwelling units. [Number and net density.]
    - 2) Living units. [Number and net density.]
5. Data and information. [Shown on the plan.]
  - a. Top of bank and center line of water courses.
  - b. Regulatory wetlands. [Wetlands shown on the Woodburn Wetlands Inventory that are within or abut the subject property require a "wetlands delineation" prepared by the applicant, at the time of application.]
  - c. 100 year flood plain .
  - d. Rights of way and street improvements.

- e. Water, sanitary sewer and storm drainage facilities, easements and public utility easements.
  - f. Driveway access points and direction of traffic flow.
- H. **Street and Utilities Plan.** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy.]
  - 1. Standard title block and legend.
  - 2. Scale of 1" = 20' to 1" = 40'.
  - 3. Image Area: 250' from the perimeter of the subject property.
  - 4. Streets. Existing and proposed. [Right of way and improvements including sidewalks and street trees].
  - 5. Water. Existing and proposed. [Lines with size, fire hydrants, meters, easements, and ownership].
  - 6. Sanitary sewers. Existing and proposed. [Lines with size, manholes and clean outs, easements and ownership].
  - 7. Storm drainage. Existing and proposed. [Pipes and culverts with size, catch basins, ditches, detention, easements and ownership].
  - 8. 100 year flood plain and regulatory wetlands.
  - 9. Traffic Impact Analysis if required by the **WDO**.
  - 10. Pedestrian and bike facilities.
  - 11. Driveways including direction of traffic flow.
  - 12. Public utility easements.
- I. **Site Design Plan.** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy.]
  - 1. Standard title block, excluding north arrow.
  - 2. Scale of 1" = 20' to 1" = 40'.
  - 3. Image Area: 250' from the perimeter of the subject property.
  - 4. Conditions of prior land use approvals, if applicable.

5. Area in square feet of :
  - a. Subject property.
  - b. Proposed development area or phase.
  - c. Landscaping.
  - d. Parking lots, excluding landscaping.
  - e. Buildings:
    - 1) Aggregate gross floor area.
    - 2) Per building: exterior dimensions, height, & gross floor area.
6. Number of parking spaces, including dimensions:
  - a. Standard.
  - b. Compact.
  - c. Disability.
  - d. Bicycle.
7. Residential units:
  - a. Dwelling units. [Number, net density & typical gross floor area/ unit.]
  - b. Living units. [Number, net density & typical gross floor area/ unit.]
8. Lot coverage by buildings and structures.
9. Open space:
  - a. Private open space area [Aggregate & by type of typical residential units.
  - b. Common open space area and facilities:
    - 1) Aggregate area.
    - 2) Recreation. [Including description of facilities.]
    - 3) Landscaped.
    - 4) Natural.
10. Top of bank and center line of water courses.
11. Regulatory wetlands.
12. 100 year flood plain .
13. Access ways, walkways and on-site bikeways.

14. Rights of way, driveways, street improvements, transit stops and easements, by function.
15. Fences, free standing walls, trash enclosures, electric transformers pads, exterior light standards and fixtures.
16. Landscaping [Depicted on plan and summarized in tabular form].
  - a. Proposed and existing landscaping [Area and location] .
  - b. Parking lot landscaping [Area and percentage of total landscaped area].
  - c. Trees [Location, species, status (retained, removed and planted) of private and street trees 4" or more in caliper] .
  - d. Plant materials. Description of plant units by species and size for each landscaped area.
  - e. Irrigation system [Type and area covered].
  - f. Replacement of topsoil [Location and depth].
17. Solid waste disposal enclosures.
18. Exterior lighting.

**J. Architectural Drawings and Materials Sample Board** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy of illustrations.] [Not less than one sample board.]

1. Standard title block and legend, excluding north arrow and property boundaries.
2. Elevations of proposed structures [Buildings, carports, garages, trash enclosures and storage facilities] at a scale of 1/16" = 1' to 1/4" = 1'.
3. Floor plans of primary buildings at a scale of 1/16" = 1' to 1/4" = 1', or Building Permit Application.
4. Exterior light fixtures, electrical transformer pads and roof top mechanical equipment.
5. Exterior materials samples showing samples and specifications for color and materials for walls, roof, windows, doors and trim:

- a. An 8.5" x 11" board; or
  - b. An accurately colored elevation with detailed narrative of specifications.
- K. **Grading Plan** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy.]
  - 1. Standard title block and legend.
  - 2. Scale of 1" = 20' to 1" = 40'.
  - 3. Contours [original and final grade] at vertical intervals of 2 feet.
  - 4. Cross-sections of the site as specified by the Public Works Director.
  - 5. Trees: Location, species, caliper over 4" [retained, removed and planted].
  - 6. Storm drainage and detention plans prepared by a registered engineer.
  - 7. Flood plain and floodway. {FEMA}
  - 8. Regulatory wetlands. [Wetlands shown on the Woodburn Wetlands Inventory that are within or abut the subject property require a "wetlands delineation" prepared by the applicant, at the time of application.]
- L. **Preliminary Subdivision, Partition, PUD or Manufactured Dwelling Park Plan.** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy.]
  - 1. Standard title block and legend, including:
    - a. Type of PUD, i.e., Single Family Residential or Mixed Use [**PUD only**].
    - b. Township, range and section.
    - c. Tax lots in subject property, with area and number.
  - 2. Scale: From 1" = 100' [1" = 50' or smaller, MDP only] or smaller.
  - 3. Image Area: 250' from the perimeter of the subject property.
  - 4. Property lines, existing and proposed.

5. Streets and easements, existing and proposed:
  - a. Public rights of way, with street names.
  - b. Public and private easements.
6. Contour lines: 2' interval.
7. Natural features:
  - a. 100 year flood plain. [FEMA]
  - b. Regulatory Wetlands. [Wetlands shown on the Woodburn Wetlands Inventory that are within or abut the subject property require a "wetlands delineation" prepared by the applicant, at the time of application.]
  - c. Rivers and streams. [USGS]
  - d. Wells. [State Water Resources]
  - e. Trees 4" or more in caliper, noting species.
8. Existing primary use of each existing lot shown within the image area.
9. Use, building footprint and dimensioned location of all existing structures within 50 feet of the subject property boundary.
10. Proposed street, driveway and lot [**MDP space**] layout with:
  - a. Lots [**MDP spaces**], showing:
    - 1) Principal dimensions.
    - 2) Lot **space**] area and building envelope. [Defined by setbacks [**MDP setbacks and separations.**]]
    - 3) Lot [**MDP space**] numbers.
    - 4) Lots of common ownership [**PUD only**].
    - 5) Play areas required by statute[ **MDP only**].
  - b. Rights of way [**MDP include private park streets**], with proposed street names.
  - c. Easements by function.
  - d. Water, sanitary sewer and storm drainage lines and locations; fire hydrant location, and storm water drainage and detention facilities.

**[For MDP only:**

- 1) Location of manufactured dwelling sewer connections and electrical outlets.
  - 2) Location of domestic water supply outlets.
  - 3) Location of water and sewer lines.
  - 4) Source of domestic water supply and private sewerage.
  - 5) Disposal system, or public water supply and sewer system.]
- e. Street lights. **[MDP only:** Location of light fixtures lighting park streets and sidewalks.]
- f. **[MDP only:** Location of permanent buildings.]
11. **[PUD only:** Draft homeowners [property owners] association agreement, including provisions for:
- a. The operation and maintenance of all common spaces and facilities; and
  - b. The architectural review process.
  - c. Draft Conditions, Covenants and Restrictions [C, C & R's] pertaining to all limitations EXCEPT architectural character and design guidelines.]

M. **Aerial Photograph.** [One copy] [An aerial photo is not acceptable as the base map for any other required exhibit.]

1. Standard title block and legend, including
  - a. Date of imagery. [Imagery shall be taken within two years of the application date].
  - b. Source of imagery.
2. Scale: 1" = 500' or smaller.
3. Image Area: 250' from the perimeter of the subject property.
4. Information and Data Requirements:
  - a. Boundary of the proposed site area.
  - b. Names and location of all major streets within the map area .



N. **Concept Plan for Adjacent Property Interests.** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11"]

1. Standard title block and legend.
2. Scale: 1" = 600' or smaller.
3. Image Area: Area within the UGB that is adjacent to the subject property and either owned or optioned by either the same property owner or the developer/applicant named in the subject application.
4. Contours: Vertical interval 2'.
5. Data and Information
  - a. A conceptual development plan for all adjacent land to the subject property that is owned or optioned by either the same property owner or the developer/applicant and that is located within the Urban Growth Boundary.
  - b. The location and classification of existing and future streets providing connectivity for the conceptual, future use of the adjacent property with existing public streets and with future major streets planned in the Woodburn Transportation System Plan.
  - c. The conceptual layout of lots and building areas by use type for the conceptual future use of the adjacent property. At a minimum the intensity, density and type of future land use shall reflect the current Comprehensive Plan designation.

O. **Preliminary PUD Design Plan.** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11"]

1. Standard title block and legend, including type of PUD, i.e., Single Family Residential or Mixed Use.
2. Image Area: Preliminary subdivision plan, or site plan for PUD's not proposed for concurrent subdivision, and area within 250' of the perimeter of the subject property.
3. Data and Information. [Tabular summary and depicted on the Preliminary PUD Design Plan.]
  - a. Net area within each zoning districts, reflecting concurrent zoning map change applications.

- b. Zoning , reflecting concurrent zoning map change applications, and area of each lot.
  - c. Use and/or density limitations within each zone as conditions of concurrent zoning map change or conditional use applications.
  - d. Area of each single family residential detached dwelling and duplex lot, indicating which lots exhibit reduced geometric standards due to off setting common open space.
  - e. Area, maximum net residential density and the equivalent number of dwelling/living units permitted on each RM and CO lot based on zoning designation after concurrent zoning map and conditional use applications.
  - f. Design standards altered, and lots, affected by concurrent variances to **WDO** standards.
  - g. Natural, recreation, and landscaped open spaces by type:
    - 1) Net area;
    - 2) Use limitations;
    - 3) Method of management [special setbacks, easements, common ownership, etc.];
    - 4) Conditions establishing the scope of improvements required to make the type of open space "useable"; and
    - 5) Location of RS and RM lots, and CO lots used for medium density residential dwelling or living units, benefitted by an equivalent density off-set provided by each open space area. The common open space and benefitted lots shall correlate with any proposed Phasing Plan.
4. Data and information. [Depicted on the Preliminary PUD Design Plan.]
- a. Streets, showing rights of way and improvements, as well as, cross sections of street classifications used, including paved surface, curbs, street, sidewalks, bike and/or golf cart lanes and street tree improvements.
  - b. Location of common areas and/or easements designated for off-street pedestrian, golf cart and/or bicycle ways and cross sectional standards for such facilities.
  - c. Location, access points, and number of common, off street parking spaces provided in lieu of on-street parking.

- d. Public water, sanitary sewer, storm drainage, and street lighting, as well as, storm water detention common areas and/or easements.
- e. Driveway access points and direction of traffic circulation for lots with controlled access.
- f. Building and off street parking envelope for each site defined by standard or proposed reduced setbacks.
- g. Type of landscaping and free standing wall buffer improvements required between zoning districts.
- h. Draft Conditions, Covenants and Restrictions [C, C & R's] pertaining to architectural character and design guidelines.

P. **Phasing Plan.** [Not less than 15 copies to scale, folded to 8.5" x 11", and one reproducible, 8.5" x 11" copy.]

- 1. Standard title block and legend.
- 2. Information and Data.


A diagram superimposed on the site plan or preliminary plat showing the location, size, sequence and estimated timing of each proposed phase and facility improvement.

Q. **Transportation Impact Analysis (TIA) Requirements.**

[Section 6.101.02Q as amended by Ordinance No. 2391, § 3, acknowledged on December 22, 2006.]

A Transportation Impact Analysis required for either a street (or access to a street) that is under City jurisdiction, a comprehensive plan map change, or a zoning map change shall be conducted to the specifications of the Public Works Department.

**Figure 6.1 Building Height Measurement  
(Composite of Several Roof Forms)**








Figure 6.2 Lots by Type




**Figure 6.3 Setbacks and Yards**

Figure 6.4 – Vision Clearance Area




## Figure 6.4 Vision Clearance Area

[Figure 6.4 as amended by Ordinance No. 2446, §38, passed on September 10, 2008.]



**Figure 6.5 Duplex on a Corner Lot**






**Figure 6.6 Street: Typical Cross Sections**

[Figure 6.6 deleted pursuant to Ordinance No. 2391, §3, acknowledge on December 22, 2006]

[Pursuant to Section 3.101.03.A, **Figure 7-2 Street Design Standards** is included here as a reference.]



**Figure 6.7 Flag Lots, Two Deep**






Figure 6.8 Flag Lots, Three and Four Deep, Infill Locations



[Not To Scale]


**Figure 6.9 Hammerhead Turnaround**




Note: C, D, D-0, E-1, & E-2 relate to Table 3.1.4, Parking Space and Aisle Dimensions

Figure 6.10 Parking Space and Aisle Dimensions


[Figure 6.10 as amended by Ordinance No. 2383, §68, passed March 16, 2005.]



**Standard Subdivision**  
15 Single Family Residential Lots




**Mixed Use PUD**  
8 Single Family Residential Lots  
7 Medium Density Residential Dwellings




**Single Family Residential PUD**  
15 Single Family Residential Lots

**Figure 6.11 Residential Development Alternatives: Subdivision & PUD**



**Figure 6.12 Connecting, Boundary and Internal Streets**





## 6.103 Tree Guidelines

The following varieties and species of trees are applicable to the requirements of the **WDO**, including:

1. The street tree requirements (*Section 2.102.07.F; 2.103.07F; 2.104.07.F; 2.105.05.F; 2.106.05.E; 2.107.07.D; 2.109.06.E; 2.110.06.E; and 2.111.06.E*);
2. The streetscape requirements (*Section 3.106.03.A*); and
3. The off street parking areas (*Sections 3.106.03.B*).

Other varieties, species, cultivars may be accepted upon review and approval by the Community Development Director.

### Small Trees

<i>18-30 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
Globosum Norway Maple	Acer platanoides >Globosum=	Kwanzan Cherry Plum	Prunus >Kwanza=
>Fastigiata= Golden Raintree	Koelreoteria paniculata >Fastigiata=		
<i>30-40 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
English Hedge Maple	Acer camestrea	Golden Raintree	Koelreoteria paniculata
Gerling Red Maple	Acer rubrum >Gerling=	Chanticleer Pear	Pyrus calleryana
Tilford Red Maple	Acer rubrum >Tilford=	Ranch Callery Pear	Pyrus calleryana
Schlesinger Red Maple	Acer rubrum >Schlesinger=	Trinity Pear	
Pyramidal European Hornbeam	Carpinus betulus >Pyramidal=	Mongolian Linden	Tilia mongolica

## Medium Trees

<i>35-50 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
Cavalier Norway Maple	Acer platanoides	Crimean Linden	Tilia x euchlora
Royal Crimson Maple	Acer platanoides >Royal Crimson=	Rancho Littleleaf Linden	Tilia cordata >Rancho=
Shade King Red Maple	Acer rubrum >Shade King=	European Hornbeam	Carpinus
Ruby Red Horse Chestnut	Aesculus x carnea >Briotii=		

## Large Trees

<i>60-120 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
Cleveland Norway Maple	Acer platanoides >Cleveland=	American Linden	Tilia americana
Norway Maple Cultivars	Acer platanoides	Beech	Fagus Species
Sycamore Maple	Acer pseudoplatanus	Tupelo, or Blackgum	Nyssa sylvatica
Red Maple	Acer rubrum	Blue Ash	Fraxinus quadrangulata
Sugar Maple	Acer saccharum	Oriental Planetree	Plantanus orientalis
Thornless Honeylocust	Gleditsia triacanthos var. inermis		

## Prohibited Trees

Fruit bearing trees, conifers, or any of the following trees are prohibited within public rights of way and utility easements.		
Common Name	Scientific Name	Negative Attributes
Almira Norway Maple	Acer platanoides >Almira=	Sidewalk damage
Box Elder	Acer negundo	Weak wood, sidewalk damage
Silver Maple	Acer saccharinum	Sidewalk damage, root invasion into pipes
Horse Chestnut	Aesculus hippocastanum	Significant litter [hard fruit (nut) 1"-3" dia.]
Tree of Heaven	Ailanthus altissima	Sidewalk damage
Lavalle Hawthorne	Crataegus lavellei	Hazardous [thorns on trunk and branches]
Hickory, Pecan	Carya Species	Significant litter [hard fruit 1"-3" dia.]
Cataplas	Catalpa Species	Significant litter [hard fruit 12" or more, elongated pod]
Hackberry, or Sugarberry	Celtis Species	Significant litter [Fleshy fruit, less than 0.5" dia.]
European Ash	Fraxinus excelsior	Disease susceptible, significant litter
Green Ash	Fraxinus pennsylvanica	Susceptible to insects and disease, crotch breakage, significant litter
Desert, or Velvet, Ash	Fraxinus velutina	Susceptible to bores, crotch breakage, significant litter
Ginko, or Maidenhair, Tree	Ginkgo biloba	Disgusting odor from squashed fruit when female near male
Winter Crab Apple	Malus >Winter Gold=	Significant litter [Fleshy fruit, 0.5" to 1.0@ dia.]
Profusion Crab Apple	Malus >Sargent=	Significant litter [Fleshy fruit, less than 0.5" dia.]
Holly	Ilex Species	Sight obstruction [evergreen, low foliage]
Walnuts	Juglans Species	Significant litter [hard fruit (nut) 1"-3" dia.]

## Prohibited Trees (continued)

Fruit bearing trees, conifers, or any of the following trees are prohibited within public rights of way and utility easements.		
Common Name	Scientific Name	Negative Attributes
Sweetgum	Liquidambar styruciflua	Significant litter [hard fruit (nut) 1"-3" dia.]
Oak	Quercus Species	Significant litter [hard fruit 0.5"-1" dia.]
Spruces	Picea Species	Sight obstruction [evergreen, low foliage]
Pines	Pinus Species	Sight obstruction [evergreen, low foliage]
Poplar, Cottonwood	Populus Species	Brittle, significant litter
Thundercloud Plum	Prunus AThundercloud=	Significant litter [Fleshy fruit, 1 to 3"dia.]
Willow	Salix Species	Root invasion into pipes
Lilac	Syringa Species	Sight obstruction [low foliage], associated with pollen allergies
Elms	Ulmus Species	Susceptible to Dutch elm disease

## 6.103 Tree Guidelines

The following varieties and species of trees are applicable to the requirements of the **WDO**, including:

1. The street tree requirements (*Section 2.102.07.F; 2.103.07F; 2.104.07.F; 2.105.05.F; 2.106.05.E; 2.107.07.D; 2.109.06.E; 2.110.06.E; and 2.111.06.E*);
2. The streetscape requirements (*Section 3.106.03.A*); and
3. The off street parking areas (*Sections 3.106.03.B*).

Other varieties, species, cultivars may be accepted upon review and approval by the Community Development Director.

### Small Trees

<i>18-30 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
Globosum Norway Maple	Acer platanoides >Globosum=	Kwanzan Cherry Plum	Prunus >Kwanza=
>Fastigiata= Golden Raintree	Koelreoteria paniculata >Fastigiata=		
<i>30-40 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
English Hedge Maple	Acer camestre	Golden Raintree	Koelreoteria paniculata
Gerling Red Maple	Acer rubrum >Gerling=	Chanticleer Pear	Pyrus calleryana
Tilford Red Maple	Acer rubrum >Tilford=	Ranch Callery Pear	Pyrus calleryana
Schlesinger Red Maple	Acer rubrum >Schlesinger=	Trinity Pear	
Pyramidal European Hornbeam	Carpinus betulus >Pyramidal=	Mongolian Linden	Tilia mongolica

## Medium Trees

<i>35-50 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
Cavalier Norway Maple	Acer platanoides	Crimean Linden	Tilia x euchlora
Royal Crimson Maple	Acer platanoides >Royal Crimson=	Rancho Littleleaf Linden	Tilia cordata >Rancho=
Shade King Red Maple	Acer rubrum >Shade King=	European Hornbeam	Carpinus
Ruby Red Horse Chestnut	Aesculus x carnea >Briotii=		

## Large Trees

<i>60-120 feet in height</i>			
Common Name	Scientific Name	Common Name	Scientific Name
Cleveland Norway Maple	Acer platanoides >Cleveland=	American Linden	Tilia americana
Norway Maple Cultivars	Acer platanoides	Beech	Fagus Species
Sycamore Maple	Acer pseudoplatanus	Tupelo, or Blackgum	Nyssa sylvatica
Red Maple	Acer rubrum	Blue Ash	Fraxinus quadrangulata
Sugar Maple	Acer saccharum	Oriental Planetree	Plantanus orientalis
Thornless Honeylocust	Gleditsia triacanthos var. inermis		

## Prohibited Trees

Fruit bearing trees, conifers, or any of the following trees are prohibited within public rights of way and utility easements.		
Common Name	Scientific Name	Negative Attributes
Almira Norway Maple	Acer platanoides >Almira=	Sidewalk damage
Box Elder	Acer negundo	Weak wood, sidewalk damage
Silver Maple	Acer saccharinum	Sidewalk damage, root invasion into pipes
Horse Chestnut	Aesculus hippocastanum	Significant litter [hard fruit (nut) 1"-3" dia.]
Tree of Heaven	Ailanthus altissima	Sidewalk damage
Lavalle Hawthorne	Crataegus lavellei	Hazardous [thorns on trunk and branches]
Hickory, Pecan	Carya Species	Significant litter [hard fruit 1"-3" dia.]
Cataplas	Catalpa Species	Significant litter [hard fruit 12" or more, elongated pod]
Hackberry, or Sugarberry	Celtis Species	Significant litter [Fleshy fruit, less than 0.5" dia.]
European Ash	Fraxinus excelsior	Disease susceptible, significant litter
Green Ash	Fraxinus pennsylvanica	Susceptible to insects and disease, crotch breakage, significant litter
Desert, or Velvet, Ash	Fraxinus velutina	Susceptible to bores, crotch breakage, significant litter
Ginko, or Maidenhair, Tree	Ginkgo biloba	Disgusting odor from squashed fruit when female near male
Winter Crab Apple	Malus >Winter Gold=	Significant litter [Fleshy fruit, 0.5" to 1.0@ dia.]
Profusion Crab Apple	Malus >Sargent=	Significant litter [Fleshy fruit, less than 0.5" dia.]
Holly	Ilex Species	Sight obstruction [evergreen, low foliage]
Walnuts	Juglans Species	Significant litter [hard fruit (nut) 1"-3" dia.]

## Prohibited Trees (continued)

Fruit bearing trees, conifers, or any of the following trees are prohibited within public rights of way and utility easements.		
Common Name	Scientific Name	Negative Attributes
Sweetgum	Liquidambar styraciflua	Significant litter [hard fruit (nut) 1"-3" dia.]
Oak	Quercus Species	Significant litter [hard fruit 0.5"-1" dia.]
Spruces	Picea Species	Sight obstruction [evergreen, low foliage]
Pines	Pinus Species	Sight obstruction [evergreen, low foliage]
Poplar, Cottonwood	Populus Species	Brittle, significant litter
Thundercloud Plum	Prunus AThundercloud=	Significant litter [Fleshy fruit, 1 to 3"dia.]
Willow	Salix Species	Root invasion into pipes
Lilac	Syringa Species	Sight obstruction [low foliage], associated with pollen allergies
Elms	Ulmus Species	Susceptible to Dutch elm disease



## 6.104 Use Classifications in the WDO

### Construction (23)

Use (NAICS #)	RS	RIS	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCWOD	SWIR	Nodal RS	Nodal RM
<b>Construction of Buildings (233-236)</b>								P	P					
<b>Heavy and Civil Engineering constructions (234-237)</b>								P	P					
<b>Special trade contractors (235-238)</b>								P	P					
Plumbing, heating and air-conditioning contractors (238220)					P									
Paper and wall covering (238320)					P									
Masonry (238140)					P									
Drywall and Installation (238310)														
Tile (238340)														
Floor laying contractors (235520)					P									
Roofing, siding, and sheet metal construction contractors (235610) entirely within a building					P									
Glass and glazing contractors (235920)					P									
Building equipment and other machinery installation contractors (235950)					P									
Ornamental ironwork contracting (235990)					P									
Carpenter (238130) entirely within a building					P									

## Manufacturing (31-33)

Use (NAICS #)	RS	RIS	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCWOD	SWIR	Nodal RS	Nodal RM
<b>Food manufacturing (311)</b>								P	P					
<b>Bakeries (31181)</b>						P	P							
<b>Beverage and tobacco product manufacturing (312)</b>								P	P					
<b>Textile product mills (314)</b>								P	P					
<b>Apparel manufacturing (315)</b>						SP	SP	P	P					
<b>Leather and allied products manufacturing (316)</b>								P	P					
Other leather manufacturing (31699)						SP	SP							
<b>Paper manufacturing (317)</b>														
Paper manufacturing (317) limited to assembly								P	P					
<b>Printing and related support activities (318)</b>								P	P					
<b>Wood products manufacturing (321)</b>								CU	P					
<b>Paper manufacturing (322)</b>									CU					
<b>Printing and related support activities (323)</b>						P	P					P		
<b>Petroleum and coal products manufacturing (324)</b>														
Petroleum and coal products manufacturing (324) with all storage underground									CU					
<b>Chemical manufacturing (325)</b>								CU	CU					
<b>Plastics and rubber product manufacturing (326)</b>								P	P					
<b>Nonmetallic mineral product manufacturing (327)</b>									P			P		
<b>Primary metal manufacturing (331)</b>									CU					
<b>Fabricated metal products manufacturing (332)</b>								P	P					

Fabricated metal product manufacturing (332) entirely within a building					P									
<b>Machinery manufacturing (333)</b>								P	P			P		
<b>Computer and electronic product manufacturing (334)</b>								P	P			P		
<b>Electrical equipment, appliance and component manufacturing (335)</b>								P	P			P		
<b>Transportation equipment manufacturing (336)</b>								P	P			P		
<b>Furniture and related product manufacturing (337)</b>						SP	SP	P	P					
Household and institutional furniture and kitchen cabinet manufacturing (3371) entirely within a building					P									
<b>Misc. Manufacturing (339)</b>								P	P					
Sporting goods manufacturing (33992)						SP	SP							
Doll, toy and game manufacturing (33993)						SP	SP							

## Wholesale Trade (42)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Wholesale trade, durable goods (423)</b> EXCEPT motor vehicle wrecking yards (423140 and 423930)								P	P			P		
<b>Wholesale trade, nondurable goods (424)</b>												P		
Wholesale trade, nondurable goods (424)								P	P					

## Retail Trade (44-45)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Motor vehicle and parts dealers (441)</b>								SP						
Motor vehicle and parts dealers (441) EXCEPT automotive parts without installation					CU									
Automotive parts (44131) without installation					P									
<b>Use (W/O NAICS classification)</b>														
Tractor and heavy equipment dealers					CU									
Tractor and farm machinery and equipment dealers								SP						
Truck dealers INCLUDING new truck, used truck, parts and tire dealers								SP						
<b>Furniture and home furnishings stores (442)</b>					P	P	P							
Picture frame shop (442299)	SCU		SCU										SCU	SCU
<b>Electronics and appliances (443)</b>					P									
Stores and repair (44310)						P								
<b>Building material and garden equipment (444)</b>														

Building material and supplies dealers (444) with all outdoor storage and display enclosed by a 7' masonry wall					P									
Paint, wallpaper, and interior decorating stores (444120)					P	P	P							
Hardware stores (44413)					P	P	P							
Light fixture stores (444190)					P	P	P							
Nursery, Garden Center and Farm Supply Stores (444220)					P	P	P							
<b>Use (W/O NAICS classification)</b>														
Farm, garden and landscaping supplies								SP						
<b>Food and beverage stores (445)</b>					P									

## Retail Trade (44-45) (continued)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
Grocery store, food market, food store (44511)						CU	P							
Meat markets (44521)					P	P	P							
Fish markets LIMITED TO sales only (44522)					P	P	P							
Candy, nut, confectionery stores. (445292)					P	P	P							
Dairy products stores LIMITED TO sales only. (44529)					P	P	P							
<b>Use</b>														
Delicatessen stores. (445110, 445210, and 722211)					P	P	P							
Wine shops. (445310 and 722410)						CU								
<b>Health and personal care stores (446)</b>					P									

Pharmacies and Drug stores. (44611)					P	P	P							
Optical goods stores. (44613)					P	P	P							
Health food stores. (446191)					P	P	P							
Hearing aid stores. (446199)					P	P	P							
<b>Gasoline stations (447)</b>					CU									
Gasoline stations with convenience stores. (447110)						CU								
<b>Clothing and clothing accessories stores (448)</b>	SCU		SCU		P								SCU	SCU
Clothing stores (44810)					P	P	P							
Men's (448110)														
Women's (448120)														
Children's (448130)														
Furriers and fur shops (44819)					P	P	P							
Jewelry, watch, and clock stores (44815 & 44831)					P	P	P							
Shoe stores (44823)					P	P	P							
Luggage stores (44832)					P	P	P							
<b>Use (W/O NAICS classification)</b>														
<b>Sporting goods, hobby, book, and music stores (451)</b>					P									
Sporting goods stores (451110)					P	P	P							
Gun Shop (451110)					P	P	P							
Hobby shops (45112)					P	P	P							

Toy stores (45112)					P	P	P							
--------------------	--	--	--	--	---	---	---	--	--	--	--	--	--	--

## Retail Trade (44-45) (continued)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
Sewing, needlework and piece goods (45113)					P	P	P							
Music, piano, and musical instrument (45114)					P	P	P							
Record and CD stores (45122)					P	P	P							
<b>General merchandise stores (452)</b>					P									
Department stores (45211)					P	P	P							
Book stores (451211)					P	P	P							
Other general merchandise stores (4529)					P	P	P							
<b>Misc. store retailers (453)</b>						P	P							
Misc. store retailers (453) EXCEPT used merchandise stores (4533), other than antique shops, and EXCEPT manufactured (mobile) home dealers. (45393)					P									
Florist shops (45311)					P	P	P							
Stationery stores (45321)					P	P	P							
Business machines, typewriters and repair (453210)					P	P	P							
Gift, novelty, souvenir shops (45322)					P	P	P							
Greeting card stores (45322)					P	P	P							
Used merchandise stores (4533), other than antique shops					CU		P							
Antique shops (453310)					P	P	P							

Used merchandise stores (45331)						P	P							
Pet stores (45391)					P	P	P							
Art gallery (45392)	SCU		SCU		P	P	P						SCU	SCU
Manufactured (mobile) home dealers. (453930)					CU		P	SP						
Artists supply stores (453998)					P	P	P							
Electronic Shopping and Mail order houses (45411)					P	P								
<b>Use (W/O) NAICS classification)</b>														
Auction houses EXCEPT livestock and poultry sales									P					
Prosthetic Stores (446199)						P								
Temporary residential sales: a. Produce and plant materials grown on the subject property b. Estate, garage and yard sales c. Crafts and other hobby items	SP	SP		SP	SP	SP							SP	



## Transportation and Warehousing (48-49)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Truck transportation (484)</b>								CU	P					
<b>Transit and ground transportation (485)</b>								CU	P					
Urban transit system (48511)					CU									
Interurban and rural transit (4852)					CU									
Taxi service (48531)					CU									
Limousine service (4853)					CU									
School transportation (4854)					CU									
Charter bus service (4859)					CU									
Special needs transportation (485991)					CU									
Support Activities for Rail Transportation (488210)						P	P							
Motor vehicle towing (48841)					CU									
Freight transportation arrangement (488510)								CU	P					
<b>Postal service (491)</b>				P	P	P	P							
<b>Warehousing and storage (493)</b>								CU	P					
<b>Use (w/o NAICS classification)</b>														
Self- and mini-storage					CU			CU	P					

## Information (51)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Publishing (511)</b>					P									
Newspaper, periodical, and book publishing. (5111)					P	P	P							
<b>Motion picture, sound recording industries (512)</b>														
Motion picture theaters (512131) EXCEPT drive-ins					P									
<b>Broadcasting and telecommunications (513)</b>														
Radio and TV (5151)					P									
Radio and TV studios and offices (5151) EXCEPT antennae and towers				P	P	P	P							
Cable networks (515210)				P	P	P	P							
Telecommunications (5171) EXCEPT telecommunication facilities subject to Section 2.204.03.				P	P	P	P							
<b>Use (w/o NAICS classification)</b>														
Telecommunication facilities subject to Section 2.204.03.								SCU	SCU					
<b>Data processing, Hosting and Related Services (518)</b>				P	P	P	P							
<b>Other Information (519120 and 519190 (CG))</b>														

## Finance and Insurance (52)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
Finance and insurance <b>(52)</b> EXCEPT pawn shops (522298) & check cashing, pay day loan and cash transfer establishments [other than banks] as a predominant, ancillary, or required supporting use				P	P									
Finance and insurance <b>(52)</b> EXCEPT check cashing, pay day loan and cash transfer establishments [other than banks] as a predominant, ancillary, or required supporting use						P	P							
<b>Credit intermediation &amp; related activities (522)</b>												P		
Pawn shops (522298)					CU	P								
<b>Use (w/o NAICS classification)</b>														
Check cashing, pay day loan and cash transfer establishments, other than banks					CU									

## Real Estate and Rental and Leasing (53)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Real estate (531)</b>				P	P	P	P							
<b>Rental and leasing (532)</b>														
Video tape and disc rental (532230)					P									
Rental and leasing (532) without outdoor display or storage, EXCEPT video tape and disk rental (532230)				P		P								
Rental and leasing (532) without outdoor display or storage						P	P							
General rental centers (532310) with all outdoor storage and display on a paved surface					P									

## Professional, Scientific and Technical Services (54)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Professional, scientific and technical services (54)</b>														
Legal services (5411)	SCU		SCU	P	P	P	P					P	SCU	SCU
Accounting (5412)	SCU		SCU	P	P	P	P					P	SCU	SCU
Architects and engineers (5413)	SCU		SCU	P	P	P	P					P	SCU	SCU
Specialized design services (5414)	SCU		SCU	P	P	P	P					P	SCU	SCU
Computer system design (5415)	SCU		SCU	P	P	P	P					P	SCU	SCU
Management, Scientific and Technical Consulting Services (5416)	SCU		SCU	P	P	P	P					P	SCU	SCU
Scientific research and development. (5417)					CU							P		
Advertising (5418)	SCU		SCU	P	P	P	P					P	SCU	SCU

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Professional, scientific and technical services (54)</b>														
Other professional services (5419), EXCEPT veterinary service (541940) not contained in a building				P	P	P	P					P		
Veterinary service. (541940)					CU							P		

## Administrative and Support Services (56)

Use (NAICS #)	RS	RIS	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Administrative and support services (561)</b>					P							P		
Administrative and facilities support services. (5611 and 5612)				P	P	P	P							
Employment services. (5613)				P	P	P	P							
Business support services INCLUDING copy shops. (5614)				P	P	P	P							
Travel and tour agencies. (5615)				P	P	P	P							
Telephone answering service (561421)	SCU		SCU	P	P	P							SCU	SCU
Investigation and security services. (5616)				P	P	P	P							
Services to buildings and dwellings (5617), offices only				P	P	P	P							
Services to buildings and dwellings (5617)					P									
Other support services (56199)				P	P	P	P							
Recycling Centers (562920)								CU	CU					

## Educational Services (61)

Use (NAICS #)	RS	RIS	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Educational services (611)</b>														
Elementary and secondary schools (6111)	CU		CU			P	P			CU			CU	CU
Community college (6112)						P	P							
Business schools (6114)				P	P	P	P							
Technical and trade schools (6115)				P	P	P	P	P	P					

## Health Care and Social Services (62)

Use (NAICS #)		R1S	RM	CO	CG	DDC	NNC	IP		P/SP	RCW OD	SWIR		Nodal RM
<b>Ambulatory health care facilities (621)</b>										CU				
Ambulatory health services (621) EXCEPT ambulance service (62191)				P	P	P	P				P	P		
Offices of Physicians (6211)	SCU		SCU	P	P	P							SCU	SCU
Offices of Dentists (6212)	SCU		SCU	P	P	P							SCU	SCU
Offices of Other Health Practitioners (6213)	SCU		SCU	P	P	P							SCU	SCU
Ambulance service (62191)				CU	CU			P	P	CU				
<b>Hospitals (622)</b>										CU				
<b>Social assistance (624)</b>				P	P	P	P							
Other individual and family services (6241)	SCU		SCU	P	P	P	P						SCU	SCU
Child day care services (6244)	SCU		P, SCU	P			P						SCU	P, SCU
Child day care services (6244), EXCEPT family child day care for 12 or fewer children	CU			P			P						CU	
<b>Use (w/o NAICS classification)</b>														
Family child day care for 12 or fewer children	P	P											P	

Group home or group care facilities			P	CU										P
Group home	P	P	P										P	P



## Arts, Entertainment and Recreation (71)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Performing arts and spectator sports (711)</b>					P									
Taxidermists. (71151)					P	P	P							
<b>Museums and historic sites (712)</b>														
Museums and historic sites (712) EXCEPT zoos (712130)				P	P	P	P							
<b>Amusement, Entertainment and Recreation (713)</b>														
Fitness and recreational sports (713940)				P	P	P	P							
Bowling centers (71395)					P									
Other amusements INCLUDING ballrooms (713990)					P									
<b>Use (w/o NAICS classification)</b>														
Aquatic facilities										CU				
Community center						P	P							
Community club buildings and facilities	SP	SP	SP										SP	SP
Golf courses without a driving range	SP	SP	SP							P			SP	SP
Golf driving range	CU		CU							CU			CU	CU
Parks	P	P								P			P	
Parks and playgrounds	P		P							P			P	P
Play or ball field										CU				
Temporary Outdoor Marketing and Special Events:					SP	SP	SP			SP				
a. Arts and crafts														

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
b. Food and beverages, including mobile food services c. Seasonal sales of fireworks, Christmas trees, produce or plant materials d. Amusement rides and games e. Entertainment f. Any other merchandise or service which is neither accessory to a primary, permanent use of the subject property nor marketed by employees of that permanent use														

## Accommodations and Food Service (72)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Accommodation (721)</b>														
Hotels (EXCEPT casino hotels) and motels (72111)				P	P	P	P							
Bed and breakfast inns (721191)	SCU		SCU	P	P	P	P						SCU	SCU
<b>Food Services and Drinking Places (722)</b>														
Food service and drinking places (722) EXCEPT mobile food service					P									
Food service and drinking places (722) EXCEPT food contractors (7231) and mobile food service				P		P	P							
Food services and drinking places (722) for industrial employees EXCEPT mobile food service.								CU	CU					
Recreational vehicle parks. (7212)					CU									
<b>Use (w/o NAICS classification)</b>														
Mobile food service subject to <i>Section 2.203.17</i> .								SP	SP			SP		

## Other Services (EXCEPT Public Administration) (81)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP		P/SP	RCW OD	SWIR		Nodal RM
<b>Repair and maintenance (811)</b>														
Automotive maintenance (8111)					CU									
Electronic and precision equipment repair (8112)					P									
Commercial and industrial equipment repair (8113)					CU			CU	P					
Home goods repair (8114) EXCEPT Upholstery (81142) and Leather repair (81143)					CU									
Upholstery (81142)					P									
Leather repair (81143)					P									
Dressmaker and tailor shops (315211)						P	P							
<b>Personal and laundry facilities (812)</b>														
Personal care services (8121)				P	P	P	P							
Funeral homes (812210)				P	P	P	P							
Cemetery (812220)										CU				
Dry cleaning and laundry service (8123) EXCEPT linen supply (81233)					P									
Laundry, self service (81231)					P	P	P							
Dry cleaning, self service (81231)					P	P	P							
Linen supply (81233)					CU									
Photo finishing (81292)				P	P	P	P							

Parking lots and garages (81293)	CU							P	P				CU	
Parking lots and garages (81293) EXCEPT extended vehicle storage (493190)				P	P	P	P							
Public parking lots and garages (81293) EXCEPT extended vehicle storage. (493190) and parking as an Accessory Use										CU				

## Other Services (EXCEPT Public Administration) (81) (continued)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL					
All other personal services (812990)				P	P	P	P							
<b>Religious, civic and social organizations (813)</b>				P	P	P	P							
<b>Use (w/o NAICS classification)</b>														
Delivery services	SP	SP	SP	SP	SP	SP	SP	SP	SP	SP		SP	SP	SP
Electric motor repair, entirely within a building					P									
Home Occupation	SP	SP	SP										SP	SP
House of worship (812990)	SP	SP	SP										SP	SP
Motor vehicle wrecking yards									CU					
Off street parking in conjunction with a non-residential use allowed in the zone	CU	CU	CU										CU	CU
Public parking for uses in the same zoning district										AU				

Residential sales office	SP	SP											SP	SP
--------------------------	----	----	--	--	--	--	--	--	--	--	--	--	----	----

## Public Administration (92)

Use (NAICS #)		R1S	RM	CO	CG	DDC	NNC	IP		P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Public Administration (92)</b>				P	P	P								
Fire protection (922160)								P	P			P		

## Public Administration (92) (continued)

Use (NAICS #)		R1S	RM	CO	CG	DDC	NNC	IP		P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Use (w/o NAICS classification)</b>														
Government maintenance facilities and storage yards								P	P			P		
Government and public utility buildings and structures EXCEPT uses permitted in the subject zone and telecommunication facilities subject to <i>Section 2.204.03</i>	CU		CU	CU	CU	CU	CU	CU	CU	CU			CU	CU
Government and public utility buildings and structures EXCEPT uses permitted in <i>Section 2.103.01</i> ; telecommunication facilities subject to <i>Section 2.204.03</i> ; and elementary, middle and high schools		CU												
Government and public utility buildings and structures EXCEPT uses permitted in <i>Section 2.110.01</i> and telecommunications facilities subject to Section 2.204.03.												CU		
Rights of way, easements and the improvements therein	P	P	P	P	P	P	P	P	P	P		P	P	P

# Residential

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
Use (w/o NAICS classification)														

## One Dwelling Unit

Site-built single family dwelling.	P	P	P										P	P
Manufactured home on a lot	SP	SP	SP										SP	SP
Dwelling for caretaker or watchperson.								P	P	AU		P		
One dwelling unit in conjunction with a commercial use				P	P	P	P							
Temporary housing for night security personnel during construction, Facilities during construction	SP	SP	SP	SP	SP	SP	SP	SP	SP	SP		SP	SP	SP

## Residential (continued)

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
Use (w/o NAICS classification)														

## Two or More Dwelling Units

Duplex dwelling	SP		P										SP	P
2 to 3 dwelling units	SCU												SCU	
Manufactured dwelling park			SP											SP
Multiple family dwelling units			P	CU		CU								P
Complementary residential use					SP	SP	SP							
Nursing care facilities. (6231)			P	CU		CU								P
Assisted living facilities. (62331)			P	CU		CU								P

Rooming and boarding house (7213)			P	CU										P
-----------------------------------	--	--	---	----	--	--	--	--	--	--	--	--	--	---



## Other Uses Associated with Residential

Use (NAICS #)	RS	R1S	RM	CO	CG	DDC	NNC	IP	IL	P/SP	RCW OD	SWIR	Nodal RS	Nodal RM
<b>Use (w/o NAICS classification)</b>														
Agricultural practices without livestock	SP	SP	SP	SP	SP			SP	SP	SP		SP	SP	SP
Boat and recreational vehicle storage pad	SP		SP										SP	SP
Boat and recreational vehicle storage area	SP		SP										SP	SP
Garage (or carport in the case of a manufactured home)	AU		AU										AU	AU
Garage with a maximum capacity of three cars (or carport with a maximum capacity of two cars in the case of a manufactured home)		AU												
Deck or patio	AU		AU										AU	AU
Fence or free standing walls	AU	AU	AU	AU	AU	AU	AU	AU	AU	AU		AU	AU	AU
Greenhouse or hobby shop	AU	AU	AU										AU	AU
Pets and pet accommodations for five or fewer pets owned by the occupants of the residence														
Private recreational facilities, including swimming pool, hot tub or sauna, and game courts	AU		AU										AU	AU
Personal storage structure	AU		AU										AU	AU
Telecommunications Facilities								SCU	SCU			SCU		
Trails											P			
Passive recreation uses and activities											P			
Maintenance of existing structures, lawns and gardens											P			
Normal maintenance and expansion of existing public facilities											P			
Removal of invasive (non-native) plant species											P			